



22101728868

B. H. Ritchie

Dec 1831

1831



A MANUAL
OF
ELEMENTARY CHEMISTRY.



W. H. Pritchard.

18319

A MANUAL
OF
ELEMENTARY CHEMISTRY,
THEORETICAL AND PRACTICAL.

BY
GEORGE FOWNES, F.R.S.,

LATE PROFESSOR OF PRACTICAL CHEMISTRY IN UNIVERSITY COLLEGE, LONDON.

FIFTH EDITION, REVISED AND CORRECTED.



LONDON:
JOHN CHURCHILL, PRINCES STREET, SOHO.
MDCCCLIV.

709

WELLCOME INSTITUTE LIBRARY	
Coll.	welMOmec
Call	
No.	QD100
	1854
	F78m

P R E F A C E.

THE design of the present volume is to offer to the student commencing the subject of Chemistry, in a compact and inexpensive form, an outline of the general principles of that science, and a history of the more important among the very numerous bodies which Chemical Investigations have made known to us. The work has no pretensions to be considered a complete treatise on the subject, but is intended to serve as an introduction to the larger and more comprehensive systematic works in our own language and in those of the Continent; and especially to prepare the student for the perusal of original memoirs, which, in conjunction with practical instruction in the laboratory, can alone afford a real acquaintance with the spirit of research and the resources of Chemical Science.

It has been my aim throughout to render the book as practical as possible, by detailing, at as great length as the general plan permitted, many of the working processes of the scientific laboratory, and by exhibiting, by the aid of numerous wood-engravings, the most useful forms of apparatus, with their adjustments and methods of use. .

As one principal object was the production of a convenient and useful class-book for pupils attending my own

lectures, I have been induced to adopt in the book the plan of arrangement followed in the lectures themselves, and to describe the non-metallic elements and some of their most important compounds before discussing the subject of the general philosophy of Chemical Science, and even before describing the principle of the equivalent quantities, or explaining the use of the written symbolical language now universal among Chemists. For the benefit of those to whom these matters are already familiar, and to render the history of the compound bodies described in the earlier part of the work more complete, I have added in foot-notes the view adopted of their Chemical constitution, expressed in symbols.

I have devoted as much space as could be afforded to the very important subject of Organic Chemistry ; and it will, I believe, be found that there are but few substances of any general interest which have been altogether omitted, although the very great number of bodies to be described in a limited number of pages rendered it necessary to use as much brevity as possible.

GEO. FOWNES.

UNIVERSITY COLLEGE, LONDON,
October 5, 1847.

ADVERTISEMENT
TO
THE THIRD EDITION.

THE correction of this Edition for the press was the daily occupation of Professor Fownes, until a few hours previous to his death in January, 1849.

His wish and his endeavour, as seen in his manuscript, were to render it as perfect and as minutely accurate as possible.

When he had finished the most important part of the Organic Chemistry, where the most additions were required, he told me he should "do no more,"—he had "finished his work."

At his request I have corrected the press throughout, and made a few alterations that appeared desirable in the only part which he had left unaltered, the Animal Chemistry.

The index and the press have also been corrected throughout by his friend Mr. Robert Murray.

H. BENCE JONES, M.D.

30, Grosvenor Street,
Jan. 1850.



ADVERTISEMENT

TO

THE FOURTH EDITION.

It has been the endeavour of the Editors to include in the present Edition of the Manual the progress of Chemistry since the Author's death.

The foundation which he laid, and the form which he gave to the work, remain untouched. But time has rendered it necessary that each portion should be revised; and a few repairs, and some considerable additions, especially in Organic Chemistry, have been made. Thus, several of the chapters on the Alcohols, the Organic Bases, Colouring Matters, &c., have been almost re-written.

Still, such changes only have been made as the Editors believed the Author himself would have desired, if his life had been spared to Science.

H. BENCE JONES.

A. W. HOFMANN.

London, September, 1852.



ADVERTISEMENT
TO
THE FIFTH EDITION.

THE short time that has elapsed since the last Edition of this Manual was printed, has rendered any great addition to its bulk unnecessary. Still, throughout each part of the work additions and improvements have been made. The whole has been most carefully revised.

The Editors have endeavoured to render the Manual a brief but perfect compendium of the Chemical facts established up to the present time.

H. BENCE JONES.

A. W. HOFMANN.

London, April, 1854.



TABLE OF CONTENTS.

	PAGE
INTRODUCTION	1

PART I.

PHYSICS.

OF DENSITY AND SPECIFIC GRAVITY	3
Methods of determining the specific gravities of fluids and solids	4
Construction and application of the hydrometer	9
OF THE PHYSICAL CONSTITUTION OF THE ATMOSPHERE, AND OF GASES IN GENERAL	11
Elasticity of gases.—Construction and use of the air-pump	11
Weight and pressure of the air.—Barometer	15
Law of Mariotte: relations of density and elastic force: correction of volumes of gases for pressure	17
HEAT	20
Expansion.—Thermometers	20
Different rates of expansion among metals; compensation-pendulum	24
Daniell's pyrometer	25
Expansion of liquids and gases.—Ventilation.—Movements of the atmosphere	27
Conduction of heat	34
Change of state.—Latent heat	35
Ebullition; steam	37
Distillation	41
Evaporation at low temperatures	43
Vapour of the atmosphere; hygrometry	46

	PAGE
Liquefaction of permanent gases	47
Production of cold by evaporation	50
Capacity for heat.—Specific heat	51
Sources of heat	55
LIGHT	58
Reflection, refraction, and polarization of light	58
Chemical rays	67
Radiation, reflection, absorption, and transmission of heat	72
MAGNETISM	81
Magnetic polarity; natural and artificial magnets	82
Terrestrial magnetism	84
ELECTRICITY	88
Electrical excitation; machines	89
Principle of induction; accumulation of electricity	93
Voltaic electricity	95
Thermo-electricity.—Animal electricity	97
Electro-magnetism; magneto-electricity	98
Electricity of steam	102

PART II.

CHEMISTRY OF THE ELEMENTARY BODIES.

NON-METALLIC ELEMENTS	103
Oxygen	104
Hydrogen; water; binoxide of hydrogen	111
Nitrogen; atmospheric air; compounds of nitrogen and oxygen	124
Carbon; carbonic oxide; carbonic acid	133
Sulphur; compounds of sulphur and oxygen	138
Selenium	145
Phosphorus; compounds of phosphorus and oxygen	146
Chlorine; hydrochloric acid.—Compounds of chlorine and oxygen	150

CONTENTS.

XV

	PAGE
Iodine	158
Bromine	161
Fluorine	162
Silicium	164
Boron	166
COMPOUNDS FORMED BY THE UNION OF THE NON-METALLIC ELEMENTS AMONG THEMSELVES	168
Compounds of carbon and hydrogen.—Light carbonetted hy- drogen; olefiant gas; coal and oil-gases.—Combustion, and the structure of flame	168
Nitrogen and hydrogen; ammonia	179
Sulphur, selenium, and phosphorus, with hydrogen	181
Nitrogen, with chlorine and iodine; chloride of nitrogen	186
Other compounds of non-metallic elements	188
Chlorine, with sulphur and phosphorus	188
ON THE GENERAL PRINCIPLES OF CHEMICAL PHILOSOPHY	191
Nomenclature	191
Laws of combination by weight	194
By volume	200
Chemical symbols	203
The atomic theory	206
Chemical affinity	208
Electro-chemical decomposition; chemistry of the voltaic pile	213
METALS	226
General properties of the metals	226
Crystallography	233
Isomorphism	242
Polybasic acids	245
Binary theory of the constitution of salts	247
Potassium	250
Sodium	259
Ammonium	271
Lithium	275
Barium	276

	PAGE
Strontium	278
Calcium	279
Magnesium	286
Aluminium	290
Beryllium (glucinum).—Yttrium	293
Cerium, lanthanum, and didymium	294
Zirconium.—Thorium	295
Manufacture of glass, porcelain, and earthenware	295
Manganese	300
Iron	305
Chromium	314
Nickel	317
Cobalt	319
Zinc	321
Cadmium	323
Bismuth	324
Uranium	326
Copper	327
Lead	330
Tin	334
Tungsten	337
Molybdenum	337
Vanadium	338
Tantalum (columbium)	339
Niobium and Pelopium	340
Titanium	340
Antimony	341
Tellurium	345
Arsenic	346
Silver	352
Gold	356
Mercury	359
Platinum	366
Palladium	371
Rhodium	372
Iridium	374
Ruthenium	375
Osmium	376

PART III.

ORGANIC CHEMISTRY.

	PAGE
INTRODUCTION	379
LAW OF SUBSTITUTION	380
THE ULTIMATE ANALYSIS OF ORGANIC BODIES	384
EMPIRICAL AND RATIONAL FORMULÆ	394
DETERMINATION OF THE DENSITY OF THE VAPOURS OF VOLA- TILE LIQUIDS	396
SACCHARINE AND AMYLACEOUS SUBSTANCES, AND THE PRO- DUCTS OF THEIR ALTERATION	399
Cane and grape sugars; sugar from ergot of rye; sugar of diabetes insipidus; liquorice-sugar; milk-sugar; mannite.	399
Starch; dextrin; starch from Iceland-moss; inulin; gum; pectin; lignin	404
Oxalic and saccharic acids	410
Xyloidin; pyroxylin; mucic acid; suberic acid.	413
Mellitic, rhodizonic, and croconic acids	414
Fermentation of sugar.—Alcohol	415
Lactic acid	420
Ether, and ethyl-compounds	423
Sulphovinic, phosphovinic, and oxalovinic acids	432
Heavy oil of wine	437
Olefiant gas; Dutch liquid; chlorides of carbon	437
Ethionic and isethionic acids	441
Chloral, &c.	442
Mercaptan; xanthic acid	444
Aldehyde; aldehydic acid; acetal	447
Acetic acid	450
Chloracetic acid	455
Acetone	457
Kakodyl	458

	PAGE
SUBSTANCES MORE OR LESS ALLIED TO ALCOHOL.	
Wood-spirit; methyl-compounds	463
Sulphomethylic acid	466
Formic acid; chloroform	468
Formomethylal; methyl-mercaptan	470
Potato-oil and its derivatives	472
Sulphamylic acid	474
Valerianic acid; chlorovaleric and chlorovalerosic acids	475
Fusel-oil from grain-spirit	478
Bitter-almond-oil and its products; benzoyl-compounds .	483
Benzoic acid; sulphobenzoic acid; benzene and benzol .	484
Sulphobenzide and hyposulphobenzic acid	486
Nitrobenzol, azobenzol, &c.	487
Formobenzoic acid; hydrobenzamide; benzoin; benzile; benzilic acid; benzimide, &c.	490
Hippuric acid	492
Homologues of benzoyl-series	493
Salicin; salicyl and its compounds	494
Chlorosamide.—Phloridzin.—Cumarin	497
Cinnamyl and its compounds; cinnamic acid; chloro-cinnose	499
VEGETABLE ACIDS	502
Tartaric acid	502
Racemic acid	505
Citric acid	507
Aconitic or equisetetic acid.	508
Malic acid	508
Fumaric and maleic acids.	510
Tannic and gallic acids	510
AZOTIZED ORGANIC PRINCIPLES OF SIMPLE CONSTITUTION	515
Cyanogen; paracyanogen; hydrocyanic acid	515
Amygdalin; amygdalic acid	519
Metallic cyanides	520
Cyanic, cyanuric, and fulminic acids	523
Chlorides, &c., of cyanogen	528
Ferro- and ferricyanogen, and their compounds; Prussian blue	528
Cobaltocyanogen	533
Sulphocyanogen, and its compounds; selenocyanogen; melam; melamine; ammeline; ammelide	534

CONTENTS.

xix

	PAGE
Urea, and uric acid	536
Allantoiu; alloxan; alloxanic acid; mesoxalic acid; myko- melinic acid; parabanic acid; oxaluric acid; thionuric acid; uramile; alloxantin; murexide; murexan	539
Xanthic and cystic oxides	545
THE VEGETO-ATKALIS, AND ALLIED BODIES	547
Morphine, and its salts	547
Narcotine; opianic and hemipinic acids; cotarnine	549
Codeine; thebaine; pseudo-morphine; narceine; meconine	549
Meconic acid.	550
Cinchonine and quinine; quinoidine	551
Kinic acid; kinone; hydrokinone	553
Strychnine and brucine	554
Veratrine; conicine; nicotine; sparteine; harmaline; har- mine; caffeine or theine; theobromine; berberine; pipe- rine; hyoscyamine; atropine; solanine; aconitine; delphi- nine; emetine; curarine	555
Gentianin; populin; daphnin; hesperidin; elaterin; an- tiarin; picrotoxin; asparagin; santonin.	557
ORGANIC BASES OF ARTIFICIAL ORIGIN	559
Bases of the ethyl-series.—Ethylamine; biethylamine; tri- ethylamine; oxide of tetrethyl-ammonium	561
Bases of the methyl-series.—Methylamine; bimethylamine; trimethylamine; oxide of tetramethyl-ammonium	564
Bases of the amyl-series.—Amylamine; biamylamine; tri- amylamine; oxide of tetramyl-ammonium	566
Bases of the phenyl-series.—Aniline; chloraniline; nitra- niline; cyaniline; melaniline	566
Bases homologous to aniline.—Toluidine; xyloidine; cumi- dine. Naphthalidine; chloronicine	571
Mixed bases.—Ethylaniline; biethylaniline; oxide of tri- ethylamyl-ammonium; biethylamylamine; oxide of me- thylbiethylamyl - ammonium; methylethylamylamine; ethylamylaniline; oxide of methyl-ethyl-amyl-phenyl- ammonium	572

	PAGE
BASES OF UNCERTAIN CONSTITUTION	574
Chinoline	574
Kyanol; leucol; picoline	574
Petinine	575
Furfurine; fucusine	575
Amarine; thiosinamine	576
Thialdine; alanine	577
Phosphorus-bases	579
Antimony-bases	579
ORGANIC COLOURING PRINCIPLES	581
Indigo; white indigo; sulphindyllic acid	581
Isatin; anilic and picric acids; chrysanic and anthranilic acids	583
Litmus—lecanorin; orcin; orexin, &c.	587
Cochineal, madder, dye-woods, &c.	590
Chrysammic, chrysolepic, and styphnic acids	593
OILS AND FATS	595
Fixed oils; margarin, stearin, and olein; saponification, and its products; glycerin	595
Palm and cocoa oils.—Elaidin and elaidic acid	600
Suberic, succinic, and sebacic acids	601
Butter.—Butyric, caproic, caprylic, and capric acids	601
Wax; spermaceti; cholesterin; cantharidin	602
Acrolein; acrylic acid	604
Products of the action of acids on fats	604
Castor-oil; caprylic alcohol	605
Volatile oils.—Oils of turpentin, lemons, aniseed, cumin, cedar, Gaultheria, valerian, peppermint, lavender, rosemary, orange-flowers, rose-petals	606
Camphor; camphoric acid	611
Oils of mustard, garlic, onions, &c.	612
Resins.—Caoutchouc	613
Balsams.—Toluol, styrol	614
COMPONENTS OF THE ANIMAL BODY	617
Albumin, fibrin, and casein; protein	617
Gelatin and chondrin	619

CONTENTS.

xxi

PAGE

Kreatin and kreatinine	626
Composition of the blood ; respiration ; animal heat . .	627
Chyle ; lymph ; mucus ; pus	633
Milk ; bile ; urine ; urinary calculi	635
Nervous substance ; membranous tissue ; bones	645
The function of nutrition in the vegetable and animal kingdoms	647

PRODUCTS OF THE DESTRUCTIVE DISTILLATION, AND SLOW PUTREFACTIVE CHANGE OF ORGANIC MATTER 653


Substances obtained from tar.—Paraffin ; eupione ; picamar ; kapnomor ; cedriret ; kreosote ; chrysen and pyren . .	653
Coal-oil.—Carbolic acid (hydrate of oxide of phenyl) . .	656
Napthalin and paranapthalin	660
Petroleum, naphtha, and other allied substances	662

POSTSCRIPT.


Acetate of alumina and alumina	666
--	-----

APPENDIX.

Hydrometer tables.—Table of the tension of the vapour of water at different temperatures.—Table of the proportion of real alcohol in spirits of different densities.—Analyses of the mineral waters of Germany.—Table of weights and measures	668
---	-----



MANUAL OF ELEMENTARY CHEMISTRY.



MANUAL OF CHEMISTRY.

INTRODUCTION.

THE Science of Chemistry has for its object the study of the nature and properties of all the materials which enter into the composition or structure of the earth, the sea, and the air, and of the various organized or living beings which inhabit these latter. Every object accessible to man, or which may be handled and examined, is thus embraced by the wide circle of Chemical Science.

The highest efforts of Chemistry are constantly directed to the discovery of the general laws or rules which regulate the formation of chemical compounds, and determine the action of one substance upon another. These laws are deduced from careful observation and comparison of the properties and relations of vast numbers of individual substances ;—and by this method alone. The science is entirely experimental, and all its conclusions the results of skilful and systematic experimental investigation.

The applications of the discoveries of Chemistry to the arts of life, and to the relief of human suffering in disease, are, in the present state of the science, both very numerous and very important, and encourage the hope of still greater benefits from more extended knowledge than that now enjoyed.

In ordinary scientific speech the term *chemical* is applied to changes which permanently affect the properties or characters of bodies, in opposition to effects termed *physical*, which are not attended by such consequences. Changes of decomposition or combination are thus easily distinguished from those temporarily brought about by heat, electricity, magnetism, and the attractive forces, whose laws and effects lie within the province of Physics or Natural Philosophy.

Nearly all the objects presented by the visible world are of a compound nature, being chemical compounds, or variously-disposed mixtures of chemical compounds, capable of being resolved into simpler forms of matter. Thus, a piece of limestone or marble by the applica-

tion of a red-heat is decomposed into quicklime and a gaseous body, carbonic acid. Both lime and carbonic acid are in their turn susceptible of decomposition, the former into a metal, calcium, and oxygen, and the latter into carbon and oxygen. For this purpose, however, simple heat does not suffice, the resolution of these substances into their components demanding the exertion of a high degree of chemical energy. Beyond this second step of decomposition the efforts of Chemistry have hitherto been found to fail, and the three bodies, calcium, carbon, and oxygen, having resisted all attempts to resolve them into simpler forms of matter, are accordingly admitted into the list of *elements*;—not from any belief in their real oneness of nature, but from the absence of any evidence that they contain more than one description of matter.

The partial study of certain branches of Physical Science, as the physical constitution of gases, the chief phenomena of heat and electricity, and a few other subjects, forms such an indispensable introduction to Chemistry itself, that it is never omitted in the usual courses of oral instruction. A sketch of these subjects is, in accordance with these views, placed at the commencement of the present volume.

PART I.—PHYSICS.

OF DENSITY AND SPECIFIC GRAVITY.

IT is of great importance in the outset to understand clearly what is meant by the terms *density* and *specific gravity*. By the *density* of a body is meant its *mass*, or *quantity of matter*, compared with the mass or quantity of matter of an *equal volume* of some standard body, arbitrarily chosen. *Specific gravity* denotes the *weight* of a body, as compared with the weight of an equal bulk, or volume, of the standard body, which is reckoned as unity.* In all cases of solids and liquids this standard of unity is pure water at the temperature of 60° Fahr. (15°·5C). Anything else might have been chosen; there is nothing in water to render its adoption for the purpose mentioned indispensable; it is simply taken for the sake of convenience, being always at hand, and easily obtained in a state of perfect purity. The ordinary expression of specific weight, therefore, is a number expressing how many times the weight of an equal bulk of water is contained in the weight of the substance spoken of. If, for example, we say that concentrated oil of vitriol has a specific gravity equal to 1·85, or that perfectly pure alcohol has a density of 0·794 at 60°, we mean that equal bulks of these two liquids and of distilled water possess weights in the proportion of the numbers 1·85, 0·794, and 1; or 1850, 794, and 1000. It is necessary to be particular about the temperature, for, as will be hereafter shown, liquids are extremely expandible by heat; otherwise, a constant bulk of the same liquid will not retain a constant weight. It will be proper to begin with the description of the mode in which the specific gravity of liquids is determined: this is the simplest case, and the one which best illustrates the general principle.

In order to obtain at pleasure the specific gravity of any particular liquid compared with that of water, it is only requisite to weigh equal bulks at the standard temperature, and then divide the weight of the liquid by the weight of the water; the quotient will of course be greater or less than unity, as the liquid experimented on is heavier or lighter than water. Now, to weigh equal bulks, of two fluids, the simplest and best method is clearly to weigh them in succession

* In other words, density means comparative *mass*, and specific gravity comparative *weight*. These expressions, although really relating to distinct things, are often used quite indifferently in chemical writings, and without practical inconvenience, since mass and weight are directly proportional to each other.

in the same vessel, taking care that it is equally full on both occasions, a condition very easy of fulfilment.

A thin glass bottle, or flask, with a narrow neck, is procured, of the figure represented in the margin, and of such capacity as to contain when filled to about half-way up the neck, exactly 1000 grains of distilled water at 60° ($15^{\circ}5\text{C}$). Such a flask is readily procured from any one of the Italian artificers, to be found in every large town, who manufacture cheap thermometers for sale. A counterpoise of the exact weight of the empty bottle is made from a bit of brass, an old weight, or something of the kind, and carefully adjusted by filing; an easy task. The bottle is then graduated, by introducing water at 60° , until it exactly balances the 1000-grain weight and counterpoise in the opposite scale; the height at which the water stands in the neck is marked by a scratch, and the instrument is complete for use. The liquid to be examined is brought to the temperature of 60° , and with it the bottle is filled up to the mark before mentioned; it is then weighed,

Fig. 1.



the counterpoise being used as before, and the specific gravity directly ascertained.

A watery liquid in a narrow glass tube always presents a curved surface from the molecular action of the glass, the concavity being upwards. It is better, on this account, in graduating the bottle, to make two scratches as represented in the drawing, one at the 'top and the other at the bottom of the curve: this prevents any future mistake. The marks are easily made by a fine, sharp, triangular file, the hard point of which, also, it may be observed, answers perfectly well for writing upon glass, in the absence of a proper diamond-pencil.

The specific-gravity bottle above described differs from those commonly made for sale by the instrument-makers. These latter are constructed with a perforated stopper, so arranged that when the bottle is quite filled, the stopper put in its place, and the excess of liquid which flows through the hole wiped from the outside, a constant measure is always had. There are inconveniences attending the use of the stopper which lead to a preference of the open bottle with merely a mark on the neck, even when very volatile liquids are experimented with.

It will be quite obvious that the adoption of a flask holding exactly 1000 grains of water has no other object than to save the trouble of a very trifling calculation; any other quantity would answer

just as well, and, in fact, the experimental chemist is often compelled to use a bottle of much smaller dimensions, from scarcity of the liquid to be examined. The shape is also in reality of little moment; any light phial with a narrow neck may be employed, not quite so conveniently perhaps, as a specific-gravity bottle.

The determination of the specific gravity of a solid is also an operation of great facility, although the principle is not so obvious. As it would be impossible to put in practice a direct method like that indicated for liquids, recourse is had to another plan. The celebrated theorem of Archimedes affords a solution of the difficulty. This theorem may be thus expressed:—


When a solid is immersed in a fluid, it loses a portion of its weight; and this portion is equal to the weight of the fluid which it displaces; that is, to the weight of its own bulk of that fluid.

It is easy to give experimental proof of this very important proposition, as well as to establish it by reasoning. The drawing represents a little apparatus for the former purpose. This consists of a thin cylindrical vessel of brass, into the interior of which fits very accurately a solid cylinder of the same metal, thus exactly filling it. When the cylinder is suspended beneath the bucket, as seen in the sketch, the whole hung from the arm of a balance and counterpoised, and then the cylinder itself immersed in water, it will be found to have lost a certain weight; and that this loss is precisely equal to the weight of an equal bulk of water, may then be proved by filling the bucket to the brim, whereupon the equilibrium will be restored.

The consideration of the great hydrostatic law of fluid pressure easily proves the truth of the principle laid down. Let the reader figure to himself a vessel of water, having immersed in it a solid cylindrical or rectangular body, and so adjusted with respect to density, that it shall float indifferently in any part beneath the surface (fig. 3).


Now the law of fluid pressure is to this effect:—The pressure exerted by a fluid upon the containing vessel, or upon anything plunged beneath its surface, depends, first, upon the density of that fluid, and, secondly, upon the perpendicular height of the column. It is independent of the form and lateral dimensions of the vessel or immersed body. Moreover, owing to the peculiar physical constitution of fluids, this pressure is exerted equally in every direction, upwards, downwards, and laterally, with equal force.

Fig. 2.



The floating body is in a state of equilibrium; therefore the pressure downwards caused by its gravitation must be exactly compensated by the upward transmitted pressure of the column of water, *a, b*.

Fig. 3.




But this pressure downwards is obviously equal to the weight of an equal quantity of water, since the body of necessity displaces its own bulk—

Hence, the weight lost or supported by the water, is the weight of a volume of water equal to that of the body immersed.

Whatever be the density of the substance it will be buoyed up to this amount; in the case supposed, the buoyancy is equal to the whole weight of the body, which is thus, while in the water, reduced to nothing.

A little reflection will show that the same reasoning may be applied to a body of irregular form; besides, a solid of any figure may be divided by the imagination into a multitude of

Fig. 4.



little perpendicular prisms, or cylinders, to each of which the argument may be applied. What is true of each individually, must necessarily be true of the whole together.

This is the fundamental principle; its application is made in the following manner:— Let it be required, for example, to know the specific gravity of a body of extremely irregular form, as a small group of rock crystals: the first part of the operation consists in determining its absolute weight, or, more correctly speaking, its weight in air; it is next suspended from the balance-pan by a fine horse-hair, immersed completely in pure water at 60° (15°·5C), and again weighed. It now weighs less, the difference being the weight of the water it displaces, that is, the weight of an equal bulk. This being known, nothing more is required than to find, by division, how many times the latter number is contained in the former; the quotient will be the density, water being

taken = 1. For example:—

The quartz-crystals weigh in air	.	.	293·7 grains.
When immersed in water, they weigh	.	.	180·1

Difference, being the weight of an equal volume of	
water	113·6

$$\frac{293\cdot7}{113\cdot6} = 2\cdot58, \text{ the specific gravity required.}$$

The arbitrary rule is generally thus written : "Divide the weight in air by the loss of weight in water, and the quotient will be the specific gravity." In reality it is not the weight in air which is required, but the weight the body would have in empty space: the error introduced, namely, the weight of an equal bulk of air, is so trifling that it is usually neglected.

Sometimes the body to be examined is lighter than water, and floats. In this case, it is first weighed and afterwards attached to a piece of metal, heavy enough to sink it, and suspended from the balance. The whole is then exactly weighed, immersed in water, and again weighed. The difference between the two weighings gives the weight of a quantity of water equal in bulk to both together. The light substance is then detached, and the same operation of weighing in air, and again in water, repeated on the piece of metal. These data give the means of finding the specific gravity, as will be at once seen by the following example :—

Light substance (a piece of wax) weighs in air	. 133.7 grains.
--	-----------------

Attached to a piece of brass, the whole now weighs	183.7
Immersed in water, the system weighs.	38.8

Weight of water equal in bulk to brass and wax	. 144.9
--	---------

Weight of brass in air	50.0
----------------------------------	------

Weight of brass in water	44.4
------------------------------------	------

Weight of equal bulk of water	5.6
---	-----

Bulk of water equal to wax and brass	144.9
--	-------

Bulk of water equal to brass alone	5.6
--	-----

Bulk of water equal to wax alone	139.3
--	-------

$$\frac{133.7}{139.3} = 0.9598.$$

In all such experiments, it is necessary to pay attention to the temperature and purity of the water, and to remove with great care all adhering air-bubbles; otherwise a false result will be obtained.

Other cases require mention in which these operations must be modified to meet particular difficulties. One of these happens when the substance is dissolved or acted upon by water. This difficulty is easily overcome by substituting some other liquid of known density which experience shows is without action. Alcohol or oil of turpentine may generally be used when water is inadmissible. Suppose, for instance, the specific gravity of crystallized sugar is required, we proceed in the following way :—The specific gravity of the oil of turpentine is first carefully determined; let it be 0.87; the sugar is next

weighed in the air, then suspended by a horse-hair, and weighed in the oil; the difference is the weight of an equal bulk of the latter; a simple calculation gives the weight of a corresponding volume of water:—

Weight of sugar in air	400 grains.
Weight of sugar in oil of turpentine	182·5

Weight of equal bulk of oil of turpentine	217·5
---	-------

$$87 : 100 = 217·5 : 250, .$$

the weight of an equal bulk of water; hence the specific gravity of the sugar,

$$\frac{400}{250} = 1·6.$$

The substance to be examined may be in small fragments, or powder. Here the operation is also very simple. A bottle holding a known weight of water is taken; the specific-gravity bottle already described answers perfectly well. A convenient quantity of the substance is next carefully weighed out, and introduced into the bottle, which is then filled up to the mark on the neck with distilled water. It is clear that the vessel now contains less water by a quantity equal to the bulk of the powder than if it were filled in the usual manner. It is, lastly, weighed. In the subjoined experiment emery powder was tried.

The bottle held, of water	1000 grains.
The substance introduced weighed	100

Weight of the whole, had no water been displaced	1100
The observed weight is, however, only	1070

Hence water displaced, equal in bulk to the powder	30
--	----

$$\frac{100}{30} = 3·333 \text{ specific gravity.}$$

By this method the specific gravities of metals in powder, metallic oxides, and other compounds, and salts of all descriptions, may be determined with great ease. Oil of turpentine may be used with most soluble salts. The crystals should be crushed or roughly powdered to avoid errors arising from cavities in their substance.

The theorem of Archimedes affords the key to the general doctrine of the equilibrium of floating bodies, of which an application is made in the common hydrometer,—an instrument for finding the specific gravities of liquids in a very easy and expeditious manner.

When a solid body is placed upon the surface of a fluid specifically heavier than itself, it sinks down until it displaces a quantity of fluid


equal to its own weight, at which point it floats. Thus, in the case of a substance floating in water, whose specific weight is one-half that of the fluid, the position of equilibrium will involve the immersion of exactly one-half of the body, inasmuch as its whole weight is counterpoised by a quantity of water equal to half its volume. If the same body were put into a fluid of one-half the specific gravity of water, if such could be found, then it would sink beneath the surface, and remain indifferently in any part. A floating body of known specific gravity may thus be used as an indicator of the specific gravity of a fluid. In this manner little glass beads of known specific gravities are sometimes employed in the arts to ascertain in a rude manner the specific gravity of liquids; the one that floats indifferently beneath the surface, without either sinking or rising, has of course the same specific gravity as the liquid itself; this is pointed out by the number marked upon the bead.

Fig. 5.



The hydrometer in general use consists of a floating vessel of thin metal or glass, having a weight beneath to maintain it in an upright position, and a stem above bearing a divided scale. The use of the instrument is very simple. The liquid to be tried is put into a small narrow jar, and the instrument floated in it. It is obvious that the denser the liquid, the higher will the hydrometer float, because a smaller displacement of fluid will counterbalance its weight. For the same reason, in a liquid of less density, it sinks deeper. The hydrometer comes to rest almost immediately, and then the mark on the stem at the fluid-level may be read off.

Fig. 6.



Very extensive use is made of instruments of this kind in the arts: they sometimes bear different names, according to the kind of liquid for which they are intended; but the principle is the same in all. The graduation is very commonly arbitrary, two or three different scales being unfortunately used. These may be sometimes reduced, however, to the true numbers expressing the specific gravity by the aid of tables of comparison drawn up for the purpose.

A very convenient and useful instrument in the shape of a small hydrometer for taking the specific gravity of urine, has lately been put into the hands of the physician; * it may be packed into a pocket-

* This and other instruments described or figured in the course of the work, may be had of Mr. Newman, 122, Regent Street, upon the excellence of whose workmanship reliance may be placed.

case, with a little jar and a thermometer, and is always ready for use.

The determination of the specific gravity of gases and vapours of volatile liquids is a problem of very great practical importance to the chemist: the theory of the operation is as simple as when liquids themselves are concerned, but the processes are much more delicate, and involve besides certain corrections for differences of temperature and pressure, founded on principles yet to be discussed. It will be proper to defer the consideration of these matters for the present. The method of determining the specific gravity of a gas will be found described under the head of "Oxygen," and that of the vapour of a volatile liquid in the Introduction to Organic Chemistry.

OF THE

PHYSICAL CONSTITUTION OF THE ATMOSPHERE,
AND OF GASES IN GENERAL.

It requires some little abstraction of mind to realize completely the singular condition in which all things at the surface of the earth exist. We live at the bottom of an immense ocean of gaseous matter, which envelopes everything, and presses upon everything with a force which appears, at first sight, perfectly incredible, but whose actual amount admits of easy proof.

Gravity being, so far as is known, common to all matter, it is natural to expect that gases, being material substances, should be acted upon by the earth's attraction, as well as solids and liquids. This is really the case, and the result is the weight or pressure of the atmosphere, which is nothing more than the effect of the attraction of the earth on the particles of air.

Before describing the leading phenomena of the atmospheric pressure, it is necessary to notice one very remarkable feature in the physical constitution of gases, upon which depends the principle of an extremely valuable instrument, the air-pump.

Gases are in the highest degree elastic; the volume or space which a gas occupies depends upon the pressure exerted upon it. Let the reader imagine a cylinder, *a*, closed at the bottom, in which moves a piston, air-tight, so that no air can escape between the piston and the cylinder. Suppose now the piston be pressed downwards with a certain force; the air beneath it will be compressed into a smaller bulk, the amount of this compression depending on the force applied; if the power be sufficient, the bulk of the gas may be thus diminished to one hundredth part or less. When the pressure is removed, the elasticity or *tension*, as it is called, of the included air or gas, will immediately force up the piston until it arrives at its first position.

Again, take fig. *b*, and suppose the piston to stand about the middle of the cylinder, having air beneath in its usual state. If the piston be now drawn upwards, the air below will expand, so as to fill com-





Fig. 7.

pletely the increased space, and this to an apparently unlimited extent. A volume of air which under ordinary circumstances occupies the bulk of a cubic inch, might, by the removal of the pressure upon it, be made to expand to the capacity of a whole room, while a renewal of the former pressure would be attended by a shrinking down of the air to its former bulk. The smallest portion of gas introduced into a large exhausted vessel becomes at once diffused through the whole space, an equal quantity being present in every part; the vessel is *full*, although the gas is in a state of extreme tenuity. This power of expansion which air possesses may have, and probably has, in reality, a limit; but the limit is never reached in practice. We are quite safe in the assumption, that for all purposes of experiment, however refined, air is perfectly elastic.

It is usual to assign a reason for this indefinite expansibility by ascribing to the particles of material bodies, when in a gaseous state,

Fig. 8.



a self-repulsive energy. This statement is commonly made somewhat in this manner: matter is under the influence of two opposite forces, one of which tends to draw the particles together, the other to separate them. By the preponderance of one or other of these forces, we have the three states called solid, liquid, and gaseous. When the particles of matter, in consequence of the direction and strength of their mutual attractions, possess only a very slight power of motion, a solid substance results; when the forces are nearly balanced, we have a liquid, the particles of which in the interior of the mass are free to move, but yet to a certain extent are held together; and, lastly, when

the attractive power seems to be completely overcome by its antagonist, we have a gas or vapour.

Various names are applied to these forces, and various ideas entertained concerning them; the attractive forces bear the name of cohesion when they are exerted between particles of matter separated by a very small interval, and gravitation, when the distance is great. The repulsive principle is often thought to be identical with the principle of heat.

The ordinary air-pump, shown in section in fig. 8, consists essentially of a metallic cylinder, in which moves a tightly fitting piston, by the aid of its rod. The bottom of the cylinder communicates with the vessel to be exhausted, and is furnished with a valve opening upwards. A similar valve, also opening upwards, is fitted to the piston; these valves are made with slips of oiled silk. When the piston is raised from the bottom of the cylinder, the space left beneath it must be void of air, since the piston-valve opens only in one direction; the air




Fig. 9.


within the receiver having on that side nothing to oppose its elastic power but the weight of the little valve, lifts the latter, and escapes into the cylinder. So soon as the piston begins to descend, the lower valve closes, by its own weight, or by the transmitted pressure from above, and communication with the receiver is cut off. As the descent of the piston continues, the air included within the cylinder becomes compressed, its elasticity is increased, and at length it forces open the

upper valve, and escapes into the atmosphere. In this manner, a cylinder full of air is at every stroke of the pump removed from the receiver. During the descent of the piston, the upper valve remains open, and the lower closed, and the reverse during the opposite movement.

In practice, it is very convenient to have two such barrels or cylinders, arranged side by side, the piston-rods of which are formed into racks, having a pinion, or small-toothed wheel, between them, moved by a winch. By this contrivance the operation of exhaustion is much facilitated and the labour lessened. The arrangement is shown in fig. 9, on the preceding page.

A simpler and far superior form of air-pump is thus constructed: the cylinder, which may be of large dimensions, is furnished with an accurately-fitted solid piston, the rod of which moves, air-tight, through a contrivance called a stuffing-box, at the top of the cylinder, where also the only valve *essential* to the apparatus is to be found; the latter is a solid conical plug of metal, shown at *a* in the figure,

Fig. 10.



kept tight by the oil contained in the chamber into which it opens. The communication with the vessel to be exhausted is made by a tube which enters the cylinder a little above the bottom. The action is the following: let the piston be supposed in the act of rising from the bottom of the cylinder; as soon as it passes the mouth of the tube *t*, all communication is stopped between the air above the piston and the vessel to be exhausted; the enclosed air suffers compression, until it acquires sufficient elasticity to lift the metal valve and escape by bubbling through the oil. When the piston makes its descent, and this valve closes, a vacuum is left in the upper part of the cylinder, into which the air of the receiver rushes so soon as the piston has passed below the orifice of the connecting tube.

In the silk valved air-pump exhaustion ceases when the elasticity of the air in the receiver becomes too feeble to raise the valve; in that last described, the exhaustion may, on the contrary, be carried to an indefinite extent, without, however, under the most favourable circumstances, becoming complete. The conical valve is made to project a little below the cover of the cylinder, so as to be forced up by the piston when the latter reaches the top of the cylinder; the oil then enters and displaces any air that may be lurking in the cavity.

It is a great improvement to the machine to supply the piston with a *relief-valve* opening upwards; this may also be of metal, and contained within the body of the piston. Its use is to avoid the momentary condensation of the air in the receiver when the piston descends.

The pump is worked by a lever in the manner represented in the drawing below.


To return to the atmosphere. Air possesses weight: a light flask or globe of glass, furnished with a stop-cock and exhausted by the air-pump, weighs considerably less than when full of air. If the capacity of the vessel be equal to 100 cubic inches, this difference may amount to nearly 30 grains.

The mere fact of the pressure of the atmosphere may be demonstrated by securely tying a piece of bladder over the mouth of an open glass receiver, and then exhausting the air from beneath it; the bladder will become more and more concave, until it suddenly breaks. A thin square glass bottle, or a large air-tight tin box, may be crushed by withdrawing the support of the air in the inside. Steam-boilers have been often destroyed in this manner by collapse, in consequence of the accidental formation of a partial vacuum within.

After what has been said on the subject of fluid pressure, it will scarcely be necessary to observe that the law of equality of pressure in all directions also holds good in the case of the atmosphere. The perfect mobility of the particles of air permits the transmission of the force generated by their gravity. The sides and bottom of an exhausted vessel are pressed upon with as much force as the top.

If a glass tube of considerable length could be perfectly exhausted of air, and then held in an upright position, with one of its ends dipping into a vessel of

Fig. 11.



liquid, the latter, on being allowed access to the tube, would rise in its interior until the weight of the column balanced the pressure of the air upon the surface of the liquid. Now, if the density of this liquid were known, and the height and area of the column measured, means would be furnished for exactly estimating the amount of pressure exerted by the atmosphere. Such an instrument is the barometer: a straight glass tube is taken, about 36 inches in length, and sealed by the blowpipe flame at one extremity; it is then filled with clean, dry mercury, care being taken to displace all air-bubbles, the open end stopped with a finger, and the tube inverted in a basin of mercury. On removing the finger, the fluid sinks away from the top of the tube, until it stands at the height of about 30 inches above the level of that in the basin. Here it remains supported by, and balancing the atmospheric pressure, the space above the mercury in the tube being of necessity empty.

Fig. 12.



The pressure of the atmosphere is thus seen to be capable of sustaining a column of mercury 30 inches in height, or thereabouts: now such a column, having an area of one inch, weighs between 14 and 15 pounds, consequently such must be the amount of the pressure exerted upon every square inch of the surface of the earth, and of the objects situated thereon, at least near the level of the sea. This enormous force is borne without inconvenience by the animal frame, by reason of its perfect uniformity in every direction, and it may be doubled, or even tripled without injury.

A barometer may be constructed with other liquids besides mercury; but, as the height of the column must always bear an inverse proportion to the density of the liquid, the length of tube required will be often considerable; in the case of water it will exceed 33 feet. It is seldom that any other liquid than mercury is employed in the construction of this instrument. The Royal Society of London possess a water-barometer at their apartments at Somerset House. Its construction was attended with great difficulties, and it has been found impossible to keep it in repair.

It will now be necessary to consider a most important law which connects the volume occupied by a gas with the pressure made upon it, and which is thus expressed:—

The volume of a gas is *inversely* as the pressure; the density and elastic force are *directly* as the pressure, and *inversely* as the volume.

For instance, 100 cubic inches of gas under a pressure of 30 inches


of mercury would expand to 200 cubic inches were the pressure reduced to one-half, and shrink, on the contrary, to 50 cubic inches if the original pressure were doubled. The change of density must necessarily be in the inverse proportion to that of the volume, and the elastic force follows the same rule.

This, which is usually called the law of Mariotte, is easily demonstrable by direct experiment. A glass tube, about 7 feet in length, is closed at one end, and bent into the form represented, the open limb of the siphon being the longer. It is next attached to a board furnished with a moveable scale of inches, and enough mercury is introduced to fill the bend, the level being evenly adjusted, and marked upon the board. Mercury is now poured into the tube until it is found that the enclosed air has been reduced to one-half of its former volume; and on applying the scale, it will be found that the level of the mercury in the open part of the tube stands very nearly 30 inches above that in the closed portion. The pressure of an additional "atmosphere" has consequently reduced the bulk of the contained air to one-half. If the experiment be still continued until the volume of air is reduced to a third, it will be found that the column measures 60 inches, and so in like proportion as far as the experiment is carried.

The above instrument is better adapted for illustration of the principle than for furnishing rigorous proof of the law; this has, however, been done. MM. Arago and Dulong published, in the year 1830, an account of certain experiments made by them in Paris, in which the law in question had been verified to the extent of 27 atmospheres.

All gases are alike subject to this law, and all vapours of volatile liquids, when remote from their points of liquefaction.* It is a matter of the greatest importance in practical chemistry, since it gives the means of making corrections for pressure, or determining by calculation the

Fig. 13.



* When near the liquefying point the law no longer holds; the volume diminishes *more rapidly* than the theory indicates, a smaller amount of pressure being then sufficient.

change of volume which a gas would suffer by any given change of external pressure.

Let it be required, for example, to solve the following problem:— We have 100 cubic inches of gas in a graduated jar, the barometer standing at 29 inches; how many cubic inches will it occupy when the column rises to 30 inches?—Now the volume must be inversely as the pressure; consequently a change of pressure in the proportion of 29 to 30 must be accompanied by a change of volume in the proportion of 30 to 29; 30 cubic inches of gas contracting to 29 cubic inches under the conditions imagined. Hence the answer:—

$$30 : 29 = 100 : 96.67 \text{ cubic inches.}$$

The reverse of the operation will be obvious. The practical pupil will do well to familiarize himself with these simple calculations of correction for pressure.

From what has been said respecting the easy compressibility of gases, it will be at once seen that the atmosphere cannot have the same density, and cannot exert equal pressures at different elevations above the sea-level, but that, on the contrary, these must diminish with the altitude, and very rapidly. The lower strata of air have to bear the weight of those above them; they become, in consequence, denser and more compressed than the upper portions. The following table, which is taken from Prof. Graham's work, shows in a very simple manner the rule followed in this respect:—

Height above the sea, in miles.	Volume of air.	Height of barometer, in inches.
0	1	30
2.705	2	15
5.41	4	7.5
8.115	8	3.75
10.82	16	1.875
13.525	32	0.9375
16.23	64	0.46875

The numbers in the first column form an *arithmetical* series, by the constant addition of 2.705; those in the second column an increasing *geometrical* series, each being double its predecessor; and those in the third, a decreasing *geometrical* series, in which each number is the half of that standing above it.

In ascending into the air in a balloon, these effects are well observed; the expansion of the gas within the machine, and the fall of the mercury in the barometer, soon indicate to the voyager the fact of his having left below him a considerable part of the whole atmosphere.


The invention of the barometer, which took place in the year 1643, by Torricelli, a pupil of the celebrated Galileo, speedily led to the

observation that the atmospheric pressure at the same level is not constant, but possesses, on the contrary, a small range of variation, seldom exceeding in Europe 2 or 2.5 inches, and within the tropics usually confined within much narrower limits. Two kinds of variations are distinguished; regular or horary, and irregular or accidental. It has been observed, that in Europe the height of the barometer is greatest at two periods in the twenty-four hours, depending upon the season. In winter, the first maximum takes place about 9 A.M., the first minimum at 3 P.M., after which the mercury again rises and attains its greatest elevation at 9 in the evening: in summer these hours of the aerial tides are somewhat altered. The accidental variations are much greater in amount, and render it extremely difficult to trace the regular changes above mentioned.

The barometer is applied with great advantage to the measurement of accessible heights, and it is also in daily use for foretelling the state of the weather; its indications are in this respect extremely deceptive, except in the case of sudden and violent storms, which are almost always preceded by a rapid fall in the mercurial column. It is often extremely useful in this respect at sea.

To the practical chemist, a moderately-good barometer is an indispensable article, since in all experiments in which volumes of gases are to be estimated, an account must be taken of the state of the pressure of the atmosphere. The marginal drawing represents a very convenient and economical siphon-barometer for this purpose. A piece of new and stout tube, of about one-third of an inch in internal diameter, is procured at the glass-house, sealed at one extremity, and bent into the siphon form, as represented. Pure and warm mercury is next introduced by successive portions until the tube is completely filled, and the latter being held in an upright position, the level of the metal in the lower and open limb is conveniently adjusted by displacing a portion by a stick or glass rod. The barometer is, lastly, attached to a board, and furnished with a long scale, made to slide, which may be of boxwood, with a slip of ivory at each end. When an observation is to be taken, the lower extremity or zero of the scale is placed exactly even with the mercury in the short limb, and then the height of the column at once read off.

Fig. 14.



HEAT.

It will be convenient to consider the subject of Heat under several sections, and in the following order :—


1. Expansion of bodies, or effects of variations of temperature in altering their dimensions.
2. Conduction, or transmission of heat.
3. Change of state.
4. Capacity of bodies for heat.

The phenomena of radiation must be deferred until a sketch has been given of the science of light.

EXPANSION.

If a bar of metal be taken, of such magnitude as to fit accurately to a gauge when cold, heated considerably, and again applied to the gauge, it will be found to have become enlarged in all its dimensions. When cold, it will once more enter the gauge.

Again, if a quantity of liquid contained in a glass bulb, furnished with a narrow neck, be plunged into hot water, or exposed to any

Fig. 15.*Fig. 16.**Fig. 17.*

other source of heat, the liquid will mount in the stem, showing that its volume has been increased.

Or, if a portion of air be confined in any vessel, the application of a slight degree of heat will suffice to make it occupy a space sensibly larger.

This most general of all the effects of heat furnishes in the outset a principle, by the aid of which an instrument can be constructed capable of taking cognizance of changes of temperature in a manner equally accurate and convenient: such an instrument is the thermometer.

A capillary glass tube is chosen, of uniform diameter: one extremity is closed and expanded into a bulb, by the aid of the blowpipe flame, and the other somewhat drawn out, and left open. The bulb is now cautiously heated by a spirit-lamp, and the open extremity plunged into a vessel of mercury, a portion of which rises into the bulb when the latter cools, replacing the air which had been expanded and driven out by the heat. By again applying the flame, and causing this mercury to boil, the remainder of the air is easily expelled, and the whole space filled with mercurial vapour, on the condensation of which the metal is forced into the instrument by the pressure of the air, until it becomes completely filled. The thermometer thus filled is now to be heated until so much mercury has been driven out by the expansion of the remainder, that its level in the tube shall stand at common temperatures at the point required. This being satisfactorily adjusted, the heat is once more applied, until the column rises quite to the top; and then the extremity of the tube is hermetically sealed by the blowpipe. The retraction of the mercury on cooling now leaves an empty space in the upper part of the tube, which is essential to the perfection of the instrument.

The thermometer has yet to be graduated; and to make its indications comparable with those of other instruments, a scale, having certain fixed points, at the least two in number, must be adapted to it.

It has been observed, that the temperature of melting ice, that is to say, of a mixture of ice and water, is always constant; a thermometer, already graduated, plunged into such a mixture, always marks the same degree of temperature, and a simple tube filled in the manner described and so treated, exhibits the same effect in the unchanged height of the little mercurial column, when tried from day to day. The freezing-point of water, or melting-point of ice, constitutes then one of the invariable temperatures demanded.

Another is to be found in the boiling-point of water, which is always the same under similar circumstances. A clean metallic vessel is taken, into which pure water is put and made to boil; a thermometer placed in the boiling liquid just so deep as is necessary to cover the bulb, invariably marks the same degree of temperature so long as the height of the barometer remains unchanged.

The tube having been carefully marked with a file at these two points, it remains to divide the interval into degrees: this division is entirely arbitrary; in the greater part of Europe and in America, the scale called *Centigrade* is employed; the space in question being divided into 100 parts, the zero being placed at the freezing-point of water. The scale is continued above and below these points, numbers below 0 being distinguished by the negative sign.

In England the very inconvenient division of Fahrenheit is still in use: the above-mentioned space is divided into 180 degrees, but the zero, instead of starting from the freezing-point of water, is placed 32

degrees below it, so that the temperature of ebullition is expressed by the number of 212° .

The plan of Reaumur is nearly confined to a few places in the north of Germany and to Russia; in this scale the freezing-point of water is made 0° , and the boiling-point 80° .

It is unfortunate that an uniform system has not been generally adopted in graduating thermometers: this would render unnecessary the labour which now so frequently has to be performed of translating the language of one scale into that of another. To effect this, presents, however, no great difficulty. Let it be required, for example, to know the degree of Fahrenheit's scale which corresponds to 60° Centigrade.

$$100^{\circ}\text{C} = 180^{\circ}\text{F, or } 5^{\circ}\text{C} = 9^{\circ}\text{F.}$$

Consequently

$$5 : 9 = 60 : 108.$$

But, then, as Fahrenheit's scale commences with 32° instead of 0° , that number must be added to the result, making $60^{\circ}\text{C} = 140^{\circ}\text{F}$.

The rule then will be the following:—To convert Centigrade degrees into Fahrenheit degrees, multiply by 9, divide the product by 5, and add 32; to convert Fahrenheit degrees into Centigrade degrees, subtract 32, multiply by 5, and divide by 9.

The reduction of negative degrees, or those below zero of one scale into those of another scale is effected in the same way. For example, to convert -15°C into degrees of Fahrenheit—

$$\text{We have } -15 \times \frac{9}{5} + 32 = -27 + 32 = +5^{\circ}\text{F.}$$

Mercury is usually chosen for making thermometers, on account of its regularity of expansion within certain limits, and because it is easy to have the scale of great extent, from the large interval between the freezing and boiling points of the metal. Other substances are sometimes used; alcohol is employed for estimating very low temperatures.


Air-thermometers are also used for some few particular purposes; indeed, the first thermometer ever made was of this kind. There are two modifications of this instrument; in the first, the liquid into which the tube dips is open to the air; and in the second, shown on the following page, the atmosphere is completely excluded. The effects of expansion are in the one case complicated with those arising from changes of pressure, and in the other cease to be visible at all when the whole instrument is subjected to alterations of temperature, because the air in the upper and lower reservoir, being equally affected by such changes, no alteration in the height of the fluid

column can occur. Accordingly, such instruments are called *differential* thermometers, since they serve to measure differences of temperatures between the two portions of air, while changes affecting both alike are not indicated. Fig. 19 shows another form of the same instrument.

Fig. 18.



Fig. 19.



The air-thermometer may be employed for measuring all temperatures from the lowest to the highest; M. Pouillet has described one by which the heat of an air-furnace could be measured. The reservoir of this instrument is of platinum, and it is connected with a piece of apparatus by which the increase of volume experienced by the included air is determined.


All bodies are enlarged in their dimensions by the application of heat, and reduced by its abstraction, or, in other words, contract on being artificially cooled: this effect takes place to a comparatively small extent with solids, to a larger amount in liquids, and most of all in the case of gases.

Each solid and liquid has a rate of expansion peculiar to itself; gases, on the contrary, expand nearly alike for the same increase of heat.

The difference of expansibility among solids is very easily illustrated by the following arrangement: a thin straight bar of iron is firmly fixed by numerous rivets, to a similar bar of brass: so long as the temperature at which the two metals were united remains unchanged, the compound bar preserves its straight figure; but any alteration of temperature gives rise to a corresponding curvature. Brass is more dilatable than iron; if the bar be heated, therefore, the


former expands more than the latter, and forces the straight bar into a curve, whose convex side is the brass; if it be artificially cooled, the brass contracts more than the iron, and the reverse of this effect is produced.

Fig. 20.



This fact has received a most valuable application. It is not necessary to insist on the importance of possessing instruments for the accurate measurement of time; such are absolutely indispensable to the successful cultivation of astronomical science, and not less useful to the navigator, from the assistance they give him in finding the longitude at sea. For a long time, notwithstanding the perfection of

Fig. 21.



finish and adjustment bestowed upon clocks and watches, an apparently insurmountable obstacle presented itself to their uniform and regular movement: this obstacle was the change of dimensions to which the regulating parts of the machine were subject by alterations of temperature. A clock may be defined as an instrument for registering the number of beats made by a pendulum: now the time of oscillation of a pendulum depends *principally* upon its length; any alteration in this condition will seriously affect the rate of the clock. The material of which the rod of the pendulum is composed is subject to expansion and contraction by changes of temperature; so that a pendulum adjusted to vibrate seconds at 60° ($15^{\circ}\cdot5\text{C}$) would go too slow if the temperature rise to 70° ($21^{\circ}\cdot1\text{C}$), from its elongation, and too fast if the temperature fall to 50° (10°C), from the opposite cause.

This great difficulty has been overcome: by making the rod of a number of bars of iron and brass, or iron and zinc, metals whose rates of expansion are different, and arranging these bars in such a manner that the expansion in one direction of the iron shall be exactly compensated by that in the opposite direction of the brass or zinc, it is possible to maintain under all circumstances

of temperature an invariable distance between the points of suspension and of oscillation. This is often called the *gridiron pendulum*; fig. 21 will clearly illustrate its principle; the shaded bars are supposed to be iron and the others brass.

A still simpler compensation-pendulum is thus constructed. The weight or bob, instead of being made of a disc of metal, consists of a cylindrical glass jar containing mercury, which is held by a stirrup at the extremity of the steel pendulum-rod. The same increase of temperature which lengthens this rod, causes the volume of the mercury to enlarge, and its level to rise in the jar; the centre of gravity is thus elevated, and by properly adjusting the quantity of mercury in the glass, the virtual length of the pendulum may be made constant.

In watches, the governing power is a horizontal weighted wheel, set in motion in one direction by the machine itself, and in the other by a fine spiral spring. The rate of going depends greatly on the diameter of this wheel, and the diameter is of necessity subject to variation by change of temperature. To remedy the evil thus involved, the circumference of the balance-wheel is made of two metals having different rates of expansion, firmly soldered together, the more expansible being on the outside.


The compound rim is also cut through in two or more places, as represented in the drawing. When the watch is exposed to a high temperature, and the diameter of the wheel becomes enlarged by expansion, each segment is made, by the same agency, to assume a sharper curve, whereby its centre of gravity is thrown inwards, and the expansive effect completely compensated. Many other beautiful applications of the same principle might be pointed out: the metallic thermometer of M. Bréguet is one of these.

Mr. Daniell very skilfully applied the expansion of a rod of metal to the measurement of temperatures above those capable of being indicated by the thermometer. A rod of iron or platinum, about five inches long, is dropped into a tube of black-lead ware; a little cylinder of baked porcelain is put over it, and secured in its place by a platinum strap and a wedge of porcelain. When the whole is exposed to heat, the expansion of the bar drives forward the cylinder, which moves with a certain degree of friction, and shows, by the extent of its displacement, the lengthening which the bar has undergone. It remains, therefore, to measure the amount of this displacement, which must be very small, even when the heat has been exceedingly intense. This is effected

Fig. 22.




Fig. 23.



by the contrivance, shown in the drawing, in which the mo-

Fig. 24.



tion of the longer arm of the lever carrying the vernier of the scale is multiplied by 10, in consequence of its superior length. The scale itself is made comparable with that of the ordinary thermometer, by plunging the instrument into a bath of mercury near its point of congelation, and afterwards into another of the same metal in a boiling state, and marking off the interval. By this instrument the melting-point of cast-iron was fixed at 2786° Fahrenheit (1530°C), and the greatest heat of a good wind-furnace at about 3300° (1815°C).

The actual amount of expansion which different solids undergo by the same increase of heat, has been carefully investigated. The following are some of the results obtained by MM. Lavoisier and Laplace. The fraction indicates the amount of expansion in length suffered by rods of the under-mentioned bodies in passing from 32° (0°C) to 212° (100°C).

English flint glass . . .	$\frac{1}{1248}$	Soft iron	$\frac{1}{819}$
Common French glass . .	$\frac{1}{1147}$	Gold	$\frac{1}{682}$
Glass without lead . . .	$\frac{1}{1142}$	Copper	$\frac{1}{584}$
Another specimen . . .	$\frac{1}{1098}$	Brass	$\frac{1}{533}$
Steel untempered . . .	$\frac{1}{927}$	Silver	$\frac{1}{521}$
Tempered steel . . .	$\frac{1}{807}$	Lead	$\frac{1}{351}$

From the *linear* expansion, the *cubic* expansion (or increase of volume) may be calculated. When the expansion of a body in different directions is equal, as, for example, in glass, hammered metals, and generally in most uncrystallized substances, it will be sufficient to triple the fraction expressing the increase in one dimension. This rule does not hold true for crystals belonging to irregular systems, for they expand unequally in the direction of the different axes.

Metals appear to expand pretty uniformly for equal increments of heat within the limits stated, but above the boiling-point of water the rate of expansion becomes irregular and more rapid.

The force exerted in the act of expansion is very great. In laying down railways, building iron bridges, erecting long ranges of steam-pipes, and in executing all works of the kind in which metal is largely used, it is indispensable to make provision for these changes of dimensions.

A very useful little application of expansion by heat is that to the cutting of glass by a hot iron; this is constantly practised in the laboratory for a great variety of purposes. The glass to be cut is marked with ink in the wished-for direction, and then a crack commenced by any convenient method, at some distance from the desired line of fracture, may be led by the point of a heated iron rod along the latter with the greatest precision.

Expansion of Fluids.—The dilatation of a fluid may be determined by filling with it a thermometer, in which the relation between the capacity of the ball and that of the stem is exactly known, and observing the height of the column at different temperatures. It is necessary in this experiment to take into account the effects of the expansion of the glass itself, the observed result being evidently the *difference* of the two.

Liquids vary exceedingly in this particular. The following table is taken from Péclet's *Elémens de Physique*.

Apparent Dilatation in Glass between 32° (0°C) and 212° (100°C).

Water	$\frac{1}{32}$
Hydrochloric acid, sp. gr. 1.137.	$\frac{1}{27}$
Nitric acid, sp. gr. 1.4	$\frac{1}{9}$
Sulphuric acid, sp. gr. 1.85	$\frac{1}{17}$
Ether	$\frac{1}{11}$
Olive oil	$\frac{1}{12}$
Alcohol	$\frac{1}{9}$
Mercury	$\frac{1}{64}$


Most of these numbers must be taken as representing mean results. For there are few fluids which, like mercury, expand regularly between these temperatures. Even mercury above 212° (100°C) shows an unequal and increasing expansion, if the temperature indicated by the air-thermometer be used for comparison. This is shown by the following abstract of a table given by Regnault.

Reading of Air Thermometer.	Reading of Mercurial Thermometer.	Temperature deduced from the absolute expansion of Mercury.
32°F = 0°C	32° F = 0°C	32° F = 0° C
212°F = 100°C	212° F = 100°C	212° F = 100° C
392°F = 200°C	392° F = 200°C	397° F = 202°·78C
572°F = 300°C	573°·8F = 301°C	587° F = 308°·34C
662°F = 350°C	669°·2F = 354°C	683°·88 F = 362°·16C

The absolute amount of expansion of mercury is, for many reasons, a point of great importance: it has been very carefully determined by a method independent of the expansion of the containing vessel. The apparatus employed for this purpose, first by MM. Dulong and Petit, and later by Regnault, is shown in fig. 25, divested, however, of many of its subordinate parts. It consists of two upright glass tubes, con-

nected at their bases by a horizontal tube of much smaller dimensions. Since a free communication exists between the two tubes, mercury poured into the one will rise to the same level in the other, provided its temperature is the same in both tubes: when this is not the case, the hotter column will be the taller, because the expansion of the metal diminishes its specific gravity, and the law of hydrostatic equilibrium requires that the heights of such columns should be inversely as their densities. By the aid of the outer cylinders, one of the tubes is maintained constantly at 32° (0°C), while the other is raised by means of heated water or oil, to any required temperature. The perpendicular heights of the columns may then be read off by a horizontal micrometer telescope, moving on a vertical divided scale.

Fig. 25.



These heights represent volumes of equal weight, because volumes of equal weight bear an inverse proportion to the densities of the liquids, so that the amount of expansion admits of being very easily calculated. Thus, let the column at 32° (0°C) be 6 inches high, and that at 212° (100°C) $6\cdot108$ inches, the increase of height, 108 on 6000 , or $\frac{1}{55\cdot5}$ part of the whole, must represent the absolute cubical expansion.

The indications of the mercurial thermometer are inaccurate when very high ranges of temperature are concerned, from the increased expansibility of the metal. The error thus caused is, however, nearly compensated for temperatures under 400°F ($204^{\circ}\cdot5\text{C}$) by the expansion of the glass tube. For higher temperatures a small correction is necessary, as the above table shows.

An exception to the regularity of expansion in fluids exists in the case of water: it is so remarkable, and its consequences so important, that it is necessary to advert to it particularly.

Let a large thermometer-tube be filled with water at the common temperature of the air, and then artificially cooled. The liquid will be observed to contract, until the temperature falls to about 40° , ($4^{\circ}\cdot44\text{C}$) or 8° above the freezing-point. After this, a farther reduction of temperature causes expansion instead of contraction in the volume of the water, and this expansion continues until the liquid arrives at its point of congelation, when so sudden and violent an

enlargement takes place, that the vessel is almost invariably broken. At the temperature of 40° ($4^{\circ}\cdot44\text{C}$), or more correctly, perhaps, $39^{\circ}\cdot5$, ($4^{\circ}\cdot1\text{C}$) water is at its maximum density;* increase or diminution of heat produces upon it, for a short time, the same effect.

A beautiful experiment by Dr. Hope, illustrates the same fact. If a tall jar filled with water at 50° (10°C) or 60° ($15^{\circ}\cdot5\text{C}$), and having in it two small thermometers, one at the bottom and the other near the surface, be placed at rest in a very cold room, the following changes will be observed. The thermometer at the bottom will fall more rapidly than that at the top, until it has attained the temperature of 40° ($4^{\circ}\cdot4\text{C}$) after which it will remain stationary. At length the upper thermometer will also mark 40° ($4^{\circ}\cdot4\text{C}$), but still continue to sink as rapidly as before, while that at the bottom remains stationary. It is easy to explain these effects: the water in the upper part of the jar is rapidly cooled by contact with the air; it becomes denser in consequence, and falls to the bottom, its place being supplied by the lighter and warmer liquid, which in its turn suffers the same change; and this circulation goes on until the whole mass of water has acquired its condition of maximum density, that is, until the temperature has fallen to 40° ($4^{\circ}\cdot4\text{C}$). Beyond this, loss of heat occasions expansion instead of contraction; so that the very cold water on the surface has no tendency to sink, but rather the reverse.

This singular anomaly in the behaviour of water is attended by the most beneficial consequences, in shielding the inhabitants of the waters from excessive cold. The deep lakes of the North American continent never freeze, the intense and prolonged cold of the winters of those regions being insufficient to reduce the temperature of such masses of water to 40° ($4^{\circ}\cdot4\text{C}$). Ice, however, of great thickness forms over the shallow portions, and the rivers, and accumulates in mounds upon the beaches, where the waves are driven up by the winds.

Above the freezing-point sea-water has no point of maximum density. The more it is cooled the denser it becomes, until it solidifies at $26^{\circ}\cdot5$ (-3°C). According to Despretz, sea-water which is cooled below $26^{\circ}\cdot5$, without freezing, obtains its maximum density at $25^{\circ}\cdot4$ ($-3^{\circ}\cdot6\text{C}$). The gradual expansion of pure water cooled below 40° ($4^{\circ}\cdot4\text{C}$) must be carefully distinguished from the great and sudden increase of volume it exhibits in the act of freezing, and in which respect it resembles many other bodies which expand on solidifying. It may be observed that the force thus exerted by freezing water is enormous. Thick iron shells quite filled with water, and exposed with their fuse-holes securely plugged, to the cold of a Canadian winter night, have been found the following morning split in fragments. The freezing of water in the joints and crevices of rocks is a most potent agent in their disintegration.

* According to the latest researches of Kopp the point of greatest density of the water is $39^{\circ}\cdot34$ ($4^{\circ}\cdot08\text{C}$).

Expansion of Gases.—This is a point of great practical importance to the chemist, and happily we have very excellent evidence upon the subject. The following four propositions exhibit, at a single view, the principal facts of the case:—

1. All gases expand nearly alike for equal increments of heat; and all vapours, when remote from their condensing-points, follow the same law.
2. The rate of expansion is not altered by a change in the state of compression, or elastic force of the gas itself.
3. The rate of expansion is uniform for all degrees of heat.
4. The actual amount of expansion is equal to $\frac{1}{460}$ part of the volume of the gas at 0° Fahrenheit, for each degree of the same scale.

It will be unnecessary to enter into any description of the methods of investigation by which these results have been obtained: the advanced student will find in Pouillet's *Elémens de Physique*, and in the papers of MM. Magnus* and Regnault,† all the information he may require.

In the practical manipulation of gases, it very often becomes necessary to make a correction for temperature, or to discover how much the volume of a gas would be increased or diminished by a particular change of temperature: this can be effected with great facility. Let it be required, for example, to find the volume which 100 cubic inches of any gas at 50° (10°C) would become on the temperature rising to 60° ($15^{\circ}\cdot 5\text{C}$).

The rate of expansion is $\frac{1}{460}$ of the volume at 0° for each degree; or 460 measures at 0° become 461 at 1° , 462 at 2° , .. $460 + 50 = 510$ at 50° , and $460 + 60 = 520$ at 60° . Hence

Meas. at 50° .	Meas. at 60° .	Meas. at 50° .	Meas. at 60° .
510	: 520	= 100	: 101·96

If this calculation is required to be made on the Centigrade scale, it must be remembered that the zero of that scale is the melting-point of ice. Above this temperature the expansion for each degree of the Centigrade scale is $\frac{1}{273}$ of the original volume.

This, and the correction for pressure, are operations of very frequent occurrence in chemical investigations, and the student will do well to become familiar with them.

Note.—Of the four propositions stated in the text, the first and second have quite recently been shown to be true within certain limits only; and the third, although in the highest degree probable, would be very difficult to demonstrate rigidly; in fact, the equal rate of expansion of air is assumed in all experiments on other substances and becomes the standard by which the results are measured.

* Poggendorff's *Annalen*, iv. 1.

† *Ann. Chim. et Phys.*, 3rd series, iv. 5, and v. 52.

The rate of expansion for the different gases is *not* absolutely the same, but the difference is so small, that for most purposes it may with perfect safety be neglected. Neither is the state of elasticity altogether indifferent, the expansion being sensibly *greater* for an equal rise of temperature when the gas is in a compressed state.


It is important to notice, that the greatest deviations from the rule are exhibited by those gases which, as will hereafter be seen, are most easily liquified, such as carbonic acid, cyanogen, and sulphurous acid; and that the discrepancies become smaller and smaller as the elastic force is lessened: so that, if means existed for comparing the different gases in states *equally distant* from their points of condensation, there is reason to believe that the law would be strictly fulfilled.

The experiments of MM. Dulong and Petit give for the rate of expansion $\frac{1}{448}$ of the volume at 0° : this is no doubt too high. Those of Rudburg give $\frac{1}{462}$; of Magnus $\frac{1}{459}$; and of Regnault $\frac{1}{458}$: the fraction $\frac{1}{460}$ is adopted in the text as a convenient number, sufficiently near the mean of the three preceding, to answer all purposes.

The ready expansibility of air by heat gives rise to the phenomena of winds. In the temperate regions of the earth these are very variable and uncertain, but within and near the tropics a much greater regularity prevails; of this the *trade-winds* furnish a beautiful example.

The smaller degree of obliquity with which the sun's rays fall in the localities mentioned, occasions the broad belt thus stretching round the earth to become more heated than any other part of the surface. The heat thus acquired by absorption is imparted to the lower stratum of air, which, becoming expanded, rises, and gives place to another, and in this manner an ascending current is established,—the colder and heavier air streaming in laterally from the more temperate regions, north and south, to supply the partial vacuum thus occasioned. A circulation so commenced will be completed in obedience to the laws of hydrostatics, by the establishment of counter-currents in the higher parts of the atmosphere, having directions the reverse of those on the surface.

Fig. 26.




Such is the effect produced by the unequal heating of the equatorial parts, or, more correctly, such would be the effect were it not greatly modified by the earth's movement of rotation.

As the circumference of the earth is, in round numbers, about

24,000 miles, and since it rotates on its axis, from west to east, once in 24 hours, the equatorial parts must have a motion of 1000 miles per hour; this velocity diminishes rapidly towards each pole, where it is reduced to nothing.

The earth in its rotation carries with it the atmosphere, whose velocity of movement corresponds, in the absence of disturbing causes, with that part of the surface immediately below it. The air which rushes towards the equator, to supply the place of that raised aloft by its diminished density, brings with it the degree of momentum belonging to that portion of the earth's surface from which it set out, and as this momentum is less than that of the earth, under its new position, the earth itself travels faster than the air immediately

Fig. 27.



over it, thus producing the effect of a wind blowing in a contrary direction to that of its own motion. The original north and south winds are thus deviated from their primitive directions, and made to blow more or less from the eastward, so that the combined effects of the unequal heating and of the movement of rotation is to generate in the northern hemisphere a constant north-east wind, and in the southern hemisphere an equally constant south-east wind.

In the same manner the upper or return current is subject to a change of direction in the reverse order; the rapidly-moving wind of the tropics, transferred laterally towards the poles, is soon found to travel faster than the earth beneath it, producing the effect of a westerly wind, which modifies the primary current.

The regularity of the trade-winds is much interfered with by the neighbourhood of large continents, which produce local effects upon a scale sufficiently great to modify deeply the direction and force of the wind. This is the case in the Indian Ocean. They usually extend from about the 28th degree of latitude in both hemispheres, to within 8° of the equator, but are subject to some variations in this respect. Between them, and also beyond their boundaries, lie belts of calms and light variable winds, and beyond these latter, extending into higher latitudes in both hemispheres, westerly winds usually prevail. The general direction of the trade-wind of the Northern hemisphere is E.N.E., and that of the Southern hemisphere E.S.E.

The trade-winds, it may be remarked, furnish an admirable physical proof of the reality of the earth's movement of rotation.


The theory of the action of chimneys, and of natural and artificial ventilation, belongs to the same subject.

Let the reader turn to the demonstration given of the Archimedean

hydrostatic theorem; let him once more imagine a body immersed in water, and having a density equal to that of the water; it will remain in equilibrio in any part beneath the surface, and for these reasons:—The force which presses it downwards is the weight of the body added to the weight of the column of water above it; the force which presses it upwards is the weight of a column of water equal to the height of both conjoined;—the density of the body is that of water, that is, it weighs as much as an equal bulk of that liquid; consequently, the downward and upward forces are equally balanced, and the body remains at rest.

Next, let the circumstances be altered; let the body be lighter than an equal bulk of water; the pressure upwards of the column of water *a c*, is no longer compensated by the downward pressure of the corresponding column of solid and water above it; the former force preponderates, and the body is driven upwards. If, on the contrary, the body be specifically heavier than water, then the latter force has the ascendancy, and the body sinks.

Fig. 28.



All things so described exist in a common chimney; the solid body, of the same density as that of the fluid in which it floats, is represented by the air in the chimney-funnel; the space *a b* represents the whole atmosphere above it. When the air inside and outside the chimney is at the same temperature, equilibrium takes place, because the downward tendency of the air within is counteracted by the upward pressure of that without.

Now, let the chimney be heated; the air suffers expansion, and a portion is expelled; the chimney therefore contains a smaller weight of air than it did before; the external and internal columns no longer balance each other, and the warmer and lighter air is forced upwards from below, and its place supplied by cold air. If the brick-work, or other material of which the chimney is constructed, retain its temperature, this second portion of air is disposed of like the first, and the ascending current continues, so long as the sides of the chimney are hotter than the surrounding air.

Sometimes, owing to sudden changes of temperature in the atmosphere, the chimney may happen to be colder than the air about it. The column within forthwith suffers contraction of volume; the deficiency is filled up from without, and the column becomes heavier than one of similar height on the outside; the result is, that it falls out of the chimney, just as the heavy body sinks in the water, and has its place occupied by air from above. A descending current is thus produced, which may be often noticed in the summer time by the smoke

from neighbouring chimneys finding its way into rooms, which have been for a considerable period, without fire.

The ventilation of mines has long been conducted upon the same principle, and more recently it has been applied to dwelling-houses and assembly-rooms. The mine is furnished with two shafts, or with one shaft, divided throughout by a diaphragm of boards; and these are so arranged, that air forced down the one shall traverse the whole extent of the workings before it escapes by the other. A fire kept up in one of these shafts, by rarefying the air within, and causing an ascending current, occasions fresh air to traverse every part of the mine, and sweep before it the noxious gases, but too frequently present.

CONDUCTION OF HEAT.

Different bodies possess very different conducting powers with respect to heat: if two similar rods, the one of iron the other of glass, be held in the flame of a spirit-lamp, the iron will soon become too hot to be touched, while the glass may be grasped with impunity within an inch of the red-hot portion.

Experiments made by analogous, but more accurate methods, have established a numerical comparison of the conducting powers of many bodies; the following may be taken as a specimen:—

Gold	1000	Tin	304
Silver	973	Lead	179
Copper	898	Marble	23·6
Iron	374	Porcelain	12·2
Zinc	363	Fire-clay	11·4

As a class the metals are by very far the best conductors, although much difference exists between them; stones, dense woods, and charcoal, follow next in order; then liquids in general and gases, whose conducting power is almost inappreciable.

Under favourable circumstances, nevertheless, both liquids and gases may become rapidly heated; heat applied to the bottom of the containing vessel is very speedily communicated to its contents: this, however, is not so much by conduction as by convection, or carrying. A complete circulation is set up; the portions in contact with the bottom of the vessel get heated, become lighter, and rise to the surface, and in this way the heat becomes communicated to the whole. If these movements be prevented by dividing the vessel into a great number of compartments, the really low conducting power of the substance is made evident; and this is the reason why certain organic fabrics, as wool, silk, feathers, and porous bodies in general, the cavities of which are full of air, exhibit such feeble powers of conduction.

The circulation of heated water through pipes is now extensively applied to the warming of buildings and conservatories, and in chemical works a serpentine metal tube containing hot oil is often used for heating stills and evaporating pans; the two extremities of the tube are

connected with the ends of another spiral built into a small furnace at a lower level, and an unintermitting circulation of the liquid takes place as long as heat is applied.

CHANGE OF STATE.

If equal weights of water at 32° (0°C) and water at 174° ($78^{\circ}\cdot 8\text{C}$) be mixed, the temperature of the mixture will be the mean of the two temperatures, or 183° ($39^{\circ}\cdot 4\text{C}$). If the same experiment be repeated with snow, or finely-powdered ice, at 32° (0°C) and water at 174° ($78^{\circ}\cdot 8\text{C}$), the temperature of the whole will be only 32° (0°C), *but the ice will have been melted.*

$$\left. \begin{array}{l} 1 \text{ lb. of water at } 32^{\circ} (0^{\circ}\text{C}) \\ 1 \text{ lb. of water at } 174^{\circ} (78^{\circ}\cdot 8\text{C}) \end{array} \right\} = 2 \text{ lb. water at } 103^{\circ} (39^{\circ}\cdot 4\text{C})$$

$$\left. \begin{array}{l} 1 \text{ lb. of ice at } 32^{\circ} (0^{\circ}\text{C}) \\ 1 \text{ lb. of water at } 174^{\circ} (78^{\circ}\cdot 8\text{C}) \end{array} \right\} = 2 \text{ lb. water at } 32^{\circ} (0^{\circ}\text{C})$$

In the last experiment, therefore, as much heat has been apparently lost as would have raised a quantity of water equal to that of the ice through a range of 142° ($78^{\circ}\cdot 8\text{C}$).

The heat, thus become insensible to the thermometer in effecting the liquefaction of the ice, is called latent heat, or, better, heat of fluidity.

Again, let a perfectly uniform source of heat be imagined, of such intensity that a pound of water placed over it would have its temperature raised 10° ($5^{\circ}\cdot 5\text{C}$) per minute. Starting with water at 32° (0°C) in rather more than 14 minutes its temperature would have risen 142° ($78^{\circ}\cdot 8$); but the same quantity of ice at 32° (0°C), exposed for the same interval of time, would not have its temperature raised a single degree. But, then, it would have become water; the heat received would have been exclusively employed in effecting the change of state.

This heat is not lost, for when the water freezes it is again evolved. If a tall jar of water, covered to exclude dust, be placed in a situation where it shall be quite undisturbed, and at the same time exposed to great cold, the temperature of the water may be reduced 10° or more below its freezing-point without the formation of ice; but then, if a little agitation be communicated to the jar, or a grain of sand dropped into the water, a portion instantly solidifies, and the temperature of the whole rises to 32° (0°C); the heat disengaged by the freezing of a small portion of the water will have been sufficient to raise the whole contents of the jar 10° ($5^{\circ}\cdot 5\text{C}$).

This curious condition of instable equilibrium shown by the very cold water in the preceding experiment, may be reproduced with a variety of solutions which tend to crystallize or solidify, but in which that change is for a while suspended. Thus, a solution of crystallized sulphate of soda in its own weight of warm water, left to cool in an open vessel, deposits a large quantity of the salt in crystals. If the warm solution, however, be filtered into a clean flask, which when full is securely corked and set aside to cool undisturbed, no crystals will be

deposited, even after many days, until the cork is withdrawn and the contents of the flask violently shaken. Crystallization then rapidly takes place in a very beautiful manner, and the whole becomes perceptibly warm.

The law thus illustrated in the case of water is perfectly general. Whenever a solid becomes a liquid, a certain fixed and definite amount of heat disappears, or becomes latent; and conversely, whenever a liquid becomes a solid, heat to a corresponding extent is given out. The amount of latent heat varies much with different substances, as will be seen by the table:—

Water*	. 142° (78°·8C)		Zinc . . . 493° (273°·8C)
Sulphur . . . 145 (80·5C)			Tin . . . 500 (277·7C)
Lead . . . 162 (90·5C)			Bismuth . . 550 (305·5C)

When a solid substance can be made to liquefy by a weak chemical attraction, cold results, from sensible heat becoming latent. This is the principle of the many frigorific mixtures to be found described in some of the older chemical treatises. When snow or powdered ice is mixed with common salt, and a thermometer plunged into the mass, the mercury sinks to 0° (17°·7C), while the whole after a short period becomes fluid by the attraction between the water and the salt; such a mixture is very often used in chemical experiments to cool receivers and condense the vapours of volatile liquids. Powdered crystallized chloride of calcium and snow produce cold enough to freeze mercury. Even powdered nitrate of potassa, or sal-ammoniac, dissolved in water, occasions a very notable depression of temperature: in every case, in short, in which solution is unaccompanied by energetic chemical action, cold is produced.

No relation is to be traced between the actual melting-point of a substance, and its latent heat when in a fused state.

A law of exactly the same kind as that described affects universally the gaseous condition; change of state from solid or liquid to gas is accompanied by absorption of sensible heat, and the reverse by its disengagement. The latent heat of steam and other vapours may be ascertained by a similar mode of investigation to that employed in the case of water.

When water at 32° (0°C) is mixed with an equal weight of water at 212° (100°C), the whole is found to possess the mean of the two temperatures, or 122° (50°C); on the other hand, 1 part by weight of steam at 212° (100°C) when condensed in cold water is found to be capable of raising 5·6 parts of the latter from the freezing to the boiling-point, or through a range of 180° (100°C). Now $180 \times 5\cdot6 = 1008$; that is to say, steam at 212° (100°C) in becoming water at 212°, parts with enough heat to raise a weight of water equal to its own (if it were possible) 1008° (560°C) of the thermometer.

* MM. De la Provostaye and Regnault, Ann. Chim. et Phys., 3rd series, viii. 1.

When water passes into steam, the same quantity of sensible heat becomes latent.

The vapours of other liquids seem to have less latent heat than that of water. The following table is by Dr. Ure, and serves well to illustrate this point :—

Vapour of water	.	.	967° (537°·2C)
„ alcohol	.	.	442 (246 ·6C)
„ ether	.	.	302 (167 ·7C)
„ petroleum	.	.	178 (98 ·8C)
„ oil of turpentine	.	.	178 (98 ·8C)
„ nitric acid	.	.	532 (295 ·5C)
„ liquor ammoniæ	.	.	837 (145 ·0C)
„ vinegar	.	.	875 (486 ·1C)

Ebullition is occasioned by the formation of bubbles of vapour within the body of the evaporating liquid, which rise to the surface like bubbles of permanent gas. This occurs in different liquids at very different temperatures. Under the same circumstances, the boiling-point is quite constant, and often becomes a physical character of great importance in distinguishing liquids which much resemble each other. A few cases may be cited in illustration :—

Substance.	Boiling-point.
Ether	96° (35°·5C)
Bisulphide of carbon	115 (46 ·1C)
Alcohol	177 (80 ·5C)
Water	212 (100 C)
Nitric acid, strong	248 (120 C)
Oil of turpentine	312 (155 ·5C)
Sulphuric acid	620 (326 ·2C)
Mercury	662 (350 C)

For ebullition to take place, it is necessary that the elasticity of the vapour should be able to overcome the cohesion of the liquid and the pressure upon its surface; hence the extent to which the boiling-point may be modified.

Water, under the usual pressure of the atmosphere, boils at 212° (100°C): in a partially-exhausted receiver or on a mountain-top it boils at a much lower temperature; and in the best vacuum of an excellent air-pump, over oil of vitriol, which absorbs the vapour, it will often enter into violent ebullition while ice is in the act of forming upon the surface.

On the other hand, water confined in a very strong metallic vessel may be restrained from boiling by the pressure of its own vapour to an almost unlimited extent; a temperature of 350° (177°C) or 400°

(204°C) is very easily obtained; and, in fact, it is said that it may be made red-hot, and yet retain its fluidity.

There is a very simple and beautiful experiment illustrative of the effect of diminished pressure in depressing the boiling-point of a liquid. A little water is made to boil for a few minutes in a flask or retort placed over a lamp, until the air has been chased out, and the steam issues freely from the neck. A tightly-fitting cork is then inserted, and the lamp at the same moment withdrawn. When the ebullition ceases it may be renewed at pleasure for a considerable time by the affusion of cold water, which, by condensing the vapour within, occasions a partial vacuum.

The nature of the vessel, or, rather, the state of its surface, exercises an influence upon the boiling-point, and this to a much greater extent than was formerly supposed. It has long been noticed that in a metallic vessel water boils, under the same circumstances of pressure, at a temperature one or two degrees below that at which ebullition takes place in glass; but it has lately been shown* that by particular management a much greater difference can be observed. If two similar glass flasks be taken, the one coated in the inside with a film of shellac, and the other completely cleansed by hot sulphuric acid, water heated over a lamp in the first will boil at 211° (99°·4C), while in the second it will often rise to 221° (105°C) or even higher; a momentary burst of vapour then ensues, and the thermometer sinks a few degrees, after which it rises again. In this state the introduction of a few metallic filings, or angular fragments of any kind, occasions a lively disengagement of vapour, while the temperature sinks to 212° (100°C), and there remains stationary. These remarkable effects must be attributed to an attraction between the surface of the vessel and the liquid.

A cubic inch of water in becoming steam under the ordinary pressure of the atmosphere expands into 1696 cubic inches, or nearly a cubic foot.

Steam, *not in contact with water*, is affected by heat in precisely the same manner as the permanent gases; its rate of expansion and increase of elastic force are the same. When water is present, however, this is no longer the case, but, on the contrary, the elastic force increases in a far more rapid proportion.

This elastic force of steam in contact with water, at different temperatures, has been very carefully determined by MM. Arago and Dulong, and very lately by M. Regnault. The force is expressed in atmospheres: the absolute pressure upon any given surface can be easily calculated, allowing 14·6 lb. to each atmosphere. The experiments were carried to twenty-five atmospheres, at which point the difficulties and danger became so great as to put a stop to the inquiry; the rest of the table is the result of calculations founded on the data so obtained.

* Marcet, Ann. Chim. et Phys., 3rd series, v. 449.

Pressure of steam in atmospheres.	Corresponding temperature.		Pressure of steam in atmospheres.	Corresponding temperature.	
	F.	C.		F.	C.
1 . . .	212°	100°	13 . . .	381°	155°·1
1·5 . . .	230	112 ·2	14 . . .	387	157 ·7
2 . . .	251	121 ·2	15 . . .	393	200 ·5
2·5 . . .	264	128 ·8	16 . . .	398	203 ·1
3 . . .	275	125	17 . . .	404	206 ·2
3·5 . . .	285	140 ·5	18 . . .	409	209 ·4
4 . . .	294	145 ·5	19 . . .	414	212 ·2
4·5 . . .	300	148 ·8	20 . . .	418	214 ·4
5 . . .	308	153 ·1	21 . . .	423	217 ·2
5·5 . . .	314	156 ·2	22 . . .	427	219 ·4
6 . . .	320	160	23 . . .	431	221 ·2
6·5 . . .	326	163 ·1	24 . . .	436	224 ·4
7 . . .	332	166 ·2	25 . . .	439	226 ·1
7·5 . . .	337	169 ·4	30 . . .	457	236 ·1
8 . . .	342	172 ·2	35 . . .	473	245 ·1
9 . . .	351	177 ·2	40 . . .	487	252 ·7
10 . . .	359	181 ·2	45 . . .	491	255
11 . . .	367	186 ·1	50 . . .	511	266 ·1
12 . . .	374	190			

It is a very remarkable fact, that the latent heat of steam diminishes as the temperature of the steam rises, so that equal weights of steam thrown into cold water exhibit nearly the same heating power, although the actual temperature of the one portion may be 212° (100°C), and that of the other 350° (176°·2C) or 400° (204°·4C). This also appears true with temperatures below the boiling-point; so that, it seems, to evaporate a given quantity of water the same *absolute* amount of heat is required, whether it be performed slowly at the temperature of the air in a manner presently to be noticed, or whether it be boiled off under the pressure of twenty atmospheres. It is for this reason that the process of distillation in vacuo at a temperature which the hand can bear, so advantageous in other respects, can effect no *direct* saving in fuel.*

The economical applications of steam are numerous and extremely valuable; they may be divided into two classes: those in which the heating power is employed, and those in which its elastic force is brought into use.

The value of steam as a source of heat depends upon the facility with which it may be conveyed to distant points, and upon the large

* The proposition in the text, of the sum of the latent and sensible heats of steam being a constant quantity, is known by the name of *Watt's law*, having been deduced by that illustrious man from experiments of his own. It has always agreed well with the rough practical results obtained by engineers, and has lately been confirmed to a great extent, although not completely, by a series of elaborate experiments by M. Regnault.


amount of latent heat it contains, which is disengaged in the act of condensation. An invariable temperature of 212° (100°C), or higher

Fig. 29.



kettle, surmounted by a double box or jacket, into which the substance to be dried is put, and loosely covered by a card. The apparatus

Fig. 30.



is placed over a lamp, and may be left without attention for many hours. A little hole in the side of the jacket gives vent to the excess of steam. It is merely a small

The principle of the steam-engine may be described in a few words: its mechanical details do not belong to the design of the present volume. The machine consists essentially of a cylinder of metal *a*, in which works a closely-fitting solid piston, the rod of which passes, air-tight, through a stuffing-box at the top of the cylinder, and is connected with the machinery to be put in motion, directly, or by the intervention of an oscillating beam. A pipe communicates with the interior of the cylinder, and also with a vessel surrounded with cold water, called the condenser, marked *b* in the sketch, and into which a jet of cold water can at pleasure be introduced. A sliding-valve arrangement, shown at *c*, serves to open a communication between the boiler and the cylinder, and the cylinder and the condenser, in such a manner that while the steam is

allowed to press with all its force upon one side of the piston, the other, open to the condenser, is necessarily vacuous. The valve is shifted by the engine itself at the proper moment, so that the piston is alternately driven by the steam up and down against a vacuum. A large air-pump, not shown in the engraving, is connected with the condenser, and serves to remove any air that may enter the cylinder, and also the water produced by condensation, together with that which may have been injected.

Such is the vacuum or condensing steam-engine. In what is called the high-pressure engine the condenser and air-pump are suppressed, and the steam is allowed to escape at once from the cylinder into the atmosphere. It is obvious that in this arrangement the steam has to overcome the whole pressure of the air, and a much greater elastic force is required to produce the same effect; but this is to a very great extent compensated by the absence of the air-pump and the increased simplicity of the whole machine. Large engines, both on shore and in steam-ships, are usually constructed on the condensing principle, the pressure seldom exceeding six or seven pounds per square inch above that of the atmosphere; for small engines the high-pressure plan is, perhaps, preferable. Locomotive engines are of this kind.


A peculiar modification of the steam-engine, employed in Cornwall for draining the deep mines of that country, is now getting into use elsewhere for other purposes. In this machine economy of fuel is carried to a most extraordinary extent, engines having been known to perform the *duty* of raising more than 100,000,000 lb. of water one foot high by the consumption of a single bushel of coals. The engines are single-acting, the down-stroke, which is made against a vacuum, being the effective one, and employed to lift the enormous weight of the pump-rods in the shaft of the mine. When the piston reaches the bottom, the communication both with the boiler and the condenser is cut off, while an *equilibrium-valve* is opened connecting the upper and lower extremities of the cylinder, whereupon the weight of the pump-rods draws the piston to the top and makes the up-stroke. The engine is worked *expansively*, as it is termed, steam of high tension being employed, which is cut off at one-eighth or even one-tenth of the stroke.

The process of distillation, which may now be noticed, is very simple: its object is either to separate substances which rise in vapour at different temperatures, or to part a volatile liquid from a substance incapable of volatilization. The same process applied to bodies which pass directly from the solid to the gaseous condition, and the reverse, is called *sublimation*. Every distillatory apparatus consists essentially of a boiler, in which the vapour is raised, and of a condenser, in which it returns to the liquid or solid condition. In the still employed for manufacturing purposes, the latter is usually a spiral metal tube immersed in a tub of water. The common retort and receiver constitute the simplest and most generally useful arrangement for distillation on

Fig. 31.

the small scale; the retort is heated by a lamp or a charcoal fire, and the receiver is kept cool, if necessary, by a wet cloth, or it may be surrounded with ice. (Fig. 31).

The condenser of Professor Liebig is a very valuable instrument in the laboratory; it consists of a glass tube tapering from end to end, fixed by perforated corks in the centre of a metal pipe, provided with tubes so arranged that a current of cold water may circulate through the apparatus. By putting a few pieces of ice into the little cistern, the temperature of this water may be kept at 32° (0°C), and extremely volatile liquids condensed.

Fig. 32.

Liquids evaporate at temperatures below their boiling-points; in this case the evaporation takes place solely from the surface. Water, or alcohol, exposed in an open vessel at the temperature of the air, gradually dries up and disappears; the more rapidly, the warmer and drier the air above it.

This fact was formerly explained by supposing that air and gases in general had the power of dissolving and holding in solution certain quantities of liquids, and that this power increased with the temperature: such an idea is incorrect.

If a barometer-tube be carefully filled with mercury and inverted in the usual manner, and then a few drops of water passed up the tube into the vacuum above, a very remarkable effect will be observed;—the mercury will be depressed to a small extent, and this depression will increase with increase of temperature. Now, as the space above the mercury is void of air, and the weight of the few drops of water quite inadequate to account for this depression, it must of necessity be imputed to the vapour which instantaneously rises from the water into the vacuum; and that this effect is really due to the elasticity or tension of the aqueous vapour, is easily proved by exposing the barometer to a heat of 212° (100°C), when the depression of the mercury will be complete, and it will stand at the same level within and without the tube; indicating that at that temperature the elasticity of the vapour is equal to that of the atmosphere—a fact which the phenomenon of ebullition has already shown.


By placing over the barometer a wide open tube dipping into the mercury below, and then filling this tube with water at different temperatures, the tension of the aqueous vapour for each degree of the thermometer may be accurately determined by its depressing effect upon the mercurial column; the same power which forces the latter *down* one inch against the pressure of the atmosphere, would of course *elevate* a column of mercury to the same height against a vacuum, and in this way the tension may be very conveniently expressed. The following table was drawn up by Dr. Dalton, to whom we owe the method of investigation:—



Temperature.			Temperature.		
F.	C.	of mercury.	F.	C.	of mercury.
32°	0°	0.200	80°	26.6	1.000
40	4.4	0.263	90	32.2	1.360
50	10	0.375	100	37.7	1.860
60	15.5	0.524	110	43.3	2.530
70	21.1	0.721	120	48.8	3.330

Temperature. F.		C.	Tension in inches of mercury.	Temperature. F.		C.	Tension in inches of mercury.
130°	.	54·4	· 4·34	180°	.	82·2	· 15·15
140	.	60	· 5·74	190	.	87·7	· 19·00
150	.	65·5	· 7·42	200	.	93·3	· 23·64
160	.	71·1	· 9·46	212	.	100	· 30·00
170	.	76·6	· 12·13				

Fig. 34.



Other liquids tried in this manner are found to emit vapours of greater or less tension, for the same temperature according to their different degrees of volatility: thus, a little ether introduced into the tube depresses the mercury 10 inches or more at the ordinary temperature of the air; oil of vitriol, on the other hand, does not emit any sensible quantity of vapour until a much greater heat is applied; and that given off by mercury itself in warm summer weather, although it may by very delicate means be detected, is far too little to exercise any effect upon the barometer. In the case of water, the evaporation is quite distinct and perceptible at the lowest temperatures, when frozen to solid ice in the barometer-tube; snow on the ground, or on a house-top, may often be noticed to vanish, from the same cause, day by day in the depth of winter, when melting is impossible.

There exists for each vapour a state of density which it cannot pass without losing its gaseous condition, and becoming liquid; this point is called the condition of maximum density. When a volatile liquid is introduced in sufficient quantity into a vacuum, this condition is always reached, and then evaporation ceases. Any attempt to increase the density of this vapour by compressing it into a smaller space will be attended by the liquefaction of a portion, the density of the remainder being unchanged. If a little ether be introduced into a barometer, and the latter slowly sunk into a very deep cistern of mercury, it will be found that the height of the column of mercury in the tube above that in the cistern remains unaltered until the upper extremity of the barometer approaches the surface of the metal in the reservoir. It will be observed also, that, as the tube sinks, the little stratum of liquid ether increases in thickness, but no increase of elastic force occurs in the vapour above it, and, consequently, no increase of density;

for tension and density are always, under ordinary circumstances at least, directly proportionate to each other in the same vapour.

The point of maximum density of vapours is dependent upon the temperature; it increases rapidly as the temperature rises. This is well shown in the case of water. Thus, taking the specific gravity of atmospheric air at 212° (100°C) = 1000, that of aqueous vapour in its greatest possible state of compression for the temperature will be as follows:—

Temperature.		Specific gravity.	Weight of 100 cubic inches
F.	C.		
32°	0°	5.690	0.136 grains.
50	10	10.293	0.247
60	15.5	14.108	0.338
100	37.7	46.500	1.113
150	65.5	170.293	4.076
212	100	625.000	14.962

The last number was experimentally found by M. Gay-Lussac; the others are calculated from that by the aid of Dr. Dalton's table of tensions, when the assumption has been made, which is however only approximatively true, that steam obeys the law of Mariotte to the limit of its greatest density, and that when it is cooled it contracts like the permanent gases.

Thus, there are two distinct methods by which a vapour may be reduced to the liquid form; *pressure*, by causing increase of density until the point of maximum density for the particular temperature is reached; and *cold*, by which the point of maximum density is itself lowered. The most powerful effects are of course produced when both are conjoined.

For example, if 100 cubic inches of perfectly transparent and gaseous vapour of water at 100° ($37^{\circ}\cdot 7\text{C}$), in the state above described, had its temperature reduced to 50° (10°C), not less than 0.89 * grain of fluid water would necessarily separate, or very nearly eight-tenths of the whole.

Evaporation into a space filled with air or gas follows the same law as evaporation into a vacuum: as much vapour rises, and the condition of maximum density is assumed in the same manner, as if the space were perfectly empty; the sole difference lies in the length of time required. When a liquid evaporates into a vacuum, the point of greatest density is attained at once, while in the other case some time elapses before this happens; the particles of air appear to oppose a sort of mechanical resistance to the rise of the vapour. The ultimate effect is, however, precisely the same.

When to a quantity of perfectly dry gas confined in a vessel closed

* 100 cubic inches aqueous vapours at 100° ($37^{\circ}\cdot 7\text{C}$), weighing 1.113 grain, would at 50° (10°C), become reduced to 91.07 cubic inches, weighing 0.225 grain.

by mercury, a little water is added, the latter immediately begins to evaporate, and after some time as much vapour will be found to have risen from it as if no gas had been present, the quantity depending entirely on the temperature to which the whole is subjected. The tension of this vapour will add itself to that of the gas, and produce an expansion of volume, which will be indicated by an alteration of level in the mercury.

Vapour of water exists in the atmosphere at all times, and in all situations, and there plays a most important part in the economy of nature. The proportion of aqueous vapour present in the air is subject to great variation, and it often becomes exceedingly important to determine its quantity. This is easily done by the aid of the foregoing principles.


If the aqueous vapour be in its condition of greatest possible density for the temperature, or, as it is frequently, but most incorrectly expressed, the air be saturated with vapour of water, the slightest reduction of temperature will cause the deposition of a portion in the liquid form. If, on the contrary, as is almost always in reality the case, the vapour of water be *below* its state of maximum density, that is, in an expanded condition, it is clear that a considerable fall of temperature may occur before liquefaction commences. The degree at which this takes place is called the dew-point, and it is determined with great facility by a very simple method. A little cup of thin tin-plate or silver, well polished, is filled with water at the temperature of the air, and a delicate thermometer inserted. The water is then cooled by dropping in fragments of ice, or dissolving in it powdered sal-ammoniac, until a deposition of moisture begins to make its appearance on the outside, dimming the bright metallic surface. The temperature of the dew-point is then read off upon the thermometer, and compared with that of the air.

Suppose, by way of example, that the latter were 70° ($21^{\circ}\cdot 1\text{C}$), and the dew-point 50° (10°C); the elasticity of the watery vapour present would correspond to a maximum density proper to 50° (10°C), and would support a column of mercury 0·375 inch high. If the barometer on the spot stood at 30 inches, therefore, 29·625 inches would be supported by the pressure of the dry air, and the remaining 0·375 inch by the vapour. Now a cubic foot of such a mixture must be looked upon as made up of a cubic foot of dry air, and a cubic foot of watery vapour, occupying the same space, and having tensions indicated by the numbers just mentioned. A cubic foot, or 1728 cubic inches of vapour at 70° ($21^{\circ}\cdot 1\text{C}$), would become reduced by contraction, according to the usual law, to 1662·8 cubic inches at 50° (10°C); this vapour would be at its maximum density, having the specific gravity pointed out in the table; hence 1662·8 cubic inches would weigh 4·11 grains. The weight of the aqueous vapour contained in a cubic foot of air will thus be ascertained. In this country the difference between the temperature of the air and the dew-point seldom reaches 30° ($16^{\circ}\cdot 6\text{C}$); but

in the Deccan, with a temperature of 90° ($32^{\circ}\cdot 2\text{C}$), the dew-point has been seen as low as 29° ($-1^{\circ}\cdot 6\text{C}$), making the degree of dryness 61° ($33^{\circ}\cdot 8\text{C}$).*

Another method of finding the proportion of moisture present in the air is to observe the rapidity with which evaporation takes place, and which is always in some relation to the degree of dryness. The bulb of a thermometer is covered with muslin, and kept wet with water; evaporation produces cold, as will presently be seen, and accordingly the thermometer soon sinks below the actual temperature of the air. When it comes to rest, the degree is noticed, and from a comparison of the two temperatures an approximation to the dew-point can be obtained by the aid of a mathematical formula contrived for the purpose. This is called the wet-bulb hygrometer; it is often made in the manner shown in the margin, where one thermometer serves to indicate the temperature of the air, and the other to show the rate of evaporation, being kept wet by the thread in connexion with the little water reservoir.

Fig. 35.



The perfect resemblance in every respect which vapours bear to permanent gases, led, very naturally, to the idea that the latter might, by the application of suitable means, be made to assume the liquid condition, and this surmise was, in the hands of Mr. Faraday, to a great extent verified. Out of the small number of such substances tried, not less than eight gave way; and it is quite fair to infer, that, had means of sufficient power been at hand, the rest would have shared the same fate, and proved to be nothing more than the vapours of volatile liquids in a state very far removed from that of their maximum density. The subjoined table represents the results of Mr. Faraday's first investigations, with the pressure in atmospheres, and the temperature at which the condensation took place.†

	Atmospheres.	Temperature.	
		F.	C.
Sulphurous acid	2	45°	7°·2
Sulphuretted hydrogen	17	50	10
Carbonic Acid	36	32	0
Chlorine	4	60	15·5
Nitrous oxide	50	45	7·2
Cyanogen	3·6	45	7·2
Ammonia	6·5	50	10
Hydrochloric acid	40	50	10

* Mr. Daniell, Introduction to Chemical Philosophy, p. 154.

† Phil. Trans. for 1823, p. 189.

The method of proceeding was very simple: the materials were sealed up in a strong narrow tube, together with a little pressure-gauge, consisting of a slender tube closed at one end, and having within it, near the open extremity, a globule of mercury. The gas

Fig. 36.



being disengaged by the application of heat, or otherwise, accumulated in the tube, and by its own pressure brought about condensation. The force required for this purpose was judged of by the diminution of volume of the air in the gauge.

Mr. Faraday has since resumed, with the happiest results, the subject of the liquefaction of the permanent gases. By using narrow green glass tubes of great strength, powerfully-condensing syringes, and an extremely low temperature, produced by means to be presently described, olefiant gas, hydriodic and hydrobromic acids, phosphoretted hydrogen, and the gaseous fluorides of silicon and boron, were successively liquefied. Oxygen, hydrogen, nitrogen, nitric oxide, carbonic oxide, and coal-gas, refused to liquefy at the temperature of -166° (-74° 4C) while subjected to pressures varying in the different cases from 27 to 58 atmospheres.*


Sir Isambard Brunel, and, more recently, M. Thilorier, of Paris, succeeded in obtaining liquid carbonic acid in great abundance. The apparatus of M. Thilorier consists of a pair of extremely strong metallic vessels, one of which is destined to serve the purpose of a retort, and the other that of a receiver. They are made either of thick cast-iron or gun-metal, or, still better, of the best and heaviest boiler-plate, and are furnished with stop-cocks of a peculiar kind, the workmanship of which must be excellent. The generating vessel or retort has a pair of trunnions upon which it swings in an iron frame. The joints are secured by collars of lead, and every precaution taken to prevent leakage under the enormous pressure the vessel has to bear. The receiver resembles the retort in every respect; it has a similar stop-cock, and is connected with the retort by a strong copper tube and a pair of union screw-joints; a tube passes from the stop-cock downwards, and terminates near the bottom of the vessel.

The operation is thus conducted: $2\frac{3}{4}$ lb. of bicarbonate of soda, and $6\frac{1}{4}$ lb. of water at 100° (37° 7C), are introduced into the generator;

* Phil. Trans. for 1845, p. 155. M. Natterer in Vienna has since succeeded, by means of a condensing pump which can be worked without any risk, in directly condensing nitrous-oxide gas, without the use of strong frigorific mixtures.

oil of vitriol to the amount of $1\frac{1}{2}$ lb. is poured into a copper cylindrical vessel, which is lowered down into the mixture, and set upright; the stop-cock is then screwed into its place, and forced home by a spanner and mallet. The machine is next tilted up on its trunnions, that the acid may run out of the cylinder and mix with the other contents of the generator; and this mixture is favoured by swinging the whole backwards and forwards for a few minutes, after which it may be suffered to remain a little time at rest.

Fig. 37.




The receiver, surrounded with ice, is next connected with the generator, and both cocks opened; the liquefied carbonic acid distils over into the colder vessel, and there again in part condenses. The cocks are now closed, the vessels disconnected, the cock of the generator opened to allow the contained gas to escape; and, lastly, when the issue of gas *has quite ceased*, the stop-cock itself unscrewed, and the sulphate of soda turned out. This operation must be repeated five or six times before any very considerable quantity of liquefied acid will have accumulated in the receiver. When the receiver thus charged has its stop-cock opened, a stream of the liquid is forcibly driven up the tube by the elasticity of the gas contained in the upper part of the vessel.

It will be quite proper to point out to the experimenter the great personal danger he incurs in using this apparatus, unless the utmost care be taken in its management. A dreadful accident has already occurred in Paris by the bursting of one of the iron vessels.

The cold produced by evaporation has been already adverted to: it is simply an effect arising from the conversion of sensible heat into latent by the rising vapour, and it may be illustrated in a variety of ways. A little ether dropped on the hand thus produces the sensation of great cold; and water contained in a thin glass tube, surrounded by a bit of rag, is speedily frozen when the rag is kept wetted with ether.

Fig. 38.



When a little water is put into a watch-glass, supported by a triangle of wire over a shallow glass dish of sulphuric acid placed on the plate of a good air-pump, the whole covered with a low receiver, and the air withdrawn as perfectly as possible, the water is in a few

minutes converted into a solid mass of ice, and the watch-glass very frequently broken by the expansion of the lower portion of water in the act of freezing, a thick crust first forming on the surface. The absence of the impediment of the air, and the rapid absorption of watery vapour by the oil of vitriol, induce such quick evaporation that the water has its temperature almost immediately reduced to the freezing-point.

The same fact is shown by a beautiful instrument contrived by Dr. Wollaston, called a *cryophorus*, or frost-carrier. It is made of glass, of the figure represented below, and contains a small quantity of water, the rest of the space being vacuous. When all the water is turned into the bulb, and the empty extremity plunged into a mixture of ice and salt, the solidification of the vapour gives rise to such a quick evaporation from the surface of the water, that the latter freezes.

Fig. 39.




All means of producing artificial cold yield to that derived from the evaporation of the liquefied carbonic acid, just mentioned. When a jet of that liquid is allowed to issue into the air from a narrow aperture, such an intense degree of cold is produced by the evaporation of a part, that the remainder freezes to a solid, and falls in a shower of snow. By suffering this jet of liquid to flow into a metal box provided for the purpose, shown in the drawing of the apparatus, a large

quantity of the solid acid may be obtained ; it closely resembles snow in appearance, and when held in the hand occasions a painful sensation of cold, while it gradually disappears. Mixed with a little ether, and poured upon a mass of mercury, the latter is almost instantly frozen, and in this way pounds of the solidified metal may be obtained. The addition of the ether facilitates the contact of the carbonic acid with the mercury.

The temperature of a mixture of solid carbonic acid and ether in the air, measured by a spirit-thermometer, was found to be -106° ($-76^{\circ}6\text{C}$) ; when the same mixture was placed beneath the receiver of an air-pump, and exhaustion rapidly made, the temperature sank to -166° (-110°C). This was the method of obtaining extreme cold employed by Mr. Faraday in his last experiments on the liquefaction of gases. Under such circumstances the liquefied hydriodic, hydrobromic, and sulphurous acid gases, carbonic acid, nitrous oxide, sulphuretted hydrogen, cyanogen, and ammonia, froze to colourless transparent *solids*, and alcohol became thick and oily.

The principle of the cryophorus has been very happily applied by Mr. Daniell to the construction of a dew-point hygrometer ; fig. 40. It consists of a bent glass tube terminated by two bulbs, one of which is half filled with ether, the whole being vacuous as respects atmospheric air. A delicate thermometer is contained in the longer limb, the bulb of which dips into the ether ; a second thermometer on the stand serves to show the actual temperature of the air. The upper bulb is covered with a bit of muslin. When an observation is to be made, the liquid is all transferred to the lower bulb, and ether dropped upon the upper one, until by the cooling effects of evaporation a distillation of the contained liquid takes place from one part of the apparatus to the other, by which such a reduction of temperature of the ether is brought about, that dew is deposited on the outside of the bulb, which is made of black glass in order that it may be more easily seen. The difference of temperature indicated by the two thermometers is then read off.

Fig. 40.



CAPACITY FOR HEAT ; SPECIFIC HEAT.

It is a very remarkable fact that equal weights of different substances having the same temperature require different amounts of heat to raise them to a given degree of temperature. If 1 lb. of water, at 100° ($37^{\circ}7\text{C}$), be mixed with 1 lb. at 40° ($4^{\circ}4\text{C}$), as is well known, a mean temperature of $\frac{100+40}{2} = 70^{\circ}$ ($21^{\circ}1\text{C}$) is obtained. In the same way the mean temperature is found when

warm and cold oil, or warm and cold mercury, &c., are mixed together. But if 1 lb. of water at 100° be mixed with 1 lb. of olive-oil at 40° , or with 1 lb. of mercury at 40° , instead of the mean temperature of 70° , in the one case 80° ($26^{\circ}\cdot6\text{C}$), in the other case 98° ($36^{\circ}\cdot7\text{C}$), will be obtained: 20 degrees of heat which the water (by cooling from 100° to 80°) gave to the same weight of oil, were sufficient to raise the oil 40° , that is from 40° to 80° , and 2° which the water lost by cooling from 100° to 98° , sufficed to heat an equal quantity of mercury 58° , namely, from 40° to 98° .

It is evident from these experiments, that the quantities of heat which equal weights of water, olive oil, and mercury, require to raise their temperature to the same height, are unequal, and that they are in the proportion of the numbers $1 : \frac{20}{40} : \frac{2}{58}$.

That quantity of heat which is necessary to raise the unit of weight of any substance one degree is called the *capacity for heat*; and those numbers which express the relation of the different capacities for heat of different bodies are called the *specific heat*. Thus the specific heat of oil is $\frac{20}{40} = \frac{1}{2}$, when that of water = 1. The specific heat of mercury is about $\frac{2}{58} = \frac{1}{29}$ that of water. There are three distinct methods by which the specific heat of various substances may be estimated. The first of these is by observing the quantity of ice melted by a given weight of the substance heated to a particular temperature; the second is by noting the time which the heated body requires to cool down through a certain number of degrees; and the third is the method of mixture, on the principle illustrated: this latter method is preferred as the most accurate.

The determination of the specific heat of different substances has occupied the attention of many experimenters; among these MM. Dulong and Petit, and recently M. Regnault, deserve especial mention.

From the observations of these and other physicists, it follows that each body has its peculiar capacity for heat, and that it increases with the increase of temperature. If, for example, the heat which the unit of water loses by cooling from 50° (10°C), to 32° (0°C), be marked at 18, then the loss by cooling from 122° (50°C), to 32° will be not 90, corresponding to the difference of temperature, but $90\cdot16$. By cooling from 212° (100°C) to 32° it is $180\cdot90$, and rises to $355\cdot76$, when the water is heated under great pressure to 392° (200°C), and afterwards cooled to 32° . Similar and even more striking differences have been found with other substances. It has also been proved that the capacity for heat of any substance is greater in its liquid than in its solid state. For example, the specific heat of ice is $0\cdot504$, that is not more than half as great as that of liquid water.

It is remarkable that the capacity for heat of water is greater than that of most other bodies. The capacity for heat of the solid parts of the crust of the globe is on an average $\frac{1}{4}$, and that of the atmosphere is a little more than $\frac{1}{4}$ that of water.

If the specific heat of any body within certain degrees of temperature be accurately known, then from the quantity of heat which this

body gives out, when quickly dipped into cold water, the temperature to which the body was heated may be determined. Pouillet has founded on this fact, a method of measuring high temperatures, and for this purpose, with the help of the air-thermometer, he has determined the specific heat of platinum up to 2912° (1600°C).

The determination of the specific heat of gases is attended with peculiar difficulties on account of the comparatively large volume of small weights of gases. Satisfactory results have, however, been obtained by the method of mixing for the following gases.

SPECIFIC HEAT AT 30 INCHES PRESSURE.

Of equal volumes.				Of equal weights.	
				Air = 1	Water = 1
Atmospheric air	. 1	.	.	1	. 0.2669
Oxygen	. 1	.	.	0.9069	. 0.2421
Hydrogen	. 1	.	.	14.5349	. 3.8793
Nitrogen	. 1	.	.	1.0318	. 0.2754
Carbonic oxide	. 1	.	.	1.0267	. 0.2740
Protoxide of nitrogen	1.227	.	.	0.8035	. 0.2145
Carbonic acid	. 1.249	.	.	0.8195	. 0.2187
Olefiant gas	. 1.754	.	.	1.7891	. 0.4777
Aqueous vapour	. 1.960	.	.	3.1360	. 0.8370

For the comparison of the specific heat of atmospheric air with that of water we are indebted to Count Rumford; for the comparison of the specific heat of the various gases to Delaroche and Berard, Dulong and Regnault.*

* Regnault's recent researches confirm the statement that equal volumes at the same pressure of the elementary gases, oxygen, nitrogen, and hydrogen, possess the same specific heat. The numbers found for chlorine and bromine, however, show that the law does not hold good for all the elementary gases. The following are Regnault's results:—

SPECIFIC HEAT AT 30 INCHES PRESSURE.

For equal volumes.				For equal weights.	
				Water = 1	
Atmospheric air	.	.	. 0.2377	.	. 0.2377
Oxygen	.	.	. 0.2412	.	. 0.2182
Nitrogen	.	.	. 0.2370	.	. 0.2440
Hydrogen	.	.	. 0.2356	.	. 0.4046
Chlorine	.	.	. 0.2962	.	. 0.1214
Bromine vapour	.	.	. 0.2992	.	. 0.0552
Carbonic oxide	.	.	. 0.2399	.	. 0.2479
Carbonic acid	.	.	. 0.3308	.	. 0.2164
Protoxide of nitrogen	.	.	. 0.3413	.	. 0.2238
Binoxide of nitrogen	.	.	. 0.2406	.	. 0.2315
Olefiant gas	.	.	. 0.3277	.	. 0.5929
Marsh gas	.	.	. 0.3572	.	. 0.3634
Aqueous vapour	.	.	. 0.2950	.	. 0.4750
Sulphuretted hydrogen	.	.	. 0.2886	.	. 0.2423
Sulphurous acid	.	.	. 0.3489	.	. 0.1553
Bisulphide of carbon	.	.	. 0.4146	.	. 0.1575
Hydrochloric acid	.	.	. 0.2302	.	. 0.1845
Ammonia	.	.	. 0.2994	.	. 0.5080

Whenever a gas expands, heat becomes thereby latent. Hence the amount of heat required to raise a gas to a certain temperature increases the more we allow it to expand. Dulong has found that if the amount of heat required to raise the temperature of a volume of gas (observed at the melting-point of ice, and at a pressure of 30 inches) to a given height without its volume undergoing any change, be represented by 1, then if the gas be allowed to expand until the pressure is reduced again to 30 inches whilst the high temperature is kept up, the additional amount of heat which is required for this purpose is, for oxygen, hydrogen, or nitrogen 0.421; for carbonic acid 0.423; for binoxide of nitrogen 0.345; and for olefiant gas 0.240.

If there be no source of heat from which this additional quantity can be obtained, then the gas is cooled during expansion, a portion of the free heat becoming latent. On the other hand, if a gas be compressed, this latent heat becomes free, and causes an elevation of temperature, which, under favourable circumstances, may be raised to ignition; syringes by which tinder is kindled are constructed on this principle. In the upper regions of the atmosphere the cold is intense; snow covers the highest mountain-tops even within the tropics, and this is due to the increased capacity for heat of the expanded air.

MM. Dulong and Petit observed in the course of their investigation a most remarkable circumstance. If the specific heats of bodies be computed upon equal weights, numbers are obtained all different, and exhibiting no simple relations among themselves; but if, instead of equal weights, quantities be taken in the proportion of the chemical equivalents, an almost perfect coincidence in the numbers will be observed, showing that some exceedingly intimate connexion must exist between the relations of bodies to heat and their chemical nature; and when the circumstance is taken into view, that relations of even a still closer kind link together chemical and electrical phenomena, it is not too much to expect that ere long some law may be discovered far more general than any with which we are yet acquainted.

The following table is extracted from the memoirs of M. Regnault, with whose results most of the experiments of Dulong and Petit closely coincide.

Substances.	Specific heat of equal weights.	Specific heat of equivalent weights.
Water	1.00000	
Oil of Turpentine	0.42593	
Glass	0.19768	
Iron	0.11379	3.0928
Zinc	0.09555	3.0872
Copper	0.09515	3.0172
Lead	0.03140	3.2581
Tin	0.05623	3.3121
Nickel	0.10863	3.2176

Substances.	Specific heat of equal weights.	Specific heat of equivalent weights.
Cobalt	0·10696	3·1628
Platinum	0·03243	3·2054
Sulphur	0·20259	3·2657
Mercury. . . .	0·03332	3·7128
Silver	0·05701	6·1742
Arsenic	0·08140	6·1326
Antimony	0·05077	6·5615
Gold	0·03244	6·4623
Iodine	0·05412	6·8462
Bismuth. . . .	0·03084	2·1917

Of the numbers in the second column, the first ten approximate far too closely to each other to be the result of mere accidental coincidence; the five that follow are very nearly twice as great; and the last is one-third less.

Independently of experimental errors, there are many circumstances which tend to show, that, if all modifying causes could be compensated, or their effects allowed for, the law might be rigorously true.

The observations thus made upon elementary substances have been extended by M. Regnault to a long series of compounds, and the same curious law found, with the above limitations, to prevail throughout, save in a few isolated cases, of which an explanation can perhaps be given.

Except in the case of certain metallic alloys, where the specific heats were the mean of those of their constituent metals, no obvious relation can be traced between the specific heat of the compound body and of its components. The most general expression of the facts that can be given is the following:—

In bodies of similar chemical constitution, the specific heats are in an inverse ratio to the equivalent weights, or to a multiple or submultiple of the latter.—Simple as well as compound bodies will be comprehended in this law.*

SOURCES OF HEAT.

The first and greatest source of heat, compared with which all others are totally insignificant, is the sun. The luminous rays are accompanied by rays of a heating nature, which, striking against the surface of the earth, elevate its temperature: this heat is communicated to the air by convection, as already described, air and gases in general not being sensibly heated by the passage of the rays.

A second source of heat is supposed to exist in the interior of the earth. It has been observed, that in sinking mine-shafts, boring for water, &c., the temperature rises in descending at the rate, it is said,

* Ann. Chim. et Phys. lxxiii. 5; and the same, 3rd series, i. 129.

of about 1° ($\frac{5}{9}^{\circ}\text{C}$) for every 45 feet, or 117° (65°C) per mile. On the supposition that the rise continues at the same rate, at the depth of less than two miles the earth would have the temperature of boiling water; at nine miles it would be red hot; and at 30 or 40 miles depth, all known substances would be in a state of fusion.*

According to this idea, the earth must be looked upon as an intensely-heated, fluid spheroid, covered with a crust of solid badly-conducting matter, cooled by radiation into space, and bearing somewhat the same proportion in thickness to the ignited liquid within, that the shell of an egg does to its fluid contents. Without venturing to offer any opinion on this theory, it may be sufficient to observe that it is not positively at variance with any known fact; that the figure of the earth is really such as would be assumed by a fluid mass; and, lastly, that it offers the best explanation we have of the phenomena of hot springs and volcanic eruptions, and agrees with the chemical nature of their products.

The smaller, and what may be called secondary, sources of heat, are very numerous: they may be divided, for the present, into two groups, mechanical motion and chemical combination. To the first must be referred elevation of temperature by friction and blows; and to the second, the effects of combustion and animal respiration. With regard to the heat developed by friction, it appears to be indefinite in amount, and principally dependent upon the nature of the rubbing surfaces. An experiment of Count Rumford is on record, in which the heat developed by the boring of a brass cannon was sufficient to bring to the boiling-point two and a half gallons of water, while the dust or shavings of metal, cut by the borer, weighed a few ounces only. Sir H. Davy melted two pieces of ice by rubbing them together in vacuo at 32° (0°C); and uncivilized men, in various parts of the world, have long been known to obtain fire by rubbing together two pieces of dry wood. The origin of the heat in these cases is by no means intelligible.

Malleable metals, as iron and copper, which become heated by hammering or powerful pressure, are found thereby to have their density sensibly increased and their capacity for heat diminished; the rise of temperature is thus in some measure explained. A soft iron nail may be made red-hot by a few dexterous blows on an anvil; but the experiment cannot be repeated until the metal has been *annealed*, and in that manner restored to its original physical state.

The disengagement of heat in the act of combination is a phenomenon of the utmost generality. The quantity of heat given out in each

* The new Artesian well at Grenelle, near Paris, has a depth of 1794.5 English feet: it is bored through the chalk basin to the sand beneath; the work occupied seven years and two months. The temperature of the water, which is exceedingly abundant, is 82° ($27^{\circ}\cdot 7\text{C}$); the mean temperature of Paris is 51° ($10^{\circ}\cdot 5\text{C}$); the difference is 31° ($17^{\circ}\cdot 2\text{C}$), which gives a rate of about 1° ($\frac{5}{9}^{\circ}\text{C}$) for 58 feet.

particular ease is in all probability fixed and definite ; its intensity is dependent upon the time over which the action is extended. Science has already been enriched by many admirable, although yet incomplete, researches on this important but most difficult subject.

It is not improbable that many of the phenomena of heat, classed at present under different heads, may hereafter be referred to one common cause, namely, alterations in the capacity for heat of the same body under different physical conditions. For example, the definite absorption and evolution of sensible heat attending change of state may be simply due to the increased capacity for heat, to a fixed and definite amount, of the liquid over the solid, and the vapour over the liquid. The experimental proof of the facts is yet generally wanting : in the very important case of water, however, the decidedly inferior capacity for heat of ice compared with that of liquid water seems fully proved from experiments on record.

The heat of combination might, perhaps, in like manner, be traced to condensation of volume, and the diminution of capacity for heat which almost invariably attends condensation. The proof of the proposition in numerous cases would be within the reach of comparatively easy experimental inquiry.

LIGHT.

THE subject of light is so little connected with elementary chemistry, that a very slight notice of some of the most important points will suffice.


Two views have been entertained respecting the nature of light. Sir Isaac Newton imagined that luminous bodies emit, or shoot out, infinitely small particles in straight lines, which, by penetrating the transparent part of the eye and falling upon the nervous tissue, produced vision. Other philosophers drew a parallel between the properties of light and those of sound, and considered that, as sound is certainly the effect of undulations, or little waves, propagated through elastic bodies in all directions, so light might be nothing more than the consequence of similar undulations transmitted with inconceivable velocity through a highly-elastic medium, of excessive tenuity, filling all space, and occupying the intervals between the particles of material substances, to which they gave the name of *ether*. The wave-hypothesis of light is at present more in favour, as it serves to explain certain singular phenomena, discovered since the time of Newton, with greater facility than the other.

A ray of light emitted from a luminous body proceeds in a straight line, and with extreme velocity. Certain astronomical observations afford the means of approximating to a knowledge of this velocity. The satellites of Jupiter revolve about the planet in the same manner as the moon about the earth, and the time required by each satellite for the purpose is exactly known from its periodical entry into or exit from the shadow of the planet. The time required by one is only 42 hours. Römer, the astronomer, at Copenhagen, found that this period appeared to be longer when the earth, in its passage round the sun, moved from the planet Jupiter; and, on the contrary, he observed that the periodic time appeared to be shorter when the earth moved in the direction towards Jupiter. The difference, though very small for a single revolution of the satellite, by the addition of many, so increases, during the passage of the earth, from its nearest to its greatest distance from Jupiter, that is, in about half a year, that it amounts to 16 minutes and 16 seconds. Römer concluded from this, that the light of the sun, reflected from the satellite, required that time to pass through a distance equal to the diameter of the orbit of the earth; and since this space is little short of 200 millions of miles, the velocity of light cannot be less than 200,000 miles in a second of time. It will be seen hereafter that this rapidity of transmission is rivalled by that of the electrical agent.

When a ray of light falls on a plane surface it may be disposed of in three ways; more or less is absorbed and so disappears, the rest is either wholly or partly reflected, and partly transmitted. Those bodies

which absorb nearly all the rays of light falling on them appear black. Those which, like glass or water, allow the greater part to pass through are called transparent. The reflected light may be reflected diffusely or regularly. Those bodies which reflect regularly the greater part of the light possess lustre like polished bodies; the perception of bodies depends on the diffused reflected light.


The law of regular reflection is extremely simple. If a line be drawn perpendicular to the surface upon which the ray falls, and the angle contained between the ray and the perpendicular measured, it will be found that the ray, after reflection, takes such a course as to make with the perpendicular an equal angle on the opposite side of the latter. A ray of light, R , falling at the point P , will be reflected in the direction PR' , making the angle $R'PP'$ equal to the angle RPP' ; or a ray from the point r falling upon the same spot will be reflected to r' in virtue of the same law. Farther, it is to be observed, that the incident and reflected rays are always contained in the same vertical plane.



The same rule holds good if the mirror be curved, as a portion of a sphere, the curve being considered as made up of a multitude of little planes. Parallel rays become permanently altered in direction when reflected from curved surfaces, becoming divergent or convergent according to the kind of curvature.

It has just been stated that light passes in straight lines; but this is only true so long as the medium through which it travels preserves the same density and the same chemical nature; when this ceases to be the case, the ray of light is bent from its course into a new one, or, in optical language, is said to be *refracted*.


Let R be a ray of light falling upon a plate of some transparent substance with parallel sides, such as a piece of thick plate glass; and A its point of contact with the upper surface. The ray, instead of holding a straight course and passing into the glass in the direction AB , will be bent downwards to C ; and, on leaving the glass, and issuing into the air on the other side, it will again be bent, but in the opposite direction, so as to make it parallel to the continuation of its former track. The general



law is thus expressed:—When the ray passes from a rare to a denser medium, it is usually refracted *towards* a line perpendicular to the surface of the latter; and conversely, when it leaves a dense medium for a rarer one, it is refracted *from* a line perpendicular to the surface of the denser substance: in the former case the angle of incidence is said to be greater than that of refraction; in the latter, it is said to be less.

The amount of refraction, for the same medium, varies with the obliquity with which the ray strikes the surface. When perpendicular to the latter, it passes without change of direction at all; and in other positions, the refraction increases with the obliquity.

Fig. 43.



Let R represent a ray of light falling upon the surface of a mass of plate glass at the point A. From this point let a perpendicular be raised and continued into the new medium, and around the same point, as a centre, let a circle be drawn. According to the law just stated, the refraction must be towards the perpendicular; in the direction AR' for example. Let the line $a-a'$, at right angles to the perpendicular, be drawn, and their length compared by means of a scale of equal parts, and noted;

their length will be in the case supposed in the proportion of 3 to 2. These lines are termed the sines of the angles of incidence and refraction respectively.

Now let another ray be taken, such as r ; it is refracted in the same manner to r' , the bending being greater from the increased obliquity of the ray; but what is very remarkable, if the sines of the two new angles of incidence and refraction be again compared, they will still be found to bear to each other the proportion of 3 to 2. The fact is expressed by saying, that the *ratio of the sines of the angles of incidence and refraction is constant for the same medium.*

The plane of refraction coincides moreover with that of incidence.


Different bodies possess different refractive powers; generally speaking, the densest substances refract most. Combustible bodies have been noticed to possess greater refractive power than their density would indicate, and from this observation Sir I. Newton predicted the combustible nature of the diamond long before anything was known respecting its chemical nature.

The method adopted for describing the comparative refractive powers of different bodies is to state the ratio borne by the sine of the angle of refraction to that of incidence, making the former unity: this is called the *index of refraction* for the substance. Thus, in the case of glass the index of refraction will be 1.5. When this is once known

for any particular transparent body, the effect of the latter upon a ray of light entering it, in any position, can be calculated by the aid of the law of sines.


Substances.	Index of refraction.	Substances.	Index of refraction.
Tabasheer*	1.10	Garnet	1.80
Ice	1.30	Glass, with much oxide	
Water	1.34	of lead	1.90
Fluor spar	1.40	Zircon	2.00
Plate glass	1.50	Phosphorus . . .	2.20
Rock crystal . . .	1.60	Diamond	2.50
Chrysolite	1.69	Chromate of lead .	3.00
Bisulphide of carbon .	1.70		

When a luminous ray enters a mass of substance differing in refractive power from the air, and whose surfaces are not parallel, it becomes permanently deflected from its course and altered in its direction. It is upon this principle that the properties of prisms and lenses depend. To take an example.—Let the sketch represent a triangular prism of glass, upon the side of which the ray of light R may be supposed to fall. This ray will of course be refracted in entering the glass towards a line perpendicular to the first surface, and again, from a line perpendicular to the second surface on emerging into the air. The result will be a total change in the direction of the ray.



A convex lens is thus enabled to converge rays of light falling upon it, and a concave lens to separate them more widely; each separate part of the surface of the lens producing its own independent effect.

The light of the sun and celestial bodies in general, as well as that of the electric spark and of all ordinary flames, is of a compound nature. If a ray of light from any of the sources mentioned be admitted into a dark room by a small hole in a shutter, or otherwise, and suffered to fall upon a glass prism in the manner described above,




it will not only be refracted from its straight course, but will be decomposed into a number of coloured rays, which may be received

* A siliceous deposit in the joints of the bamboo.

upon a white screen placed behind the prism. When solar light is employed, the colours are extremely brilliant, and spread into an oblong space of considerable length. The upper part of this image or *spectrum* will be violet and the lower red, the intermediate portion, commencing from the violet, being indigo, blue, green, yellow, and orange, all graduating imperceptibly into each other. This is the celebrated experiment of Sir I. Newton; and from it he drew the inference that white light is composed of seven primitive colours, the rays of which are differently refrangible by the same medium, and hence capable of being thus separated. The violet rays are most refrangible, and the red rays least.

Sir D. Brewster is disposed to think, that out of Newton's seven primitive colours four are really compound, and formed by the superposition of the three remaining, namely, blue, yellow, and red, which alone deserve the name of primitive. When these three kinds of rays are mixed, or superimposed, in a certain definite manner, they produce white light, but when one or two of them are in excess, then an effect of colour is perceptible, simple in the first case, and compound in the second. There are, according to this hypothesis, rays of all refrangibilities of each colour, and consequently white light in every part of the spectrum, but then they are unequally distributed; the blue rays are more numerous near the top, the yellow towards the middle, and the red at the bottom, the excess of each colour producing its characteristic effect. In the diagram below, the intensity of each colour is represented by the height of a curve, and the effects of mixture will be intelligible by a little consideration.

Fig. 46.



Bodies of the same mean refractive power do not always equally disperse or spread out the differently-coloured rays: because the principal yellow or red rays, for instance, are equally refracted by two prisms of different materials, it does not follow that the blue or the violet shall be similarly affected. Hence, prisms of different varieties of glass, or other transparent substances, give, under similar circumstances, very different spectra, both as respects the length of the image, and the relative extent of the coloured bands.

The colours of natural objects are supposed to result from the power which the surfaces of the bodies possess of absorbing some of the coloured rays, while they reflect or transmit, as the case may be, the remainder. Thus, an object appears red because it absorbs, or causes to disappear, a portion of the yellow and blue rays composing the white light by which it is illuminated.

A ray of common light made to pass through certain crystals of a particular order is found to undergo a very remarkable change. It becomes split or divided into two rays, one of which follows the general law of refraction, and the other takes a new and extraordinary course, dependent on the position of the crystal. This effect, which is called double refraction, is beautifully illustrated in the case of Iceland spar, or crystallized carbonate of lime. On placing a rhomb of this substance on a piece of white paper, on which a mark or line has been made, the object will be seen double.

Again, if a ray of light be suffered to fall upon a plate of glass at an angle of $56^{\circ} 45'$, the portion of the ray which suffers reflection will be found to have acquired properties which it did not before possess; for on throwing it, under the same angle, upon a second glass plate, it will be observed that there are two particular positions of the latter in which the ray ceases to be reflected. Light which has suffered this change is said to be *polarized*.

The light which passes through the first or polarizing plate is, also, to a certain extent, in this peculiar condition, and by employing a series of similar plates, held parallel to the first, this effect may be greatly increased; a bundle of fifteen or twenty such plates may be used with great convenience for the experiment. It is to be remarked, also, that the light polarized by transmission in this manner is in an opposite state to that polarized by reflection; that is, when examined by a second or *analyzing* plate, held at the angle before mentioned, it will be seen to be reflected when the other disappears, and to be absorbed when the first is reflected.

It is not every substance which is capable of polarizing light in this manner; glass, water, and certain other bodies bring about the change in question, each having a particular polarizing angle at which the effect is greatest. The metals also can, by reflection, polarize the light, but they do so very imperfectly. The two rays into which a pencil of common light divides itself in passing through a doubly-refracting crystal are found on examination to be polarized in a very complete manner, and also transversely, the one being capable of reflection when the other vanishes. It is said that both rays are polarized in opposite directions. With a rhomb of transparent Iceland

Fig. 47.



spar of tolerably large dimensions the two oppositely-polarized rays may be widely separated and examined apart.

There is yet another method of polarization, by the employment of plates of the mineral tourmaline cut parallel to the axis of the crystal. This body polarizes by simple transmission, the ray falling perpendicular to its surface; a part of the light is absorbed, and the remainder modified in the manner described. When two such plates are held with their axes parallel, as in fig. 48, light traverses them

Fig. 48.





Fig. 49.



both freely; but when one of them is turned round in the manner shown in the second cut, so as to make the axes cross at right angles, the light is almost wholly stopped, if the tourmalines be good. A plate of the mineral thus becomes an excellent test for discriminating between polarized light and that which has not undergone the change.

Some of the most splendid phenomena of the science of light are exhibited when thin plates of doubly refracting substances are interposed between the polarizing arrangement and the analyzer.

Instead of the tourmaline plate, which is always coloured, frequent use is made of two Nicol's prisms, or conjoined prisms of carbonate of lime, which, in consequence of a peculiar cutting and combination, possess the property of allowing only one of the oppositely-polarized rays to pass. If the two Nicol's prisms are placed one behind the other in precisely similar positions the light polarized by the one goes through the other unaltered. But when one prism is slightly turned round in its setting, a cloudiness is produced, and by continuing to turn the prism this increases until perfect darkness ensues. This happens, as with the tourmaline plates, when the two prisms cross one another. The phenomenon is the same with colourless as with coloured light.

Supposing that polarized light, coloured, for example, by going through a plate of red glass, passed through the first Nicol's prism, and was altogether obstructed, in consequence of the position of the second prism, then, if between the two prisms a plate of rock-crystal, formed by a section at right angles to the principal axis of the crystal, is interposed, the light polarized by the first prism by passing through the plate of quartz is enabled partially to pass through the second Nicol's prism. Its passage through the second prism can then again be interrupted by turning the second prism


round to a certain extent. The rotation required varies with the thickness of the plate of rock-crystal, and also with the colour of the light that is employed. It increases from red in the following order, green, yellow, blue, violet.

This property of rock-crystal was discovered by Arago. The kind of polarization has been called circular polarization. No other crystals are known to produce the same effect. The direction of the rotation is with many plates towards the right hand; in other plates it is towards the left. The one class is said to possess right-handed polarization; the other class left-handed polarization.

Biot observed that many solutions of organic substances exhibit the property of circular polarization, though to a far less extent than rock-crystal. Thus, solution of cane-sugar and tartaric acid possess right-handed polarization, whilst albumen, fruit-sugar, and oil of turpentine are left-handed. In all these solutions the amount of circular polarization increases with the concentration of the fluid and the thickness of the column of liquid through which the light passes. Hence circular polarization is an important auxiliary in chemical analysis. In order to determine the amount of polarization which any fluid exhibits, the liquid is put into a glass tube not less than from ten to twelve inches long, which is closed with glass plates, one of which should be coloured red, for example. This is then placed between the two Nicol's prisms, which have previously been so arranged with regard to each other that no light could pass through. An apparatus of this description, the saccharometer, is chiefly used for determining the concentration of solutions of cane-sugar.

The form of this instrument may be seen in the fig. 50. The two Nicol's prisms are enclosed in the corresponding fastenings *a* and *b*. Between the two there is a space to receive the tube which is filled with the solution of sugar. If the prisms are crossed in the way mentioned above before the tube is put in its place, that is, if they are placed so that no light passes them, by the action of the solution of sugar the light is enabled to pass, and the Nicol's prism, for instance, *a* must be turned through a certain angle before the light is again perfectly stopped. The magnitude of this angle is observed on the circular disk *s s*, which is divided into degrees, and upon which, by the turning of the prism, an index *a* is moved along the division. When the tube is exactly 10 inches long, and is closed at both ends by flat glass plates, one of which has a pure red colour, and when it is filled with a solution containing ten per cent. by weight of cane-sugar and free from any other substance possessing an action on light, the angle of rotation is $13\cdot35$. Since the magnitude of this angle stands in direct relation to the length of the column of fluid and also to the quantity of sugar in solution, it is clear that the quantity of sugar in any given solution, when the length of the column of fluid is *l* inches, and the angle of rotation is *a* degrees, can be determined by the equation $z = \frac{a \times l}{13\cdot35}$

Fig. 50.



This process is not sufficient when the solution contains cane-sugar and fruit-sugar, for the latter rotates the ray to the left; then only the difference of the two actions is obtained. But if the whole quantity of sugar be changed into fruit-sugar, and the experiment be repeated, from the results of the two observations the quantity of both kinds of sugar can easily be calculated. It is difficult to find exactly that position of the Nicol's prisms in which the greatest darkness prevails. To make the measurements more exact and easy, Soleil has made some additions to the apparatus. At *g* before the prism *b*, a plate of rock-crystal cut at right angles to the axis is placed. It is divided in the centre of the field of vision, half consisting of quartz, rotating to the right hand, and half of the variety that rotates to the left; it is 0.148 inch (3.75 millimetre) thick; this thickness being found by experiment to produce the greatest difference in the colour of the two halves, when one prism is slightly rotated. The solution of sugar has precisely

the same action as the rotation, since it increases the action of the half which has a right-handed rotation and lessens the action of the half which rotates to the left. Hence the two halves will assume a different colour when the smallest quantity of sugar is present in the fluid. By slightly turning the Nicol's prism α , this difference can be again removed. Soleil has introduced another more delicate means of effecting this at the part l , which he calls the compensator. The most important parts of this are separately represented in fig. 50. It consists of two exactly equal right-angled prisms, of left-handed quartz, whose surfaces, c' and c , are cut perpendicular to the optic axis. These prisms can, by means of the screw v and a rack and pinion, be made to slide on one another, so that, when taken together, they form a plate of varying thickness, bounded by parallel surfaces. One of the frames has a scale l , the other a vernier n . When this points to zero of the scale the optical action of the two prisms is exactly compensated by a right-handed plate of rock crystal, so that an effect is obtained as regards circular polarization, as if the whole system were not present. As soon, however, as the screw is moved, and thus the thickness of the plate formed by the two prisms is changed, we will suppose it increased, then a left-handed action ensues which must be properly regulated, until it compensates the opposite action of a solution of sugar. Thus a convenient method is obtained of rendering the colour of the double plate uniform, when it has ceased to be so in consequence of the action of a solution of sugar.

Faraday has made the remarkable discovery, that if a very strong electric current is passed round a substance which possesses the property of circular polarization, the amount of rotation is altered to a considerable degree.

The luminous rays of the sun are accompanied, as already mentioned, by others which possess heating powers. If the temperature of the different coloured spaces in the spectrum be tried with a delicate thermometer, it will be found to increase from the violet to the red extremity, and when the prism is of some particular kinds of glass, the greatest effect will be manifest a little beyond the visible red ray. It is inferred from this that the chief mass of the heating rays of the sun are among the least refrangible components of the solar beam.

Again, it has long been known that chemical changes both of combination and of decomposition, but more particularly the latter, could be effected by the action of light. Chlorine and hydrogen combine at common temperatures only under the influence of light, and parallel cases occur in great numbers in organic chemistry: the blackening and decomposition of salts of silver are familiar instances of the chemical powers of the same agent. Now it is not always the luminous part of the ray which effects these changes; they are chiefly produced by certain invisible rays, accompanying the others, and which are found most abundantly in, and even beyond, the violet part of the spectrum. It is there that certain chemical effects are most

marked, although the intensity of the light is exceedingly feeble. From the fact that some salts of silver are less readily decomposed by the luminous—yellow, orange, and red rays—than by certain rays which extend beyond the ordinary visible spectrum, it has been concluded that there exists in the sunbeam, in addition to heat and light, a principle having a distinct action, to which the provisional term *actinism* has been given—from *ἄκτιν*, a ray. The actinic rays are thus directly opposed to the heating rays in the common spectrum in their degree of refrangibility, since they exceed all the others in this respect. The luminous rays, too, under peculiar conditions, exert decomposing powers upon salts of silver, and that even with greater force than the so-called chemical or actinic rays. The result of the action of any ray depends, moreover, greatly on the physical state of the surface upon which it falls, and on the chemical constitution of the body; indeed for every kind of rays a substance may be found which under particular circumstances will affect it, and thus it appears that the chemical functions are by no means confined to any set of rays to the exclusion of the rest.

Upon the chemical changes produced by light is based the art of *photography*. In the year 1802,* Mr. Thomas Wedgwood purposed a method of copying paintings on glass by placing behind them white paper or leather moistened with a solution of nitrate of silver, which became decomposed and blackened by the transmitted light in proportion to the intensity of the latter; and Davy, in repeating these experiments, found that he could thus obtain tolerably accurate representations of objects of a texture partly opaque and partly transparent, such as leaves and the wings of insects, and even copy with a certain degree of success the images of small objects obtained by the solar microscope. These pictures however, required to be kept in the dark, and could only be examined by candle-light, otherwise they became obliterated by the blackening of the whole surface from which the salt of silver could not be removed. These attempts at light-painting attracted but little notice till the publication of Mr. Fox Talbot's † papers, read before the Royal Society, in January and February, 1839, in which he detailed two methods of fixing the pictures produced by the action of light on paper impregnated with chloride of silver, and at the same time described a plan by which the sensibility of the prepared paper may be increased to the extent required for receiving impressions from the images of the camera obscura.

Very shortly afterwards, Sir John Herschel ‡ proposed to employ solutions of the alkaline hyposulphites for removing the excess of chloride of silver from the paper, and thus preventing the farther action of light, and this plan has been found exceedingly successful. The greatest improvement, however, which the curious art of photographic drawing has received, is due to Mr. Talbot, § who, in a

* Journal of the Royal Institution, i. 170.

† Phil. Mag. March, 1839.

‡ Phil. Trans. for 1840, p. 1.

§ Phil. Mag. August, 1841.

communication to the Royal Society, described a method by which paper of such sensibility could be prepared as to permit its application to the taking of portraits of living persons by the aid of a good camera obscura, the time required for a perfect impression never exceeding a few seconds. The general plan at present in use is the following:—

Writing-paper of good quality is washed on one side with a solution of thirty grains of nitrate of silver in an ounce of distilled water, and then left to dry spontaneously in a dark room; when dry, it is immersed for from five to ten minutes, in a solution of one ounce of iodide of potassium in twenty ounces of water. The paper is then soaked in water for half an hour, changing the water three or four times to remove the excess of iodide of potassium, and is then dried. These operations should be performed by candle-light. When required for use, the paper, thus coated with yellow iodide of silver, is brushed over with a solution made by adding together, one part of a solution of nitrate of silver fifty grains, to an ounce of water; two parts glacial acetic acid, and three parts of a saturated solution of gallic acid; after a few seconds the excess is removed by blotting-paper. This, which is called *Talbotype* or *Calotype* paper, is now ready for use; exposure to diffused daylight for one second suffices to make an impression upon it, and even the light of the moon produces the same effect, although a much longer time is required. For landscapes and fixed objects, and when the paper is required to be prepared long beforehand, the above mixture of “*gallo-nitrate*” should be diluted with from twenty to fifty volumes of water, since, especially in hot weather, without this precaution the paper blackens spontaneously.

The images of the camera obscura are at first invisible, but are made to appear in full intensity, by once more washing the paper with a mixture of one part of the silver solution (fifty grains to an ounce of water), and four parts of the saturated solution of gallic acid. The development of the image soon commences, and should reach its maximum in a few minutes.

The picture is of course *negative*, the lights and shadows being reversed; to obtain *positive* copies nothing more is necessary than to place a piece of photographic paper prepared with chloride of silver, or a piece of talbotype paper, beneath the negative cover, to press the two papers in contact by means of a glass, and to expose the whole to the light of the sun for a short time, or longer to diffused daylight.

Before this can be done the negative must, however, be fixed, otherwise it will blacken: this is done temporarily by washing with a solution of bromide of potassium, ten grains in an ounce of water, and then rinsing in common water. The ultimate fixing is effected by immersion in a solution of one part of hyposulphite of soda, in from four to ten parts of water: the weaker solution should be used hot, about 180° ($82^{\circ}\cdot 22^{\circ}\text{C}$), and the immersion continued until the yellow tint arising from the undecomposed iodide disappears: finally,

repeatedly washing in hot water, drying, and saturating with white wax terminates the process.

The positives are also fixed by hyposulphite of soda, by cyanide of potassium, or by ammonia; all of which act by removing the undecomposed chloride of silver. The conservation of the positive is a point of difficulty. Mr. Malone recommends immersion in a strong solution of caustic potassa, heated to about 180° ($82^{\circ}\cdot 22^{\circ}\text{C}$); a change of tint ensues, and greater permanence is acquired. After removal of the alkali and any sulphur and chlorine compounds present, the picture should be sized and hot-pressed, or varnished, keeping the finished proof most carefully excluded from sulphuretted vapours.

Sir John Herschel has shown that a great number of other substances can be employed in these photographic processes by taking advantage of the singular deoxidizing effects of certain portions of the solar rays. Paper washed with a solution of a salt of sesquioxide of iron becomes capable of receiving impressions of this kind, which may afterwards be made evident by ferricyanide of potassium, or tetrachloride of gold. Vegetable colours are also acted upon in a very curious and apparently definite manner by the different parts of the spectrum.*

The daguerreotype, the announcement of which was first made in the summer of 1839 by M. Daguerre, who had been occupied with this subject from 1826, if not earlier, is another remarkable instance of the decomposing effects of the solar rays. A clean and highly-polished plate of silvered copper is exposed for a certain period to the vapour of iodine, and then transported to the camera obscura. In the most improved state of the process, a very short time suffices for effecting the necessary change in the film of iodide of silver. The picture, however, only becomes visible by exposing it to the vapour of mercury, which attaches itself, in the form of exceedingly minute globules, to those parts which have been most acted upon, that is to say, to the lights, the shadows being formed by the dark polish of the metallic plate. Lastly, the drawing is washed with a solution of hyposulphite of soda to remove the undecomposed iodide of silver, and render it permanent.

The images of objects thus produced bear the most minute examination with a magnifying-glass, the smallest details being depicted with perfect fidelity.

Great improvements have been necessarily made in the application of this beautiful art to taking portraits. By the joint use of bromine and iodine the plates are rendered far more sensitive, and the time of sitting is shortened to a very few seconds. When the operation is completed, the colour of the plate is much improved by the deposition of an exceedingly thin film of gold, which communicates a warm purplish tint, and removes the previous dull leaden-grey hue, to most persons very offensive.

* Phil. Trans. 1842, p. 1.

The difficulty of obtaining good paper for the talbotype has led to the devisal of various substitutes: albumen on glass and *collodion* are used with success; a soluble iodide, with or without bromine, chlorine, or fluorine, is mixed with either liquid, and applied to a glass or porcelain plate, dried, and immersed in a solution of nitrate of silver; thus a sensitive coating is formed upon which the images of the camera or microscope are thrown, and developed by subsequent treatment with deoxidizing agents—either pyro-gallic acid, gallic acid, or sulphate of protoxide of iron may be used. The fixing is accomplished by hyposulphite of soda. The result is either negative or positive at the will of the operator. The proofs on porcelain or glass may be burned in, and perhaps thus rendered indestructible by time.

Etching and lithographic processes, by combined chemical and photographic agency, promise to be of considerable utility. The earliest is that of Niépce; he applied a bituminous coating to a metal plate, upon which an engraving was superimposed. The light being thus partially interrupted acted unequally upon the varnish; a liquid hydro-carbon *petroleum* used as a solvent removed the bitumen wherever the light had not acted; an engraving acid could now bite the unprotected metal, which could eventually be printed from in the usual way. Dr. Donne and Dr. Berres, by submitting the daguerreotype to the action of nitric acid and its vapour, obtained etchings from which proofs could be taken. Mr. Grove, by using chlorine evolved by voltaic agency, succeeded in obtaining a more manageable process; and very successful results have been obtained by M. Fizeau: he submits the daguerreotype to the action of a mixture of dilute nitric acid, common salt, and nitrate of potassa, the silver only is attacked, the mercurialized portion of the image resisting the acid, and an etching is obtained following minutely the lights and shadows of the picture. To deepen this etching the chloride of silver formed is removed by ammonia, the plate is boiled in caustic potassa and again treated with acid, and so on till the etching is of sufficient depth. In extreme cases electro-gilding is resorted to, and an engraving acid used to get still more powerful impressions.

Among the latest results are those obtained by Mr. Talbot on steel plates; he uses a mixture of bichromate of potassa and gelatine, which hardens by exposure to the light; the parts not affected are removed by washing; bichloride of platinum is used as an etching liquid, it has the advantage of biting with greater regularity than nitric acid.

The bitumen process of M. Niépce has been applied to lithographic stone, and positives obtained from negative talbotypes have been printed off by a modification of the ordinary lithographic process. M. Niépce finds that ether dissolves the altered bitumen, while coal-tar-naphtha, or benzol, attacks by preference the bitumen in its normal condition.

RADIATION, REFLECTION, ABSORPTION, AND TRANSMISSION OF HEAT.

RADIATION OF HEAT.

IF a red-hot ball be placed upon a metallic support, and left to itself, cooling immediately commences, and only stops when the temperature of the ball is reduced to that of the surrounding air. This effect takes place in three ways: heat is conducted away from the ball through the substance of the support; another portion is removed by the convective power of the air; and the residue is thrown off from the heated body in straight lines or rays, which pass through air without interruption, and become absorbed by the surfaces of neighbouring objects which happen to be presented to their impact.

This radiant or radiated heat resembles, in very many respects, ordinary light; it suffers reflection from polished surfaces according to the same law; it is by dull and rough surfaces partly reflected, partly absorbed; it moves with extreme velocity; and, finally, it traverses certain transparent media, undergoing refraction at the same time, in obedience to the laws which regulate that phenomenon in optics.

The fact of the *reflection* of heat may be very easily proved. If a person stand before a fire in such a position that his face may be screened by the mantelshelf, and if he then take a bright piece of metal, as a sheet of tinned plate, and hold it in such a manner that the fire may be seen by reflection, at the same moment a distinct sensation of heat will be felt.

The apparatus best fitted for studying these facts consists of a pair of concave metallic mirrors of the form called parabolic. The parabola is a curve possessing very peculiar properties, one of the most prominent being the following:—A tangent drawn to any part of the curve makes equal angles with two lines, one of which proceeds from the point where the tangent touches the curve in a direction parallel to what is called the axis of the parabola, and the other from the same spot through a point in front of the curve called the focus. It results from this that parallel rays, either of light or heat, falling upon a mirror of this particular curvature in a direction parallel to the axis of the parabola, will be all reflected to a single point at the focus; and rays diverging from this focus, and impinging upon the mirror will, after reflection, become parallel (fig. 51).

If two such mirrors be placed opposite to each other at a considerable distance, and so adjusted that their axes shall be coincident, and a hot body placed in the focus of the one, while a thermometer occupies

that of the other, the reflection of the rays of heat will become manifest by their effect upon the instrument. In this manner, with a pair of by no means very perfect mirrors, 18 inches in diameter, separated by an interval of 20 feet or more, amadou or gunpowder may be readily fired by a red-hot ball in the focus of the opposite mirror (fig. 52).

The power of radiation varies exceedingly with different bodies, as may be easily proved. If two similar vessels of equal capacity be constructed of thin metal, and the surface of one be highly polished, while that of the other is covered with lamp-black, and both filled with hot water of the same temperature, and their rate of cooling observed from time to time with a thermometer, it will be constantly found that the blackened vessel loses heat much faster than the one with bright surfaces; and since both are put on a footing of equality in other respects, this difference, which will often amount

Fig. 51.





Fig. 52.



to many degrees, must be ascribed to the superior emissive power of the film of soot.

By another arrangement, a numerical comparison can be made of these differences. A cubical metallic vessel is prepared, each of whose sides is in a different condition, one being polished, another rough, a third covered with lampblack, &c. This vessel is filled with water, kept constantly at 212° (100°C) by a small steam-pipe. Each of its sides is then presented in succession to a good parabolic mirror, having in its focus one of the bulbs of the differential thermometer before described (fig. 19), the bulb itself being blackened. The effect produced on this instrument is taken as a measure of the comparative radiating powers of the different surfaces. The late Sir John Leslie obtained by this method of experiment the following results:—

Emissive power.		Emissive power.	
Lampblack . . .	100	Tarnished lead . .	45
Writing-paper . .	98	Clean lead . . .	19*
Glass	90	Polished iron . .	15
Plumbago	75	Polished silver . .	12

The best reflecting surfaces are always the worst radiators; polished metal reflects nearly all the heat that falls upon it, while its radiating power is the feeblest of any substance tried, and lampblack, which reflects nothing, radiates most perfectly.

The power of *absorbing* heat is in direct proportion to the power of emission. The polished metal mirror, in the experiment with the red-hot ball, remains quite cold, although only a few inches from the latter; or, again, if a piece of gold leaf be laid upon paper, and a heated iron held over it until the paper is completely scorched, it will be found that the film of metal has perfectly defended that portion beneath it.

The faculty of absorption seems to be a good deal influenced by colour; Dr. Franklin found that when pieces of cloth of various colours were placed on snow exposed to the feeble sunshine of winter, the snow beneath became unequally melted, the effect being always in proportion to the depth of the colour; and Dr. Stark has since obtained a similar result by a different method of experimenting. According to the late researches of Melloni, this effect depends less on the colour than on the nature of the colouring matter which covers the surface of the cloth.

These facts afford an explanation of two very interesting and important natural phenomena, namely, the origin of dew, and the cause of the land and sea breezes of tropical countries. While the sun remains above the horizon, the heat radiated by the surface of the earth into space is compensated by the absorption of the solar beams; but when the sun sets, and the supply ceases, while the emission of heat goes on as actively as before, the surface becomes cooled until its temperature sinks below that of the air. The air in contact with the earth of course participates in this reduction of temperature; the aqueous vapour present speedily reaches its point of maximum density, and then begins to deposit moisture, whose quantity will depend upon the proportion of vapour in the atmosphere, and on the extent to which the cooling process has been carried.

* The supposed influence of mere difference of surface has been called in question by M. Melloni, who attributes to other causes the effects observed by Sir John Leslie and others, among which superficial oxidation and differences of physical condition with respect to hardness and density, are among the most important. With metals not subject to tarnish, scratching the surface *increases* the emissive power when the plates have been rolled or hammered, *i. e.*, are in a compressed state, and diminishes it, on the contrary, when the metal has been cast and carefully polished without burnishing. In the case of ivory, marble, and jet, where compression cannot take place, no difference is perceptible in the radiating power of polished and rough surfaces.—Ann. Chim. et Phys. lxx. 435

It is observed that dew is most abundant in a clear calm night, succeeding a hot day; under these circumstances the quantity of vapour in the air is usually very great, and at the same time radiation proceeds with most facility. At such times a thermometer laid on the ground will, after some time, indicate a temperature of 10° ($5^{\circ}\cdot5\text{C}$), 15° ($8^{\circ}\cdot3\text{C}$), or even 20° ($11^{\circ}\cdot1\text{C}$) below that of the air a few feet higher. Clouds hinder the formation of dew, by reflecting back to the earth the heat radiated from its surface, and thus preventing the necessary reduction of temperature; and the same effect is produced by a screen of the thinnest material stretched at a little height above the ground. In this manner gardeners often preserve delicate plants from destruction by the frosts of spring and autumn. The piercing cold felt just before and at sunrise, even in the height of summer, is the consequence of this refrigeration having reached its maximum.

Wind also effectually prevents the deposition of dew, by constantly renewing the air lying upon the earth before it has had its temperature sufficiently reduced to cause condensation of moisture.

Many curious experiments may be made by exposing on the ground at night bodies which differ in their powers of radiation. If a piece of black cloth and a plate of bright metal be thus treated, the former will often be found in the morning covered with dew, while the latter remains dry.

Land and sea breezes are certain periodical winds common to most sea-coasts within the tropics, but by no means confined to those regions. It is observed, that a few hours after sunrise a breeze springs up at sea, and blows directly on shore, and that its intensity increases as the day advances, and declines and gradually expires near sunset. Shortly afterwards a wind arises in exactly the opposite direction, namely, from the land towards the sea, lasts the whole of the night, and only ceases with the reappearance of the sun.

It is easy to give an explanation of these effects. When the sun shines at once upon the surface of the earth and that of the sea, the two become unequally heated, because the water, although it possesses greater power of absorbing heat, yet is more slowly warmed in consequence of its greater capacity for heat, and the greater depth to which the rays of the sun can penetrate. The air over the heated surface of the ground, being expanded by heat, rises, and has its place supplied by colder air flowing from the sea, producing the sea-breeze. When the sun sets, both sea and land begin to cool by radiation; the rate of cooling of the latter will, however, far exceed that of the former, and its temperature will rapidly fall. The air above becoming cooled and condensed, flows outwards in obedience to the laws of fluid pressure, and displaces the warmer air of the ocean. In this manner, by an interchange of air between sea and land, the otherwise oppressive heat is moderated, to the great advantage of those who inhabit such localities. The land and sea breezes extend to a small

distance only from shore, but afford, notwithstanding, essential aid to coasting navigation, since vessels on either tack enjoy a fair wind during the greater part of both day and night.


TRANSMISSION OF HEAT ; DIATHERMANCY.

Rays of heat, in passing through air, receive no more obstruction than those of light under similar circumstances ; but with other transparent media the case is different. If a parabolic mirror be taken and its axis directed towards the sun, the rays both of heat and light will be reflected to the focus, which will exhibit a temperature sufficiently high to fuse a piece of metal, or fire a combustible body. If a plate of glass be now placed between the mirror and the sun, the effect will be but little diminished.

Now, let the same experiment be made with the heat of a kettle filled with boiling water ; the heat will be concentrated by reflection as before, but, on interposing the glass, the heating effect at the focus will be reduced to nothing. Thus, the rays of heat coming from the sun traverse glass with facility, which is not the case with those emanating from the boiling water.

In the year 1833, M. Melloni published the first of a series of exceedingly valuable researches on this subject, which are to be found in detail in various volumes of the *Annales de Chimie et de Physique*.* It will be necessary, in the first instance, to describe the method of operation followed by this philosopher.

Not long before, two very remarkable facts had been discovered : Oersted, in Copenhagen, showed that a current of electricity, however produced, exercises a singular and perfectly definite action on a magnetic needle ; and Seebeck, in Berlin, found that an electric current may be generated by the unequal effects of heat on different metals in contact. If a wire conveying an electrical current be brought near a magnetic needle, the latter will immediately alter its position and assume a new one, as nearly perpendicular to the wire as the mode of suspension and the magnetism of the earth will permit. When the




wire, for example, is placed directly over the needle, while the current it carries travels from north to south, the needle is deflected from its ordinary direction and the north pole driven to the eastward. When the current is reversed, the same pole deviates to an equal amount towards the west. Placing the wire below the needle instead of above produces the same effect as reversing the current.


When the needle is subjected to the action of two currents in opposite directions, the one

* Translated also in Taylor's Scientific Memoirs.

above and the other below, they will obviously concur in their effects. The same thing happens when the wire carrying the current is bent upon itself, and the needle placed between the two portions; and since every time the bending is repeated a fresh portion of the current is made to act in the same manner upon the needle, it is easy to see how a current too feeble to produce any effect when a simple straight wire is employed, may be made by this contrivance to exhibit a powerful action on the magnet. It is on this principle that instruments called *galvanometers*, *galvanoscopes*, or *multipliers*, are constructed; they serve, not only to indicate the existence of electrical currents, but to show by the effect upon the needle the direction in which they are moving. By using a very long coil of wire, and two needles, immovably connected, and hung by a fine filament of silk, almost any degree of sensibility may be communicated to the apparatus.



When two pieces of different metals, connected together at each end, have one of their joints more heated than the other, an electric current is immediately set up. Of all the metals tried, bismuth and antimony form the most powerful combination. A single pair of bars, having one of their junctions heated in the manner shown, can develop a current




strong enough to deflect a compass-needle placed within, and, by arranging a number in a series and heating their alternate ends, the intensity of the current may be very much increased. Such an arrangement is called a thermo-electric pile. M. Melloni constructed a very small thermo-electric pile of this kind, containing fifty-five slender bars of bismuth and antimony, laid side by side, and soldered together at their alternate ends. He connected this pile with an exceedingly delicate multiplier, and found himself in the possession of an instrument for measuring small variations of temperature far surpassing in delicacy the air-thermometer in its most sensitive form, and having great advantages in other respects over that instrument when employed for the purposes to which he devoted it.

The substances whose powers of transmission were to be examined were cut into plates of a determinate thickness, and, after being well polished, arranged in succession in front of the little pile, the extremity of which was blackened to promote the absorption of the rays. A perforated screen, the area of whose aperture equalled that of the face of the pile, was placed between the source of heat and the body under trial, while a second screen served to intercept all radiation until the moment of the experiment.

After much preliminary labour for the purpose of testing the capabilities of the apparatus and the value of its indications, an extended series of researches was undertaken and carried on during a long

Fig. 56.



period with great success: some of the most curious results are given in the subjoined table.

Four different sources of heat were employed in these experiments, differing in their degrees of intensity: the naked flame of an oil-lamp; a coil of platinum wire heated to redness; blackened copper at 734° (390°C); and the same heated to 212° (100°C).

Substances. (Thickness of plate 0.1 inch, nearly.)	Transmission of 100 rays of heat from			
	Oil-lamp.	Red-hot Platinum.	Copper at 734° (390°C).	Copper at 212° (100°C).
Rock-salt, transparent and colourless .	92	92	92	92
Fluor-spar, colourless	78	69	42	33
Rock-salt, muddy	65	65	65	65
Beryl	54	23	13	0
Fluor-spar, greenish	46	38	24	20
Ice-land-spar	39	28	6	0
Plate-glass	39	24	6	0
Rock-crystal	38	28	6	0
Rock-crystal, brown	37	28	6	0
Tourmaline, dark green	18	16	3	0
Citric acid, transparent	11	2	0	0
Alum, transparent	9	2	0	0
Sugar-candy	8	0	0	0
Fluor-spar, green, translucent	8	6	4	3
Ice, pure and transparent	6	0	0	0

On examining this remarkable table, which is an abstract of one much more extensive, the first thing that strikes the eye is the want of connexion between the power of transmitting heat and that of transmitting light; taking, for instance, the oil-lamp as the source of heat, out of a quantity of heat represented by 100 rays falling upon the pile, the proportion intercepted by similar plates of rock-salt, glass, and alum, may be expressed by the numbers, 8, 61, and 91; and yet these bodies are equally transparent with respect to light. Generally speaking, colour was found to interfere with the transmissive power, but to a very unequal extent; thus, in fluor-spar, colourless, greenish, and deep green, the quantities transmitted were 78, 46, and 8, while the difference between colourless and brown rock-crystal was only 1. Bodies absolutely opaque, as wood, metals, and black marble, stopped the rays completely, although it was found that the faculty of transmission was possessed, to a certain extent, by some which were nearly in that condition, as thick plates of brown quartz, black mica, and black glass.

When rays of heat had once passed through a plate of any substance, the interposition of a second similar plate occasioned much less loss than the first; the same thing happened when a number were interposed, the rays, after traversing one plate, being but little interrupted by others of a similar nature.

The next point to be noticed is the great difference in the properties of the rays from different sources. Out of 100 rays from each source which fell on rock-salt, the same proportion was always transmitted whether the rays proceeded from the intensely-heated flame, the red-hot platinum wire, or the copper at 734° (390°C) or 212° (100°C); but this is true of no other substance in the list. In the case of plate-glass, we have the numbers 39, 24, 6, and 0, as representatives of the comparative quantities of heat transmitted through the plate from each source; or in three varieties of fluor-spar, as below stated:—

	Flame.	Red-heat.	734° (390°C).	212° (100°C).
Colourless . . .	78	69	42	33
Greenish . . .	46	38	24	20
Dark green . . .	8	6	4	3

One substance, beryl, out of 100 rays from an intensely-heated source, suffers 54 to pass; and out of the same number (that is, an equal quantity of heat) from metal at 212° (100°C), none at all; whilst another substance, fluor-spar transmits rays from the two sources mentioned, in the proportion of 8 to 3.

These, and many other curious phenomena, are fully and completely explained on the supposition, that among the invisible rays of heat differences are to be found exactly analogous to those differences between rays of light which we are accustomed to call colours. Rock-salt and air are the only substances yet known which are truly

diathermanous, or equally transparent to all kinds of heat-rays ; it is to the latter what white glass or water is to light ; it suffers rays of every description to pass with equal facility. All other bodies act like coloured glasses, absorbing certain of the rays more abundantly than the rest, and *colouring*, as it were, the heat which passes through them.

These heat-tints have no direct relation to ordinary colours ; their existence is, nevertheless, almost as clearly made out as that of the coloured rays of the spectrum. Bodies at a comparatively low temperature emit rays of such a tint only as to be transmissible by a few substances ; as the temperature rises, rays of other heat-colours begin to make their appearance, and transmission of some portion of these rays takes place through a great number of bodies ; while at the temperature of intense ignition we find rays of all colours thrown out, some of which will certainly find their way through a great variety of substances.

By cutting rock-salt into prisms and lenses, it is easy to show that radiant heat may be refracted like ordinary light, and its beams made to converge or diverge at pleasure ; and, lastly, to complete the analogy, it has been shown to be susceptible of polarization by transmission through plates of doubly-refracting minerals, in the same manner as light itself.*

* Dr. Forbes, Phil. Mag. for 1835 ; also M. Melloni, Ann. Chim. et Phys. lxxv. 5.

MAGNETISM.

A PARTICULAR species of iron ore has long been remarkable for its property of attracting small pieces of iron, and causing them to adhere to its surface: it is called loadstone, or magnetic iron ore.

If a piece of this loadstone be carefully examined, it will be found that the attractive force for particles of iron is greatest at certain particular points of its surface, while elsewhere it is much diminished, or even altogether absent. These attractive points, or centres of greatest force, are denominated poles, and the loadstone itself is said to be endued with magnetic polarity.

If one of the poles of a natural loadstone be rubbed in a particular manner over a bar of steel, its characteristic properties will be communicated to the bar, which will then be found to attract iron-filings like the loadstone itself. Farther, the attractive force will be greatest at two points situated very near the extremities of the bar, and least of all towards the middle. The bar of steel so treated is said to be magnetized, or to constitute an artificial magnet.

When a magnetized bar or natural magnet is suspended at its centre in any convenient manner, so as to be free to move in a horizontal plane, it is always found to assume a particular direction with regard to the earth, one end pointing nearly north and the other nearly south. If the bar be moved from this position, it will tend to reassume it, and, after a few oscillations, settle at rest as before. The pole which points towards the astronomical north is usually distinguished as the north pole of the bar, and that which points southward, as the south pole. A suspended magnet, either natural or artificial, of symmetrical form, serves to exhibit certain phenomena of attraction and repulsion in the presence of a second magnet, which deserve particular attention. When a north pole is presented to a south pole, or a south pole to a north, attraction ensues between them; the ends of the bars approach each other, and, if permitted, adhere with considerable force; when, on the other hand, a north pole is brought near a second north pole, or a south pole near another south pole, mutual repulsion is observed, and the ends of the bars recede from each other as far as possible. *Poles of an opposite name attract, and of a similar name repel each other.* Thus, a small bar or needle of steel, properly magnetized and suspended, and having its poles marked, becomes an instrument fitted not only to discover the existence of magnetic power in other bodies, but to estimate the kind of polarity affected by their different parts.

A piece of iron brought into the neighbourhood of a magnet ac-


quires itself magnetic properties; the intensity of the power thus conferred depends upon that of the magnet and upon the interval which divides the two, becoming greater as that interval decreases, and greatest of all when in actual contact. The iron, under these circumstances, is said to be magnetized by induction or influence, and the effect which in an instant reaches its maximum, is at once destroyed by removing the magnet.

When steel is substituted for iron in this experiment, the inductive action is hardly perceptible at first, and only becomes manifest after the lapse of a certain time; in this condition, when the steel bar is removed from the magnet, it retains a portion of the induced polarity. It becomes, indeed, a permanent magnet, similar to the first, and retains its peculiar properties for an indefinite period.

A particular name is given to this resistance which steel always offers in a greater or less degree both to the development of magnetism and its subsequent destruction; it is called *specific coercive power*.

The rule which regulates the induction of magnetic polarity in all cases is exceedingly simple, and most important to be remembered.

Fig. 57.



The pole produced is always of the opposite name to that which produced it, a north pole developing south polarity, and a south pole north polarity. The north pole of the magnet figured in the sketch induces south polarity in all the nearer extremities of the pieces of iron or steel which surround it, and a state similar to its own in all the more remote extremities. The iron thus magnetized is capable of exerting a similar inductive action on a second piece, and that upon a third, and so to a great number, the intensity of the force diminishing as the distance from the permanent magnet increases. It is in this

way that a magnet is enabled to hold up a number of small pieces of iron, or a bunch of filings, each separate piece becoming a magnet for the time by induction.

Magnetic polarity, similar in degree to that which iron presents, has been found only in some of the compounds of iron, in nickel, and in cobalt.

Magnetic attractions and repulsions are not in the slightest degree interfered with by the interposition of substances destitute of magnetic properties. Thick plates of glass, shellac, metals, wood, or of any sub-

stances except those above mentioned, may be placed between a magnet and a suspended needle, or a piece of iron under its influence, the distance being preserved, without the least perceptible alteration in its attractive power, or force of induction.

One kind of polarity cannot be exhibited without the other. In other words, a magnetic pole cannot be insulated. If a magnetized bar of steel be broken at its neutral point, or in the middle, each of the broken ends acquires an opposite pole, so that both portions of the bar become perfect magnets; and, if the division be carried still farther, if the bar be broken into a hundred pieces, each fragment will be a complete magnet, having its own north and south poles.

This experiment serves to show very clearly that the apparent polarity of the bar is the consequence of the polarity of each individual particle, the poles of the bar being merely points through which the resultants of all these forces pass; the large magnet is made up of an

Fig. 58.



immense number of little magnets regularly arranged side by side, all having their north poles looking one way, and their south poles the other. The middle portion of such a system cannot possibly exhibit attractive or repulsive effects on an external body, because each pole is in close juxtaposition with one of an opposite name and of equal power; hence their forces will be exerted in opposite directions and neutralize each other's influence. Such will not be the case at the extremities of the bar; there uncompensated polarity will be found capable of exerting its specific power.

This idea of regular polarization of particles of matter in virtue of a pair of opposite and equal forces, is not confined to magnetic phenomena; it is the leading principle in electrical science, and is constantly reproduced in some form or other in every discussion involving the consideration of molecular forces.

Artificial steel magnets are made in a great variety of forms; such as small light needles, mounted with an agate cap for suspension upon a fine point; straight bars of various kinds; bars curved into the shape of a horse-shoe, &c. All these have regular polarity communicated to them by certain processes of rubbing or touching with another magnet, which require care, but are not otherwise difficult of execution. When great power is wished for, a number of bars may be screwed together, with their similar ends in contact, and in this way it is easy to construct permanent steel magnets capable of sustaining great weights. To prevent the gradual destruction of magnetic force, which would otherwise occur, it is usual to arm each pole with a piece of soft

iron or keeper, which, becoming magnetized by induction, serves to sustain the polarity of the bar, and even increases in some cases its energy.

The direction spontaneously assumed by a suspended needle indicates that the earth itself has the properties of an enormous magnet, whose south pole is in the northern hemisphere. A line joining the two poles of such a needle or bar indicates the direction of the *magnetic meridian* of the place, which is a vertical plane coincident with the direction of the needle.

The magnetic meridian of a place is not usually coincident with its geographical meridian, but makes with the latter a certain angle called the *declination* of the needle; in other words, the magnetic poles are not situated within the line of the axis of rotation.

The amount of this declination of the needle from the true north and south not only varies at different places, but in the same place is subject to daily, yearly, and secular fluctuations, which are called the variations of declination. Thus, at the commencement of the 17th century, the declination was eastward; in 1660, it was 0; that is, the needle pointed due north and south. Afterwards it became westerly, slowly increasing until the year 1818, when it reached $24^{\circ} 30'$, since which time it has been slowly diminishing.

If a steel bar be supported on a horizontal axis passing exactly through its centre of gravity, it will of course remain equally balanced in any position in which it may happen to be placed; if the bar so adjusted be then magnetized, it will be found to take a permanent direction, the north pole being downwards, and the bar making an angle of about 70° , with a horizontal plane passing through the axis. This is called the *dip* or *inclination* of the needle, and shows the direction in which the force of terrestrial magnetism is most energetically exerted. The amount of this dip is different in different latitudes; near the equator it is very small, the needle remaining nearly or quite horizontal; as the latitude increases the dip becomes more decided; and over the magnetic pole the bar becomes completely vertical. Such a situation is, in fact, to be found in the northern hemisphere, considerably south of the geographical pole on the west coast of Boothia Felix, lat. $70^{\circ} 5' N.$ and longitude $96^{\circ} 46' W.$; the dipping-needle has here been seen to point directly downwards, while the horizontal or compass-needle ceased to traverse. The position of the south magnetic pole has lately been determined by the observations of Captain James Ross to be about lat. $73^{\circ} S.$ and long. $130^{\circ} E.$

By observing a great number of points near the equator in which the dip becomes reduced to nothing, a line may be traced around the earth, called the magnetic equator, and nearly parallel to this, on both sides, a number of smaller circles called lines of equal dip. These lines present great irregularities when compared with the equator itself and the parallels of latitude, the magnetic equator deviating from the terrestrial one as much as 12° at its point of greatest divergence.

Like the horizontal declination, the dip is also subject to change at the same place. Observations have not yet been made during sufficient time to determine accurately the law and rate of alteration, and great practical difficulties exist also in the construction of the instruments. In the year 1773 it was about 72° ; at the present time it is near $69^{\circ} 5'$ in London.

The inductive power of the magnetism of the earth may be shown by holding in a vertical position a bar of very soft iron; the lower end will be found to possess north polarity, and the upper, the contrary state. On reversing the bar the poles are also reversed. All masses of iron whatever, when examined by a suspended needle, will be found in a state of magnetic polarity by the influence of the earth; iron columns, tools in a smith's shop, fire-irons, and other like objects, are all usually magnetic, and those made of steel permanently so. On board ship, the presence of so many large masses of iron—guns, anchors, water-tanks, &c.—thus polarized by the earth, causes a derangement of the compass-needles to a very dangerous extent; happily, a plan has been devised for determining the amount of this local attraction in different positions of the ship, and making suitable corrections.

The mariner's compass, which is nothing more than a suspended needle attached to a circular card marked with the points, was not in general use in Europe before the year 1300, although the Chinese have had it from very early antiquity. Its value to the navigator is now very much increased by correct observations of the exact amount of the declination in various parts of the world.

Probably every substance in the world contributes something to the magnetic action of the earth; for, according to the latest discoveries of Mr. Faraday, magnetism is not peculiar to those substances which have more especially been called magnetic, such as iron, nickel, cobalt, but it is the property of all matter, though to a much smaller degree. Very powerful magnets are required to show this remarkable fact. Large horse-shoe magnets, made by the action of the electric current, are most proper. The magnetic action on different substances which are capable of being easily moved, differs not only according to the size, but also according to the nature of the substance. In consequence of this, Faraday divides all bodies into two classes. He calls the one magnetic, or, better, paramagnetic, and the other diamagnetic.

The matter of which a paramagnetic (magnetic) body consists is attracted by both poles of the horse-shoe magnet; on the contrary, the matter of a diamagnetic body is repelled. When a small iron bar is hung by untwisted silk between the poles of the magnet, so that its long diameter can easily move in a horizontal plane, it arranges itself axially, that is, parallel to the straight line which joins the poles, or to the magnetic axis of the poles; assuming at the end which is nearest the north pole, a south pole, and at the end nearest the south pole, a north pole. Whenever the little bar is removed from this

position, after a few oscillations, it returns again to its previous position. The whole class of paramagnetic bodies behave in a precisely similar way under similar circumstances; only in the intensity of the effects great differences occur.

On the contrary, diamagnetic bodies have their long diameters placed equatorially, that is, at right angles to the magnetic axis. They behave, as if at the end opposite to each pole of the magnet, the same kind of polarity existed.

In the first class of substances, besides iron, which is the best representative of the class, we have nickel, cobalt, manganese, chromium, cerium, titanium, palladium, platinum, osmium, aluminium, oxygen, and also most of the compounds of these bodies; most of them, even when in solution. According to Faraday, the following substances are also feebly paramagnetic (magnetic): paper, sealing-wax, Indian-ink, porcelain, asbestos, fluorspar, minium, cinnabar, binocide of lead, sulphate of zinc, tourmaline, graphite, and charcoal.

In the second class are placed bismuth, antimony, zinc, tin, cadmium, sodium, mercury, lead, silver, copper, gold, arsenic, uranium, rhodium, iridium, tungsten, phosphorus, iodine, sulphur, chlorine, hydrogen, and many of their compounds. Also, glass free from iron, water, alcohol, ether, nitric acid, hydrochloric acid, resin, wax, olive oil, oil of turpentine, caoutchouc, sugar, starch, gum, and wood. These are diamagnetic.

If diamagnetic and paramagnetic bodies are combined, their peculiar properties are destroyed. In most of these compounds, occasionally, in consequence of the presence of the smallest quantity of iron, the peculiar magnetic power remains more or less in excess. Thus green bottle glass and many varieties of crown glass are magnetic in consequence of the iron in it.

In order to examine the magnetic properties of fluids they are placed in very thin glass tubes, the ends of which are then closed by melting, they are then hung horizontally between the poles of the magnet. Under the influence of poles sufficiently powerful, they begin to swing, and according as the fluid contents are paramagnetic (magnetic), or diamagnetic, they assume an axial or equatorial position.

Under certain circumstances substances which belong to the paramagnetic class behave as if they were diamagnetic. This happens in consequence of a differential action. Thus, for example, when a glass tube full of a dilute solution of sulphate of iron is allowed to swing in a concentrated solution of sulphate of iron, instead of in the air, it assumes an equatorial position. The air, in consequence of the oxygen in it, is itself paramagnetic (magnetic). Hence, such bodies as appear to possess feeble diamagnetic properties, can only show their true properties when hung in a vacuum.

Faraday has tried the magnetic condition of gases in different ways. One way consisted in making soap bubbles with the gas, which he wished to investigate, and bringing these near the poles. Soap and

water alone is feebly diamagnetic. A bubble filled with oxygen was strongly attracted by the magnet. All other gases in the air are diamagnetic, that is, they are repelled. But, as Faraday has shown, in a different way, this partly arises from the paramagnetic (magnetic) property of the air. Thus he found that nitrogen, when this differential action was eliminated, was perfectly indifferent, whether it was condensed or rarefied, whether cooled or heated. When the temperature is raised, the diamagnetic property of gases in the air is increased. Hence the flame of a candle or of hydrogen is strongly repelled by the magnet. Even warm air is diamagnetic in cold air.

For some time it has been believed that bodies in a crystalline form had a special and peculiar behaviour when placed between the poles of a magnet. It appeared as though the magnetic directing power of the crystal had some peculiar relation to the position of its optic axis; so that, independently of the magnetic property of the substance of the crystal, if the crystal was positively optical, it possessed the power of placing its optic axis parallel with the line which joined the poles of the magnet, while optically negative crystals tried to arrange their axis at right angles to this line. This supposition is disproved by the excellent investigation of Tyndall and Knoblauch, who showed that exceptions to the above law were furnished by all classes of crystals, and proved that the action, instead of being independent of the magnetic nature of the mass, was completely reversed where, in isomorphous crystals, a magnetic constituent was substituted for a diamagnetic one. Rejecting the various new forces assumed, Tyndall and Knoblauch referred the observed phenomena to the modification of the magnetic force by structure, and they imitated the effects exactly, by means of substances whose structure had been modified by compression. In a later investigation Tyndall demonstrates the fundamental principle on which these phenomena depend, showing that the *entire mass* of a magnetic body is most strongly attracted when the attracting force acts parallel to the line of compression; and that a diamagnetic substance is most strongly repelled, when the repulsion acts along the same line. Hence, when such a body is freely suspended in the magnetic field, the line of compression must set axial or equatorial, according as the mass is magnetic or diamagnetic. Faraday was the first to establish a differential action of this kind in the case of bismuth; Tyndall extended it to several magnetic and diamagnetic crystals, and showed that it was not confined to them, but was a general property of matter. It was also proved that for a fixed distance the attraction of a magnetic sphere, and the repulsion of a diamagnetic sphere followed precisely the same law, both being exactly proportioned to the square of the exciting current.

ELECTRICITY.

IF glass, amber, or sealing-wax be rubbed with a dry cloth, it acquires the power of attracting light bodies, as feathers, dust, or bits of paper; this is the result of a new and peculiar condition of the body rubbed, called electrical excitation.

If a light downy feather be suspended by a thread of white silk, and a dry glass tube, excited by rubbing, be presented to it, the feather will be strongly attracted to the tube, adhere to its surface for a few seconds, and then fall off. If the tube be now excited anew, and presented to the feather, the latter will be strongly repelled.

The same experiment may be repeated with shellac or resin; the feather in its ordinary state will be drawn towards the excited body, and after touching, again driven from it with a certain degree of force.


Now, let the feather be brought into contact with the excited glass, so as to be repelled by that substance, and let a piece of excited sealing-wax be presented to it, a degree of attraction will be observed far exceeding that exhibited when the feather is in its ordinary state. Or, again, let the feather be made repulsive for sealing-wax, and then the excited glass be presented, strong attraction will ensue.

The reader will at once see the perfect parallelism between the effects described and some of the phenomena of magnetism; the electrical excitement having a twofold nature, like the opposite polarities of the magnet. A body to which one kind of excitement has been communicated is attracted by another body in the opposite state, and repelled by one in the same state. The excited glass and resin being to each other as the north and south poles of a pair of magnetized bars.

To distinguish these two different forms of excitement, terms are employed, which, although originating in some measure in theoretical views of the nature of the electrical disturbance, may be understood by the student as purely arbitrary and distinctive: it is customary to call the electricity manifested by glass *positive* or *vitreous*, and that developed in the case of shellac, and bodies of the same class, *negative* or *resinous*. The kind of electricity depends in some measure upon the nature of the surface; smooth glass rubbed with silk or wool becomes ordinarily positive, but when ground or roughened by sand or emery, it acquires, under the same circumstances, a negative charge.

The repulsion shown by bodies in the same electrical state is taken advantage of to construct instruments for indicating electrical excitement and pointing out its kind. Two balls of alder-pith, hung by threads or very fine metal wires, serve this purpose in many cases; they open out when excited in virtue of their mutual repulsion, and


show by the degree of divergence the extent to which the excitement has been carried. A pair of gold leaves suspended beneath a bell jar, and communicating with a metal cap above, constitute a much more

Fig. 59.*Fig. 60.*

delicate arrangement, and one of great value in all electrical investigations. These instruments are called *electroscopes* or *electrometers*: when excited by the communication of a known kind of electricity, they show, by an increased or diminished divergence, the state of an electrified body brought into their neighbourhood.

One kind of electricity can no more be developed without the other than one kind of magnetism; the rubber and the body rubbed always assume opposite states, and the positive condition on the surface of a mass of matter is invariably accompanied by a negative state in all surrounding bodies.

The induction of magnetism in soft iron has its exact counterpart in electricity; a body already electrified disturbs or polarizes the particles of all surrounding substances in the same manner and according to the same law, inducing a state opposite to its own in the nearer portions, and a similar state in the more remote parts. A series of globes suspended by silk threads, in the manner represented, will each

Fig. 61.

become electric by induction when a charged body is brought near the end of the series, like so many pieces of iron in the vicinity of a magnet, the positive half of each globe looking in one and the same

direction, and the negative half in the opposite one. The positive and negative signs are intended to represent the states.

The intensity of the induced electrical disturbance diminishes with the distance from the charged body; if this be removed or discharged, all the effects cease at once.

So far, the greatest resemblance may be traced between these two sets of phenomena; but here it seems in great measure to cease. The magnetic polarity of a piece of steel can awaken polarity in a second piece in contact with it by the act of induction, and in so doing loses nothing whatever of its power: this is an effect completely different from the apparent transfer or discharge of electricity constantly witnessed, which in the air and in liquids often gives rise to the appearance of a bright spark of fire. Indeed, ordinary magnetic effects comprise two groups of phenomena only, those namely of attraction and repulsion, and those of induction. But in electricity, in addition to phenomena very closely resembling these, we have the effects of *discharge*, to which there is nothing analogous in magnetism, and which takes place in an instant when any electrified body is put in communication with the earth by any one of the class of substances called conductors of electricity; all signs of electrical disturbance then ceasing.

These conductors of electricity, which thus permit discharge to take place through their mass, are contrasted with another class of substances called non-conductors or insulators. The difference, however, is only one of degree, not of kind; the very best conductors offer a certain resistance to the electrical discharge, and the most perfect insulators permit it to a small extent. The metals are by far the best conductors; glass, silk, shellac, and dry gas, or vapour of any sort, the very worst; and between these there are bodies of all degrees of conducting power.

Electrical discharges take place silently and without disturbance in good conductors of sufficient size. But if the charge be very intense, and the conductor very small or imperfect from its nature, it is often destroyed with violence.

When a break is made in a conductor employed in effecting the discharge of a highly-excited body, disruptive or spark-discharge, so well known, takes place across the intervening air, provided the ends of the conductor be not too distant. The electrical spark itself presents many points of interest in the modifications to which it is liable.


The time of transit of the electrical wave through a chain of good conducting bodies of great length is so minute as to be altogether inappreciable to ordinary means of observation. Professor Wheatstone's very ingenious experiments on the subject give, in the instance of motion through a copper wire, a velocity approaching that of light.

Electrical excitation is *apparent* only upon the surfaces of bodies, or those portions directed towards other objects capable of assuming the opposite state. An insulated ball charged with positive electricity,

and placed in the centre of the room, is maintained in that state by the inductive action of the walls of the apartment, which immediately become negatively electrified; in the interior of the ball there is absolutely no electricity to be found, although it may be constructed of open metal gauze, with meshes half an inch wide. Even on the surface the distribution of electrical force will not always be the same; it will depend upon the figure of the body itself, and its position with regard to surrounding objects. The polarity will always be highest in the projecting extremities of the same conducting mass, and greatest of all when these are attenuated to points, in which case the inequality becomes so great that discharge takes place to the air, and the excited condition cannot be maintained.

The construction and use of the common electrical machine, and other pieces of apparatus of great practical utility, will, by the aid of these principles, become intelligible.


Fig. 62.



A glass cylinder is mounted with its axis in a horizontal position, and provided with a handle or winch by which it may be turned. A leather cushion is made to press by a spring against one side of the cylinder, while a large metal conducting body, armed with a number of points next the glass, occupies the other; both cushion and conductor are insulated by glass supports, and to the upper edge of the former a piece of silk is attached long enough to reach half round the cylinder. Upon the cushion is spread a quantity of a soft amalgam

of tin, zinc, and mercury,* mixed up with a little grease; this substance is found by experience to excite glass most powerfully. The cylinder as it turns thus becomes charged by friction against the rubber, and as quickly discharged by the row of points attached to the great conductor; and as the latter is also completely insulated, its surface speedily acquires a charge of positive electricity, which may be communicated by contact to other insulated bodies. The maximum effect is produced when the rubber is connected by a chain or wire with the earth. If negative electricity be wanted, the rubber must be insulated and the conductor discharged.

Fig. 63.



Another form of the electrical machine consists of a circular plate of glass moving upon an axis, and provided with two pairs of cushions or rubbers, attached to the upper and lower parts of the wooden frame, covered with amalgam, between which the plate moves with considerable friction. An insulated conductor, armed as before with points, discharges the plate as it turns, the rubbers being at the same time connected with the ground by the wood-work of the machine, or by a strip of metal. This modification of the apparatus is preferred in all cases where considerable power is wanted.

* 1 part tin, 1 zinc, and 6 mercury.

In the practical management of electrical apparatus, great care must be taken to prevent deposition of moisture from the air upon the surface of the glass supports, which should always be varnished with fine lac dissolved in alcohol; the slightest film of water is sufficient to destroy the power of insulation. The rubbers also must be carefully dried before use, and the amalgam renewed if needful; in damp weather much trouble is often experienced in bringing the machine into powerful action.

When the conductor of the machine is charged with electricity, it acts indirectly on, and accumulates the contrary electricity to its own, at the surface of all the surrounding conductors. It produces the greatest effect on the conductor that is nearest to it, and which is in the best connexion with the ground whereby the electricity of the same kind as that of the machine may pass to the earth. As the inducing electricity attracts the induced electricity of an opposite kind; so, on the other hand, is the former attracted by the latter. Hence, the fluid which the conductor receives from the machine must especially accumulate at that spot to which another good conductor of electricity is opposed. If a metal disc is in connexion with the conductor of a machine, and if another similar disc, which is in good connexion with the earth, is placed opposite to it, we have an arrangement by which tolerably large and good conducting surfaces can be brought close to one another: thus the positive condition of the first disc, as well as the negative condition of the other, must be increased to a very considerable degree; the limit is in this case, however, soon reached, because the intervening air easily permits spark discharge to take place through its substance. With a solid insulating body, as glass or lac, this happens with much greater difficulty, even when the plate of insulating matter is very thin. It is on this principle that instruments for the *accumulation* of electricity depend, among which the Leyden jar is the most important.

A thin glass jar is coated on both sides with tin-foil, care being taken to leave several inches of the upper part uncovered; a wire, terminating in a metallic knob, communicates with the internal coating. When the outside of the jar is connected with the earth, and the knob put in contact with the conductor of the machine, the inner and outer surfaces of the glass become respectively positive and negative, until a very great degree of intensity has been attained. On completing the connexion between the two coatings by a metallic wire or rod, discharge occurs in the form of an exceedingly bright spark, accompanied by a loud snap; and if the body be interposed in the circuit, the peculiar and disagreeable sensation of the electric shock is felt at the moment of its completion.


Fig. 64.



By enlarging the dimensions of the jar, or by connecting together a number in such a manner that all may be charged and discharged simultaneously, the power of the apparatus may be greatly augmented. Thin wires of metal may be fused and dissipated; pieces of wood may be shattered, many combustible substances set on fire, and all the well-known effects of lightning exhibited upon a small scale.

The electric spark is often very conveniently employed in chemical inquiries for firing gaseous mixtures in close vessels. A small Leyden jar charged by the machine is the most effective contrivance for this purpose; but, not unfrequently, a method may be resorted to which involves less preparation. This is by the use of the electrophorus. A round tray or dish of tinned plate is prepared, having a stout wire

Fig. 65.



round its upper edge; the width may be about twelve inches, and the depth half an inch. This tray is filled with melted shellac, and the surface rendered as even as possible. A brass disc, with rounded edge, of about nine inches diameter, is also provided, and fitted with an insulating handle. When a spark is wanted, the resinous plate is excited by

striking with a dry, warm piece of fur, or a silk handkerchief; the cover is placed upon it, and touched by the finger. When the cover is raised, it is found so strongly charged by induction with positive electricity, as to give a bright spark; and, as the resin is not discharged by the cover, which merely touches it at a few points, sparks may be drawn as often as may be wished.

It is not known to what cause the disturbance of the electrical equilibrium of the atmosphere is due; experiment has shown that the higher regions of the air are usually in a positive state, the intensity of which reaches a maximum at a particular period of the day. In cloudy and stormy weather the distribution of the atmospheric electricity becomes much deranged, clouds near the surface of the earth often appearing in a negative state.

The circumstances of a thunderstorm exactly resemble those of the charge and discharge of a coated plate or jar; the cloud and the earth represent the two coatings, and the intervening air, the bad conducting body or *dielectric*. The polarities of the opposed surface and of the insulating medium between them become raised by mutual induction, until violent disruptive discharge takes place through the air itself, or through any other bodies which may happen to be in the interval. When these are capable of conducting freely, the discharge is silent and harmless; but in other cases it often proves highly destructive. These dangerous effects are now in a great measure

obviated by the use of lightning-rods attached to buildings, the erection of which, however, demands a number of precautions not always understood or attended to. The masts of ships may be guarded in like manner by metal conductors; Sir W. Snow Harris has devised a most ingenious plan for the purpose, which is now adopted, with the most complete success in the Royal Navy.

ELECTRIC CURRENT; ELECTRIC BATTERY.

When two solid conducting bodies are plunged into a liquid which acts upon them unequally, the electric equilibrium is also disturbed, the one acquiring the positive condition, and the other the negative. Thus, pieces of zinc and platinum put into dilute sulphuric acid, constitute an arrangement capable of generating electrical force: the zinc being the metal attacked, becomes negative; and the platinum remaining unaltered, assumes the positive condition; and on making a metallic communication in any way between the two plates, discharge ensues, as when the two surfaces of a coated and charged jar are put into connexion.


No sooner, however, has this occurred, than the disturbance is repeated; and as these successive charges and discharges take place through the fluid and metals with inconceivable rapidity, the result is an apparently continuous action, to which the term *electrical current* is given.

It is necessary to guard against the idea which the term naturally suggests, of an actual bodily transfer of something through the substance of the conductors, like water through a pipe; the real nature of all these phenomena is entirely unknown, and may perhaps remain so; the expression is convenient notwithstanding, and consecrated by long use; and with this caution, the very dangerous error of applying figurative language to describe an effect, and then seeking the nature of the effect from the common meaning of words, may be avoided.

The intensity of the electrical excitement developed by a single pair of metals and a liquid is too feeble to affect the most delicate gold-leaf electroscope; but, by arranging a number of such alterations in a connected series, in such a manner that the direction of the current shall be the same in each, the intensity may be very greatly exalted. The two instruments invented by Volta, called the pile and crown of cups, depend upon this principle.

Upon a plate of zinc is laid a piece of cloth, rather smaller than itself, steeped in dilute acid, or any liquid capable of exerting chemical action upon the zinc; upon this is placed a plate of copper, silver, or platinum; then a second piece of zinc, another cloth, and plate of inactive metal,


Fig. 66.



until a pile of about twenty alterations has been built up. If the two terminal plates be now touched with wet hands, the sensation of the electric shock will be experienced; but, unlike the momentary effect produced by the discharge of a jar, the sensation can be repeated at will by repeating the contact, and with a pile of one hundred such pairs, excited by dilute acid, it will be nearly insupportable. When such a pile is insulated, the two extremities exhibit strong positive and negative states; and when connexion is made between them by wires armed with points of hard charcoal or plumbago, the discharge takes place in the form of a bright enduring spark or stream of fire.

The second form of apparatus, or crown of cups, is precisely the same in principle, although different in appearance. A number of cups or glasses are arranged in a row or circle, each containing a piece of active and a piece of inactive metal, and a portion of exciting

Fig. 67.



liquid; zinc, copper, and dilute sulphuric acid, for example. The copper of the first cup is connected with the zinc of the second, the copper of the second with the zinc of the third, and so to the end of the series. On establishing a communication between the first and last plates by means of a wire, or otherwise, discharge takes place as before.

When any such electrical arrangement consists merely of a single pair of conductors and an interposed liquid, it is called a simple circuit; when two or more alterations are concerned, the term "compound circuit" is applied: they are called also, indifferently, voltaic batteries. In every form of such apparatus, however complex it may appear, the direction of the current may be easily understood and remembered. The polarity or disturbance may be considered to commence at the surface of the metal attacked, and to be propagated through the liquid to the inactive conductor, and thence back again by the connecting wire, these extremities of the battery being always respectively negative and positive when the apparatus is insulated. In common parlance, it is said that the current in every battery in an active state starts from the metal attacked, passes through the liquid to the second metal or conducting body, and returns by the wire or

other channel of communication; hence, in the pile and crown of cups just described, the current *in* the battery is always from the zinc to the copper; and *out* of the battery, from the copper to the zinc, as shown by the arrows.

In the modification of Volta's original pile, made by Mr. Cruikshank, the zinc and copper plates are soldered together and cemented water-tight into a mahogany trough, which thus becomes divided into a series of cells or compartments capable of receiving the exciting liquid. This apparatus is well fitted to exhibit effects of *tension*, to act upon the electroscopie and give shocks; hence its advantageous employment in the application of electricity to medicine, as a very few

Fig. 68.



minutes suffices to prepare it for use. The crown of cups was also put into a much more manageable form by Dr. Babington, and still farther improved, as will hereafter be seen, by Dr. Wollaston. Subsequently, various alterations have been made by different experimenters with a view of obviating certain defects in the common batteries, of which a description will be found towards the middle of the volume.

The term "galvanism," sometimes applied to this branch of electrical science, is used in honour of Professor Galvani, of Bologna, who, in 1790, made the very curious observation that convulsions could be produced in the limbs of a dead frog when certain metals were made to touch the nerve and muscle at the same moment. It was Volta, however, who pointed out the electrical origin of these motions, and although the explanation he offered of the source of the electrical disturbance is no longer generally adopted, his name is very properly associated with the invaluable instrument his genius gave to science.

In the year 1822 Professor Seebeck, of Berlin, discovered another source of electricity, to which allusion has already been made, namely, inequality of temperature and conducting power in different metals placed in contact, or in the same metal in different states of compression and density. Even with a great number of alternations, the current produced is exceedingly feeble compared with that generated by the voltaic pile.

Two or three animals of the class of fishes, as the *torpedo*, or *electric ray*, and the *electric eel* of South America, are furnished with a special organ or apparatus for developing electrical force, which is employed in defence, or in the pursuit of prey. Electricity is here seen to be


closely connected with nervous power; the shock is given at the will of the animal, and great exhaustion follows repeated exertion of the power.

ELECTRO-MAGNETISM.

Although the fact that electricity is capable, under certain circumstances, both of inducing and of destroying magnetism, has long been known, from the effects of lightning on the compass-needle and upon small steel articles, as knives and forks, to which polarity has suddenly been given by the stroke, it was not until 1819, that the laws of these phenomena were discovered by Professor Ørsted, of Copenhagen, and shortly afterwards fully developed by M. Ampère.

The action which a current of electricity, proceeding from any source, exerts upon a magnetized needle is quite peculiar. The poles or centres of magnetic force are neither attracted nor repelled by the wire carrying the current, but made to move *around* the latter, by a force which may be termed *tangential*, and which is exerted in a direction perpendicular at once to that of the current, and to the line joining the pole and the wire. Both poles of the magnet being thus acted upon at the same time, and in contrary directions, the needle is forced to arrange itself across the current, so that its axis, or the line joining the poles, may be perpendicular to the wire; and this is always the position which the needle will assume when the influence of terrestrial magnetism is in any way removed. This curious angular motion may even be shown by suspending a magnet in such a way that only one of its poles shall be subjected to the current; a permanent movement of rotation will continue as long as the current is kept up, its direction being changed by altering the pole, or reversing the current. The moveable connexions are made by mercury, into which the points of the conducting-wires dip. It is often of great practical consequence to be able to predict the direction in which a particular pole shall move by a given current, because in all galvanoscopes, and other instruments involving these principles, the movement of the needle is taken as an indication of the direction of the circulating current. And this is easily done by a simple mechanical aid to the memory:—Let the current be supposed to pass through a watch from

Fig. 69.




the face to the back; the motion of the north pole will be in the direction of the hands. Or a little piece of apparatus may be used if

reference is often required; this is a piece of pasteboard, or other suitable material cut into the form of an arrow for indicating the current, crossed by a magnet having its poles marked, and arranged in the true position with respect to the current. The direction of the latter in the wire of the galvanoscope can at once be known by placing the representative magnet in the direction assumed by the needle itself.

The common galvanoscope, consisting of a coil of wire having a compass-needle suspended on a point within it, is greatly improved by the addition of a second needle, as already in part described, and by a better mode of suspension, a long fibre of silk being used for the purpose. The two needles are of equal size, and magnetized as nearly as possible to the same extent; they are then immovably fixed together, parallel, and with their poles opposed, and hung with the lower needle in the coil and the upper one above it. The advantage gained is twofold; the system is *astatic*, unaffected, or nearly so, by the magnetism of the earth; and the needles being both acted upon in the same manner by the current, are urged with much greater force than one alone would be, all the actions of every part of the coil being strictly concurrent. A divided circle is placed below the upper needle, by which the angular motion can be measured; and the whole is inclosed in glass, to shield the needles from the agitation of the air. The whole is shown in fig. 70.


Fig. 70.



The action between the pole and the wire is mutual, as may be shown by rendering the wire itself moveable and placing a magnet in its vicinity: on completing the circuit the wire will be put in motion, and, if the arrangement permits, rotate around the magnetic pole.

A little consideration will show, that, from the peculiar nature of the


electro-dynamic force, a wire carrying a current, bent into a spiral or helix, must possess the properties of an ordinary magnetized bar, its extremities being attracted and repelled by the poles of a magnet. Such is really found to be the case, as may be proved by a variety of arrangements, among which it will be sufficient to cite the beautiful little apparatus of Professor de la Rive.—A short wide glass tube



is fixed into a cork ring of considerable size; a little voltaic battery, consisting of a single pair of copper and zinc plates is fitted to the tube, and to these the ends of the spiral are soldered. On filling the tube with dilute acid and floating the whole in a large basin of water, the helix will be observed to arrange itself in the magnetic meridian, and on trial it will be found to obey a magnet held near it in the most perfect manner, as long as the current circulates.

When an electric current is passed at right angles to a piece of iron or steel, the latter acquires magnetic polarity, either temporary or permanent as the case may be, the direction of the current determining the position of the poles. This effect is prodigiously increased by

Fig. 72.



causing the current to circulate a number of times round the bar, which then acquires extraordinary magnetic power. A piece of soft iron, worked into the form of a horse-shoe, and surrounded by a coil of copper wire covered with silk or cotton for the purpose of insulation, furnishes an excellent illustration of the inductive energy of the current in this respect; when the ends of the wire are put into communication with a small voltaic battery of a single pair of plates, the iron instantly becomes so highly magnetic as to be capable of sustaining a very heavy weight.


MAGNETO-ELECTRICITY.

A current of electricity can thus develop magnetism in a transverse direction to its own; in the same manner, magnetism can call into activity electric currents. If the two extremities of the coil of the electro-magnet above described be connected with a galvanoscope, and the iron magnetized by the application of a permanent steel horse-shoe magnet to the ends

of the bar, a momentary current will be developed in the wire, and pointed out by the movement of the needle. It lasts but a single

instant, the needle returning after a few oscillations to a state of rest. On removing the magnet, whereby the polarity of the iron is at once destroyed, a second current or wave will become apparent, but in the opposite direction to that of the first. By employing a very powerful steel magnet, surrounding its iron keeper or armature with a very long coil of wire, and then making the armature itself rotate in front of the faces of the magnet, so that its induced polarity shall be rapidly reversed, magneto-electric currents may be produced, of such intensity as to give bright sparks and most powerful shocks, and exhibit all the phenomena of voltaic electricity. Fig. 73 represents a very powerful arrangement of this kind.

Fig. 73.



When two covered wires are twisted together or laid side by side for some distance, and a current transmitted through the one, a momentary electrical wave will be induced in the other in the reverse direction, and on breaking connexion with the battery, a second single wave will become evident by the aid of the galvanoscope, in the same direction as that of the primary current. In the same way when a current of electricity passes through one turn in a coil of wire, it induces two secondary currents in all the other turns of the coil; when the circuit is closed, the first is moving in the opposite direction to the primary current; the second, when the circuit is broken, has a motion in the same direction as the primary current. The effect of

the latter is added to that of the primary current. Hence, if a wire coil be made part of the conducting wire of a weak electric pile, and if the primary current, by means of an appropriate arrangement, be made and broken in rapid succession, we can increase in a remarkable manner the effects which are produced at the moment of breaking the circuit either at the place of interruption—such as the spark-discharges; or, in secondary closing conductors, such as the action on the nerves or the decomposition of water.

M. Ampère discovered in the course of his investigations a number of extremely-interesting phenomena resulting from the action of electrical currents on each other, which become evident when arrangements are made for giving mobility to the conducting-wires. He found, that when two currents flowing in the same direction were made to approach each other, strong attraction took place between them, and, when in opposite directions, an equally strong repulsion. These effects, which are not difficult to demonstrate, have absolutely no relation that can be traced to ordinary electrical attractions and repulsions, from which they must be carefully distinguished; they are purely *dynamic*, having to do with electricity in motion. M. Ampère founded upon this discovery a most beautiful and ingenious hypothesis of magnetic actions in general, which explains very clearly the influence of the current upon the needle.

ELECTRICITY OF VAPOUR.

The electricity exhibited under certain peculiar circumstances by a jet of steam, first observed by mere accident, but since closely investigated by Mr. Armstrong, and also by Mr. Faraday, is now referred to the friction, not of the pure steam itself, but of particles of condensed water, against the interior of the exit tube. It is very doubtful whether *mere evaporation* can cause electrical disturbance, and the hope first entertained that these phenomena would throw light upon the cause of electrical excitement in the atmosphere, is now abandoned. The steam is usually positive, if the jet-pipe be constructed of wood or clean metal, but the introduction of the smallest trace of oily matter causes a change of sign. The intensity of the change is, *cæteris paribus*, increased with the elastic force of the steam. By this means effects have been obtained very far surpassing those of the most powerful plate electrical machines ever constructed.

PART II.

CHEMISTRY OF ELEMENTARY BODIES.

THE term *element* or *elementary substance* is applied in chemistry to those forms or modifications of matter which have hitherto resisted all attempts to decompose them. Nothing is ever meant to be affirmed concerning their real nature; they are simply elements to us at the present time; hereafter, by new methods of research, or by new combinations of those already possessed by science, many of the substances which now figure as elements may possibly be shown to be compounds; this has already happened, and may again take place.

The elementary bodies, at present recognized, amount to sixty-two in number; of these, about forty-seven belong to the class of metals. Several of these are of recent discovery and as yet very imperfectly known. The distinction between metals and non-metallic substances, although very convenient for purposes of description, is entirely arbitrary, since the two classes graduate into each other in the most complete manner.

It will be proper to commence with the latter and less numerous division. The elements are named as in the subjoined table, which however does not indicate the order in which they will be discussed.

NON-METALLIC
ELEMENTS.

Oxygen
Hydrogen
Nitrogen
Chlorine
Iodine
Bromine
Fluorine
Carbon
Silicon
Boron
Sulphur
Selenium
Phosphorus.

—

ELEMENTS OF INTER-
MEDIATE CHARACTERS.
Arsenic
Tellurium

Antimony
Chromium
Vanadium
Tungsten
(or Wolfram)
Molybdenum
Tantalum
(or Columbium)
Niobium
Pelopium
Titanium
Uranium
Platinum
Palladium
Rhodium
Iridium
Ruthenium
Osmium

METALS.

Gold
Aluminium
Beryllium
(or Glucinum)
Zirconium
Norium
Thorium
Yttrium
Cerium
Erbium
Terbium
Lantanum
Didymium
Bismuth
Tin
Mercury
Silver
Lead

Barium
Strontium
Calcium
Magnesium
Zinc
Cadmium
Nickel
Cobalt
Copper
Iron
Manganese
Lithium
Sodium
Potassium.


OXYGEN.

Whatever plan of classification, founded on the natural relations of the elements, be adopted, in the practical study of chemistry, it will always be found most advantageous to commence with the consideration of the great constituents of the ocean and the atmosphere.

Oxygen was discovered in the year 1774, by Scheele, in Sweden, and Dr. Priestley, in England, independently of each other, and described under the terms *empyreal air* and *dephlogisticated air*. The name oxygen* was given to it by Lavoisier some time afterwards. Oxygen exists in a free and uncombined state in the atmosphere, mingled with another gaseous body, nitrogen: no good direct means exist, however, for separating it from the latter, and, accordingly, it is always obtained for purposes of experiment by decomposing certain of its compounds, which are very numerous.

The red oxide of mercury, or *red precipitate* of the old writers, may be employed with this view. In this substance the attraction which holds together the mercury and the oxygen is so feeble, that simple exposure to heat suffices to bring about decomposition. The red pre-

Fig. 74.



cipitate is placed in a short tube of hard glass, to which is fitted a perforated cork, furnished with a piece of narrow glass tube, bent as in the figure. The heat of a spirit lamp being applied to the substance, decomposition speedily commences, globules of metallic mercury collect in the cool part of the wide tube, which answers the purpose of a

* From *ὀξύς*, acid, and *γεννάω*, I give rise to.


retort, while gas issues in considerable quantity from the apparatus.* This gas is collected and examined by the aid of the pneumatic trough, which consists of a vessel of water provided with a shelf, upon which stand the jars or bottles destined to receive the gas, filled with water and inverted. By keeping the level of the liquid above the mouth of the jar, the water is retained in the latter by the pressure of the atmosphere, and entrance of air is prevented. When brought over the extremity of the gas-delivering tube, the bubbles of gas rising through the water collect in the upper part of the jar and displace the liquid. As soon as one jar is filled, it may be removed, still keeping its mouth below the water-level, and another substituted. The whole arrangement is shown in fig. 74.

The experiment described is more instructive as an excellent case of the resolution by simple means of a compound body into its constituents, than valuable as a source of oxygen gas. A better and more economical method is to expose to heat in a retort, or flask furnished with a bent tube, a portion of the salt called chlorate of potassa. A common Florence flask serves perfectly well, the heat of a spirit-lamp being sufficient. The salt melts and decomposes with ebullition, yielding a very large quantity of oxygen gas, which may be collected in the way above described. The first portion of the gas often contains a little chlorine. The white saline residue in the flask is chloride of potassium. This plan, which is very easy of execution, is always adopted when very pure gas is required for analytical purposes.†

A third method, very good when perfect purity is not demanded, is to heat to redness, in an iron retort or gun-barrel, the black oxide of manganese of commerce, which under these circumstances suffers decomposition, although not to the extent manifest in the red precipitate.‡

If a little of the black oxide of manganese be finely powdered and mixed with chlorate of potassa, and this mixture heated in a flask or retort by a lamp, oxygen will be disengaged with the utmost facility, and at a far lower temperature than when the chlorate alone is used. All the oxygen comes from the chlorate, the manganese remaining quite


* Chemists are in the habit of representing the elements by symbols, and their compounds by formulæ. The same symbolical language which is fully explained in a subsequent section of the work (General Principles of Chemical Philosophy), is used for representing the changes which the chemical compounds undergo. For the benefit of the advanced student, the formulæ expressing the more important decompositions are now given in foot notes. The decomposition of oxide of mercury is thus represented:—



unaltered. The materials should be well dried in a capsule before their introduction into the flask. This experiment affords an instance of an effect by no means rare, in which a body seems to act by its mere presence, without taking any obvious part in the change brought about.


Whatever method be chosen—and the same remark applies to the collection of all other gases by similar means—the first portions of gas must be suffered to escape, or be received apart, as they are contaminated by the atmospheric air of the apparatus. The practical management of gases is a point of great importance to the chemical student, and one with which he must endeavour to familiarize himself. The water-trough just described is one of the most indispensable

Fig. 75.



articles of the laboratory, and by its aid all experiments on gases are carried on when the gases themselves are not sensibly acted upon by water. The trough is best constructed of japanned copper, the form and dimensions being regulated by the magnitude of the jars. It should

Fig. 76.



have a firm shelf, so arranged as to be always about an inch below the level of the water, and in the shelf a groove should be made about half an inch in width, and the same in depth, to admit the extremity of the delivery-tube beneath the jar, which stands securely upon the shelf. When the pneumatic trough is required of tolerably large dimensions, it may with great advantage have the form and disposition represented in the cut (fig. 75), one end of the groove spoken of, which crosses the shelf or shallow portion, is shown at *a*.

Gases are transferred from jar to jar with the utmost facility, by first filling the vessel into which the gas is to be passed with water,

inverting it, carefully retaining its mouth below the water-level, and then bringing beneath it the aperture of the jar containing the gas. On gently inclining the latter, the gas passes by a kind of inverted decantation into the second vessel. When the latter is narrow, a funnel may be placed loosely in its neck, by which loss of gas will be found to be prevented.


A jar wholly or partially filled with gas at the pneumatic trough may be removed by placing beneath it a shallow basin, or even a common plate so as to carry away enough water to cover the edge of the jar; and many gases, especially oxygen, may be so preserved for many hours without material injury.

Gas-jars are often capped at the top, and fitted with a stop-cock for transferring to bladders or caoutchouc bags. When such a vessel is to be filled with water, it may be slowly sunk in an upright position in the well of the pneumatic trough, the stop-cock being open to allow the air to escape, until the water reaches the brass cap. The cock is then to be turned, and the jar lifted upon the shelf, and filled with gas in the usual way. If the trough be not deep enough for this method of proceeding, the mouth may be applied to the stop-cock, and the vessel filled by sucking out the air until the water rises to the cap. In all cases it is proper to avoid as much as possible wetting the stop-cocks, and other brass apparatus.

Mr. Pepys contrived some years ago an admirable piece of apparatus for storing and retaining large quantities of gas. It consists of a drum or reservoir of sheet copper, surmounted by a shallow trough or cistern, the communication between the two being made by a couple of tubes furnished with stop-cocks, one of which passes nearly to the bottom of the drum, as shown in the sectional sketch. A short wide open tube is inserted obliquely near the bottom of the vessel, into which a plug may be tightly screwed. A stop-cock near the top serves to transfer gas to a bladder or tube apparatus. A glass water-gauge, affixed to the side of the drum, and communicating with both top and bottom, indicates the level of the liquid within.

To use the gas-holder, the plug is first to be screwed into the lower opening, and the drum completely filled with water. All three stop-cocks are then to be closed, and the plug removed. The pressure of the atmosphere retains the water in the gas-holder, and if no air-leakage occur, the escape of water is inconsiderable. The extremity of the delivery-tube is now to be well pushed through the open aperture into the drum, so that the bubbles of gas may rise without hindrance to the upper part, displacing the water, which flows out in the same proportion into a vessel


Fig. 77.



placed for its reception. When the drum is filled, or enough gas has been collected, the tube is withdrawn and the plug screwed into its place.

When a portion of the gas is to be transferred to a jar, the latter is to be filled with water at the pneumatic trough, carried by the help of a basin or plate to the cistern of the gas-holder, and placed over the shorter tube. On opening the cock of the neighbouring tube, the hydrostatic pressure of the column of water will cause condensation of the gas, and increase its elastic force, so that on gently turning

Fig. 78.



the cock beneath the jar, it will ascend into the latter in a rapid stream of bubbles. The jar, when filled, may again have the plate slipped beneath it, and be removed without difficulty.

Oxygen, when free or uncombined, is only known in the gaseous state, all attempts to reduce it to the liquid or solid condition by cold and pressure having completely failed. It is, when pure, colourless, tasteless, and inodorous, the sustaining principle of animal life, and of all the ordinary phenomena of combustion.

Bodies which burn in the air, burn with greatly-increased splendour in oxygen gas. If a taper be blown out, and then introduced while the wick remains red-hot, it is instantly rekindled: a slip of wood or a match is relighted in the same manner. This effect is highly characteristic of oxygen, there being but one other gas which possesses the same property; and this is easily distinguished by other means. The experiment with the match is also constantly used as a rude test of the purity of the gas when it is about to be collected from the retort, or when it has stood some time in contact with water exposed to air.

When a bit of charcoal is affixed to a wire, and plunged with a single point red-hot into a jar of oxygen, it burns with great brilliancy, throwing off beautiful scintillations, until, if the oxygen be in excess, it is completely consumed. An iron wire, or, still better, a steel watch-spring, armed at its extremity with a bit of lighted amadou, and introduced into a vessel of oxygen gas, exhibits a most beautiful appearance of combustion. If the experiment be made in a jar standing on a plate, the fused globules of black oxide of iron fix themselves in the glaze of the latter, after falling through a stratum of water half an inch in depth. Kindled sulphur burns with great beauty in oxygen, and phosphorus, under similar circumstances, exhibits a splendour which the eye is unable to support.

In these and many other similar cases which might be mentioned, the same ultimate effect is produced as in atmospheric air; the action is, however, more energetic, from the absence of the gas which in the air dilutes the oxygen, and enfeebles its chemical powers. The process

of respiration in animals is an effect of the same nature as common combustion. The blood contains substances which slowly burn by the aid of the oxygen thus introduced into the system. When this action ceases, life becomes extinct.

Oxygen is bulk for bulk a little heavier than atmospheric air, which is usually taken as the standard of unity for the specific gravity of gases. Its specific gravity is expressed by the number 1.1057;* 100 cubic inches at 60° (15°·5C), and under the mean pressure of the atmosphere, that is, 30 inches of mercury, weigh 34.29 grains.

It has been already remarked, that to determine with the utmost degree of accuracy the specific gravity of a gas is an operation of very great practical difficulty, but at the same time of very great importance. There are several methods which may be adopted for this purpose; the one below described appears, on the whole, to be the simplest and best. It requires, however, the most scrupulous care, and the observance of a number of minute precautions, which are absolutely indispensable to success.

The plan of the operation is as follows:—A large glass globe is to be filled with the gas to be examined, in a perfectly pure and dry state, having a known temperature, and an elastic force equal to that of the atmosphere at the time of the experiment. The globe so filled is to be weighed. It is then to be exhausted at the air-pump as far as convenient, and again weighed. Lastly, it is to be filled with dry air, the temperature and pressure of which are known, and its weight once more determined. On the supposition that the temperature and elasticity are the same in both cases, the specific gravity is at once obtained by dividing the weight of the gas by that of the air.

The globe or flask must be made very thin, and fitted with a brass cap, surmounted by a small but excellent stop-cock. A delicate thermometer should be placed in the inside of the globe secured to the cap. The gas must be generated at the moment, and conducted at once into the previously-exhausted vessel, through a long tube filled with fragments of pumice moistened with oil of vitriol, or some other extremely-hygroscopic substance, by which it is freed from all moisture. As the gas is necessarily generated under some pressure, the elasticity of that contained in the filled globe will slightly exceed the pressure of the atmosphere; and this is an advantage, since, by opening the stop-cock for a single instant, when the globe has attained an equilibrium of temperature, the tension becomes exactly that of the air, so that all barometrical correction is avoided, unless the pressure of the atmosphere should sensibly vary during the time occupied by the experiment. It is hardly necessary to remark that the greatest care must also be taken to purify and dry the air used as the standard of comparison, and to bring both gas and air as nearly as possible to the same temperature, to obviate the necessity of a correction, or at least to diminish almost to nothing the errors involved by such a process.

The compounds formed by the direct union of oxygen with other

* Dumas, *Ann. Chim. et Phys.*, 3rd Series, iii. 275.

bodies, bear the general name of oxides; these are very numerous and important. They are conveniently divided into three principal groups or classes. The first division contains all those oxides which resemble in their chemical relations potassa, soda, or the oxide of silver or of lead; these are denominated *alkaline* or *basic* oxides, or sometimes *salifiable bases*. The oxides of the second group have properties exactly opposed to those of the bodies mentioned; oil of vitriol and phosphoric acid may be taken as the typical representatives of the class: they are called *acids*, and they tend strongly to unite with the basic oxides. When this happens, what is called a *salt* is generated as sulphate of potassa, or phosphate of silver, each of these substances being compounded of a pair of oxides, one of which is highly basic and the other highly acid.

Then there remains a third group of what may be termed *neutral* oxides, from their slight disposition to enter into combination. The black oxide of manganese, already mentioned, is an excellent example.

It very frequently happens that a body is capable of uniting with oxygen in several proportions, forming a series of oxides, to which it is necessary to give distinguishing names. The rule in such cases is very simple, at least when the oxides of the metals are concerned. In such a series it is always found that one out of the number has a strongly-marked basic character; to this the term *protoxide* is generally given. The compounds next succeeding receive the names of *binoxide* or *deutoxide*, *teroxide* or *tritoxide*, &c., from the Latin or Greek numerals, the different grades of oxidation being thus indicated. If there be a compound between the protoxide and binoxide, the name *sesquioxide* is usually applied. So it is usual to call the highest oxide, not having distinctly acid characters, *peroxide*, from the Latin prefix, signifying excess. Any compound containing less oxygen than the protoxide, is called a *suboxide*. *Superoxide* or *hyperoxide* is a word sometimes used instead of peroxide.

Ozone.—It has long been known that dry oxygen, or atmospheric air, when exposed to the passage of a series of electric sparks, emits a peculiar and somewhat metallic odour. The same odour may be imparted to moist oxygen, by allowing phosphorus to remain for some time in it, and by several other processes. A more accurate examination of this odorous air has shown that, in addition to the smell, it assumes several properties not exhibited by pure oxygen. One of its most curious effects is the liberation of iodine from iodide of potassium. The odorous principle has been the subject of many researches lately—particularly by Prof. Schoenbein, of Basel, who proposed the name of *ozone** for it. It appears, however, that the peculiar odour perceived in the above processes, is not always occasioned by the same substance. Ozone, as produced by electrical processes, is probably a peculiar modification of oxygen, in which the affinities of this element are enhanced in a remarkable manner.†

* From $\delta\zeta\omega$, I smell.

† Another substance, which has been confused with this ozone, will be mentioned among the oxides of hydrogen.

HYDROGEN.

Hydrogen is always obtained for experimental purposes by deoxidizing water, of which it forms the characteristic component.*

If a tube of iron or porcelain, containing a quantity of filings, or turnings of iron, be fixed across a furnace, and its middle portion be made red-hot, and then the vapour of water transmitted over the heated metal, a large quantity of permanent gas will be disengaged from the tube, and the iron will become converted into oxide, and acquire an increase in weight. The gas is hydrogen; it may be collected over water and examined.

When zinc is put into water, chemical action of the liquid upon the metal is imperceptible; but if a little sulphuric acid be added, decomposition of the water ensues, the oxygen unites with the zinc, forming oxide of zinc, which is instantly dissolved by the acid, while the hydrogen, previously in union with that oxygen, is disengaged in the gaseous form. The reaction is represented in the subjoined diagram.†




The simplest method of preparing the gas is the following:—A wide-necked bottle is chosen, and fitted with a sound cork, perforated by two holes for the reception of a small tube-funnel reaching nearly to the bottom of the bottle, and a piece of bent glass tube to convey away the disengaged gas. Granulated zinc, or scraps of the malleable metal, are put into the bottle, together with a little water, and sulphuric acid slowly added by the funnel, the point of which should dip into the liquid. The evolution of gas is easily regulated by the supply of acid; and when enough has been discharged to expel the air of the vessel, it may be collected over water in a jar, or passed into a gas-holder. In the absence of zinc, filings of iron or small nails may be used, but with less advantage.

A little practice will soon enable the pupil to construct and arrange a variety of useful forms of apparatus, in which bottles and other

Fig. 79.



* Hence the name, from $\psi\delta\omega\rho$, water, and $\gamma\epsilon\nu\nu\acute{\alpha}\omega$.



articles always at hand, are made to supersede more costly instruments. Glass tube, purchased by weight of the maker, may be cut by seratching with a file, and then applying a little force with both hauds. It may be softened and bent, when of small dimensions, by the flame of a spirit-lamp, or even a candle or gas jet. Corks may be perforated by a heated wire, and the hole rendered smooth and eylin-driual by a round file; or the ingenious cork-borer of Dr. Mohr, now to be had of most instrument makers, may be used instead. Lastly, in the event of bad fitting, or unsoundness in the cork itself, a little yellow wax melted over the surface, or even a little grease applied with the finger, renders it sound and air-tight, when not exposed to heat.

Hydrogen is colourless, tasteless, and inodorous when quite pure. To obtain it in this condition, it must be prepared from the purest zinc that can be obtained, and passed in suceession through solutions of potassa and nitrate of silver. When prepared from commercial zinc it has a slight smell, which is due to impurity, and when iron has been used, the odour becomcs very strong and disagreeable. It is inflammable, burning, when kindled, with a pale-yellowish flame, and evolving much heat, but very little light. The result of the combustion is water. It is even less soluble in water than oxygen, and has never been liquefied. Although destitute of poisonous properties, it is ineapable of sustaining life.

In point of specific gravity, hydrogen is the lightest substance known; Dumas and Boussingault place its density between 0.0691 and 0.0695;* hence 100 cubic inches will weigh, under ordinary circumstances of pressure and temperature, 2.14 grains.

When a gas is much lighter or much heavier than atmospheric air, it may often be collected and examined without the aid of the pneu-

Fig. 80.



matic trough. A bottle or narrow jar may be filled with hydrogen without much admixture of air, by inverting it over the extremity of an upright tube delivering the gas. In a short time, if the supply be copious, the air will be wholly displaced and the vessel filled. It may now be removed, the vertical position being carefully retained, and closed by a stopper or glass plate. If the mouth of the jar be wide, it must be partially closed by a piece of earboard during the operation. This method of collecting gases by displacement is often extremely useful. Hydrogen was formerly used for filling air-balloons, being made for the purpose on the spot from zinc or iron and dilute sulphuric acid. Its use is superseded by that of coal-gas, which may be made very light by employing a high temperature in the manufacture. Although far inferior to pure hydrogen in buoyant power, it is found

in practice to possess advantages over that substance, while its greater

* Ann. Chim. et Phys., 3rd Series, viii. 201.

density is easily compensated by increasing the magnitude of the balloon.

There is a very remarkable property enjoyed by gases and vapours in general, which is seen in a high degree of intensity in the case of hydrogen; this is what is called *diffusive power*. If two bottles containing gases, which do not act chemically upon each other at common temperatures, be connected by a narrow tube and left for some time, these will be found at the expiration of a certain period, depending much upon the narrowness of the tube and its length, uniformly mixed, even though the gases differ greatly in density, and the system has been arranged in a vertical position, with the heavier gas downwards. Oxygen and hydrogen can thus be made to mix, in a few hours, against the action of gravity, through a tube a yard in length, and not more than one quarter of an inch in diameter; and the fact is true of all other gases which are destitute of direct action upon each other.

If a vessel be divided into two portions by a diaphragm or partition of porous earthenware or dry plaster of Paris, and each half filled with a different gas, diffusion will immediately commence through the pores of the dividing substance, and will continue until perfect mixture has taken place. All gases, however, do not permeate the same porous body, or, in other words, do not pass through narrow orifices with the same degree of facility. Professor Graham, to whom we are indebted for a very valuable investigation of this interesting subject, has established the existence of a very simple relation between the rapidity of diffusion and the density of the gas which is expressed by saying that the diffusive power varies inversely as the square root of the density of the gas itself. Thus, in the experiment supposed, if one half of the vessel be filled with hydrogen and the other half with oxygen, the two gases will penetrate the diaphragm at very different rates; four cubic inches of hydrogen will pass into the oxygen side, while one cubic inch of oxygen travels in the opposite direction. The densities of the two gases are to each other in the proportion of 1 to 16; their relative rates of diffusion will be inversely as the square roots of these numbers, *i. e.* as 4 to 1.

By making the diaphragm of some flexible material, as a piece of membrane, the accumulation of the lighter gas on the side of the heavier may be rendered evident by the bulging of the membrane. The simplest and most striking method of making the experiment is by the use of Professor Graham's diffusion-tube. This is merely a piece of wide glass tube ten or twelve inches in length, having one of its extremities closed by a plate of plaster of Paris about half an inch thick,

Fig. 81.



and well dried. When the tube is filled by displacement with hydrogen, and then set upright in a glass of water, the level of the liquid rises in the tube so rapidly, that its movement is apparent to the eye, and speedily attains a height of several inches above the water in the glass. The gas is actually rarefied by its superior diffusive power over that of the external air.

It is impossible to over-estimate the importance in the economy of Nature of this very curious law affecting the constitution of gaseous bodies: it is the principal means by which the atmosphere is preserved in an uniform state, and the accumulation of poisonous gases and exhalations in towns and other confined localities prevented.

A distinction must be carefully drawn between real diffusion through small apertures, and the apparently similar passage of gas through wet or moist membranes and other substances, which is really due to temporary liquefaction or solution of the gas, and is an effect completely different from diffusion properly so called. For example, the diffusive power of carbonic acid into atmospheric air is very small, but it passes into the latter through a wet bladder with the utmost ease, in virtue of its solubility in the water with which the membrane is moistened. It is by such a process that the function of respiration is performed; the aëration of the blood in the lungs, and the disengagement of the carbonic acid, are effected through wet membranes; the blood is never brought into actual contact with the air, but receives its supply of oxygen, and disengarrasses itself of carbonic acid by this kind of spurious diffusion.

The high diffusive power of hydrogen against air renders it impossible to retain that gas for any length of time in a bladder or caoutchouc bag: it is even unsafe to keep it long in a gas-holder, lest it should become mixed with air by slight accidental leakage, and rendered explosive.*

It has been stated that, although the light emitted by the flame of pure hydrogen is exceedingly feeble, yet the temperature of the flame is very high. This temperature may be still farther exalted by previously mixing the hydrogen with as much oxygen as it requires for combination, that is, as will presently be seen, exactly half its volume. Such a mixture burns like gunpowder, independently of the external air. When raised to the requisite temperature for combination, the two gases unite with explosive violence. If a strong bottle, holding not more than half a pint, be filled with such a mixture, the introduction of a lighted match or red-hot wire determines in a moment the union of the gases. By certain precautions, a mixture of oxygen and hydrogen can be burned at a jet without communication of fire to the contents of the vessel; the flame is in this case *solid*.

* Professor Graham has since published a very extensive series of researches on the passage of gases through narrow tubes, which will be found in detail in the Philosophical Transactions for 1846, p. 572.

A little consideration will show, that all ordinary flames burning in the air or in pure oxygen are, of necessity, hollow. The act of combustion is nothing more than the energetic union of the substance burned with the surrounding oxygen; and this union can only take place at the surface of the burning body. Such is not the case, however, with the flame now under consideration; the combustible and the oxygen are already mixed, and only require to have their temperature a little raised to cause them to combine in every part. The flame so produced is very different in physical characters from that of a simple jet of hydrogen or any other combustible gas; it is long and pointed, and very remarkable in appearance.

The safety-jet of Mr. Hemming, the construction of which involves a principle not yet discussed, may be adapted to a common bladder containing the mixture, and held under the arm, and the gas forced through the jet by a little pressure. Although the jet, properly constructed, is believed to be safe, it is best to use nothing stronger than a bladder, for fear of injury in the event of an explosion. The gases are often contained in separate reservoirs, a pair of large gas-holders, for example, and only suffered to mix in the jet itself; as in the contrivance of Professor Daniell: in this way all danger is avoided. The eye speedily becomes accustomed to the peculiar appearance of the true hydro-oxygen flame, so as to permit the supply of each gas to be exactly regulated by suitable stop-cocks attached to the jet (fig. 82).

Fig. 82.



Fig. 83.



A piece of thick platinum wire introduced into the flame of the hydro-oxygen blowpipe melts with the greatest ease; a watch-spring or small steel file burns with the utmost brilliancy, throwing off showers of beautiful sparks; an incombustible oxidized body, as magnesia or lime, becomes so intensely ignited, as to glow with a light insupportable to the eye, and to be susceptible of employment as a most powerful illuminator, as a substitute for the sun's rays in the solar microscope, and for night-signals in trigonometrical surveys.

If a long glass tube, open at both ends, be held over a jet of hydrogen (fig. 83), a series of musical sounds are sometimes produced by the partial extinction and rekindling of the flame by the ascending current of air. These little explosions succeed each other at regular intervals, and so rapidly as to give rise to a musical note, the pitch depending chiefly upon the length and diameter of the tube.

Although oxygen and hydrogen may be kept mixed at common temperatures for any length of time without combination taking place, yet, under particular circumstances, they unite quietly and without explosion. Some years ago Professor Döbereiner, of Jena, made the curious observation, that finely-divided platinum possessed the power of determining the union of the gases; and, more recently, Mr. Faraday has shown that the state of minute division is by no means indispensable, since rolled plates of the metal have the same property, provided their surfaces are absolutely clean. Neither is the effect strictly confined to platinum; other metals, as palladium and gold, and even stones and glass, enjoy the same property, although to a far inferior degree, since they often require to be aided by a little heat. When a piece of platinum-foil, which has been cleaned by hot oil of vitriol and thorough washing with distilled water, is thrust into a jar containing a mixture of oxygen and hydrogen standing over water, combination of the two gases immediately begins, and the level of the water rapidly rises whilst the platinum becomes so hot, that drops of water accidentally falling upon it enter into ebullition. If the metal be very thin and exceedingly clean, and the gases very pure, then its temperature rises after a time to actual redness, and the residue of the mixture explodes. But this is an effect altogether accidental, and dependent upon the high temperature of the platinum, which high temperature has been produced by the preceding quiet combination of the two bodies. When the platinum is reduced to a state of minute division, and its surface thereby much extended, it becomes immediately red-hot in a mixture of hydrogen and oxygen, or hydrogen and air; a jet of hydrogen thrown upon a little of the spongy metal, contained in a glass or capsule, becomes at once kindled, and on this principle machines for the production of instantaneous light have been constructed. These, however, only act well when constantly used; the spongy platinum is apt to become damp by absorption of moisture from the air, and its power is then for the time lost.

The best explanation that can be given of these curious effects is to

suppose that solid bodies in general have, to a greater or less extent, the property of condensing gases upon their surfaces, and that this faculty is enjoyed pre-eminently by certain of the non-oxidizable metals as platinum and gold. Oxygen and hydrogen may thus, under these circumstances, be brought, as it were, within the sphere of their mutual attractions by a temporary increase of density, whereupon combination ensues.

Coal-gas and ether or alcohol vapour may be made to exhibit the phenomenon of quiet oxidation under the influence of this remarkable surface-action. A close spiral of slender platinum wire, a roll of thin foil or even a common platinum crucible, heated to dull redness, and then held in a jet of coal-gas, becomes strongly ignited, and remains in that state as long as the supply of mixed gas and air is kept up, the temperature being maintained by the heat disengaged in the act of union. Sometimes the metal becomes white hot, and then the gas takes fire.


A very pleasing experiment may be made by attaching such a coil of wire to a card, and suspending it in a glass containing a few drops of ether, having previously made it red-hot in the flame of a spirit-lamp. The wire continues to glow until the oxygen of the air is exhausted, giving rise to the production of an irritating vapour which attacks the eyes. The combustion of the ether is in this case but partial; a portion of its hydrogen is alone removed, and the whole of the carbon left untouched.

A coil of thin platinum wire may be placed over the wick of a spirit-lamp, or a ball of spongy platinum sustained just above the cotton; on lighting the lamp, and then blowing it out as soon as the metal appears red-hot, slow combustion of the spirit drawn up by the capillarity of the wick will take place, accompanied by the pungent vapours just mentioned, which may be modified, and even rendered agreeable, by dissolving in the liquid some sweet-smelling essential oil or resin.

Hydrogen forms numerous compounds with other bodies, although it is greatly surpassed in this respect not only by oxygen, but by many of the other elements. The chemical relations of hydrogen tend to place it among the metals. The great discrepancy in physical properties is perhaps more apparent than real. Hydrogen is yet unknown in the solid condition, while, on the other hand, the vapour of the metal mercury is as transparent and colourless as hydrogen itself. This vapour is only about seven times heavier than atmospheric air, so that the difference in this respect is not nearly so great as that in the other direction between air and hydrogen.

There are two oxides of hydrogen, namely, *water*, and a very pecu-

Fig. 84.




liar substance, discovered in the year 1818 by M. Thenard, called *binoxide of hydrogen*.

It appears that the composition of water was first demonstrated in the year 1781 by Mr. Cavendish,* but the discovery of the exact proportions in which oxygen and hydrogen unite in generating that most important compound has from time to time to the present day occupied the attention of some of the most distinguished cultivators of chemical science. There are two distinct methods of research in chemistry, the *analytical*, or that in which the compound is resolved into its elements, and the *synthetical*, in which the elements are made to unite and produce the compound. The first method is of much more general application than the second; but in this particular instance both may be employed, although the results of the synthesis are the more valuable.

The most elegant example of analysis of water would probably be found in its decomposition by voltaic electricity. When water is acidulated so as to render it a conductor, and a portion interposed between a pair of platinum plates connected with the extremities

Fig. 85.



of a voltaic apparatus of moderate power, decomposition of the liquid takes place in a very interesting manner; oxygen, in a state of perfect purity, is evolved from the water in contact with the plate belonging to the copper end of the battery, and hydrogen, equally pure, is disengaged at the plate connected with the zinc extremity, the middle portions of liquid remaining apparently unaltered. By placing small graduated jars, over the platinum plates, the gases can be collected, and their quantities determined. The figure in the margin will show at a glance the whole arrangement; the conducting wires pass through the bottom of the glass cup, and away to the battery.

When this experiment has been continued a sufficient time, it will be found that the volume of the hydrogen is a *very* little above twice that of the oxygen; were it not for the accidental circumstance of

* A claim to the discovery of the composition of water on behalf of Mr. James Watt has been very strongly urged, and supported by such evidence that the reader of the controversy may be led to the conclusion that the discovery was made by both parties, nearly simultaneously, and unknown to each other.

Fig. 86.



oxygen being sensibly more soluble in water than hydrogen, the proportion of two to one by measure would come out exactly.


Water, as Mr. Grove has lately shown, is likewise decomposed into its constituents by heat. The effect is produced by introducing platinum balls, ignited by electricity or other means, into water or steam. The two gases are, however, obtained in very small quantities at a time.

When oxygen and hydrogen, both as pure as possible, are mixed in the proportions mentioned, passed into a strong glass tube filled with mercury, and exploded by the electric spark, all the mixture disappears, and the mercury is forced up into the tube, filling it completely. The same experiment may be made with the explosion-vessel or eudiometer of Mr. Cavendish. (Fig. 86.) The instrument is exhausted at the air-pump, and then filled from a capped jar with the mixed gases; on passing an electric spark by the wires shown at *a*, explosion ensues, and the glass becomes bedewed with moisture, and if the stop-cock be then opened under water, the latter will rush in and fill the vessel, leaving merely a bubble of air, the result of imperfect exhaustion.

The process upon which most reliance is placed is that in which pure oxide of copper is reduced at a red heat by hydrogen, and the water so formed collected and weighed. This oxide suffers no change by heat, alone, but the momentary contact of hydrogen, or any common combustible matter at a high temperature, suffices to reduce a corresponding portion to the metallic state. Fig. 87 will serve to convey some idea of the arrangement adopted in researches of this kind.

A copious supply of hydrogen is procured by the action of dilute sulphuric acid upon the purest zinc that can be obtained; the gas is made to pass in succession through solutions of silver and strong caustic potassa, by which its purification is completed. After this, it

Fig. 87.



is conducted through a tube three or four inches in length, filled with fragments of pumice-stone steeped in concentrated oil of vitriol, or with anhydrous phosphoric acid. These substances have such an extraordinary attraction for aqueous vapour, that they dry the gas completely during its transit. The extremity of this tube is shown at *a*. The dry hydrogen thus arrives at the part of the apparatus con-

taining the oxide of copper, represented at *b*; this consists of a two-necked flask of very hard white glass, maintained at a red heat by a spirit-lamp placed beneath. As the decomposition proceeds, the water produced by the reduction of the oxide begins to condense in the second neck of the flask, whence it drops into the receiver *c*, provided for the purpose. A second desiccating tube prevents the loss of aqueous vapour by the current of gas which passes in excess.

Before the experiment can be commenced, the oxide of copper, the purity of which is well ascertained, must be heated to redness for some time in a current of dry air; it is then suffered to cool, and very carefully weighed with the flask. The empty receiver and second drying tube are also weighed, the disengagement of gas set up, and when the air has been displaced, heat slowly applied to the oxide. The action is at first very energetic; the oxide often exhibits the appearance of ignition; as the decomposition proceeds, it becomes more sluggish, and requires the application of a considerable heat to effect its completion.

When the process is at an end, and the apparatus perfectly cool, the stream of gas is discontinued, dry air is drawn through the whole arrangement, and, lastly, the parts are disconnected and reweighed. The loss of the oxide of copper gives the oxygen; the gain of the receiver and its drying-tube indicates the water, and the difference between the two the hydrogen.

A set of experiments, made in Paris in the year 1820,* by MM. Dulong and Berzelius, gave as a mean result for the composition of water by weight, 8.009 parts oxygen to 1 part hydrogen; numbers so nearly in the proportion of 8 to 1, that the latter have usually been assumed to be true.

Quite recently the subject has been reinvestigated by M. Dumas,† with the most scrupulous precision, and the above supposition fully confirmed. The composition of water may therefore be considered as established; it contains by weight 8 parts oxygen to 1 part hydrogen, and by measure, 1 volume oxygen to 2 volumes hydrogen. The densities of the gases, as already mentioned, correspond very closely with these results.

The physical properties of water are too well known to need lengthened description: it is, when pure, colourless and transparent, destitute of taste and odour, and an exceedingly bad conductor of electricity of low tension. It attains its greatest density towards 40° (4°.5C), freezes at 32° (0°C), and boils under the pressure of the atmosphere at or near 212° (100°C). It evaporates at all temperatures. One cubic inch at 62° (15°.7C) weighs 252.45 grains. It is 815 times heavier than air; an imperial gallon weighs 70,000 grains or 10 lbs. avoirdupois. To all ordinary observation, water is incompressible; very accurate experiments have nevertheless shown

* Ann. Chim. et Phys. xv. 386.

† Ann. Chim. et Phys. 3rd series, viii. 189.

that it does yield to a small extent when the power employed is very great; the diminution of volume for each atmosphere of pressure being about 51-millionths of the whole.

Clear water, although colourless in small bulk, is blue like the atmosphere when viewed in mass. This is seen in the deep ultramarine tint of the ocean, and perhaps in a still more beautiful manner in the lakes of Switzerland and other Alpine countries, and in the rivers which issue from them; the slightest admixture of mud or suspended impurity destroying the effect. The same magnificent colour is visible in the fissures and caverns found in the ice of the glaciers, which is usually extremely pure and transparent within, although foul upon the surface.

Steam, or vapour of water, in its state of greatest density at 212° (100°C), compared with air at the same temperature, and possessing an equal elastic force, has a specific gravity expressed by the fraction 0.625. In this condition it may be represented as containing, in every two volumes, two volumes of hydrogen, and one volume of oxygen.

Water seldom or never occurs in nature in a state of perfect purity: even the rain which falls in the open country contains a trace of ammoniacal salt, while rivers and springs are invariably contaminated to a greater or less extent with soluble matters, saline and organic. Simple filtration through a porous stone or a bed of sand will separate suspended impurities, but distillation alone will free the liquid from those that are dissolved. In the preparation of distilled water, which is an article of large consumption in the scientific laboratory, it is proper to reject the first portions which pass over, and to avoid carrying the distillation to dryness. The process may be conducted in a metal still furnished with a worm or condenser of silver or tin; lead must not be used.

The ocean is the great recipient of the saline matter carried down by the rivers which drain the land; hence the vast accumulation of salts. The following table will serve to convey an idea of the ordinary composition of sea-water; the analysis is by Dr. Schweitzer,* of Brighton, the water being that of the British Channel:—

1000 grains contained

Water	964.745
Chloride of sodium	27.059
Chloride of potassium	0.766
Chloride of magnesium	3.666
Bromide of magnesium	0.029
Sulphate of magnesia	2.296
Sulphate of lime	1.406
Carbonate of lime	0.033
Traces of iodine and ammonical salt	.

1000.000

* Phil. Mag. July, 1839.

Its specific gravity was found to be 1.0274 at 60° (15°·5C).

Sea-water is liable to variations of density and composition by the influence of local causes, such as the proximity of large rivers or masses of melting ice, and other circumstances.

Natural springs are often impregnated to a great extent with soluble substances derived from the rocks they traverse; such are the various mineral waters scattered over the whole earth, and to which medicinal virtues are attributed. Some of these hold protoxide of iron in solution, and are effervescent from carbonic acid gas; others are alkaline, probably from traversing rocks of volcanic origin; some contain a very notable quantity of iodine or bromine. Their temperatures also are as variable as their chemical nature. A tabular notice of some of the most remarkable of these waters will be found in the Appendix.

Water enters into direct combination with other bodies, forming a class of compounds called *hydrates*; the action is often very energetic, much heat being evolved, as in the case of the slaking of lime, which is really the production of a hydrate of that base. Sometimes the attraction between the water and the second body is so great that the compound is not decomposable by any heat that can be applied; the hydrates of potassa and soda, and of phosphoric acid, furnish examples. Oil of vitriol is a hydrate of sulphuric acid, from which the water cannot be thus separated.

Water very frequently combines with saline substances in a less intimate manner than that above described, constituting what is called water of crystallization, from its connexion with the geometrical figure of the salt. In this case it is easily driven off by the application of heat.

Lastly, the solvent properties of water far exceed those of any other liquid known. Among salts, a very large proportion are soluble to a greater or less extent, the solubility usually increasing with the temperature, so that a hot saturated solution deposits crystals on cooling. There are a few exceptions to this law, one of the most remarkable of which is common salt, the solubility of which is nearly the same at all temperatures; the hydrate and certain organic salts of lime, also, dissolve more freely in cold than in hot water.

Water dissolves gases, but in very unequal quantities; some, as hydrogen, oxygen, and atmospheric air, are but little acted upon; others, as ammonia and hydrochloric acid, are absorbed to an enormous extent; and between these extremes there are various intermediate degrees. Generally, the colder the water, the more gas does it dissolve; a boiling heat disengages the whole, if the gas be not very soluble.

When water is heated in a strong vessel to a temperature above that of the ordinary boiling-point, its solvent powers are still farther increased. Dr. Turner inclosed in the upper part of a high-pressure steam-boiler, worked at 300° (149°C), pieces of plate and crown

glass. At the expiration of four months the glass was found completely corroded by the action of the water; what remained was a white mass of silica, destitute of alkali, while stalactites of siliceous matter, above an inch in length, depended from the little wire cage which inclosed the glass. This experiment tends to illustrate the changes which may be produced by the action of water at a high temperature in the interior of the earth upon felspathic and other rocks. Something of the sort is manifest in the Geyser springs of Iceland, which deposit siliceous sinter.*

Binoxide of hydrogen, sometimes called *oxygenated water*, is an exceedingly interesting substance, but unfortunately very difficult of preparation. It is formed by dissolving the binoxide of barium in dilute hydrochloric acid, carefully cooled by ice, and then precipitating the baryta by sulphuric acid; the excess of oxygen of the binoxide, instead of being disengaged as gas, unites with a portion of the water, and converts it into binoxide of hydrogen. This treatment is repeated with the same solution and fresh portions of the binoxide of barium until a considerable quantity of the latter has been consumed, and a corresponding amount of binoxide of hydrogen formed. The liquid yet contains hydrochloric acid, to get rid of which it is treated in succession with sulphate of silver and baryta-water. The whole process requires the utmost care and attention. The binoxide of barium itself is prepared by exposing pure baryta, contained in a red-hot porcelain tube, to a stream of oxygen. The solution of binoxide of hydrogen may be concentrated under the air-pump receiver until it acquires the specific gravity of 1.45. In this state it presents the aspect of a colourless, transparent, inodorous liquid, possessing remarkable bleaching powers. It is very prone to decomposition; the least elevation of temperature causes effervescence, due to the escape of oxygen gas; near 212° (100°C) it is decomposed with explosive violence. Binoxide of hydrogen contains exactly twice as much oxygen as water, or 16 parts to 1 part of hydrogen.

A *teroxide of hydrogen*† likewise exists, although it has never been obtained in the pure state. Its properties are similar to those of the binoxide; it is likewise a powerful oxidizing agent. According to recent researches of Dr. Baumert, minute quantities of this substance are formed in the decomposition of water by electricity, and impart the odour by which the products of this process are characterized. It has been mentioned that this peculiar odour, which is evolved in several processes, such as the oxidation of phosphorus, the passage of the electric spark through gases containing oxygen, is ascribed to the

* Phil. Mag. Oct. 1834.

† In symbols the composition of water and binoxide of hydrogen is thus expressed :—

Water	HO
Binoxide of Hydrogen	HO ₂
Teroxide of Hydrogen	HO ₃

same substance, namely, *ozone*. Dr. Baumert's experiments show there are at least two substances which have hitherto been confounded under the term ozone; for the odour produced by the passage of the electric spark through atmospheric air cannot possibly be due to the formation of teroxide of hydrogen. It is not known whether the odorous substance, which is generated during the oxidation of phosphorus, is teroxide of hydrogen, or identical with the ozone of the electric spark.

NITROGEN.

Nitrogen* constitutes about $\frac{4}{5}$ of the atmosphere, and enters into a great variety of combinations. It may be prepared for the purpose of experiment by several methods. One of the simplest of these is to burn out the oxygen from a confined portion of air by phosphorus, or by a jet of hydrogen.

A small porcelain capsule is floated on the water of the pneumatic trough, and a piece of phosphorus placed in it and set on fire. A bell-jar is then inverted over the whole, and suffered to rise on the

shelf of the trough, so as to project a little over its edge. At first the heat causes expansion of the air of the jar, and a few bubbles are expelled, after which the level of the water rises considerably. When the phosphorus becomes extinguished by exhaustion of the oxygen, and time has been given for the subsidence of the cloud of finely-divided snow-like phosphoric acid, which floats in the residual gas, the nitrogen may be decanted into another vessel, and its properties examined.

Fig. 88.



Prepared by the foregoing process, nitrogen is contaminated by a little vapour of phosphorus, which communicates its peculiar odour. A preferable method is to fill a porcelain tube with turnings of copper, or, still better, with the spongy metal obtained by reducing the oxide by hydrogen; to heat this tube to redness, and then pass through it a stream of atmospheric air, the oxygen of which is entirely removed during its progress by the heated copper.

If chlorine gas be passed into solution of ammonia, the latter substance, which is a compound of nitrogen with hydrogen, is decomposed; the chlorine combines with the hydrogen, and the nitrogen is

* *i. e.* Generator of nitre; also called azote, from α , privative, and $\zeta\omega\eta$, life.

set free with effervescence. In this manner very pure nitrogen can be obtained. In making this experiment, it is necessary to stop short of saturating or decomposing the whole of the ammonia, otherwise there will be great risk of accident from the formation of an exceedingly dangerous explosive compound formed by the contact of chlorine with an ammoniacal salt.

Nitrogen is destitute of colour, taste, and smell; it is a little lighter than air, its density being according to Dumas, 0.972. 100 cubic inches, at 60° (15°·5C), and 30 inches barometer, will therefore weigh 30.14 grains. Nitrogen is incapable of sustaining combustion or animal existence, although, like hydrogen, it has no positive poisonous properties; neither is it soluble to any notable extent in water or in caustic alkali; it is, in fact, best characterized by negative properties.

The exact composition of the atmosphere has repeatedly been made the subject of experimental research. Besides nitrogen and oxygen, the air contains a little carbonic acid, a very variable proportion of aqueous vapour, a trace of ammonia, and, *perhaps*, a little carbonetted hydrogen. The oxygen and nitrogen are in a state of mixture, not of combination, yet their ratio is always uniform. Air has been brought from lofty Alpine heights, and compared with that from the plains of Egypt; it has been brought from an elevation of 21,000 feet by the aid of a balloon; it has been collected and examined in London and Paris, and many other districts; still the proportions of oxygen and nitrogen remain unaltered, the diffusive energy of the gases being adequate to maintain this perfect uniformity of mixture. The carbonic acid, on the contrary, being much influenced by local causes, varies considerably. In the following table the proportion of oxygen and nitrogen are given on the authority of M. Dumas, and the carbonic acid on that of De Saussure; the ammonia, the discovery of which in atmospheric air is due to Liebig, is too small in quantity for direct estimation.

Composition of the Atmosphere.

	By weight.	By measure.
Nitrogen	77 parts	79.19
Oxygen	23 „	20.81
	<hr/> 100	<hr/> 100.00

Carbonic acid, from 3.7 measures to 6.2 measures, in 10,000 measures of air.

Aqueous vapour variable, depending much upon the temperature.

Ammonia, a trace.

100 cubic inches of pure and dry air weigh, according to Dr. Prout, 31.0117 grains; the temperature being 60° F. (15°·5C) and the barometer standing at 30 inches.

Fig. 89.



The analysis of air is very well effected by passing it over finely-divided copper contained in a tube of hard glass, carefully weighed, and then heated to redness; the nitrogen is suffered to flow into an exhausted glass globe, also previously weighed. The increase of weight after the experiment gives the information sought.

An easier, but less accurate method, consists in introducing into a graduated tube, standing over water, a known quantity of the air to be examined, and then passing into the latter a stick of phosphorus affixed to the end of a wire. The whole is left about twenty-four hours, during which the oxygen is slowly but completely absorbed, after which the phosphorus is withdrawn, and the residual gas read off.


Professor Liebig has lately proposed to use an alkaline solution of pyrogallic acid (a substance which will be described in the department of organic chemistry) for the absorption of oxygen. The absorptive power of such a solution, which turns deep black on coming in contact with the oxygen, is very considerable. Liebig's method combines great accuracy with unusual rapidity and facility of execution.

Another plan is to mix the air with hydrogen and pass an electric spark; after explosion the volume of gas is read off and compared with that of the air employed. Since the analysis of gaseous bodies by explosion is an operation of great importance in practical chemistry, it may be worth while describing the process in detail, as it is applicable, with certain obvious variations, to a number of analogous cases.

A convenient form of apparatus for the purpose is the siphon eudiometer of Dr. Ure; this consists of a stout glass tube, having an internal diameter of about one-third of an inch, closed at one end, and bent into the form represented in the drawing. (Fig. 90.) Two pieces of platinum wire, melted into the glass near the closed extremity, serve to give passage to the spark. The closed limb is carefully graduated. When required for use, the instrument is filled with mercury and inverted into a vessel of the same fluid. A quantity of the air to be examined is then introduced, the manipulation being precisely the same as with experiments over water; the open end is stopped with the thumb, and the air transferred to the closed extremity. The instrument is next held upright, and after the level of the mercury has been made equal on both sides by displacing a portion from the open limb by thrusting down a piece of stick, the volume of air is read off. This done, the open part of the tube is again filled up with mercury, closed with the finger,

inverted into the liquid metal, and a quantity of pure hydrogen introduced, equal, as nearly as can be guessed, to about half the volume of the air. The eudiometer is once more brought into an erect position, the level of the mercury equalized, and the volume again read off; the quantity of hydrogen added is thus accurately ascertained. All is now ready for the explosion; the instrument is held in the way represented, the open end being firmly closed by the thumb, while the knuckle of the forefinger touches the nearer platinum wire; the spark is then passed by the aid of a charged jar or a good electrophorus, and the explosion ensues. The air confined by the thumb in the open part of the tube acts as a spring and moderates the explosive effect. Nothing now remains but to equalize the level of the mercury by pouring a little more into the instrument, and then to read off the volume for the last time.

Fig. 90.



What is required to be known from this experiment is the *diminution* the mixture suffers by explosion; for since the hydrogen is in excess, and since that body unites with oxygen in the proportion by measure of two to one, one-third part of that diminution must be due to the oxygen contained in the air introduced. As the amount of the latter is known, the proportion of oxygen it contains thus admits of determination. The case supposed will render this clear.

Air introduced	100 measures.
Air and hydrogen	150
Volume after explosion	87
Diminution	63
$\frac{63}{3} = 21$; oxygen in the hundred measures.	

The working pupil will do well to acquire dexterity in the use of this valuable instrument, by practising the transference of gas or liquid from the one limb to the other, &c. In the analysis of combustible gases by explosion with oxygen, solution of caustic potassa is often required to be introduced into the closed part.


Compounds of Nitrogen and Oxygen.

There are not less than five distinct compounds of nitrogen and oxygen, thus named and constituted.

	Composition by weight.	
	Nitrogen.	Oxygen.
Protoxide of nitrogen*	14	8
Binoxide of nitrogen†	14	16
Nitrous acid	14	24
Hyponitric acid‡	14	32
Nitric acid§	14	40

Nitric or Azotic Acid.—In certain parts of India, and also in other hot dry climates where rain is rare, the surface of the soil is occasionally covered by a saline efflorescence, like that sometimes apparent on newly-plastered walls: this substance collected, dissolved in hot water, the solution filtered and made to crystallize, furnishes the highly-important salt known in commerce as nitre or saltpetre: it is a compound of nitric acid and potassa. To obtain liquid nitric acid, equal weights of powdered nitre and oil of vitriol are introduced into a glass retort, and heat applied by means of an Argand gas-lamp or charcoal chauffer. A flask, cooled by a wet cloth, is adapted to the retort, to serve for a receiver. No luting of any kind must be used.

As the distillation advances, the red fumes which first arise disappear, but towards the end of the process again become manifest. When this happens, and very little liquid passes over, while the greater part of the saline matter of the retort is in a state of tranquil fusion, the operation may be stopped; and when the retort is quite cold, water may be introduced to dissolve out the bisulphate of potassa. The reaction is thus explained.||




In the manufacture of nitric acid on the large scale, the glass retort is replaced by a cast-iron cylinder, and the receiver by a series of earthen condensing vessels connected by tubes. Nitrate of soda, found native in Peru, is often substituted for nitrate of potassa.

* Otherwise called nitrous oxide. † Otherwise called nitric oxide.

‡ Called by Professor Graham peroxide of nitrogen.

§ In symbols the composition of these substances is thus expressed:—



Liquid nitric acid so obtained has a specific gravity of from 1.5 to 1.52; it has a golden-yellow colour, which is due to nitrous or hyponitric acid held in solution, and which, when the acid is diluted with water, gives rise by its decomposition to a disengagement of nitric oxide. It is exceedingly corrosive, staining the skin deep yellow, and causing total disorganization. Poured upon red-hot powdered charcoal, it causes brilliant combustion; and when added to warm oil of turpentine, acts upon that substance so energetically as to set it on fire.

Pure liquid nitric acid, in its most concentrated form, is obtained by mixing the above with about an equal quantity of oil of vitriol, redistilling, collecting apart the first portion which comes over, and exposing it in a vessel slightly warmed, and sheltered from the light, to a current of dry air, made to bubble through it, which completely removes the nitrous acid. In this state the product is as colourless as water; it has the sp. gr. 1.517 at 60° (15.5°C), boils at 184° (84.5°C), and consists of 54 parts real acid, and 9 parts water. Although nitric acid in a more dilute form acts very violently upon many metals, and upon organic substances generally, this is not the case with the compound in question; even at a boiling heat it refuses to attack iron or tin, and its mode of action on lignin, starch, and similar substances is quite peculiar, and very much less energetic than that of an acid containing more water.

A second definite compound of real nitric acid and water exists, containing 54 parts of the former to 36 parts of the latter. Its sp. gr. at 60° (15.5°C) is 1.424, and it boils at 250° (121°C). An acid weaker than this is concentrated to this point by evaporation; and one stronger, reduced to the same strength by loss of nitric acid and water in the form of the first hydrate.*

Absolute nitric acid, in the separate state, was unknown up to 1849, when M. Deville succeeded in obtaining this remarkable substance by exposing nitrate of silver, which is a combination of nitric acid, silver, and oxygen, to the action of chlorine gas. Chlorine and silver combine, forming chloride of silver, which remains in the apparatus, whilst oxygen and anhydrous nitric acid separate. The latter is a colourless substance, crystallizing in six-sided columns, which fuse at 86° (30°C), and boil between 113° and 122° (45° and 50°C), when they commence to be decomposed. Anhydrous nitric acid has been found to explode sometimes spontaneously. It dissolves in water with evolution of much heat, forming hydrated nitric acid. It consists of 14 parts of nitrogen and 40 parts of oxygen.

Nitric acid forms with bases a very extensive and important group of salts, the nitrates, which are remarkable for all being soluble in water. The hydrated acid is of great use in the laboratory, and also in many branches of industry.

* The two hydrates of nitric acid are thus expressed by symbols:— NO_5 , HO and NO_5 , 4HO . No compound containing two equivalents of water appears to exist.

The acid prepared in the way described is apt to contain traces of chlorine from common salt in the nitre, and sometimes of sulphate from accidental splashing of the pasty mass in the retort. To discover these impurities, a portion is diluted with four or five times its bulk of distilled water, and divided between two glasses. Solution of nitrate of silver is dropped into the one, and solution of nitrate of baryta into the other; if no change ensue in either case, the acid is free from the impurities mentioned.


Nitric acid has been formed in small quantity by a very curious process, namely, by passing a series of electric sparks through a portion of air: water, or an alkaline solution being present. The amount of acid so formed after many hours is very minute; still it is not impossible that powerful discharges of atmospheric electricity may sometimes occasion a trifling production of nitric acid in the air. A very minute quantity of nitric acid is also produced by the combustion of hydrogen and other substances in the atmosphere; it is also formed by the oxidation of ammonia.

Nitric acid is not so easily detected in solution in small quantities as many other acids. Owing to the solubility of all its compounds, no *precipitant* can be found for this substance. One of the best tests is its power of bleaching a solution of indigo in sulphuric acid when boiled with that liquid. The absence of chlorine must be insured in this experiment by means which will hereafter be described, otherwise the result is equivocal.

Protoxide of Nitrogen; Nitrous Oxide; (laughing gas).—When solid nitrate of ammonia is heated in a retort or flask,* fig. 91, furnished with a perforated cork and bent tube, it is resolved into water and nitrous oxide. The nature of the decomposition will be understood from the subjoined diagram.†

Nitrate of Ammonia 80	{	Nitric acid	{ Nitrogen 14	}	Protox. nitrogen 22
		54	{ Oxygen 8		
	{	Ammonia	{ Oxygen 8	}	Protox. nitrogen 22
			{ Oxygen 24		
			{ Nitrogen 14		
	{	Water	{ Hydrogen 3	}	Water 27
			9		
					Water 9.

* Florence oil-flasks, which may be purchased at a very trifling sum, constitute exceedingly useful vessels for chemical purposes, and often supersede retorts or other expensive apparatus. They are rendered still more valuable by cutting the neck smoothly round with a hot iron, softening it in the flame of a good Argand gas-lamp, and then turning over the edge so as to form a lip, or border. The neck will then bear a tightly-fitting cork without risk of splitting.



No particular precaution is required in the operation, save due regulation of the heat, and the avoidance of tumultuous disengagement of the gas.

Protoxide of nitrogen is a colourless, transparent, and almost inodorous gas, of distinctly sweet taste. Its specific gravity is 1.525; 100 cubic inches weigh 47.29 grains. It supports the combustion of a taper or a piece of phosphorus with almost as much energy as pure oxygen; it is easily distinguished, however, from that gas by its solubility in cold water, which dissolves nearly its own volume; hence it is necessary to use tepid water in the pneumatic trough or gas-holder, otherwise great loss of gas will ensue. Nitrous oxide has been liquefied, but with difficulty; it requires, at 45°


(7° 2C), a pressure of 50 atmospheres; the liquid when exposed under the bell-glass of the air-pump is rapidly converted into a snow-like solid. When mixed with an equal volume of hydrogen, and fired by the electric spark in the eudiometer, it explodes with violence, and liberates its own measure of nitrogen. Every two volumes of the gas must consequently contain two volumes of nitrogen and one volume of oxygen, the whole being condensed or contracted one-third; a constitution resembling that of vapour of water.*

The most remarkable feature in this gas is its intoxicating power upon the animal system. It may be respired, if quite pure, or merely mixed with atmospheric air, for a short time, without danger or inconvenience. The effect is very transient, and is not followed by depression.

Binoxide of Nitrogen.—Clippings or turnings of copper are put into the apparatus employed for preparing hydrogen,† together with a little water, and nitric acid added by the funnel until brisk effervescence is excited. The gas may be collected over cold water, as it is not sensibly soluble.

The reaction is a simple deoxidation of some of the nitric acid by the copper; the metal is oxidized, and the oxide so formed is dissolved by another portion of the acid. Nitric acid is very prone to act thus upon certain metals.‡

* See page 121.



† See page 111.




Fig. 91.

The gas obtained in this manner is colourless and transparent; in contact with air or oxygen gas it produces deep-red fumes, which are readily absorbed by water: this character is sufficient to distinguish it from all other gaseous bodies. A lighted taper plunged into the gas is extinguished; lighted phosphorus, however, burns in it with great brilliancy.

The specific gravity of binoxide of nitrogen is 1.039; 100 cubic inches weigh 32.22 grains. It contains equal measures of oxygen and nitrogen gases united without condensation. When this gas is passed into a solution of protoxide of iron it is absorbed in large quantity, and a deep-brown or nearly black liquid produced, which seems to be a definite compound of the two substances. The compound is again decomposed by boiling.

Nitrous Acid.—Four measures of binoxide of nitrogen are mixed with one measure of oxygen, and the gases, perfectly dry, exposed to a temperature of 0° (-172.8°C). They condense to a thin mobile green liquid. Its vapour is orange-red.

Nitrous acid is decomposed by water, being converted into nitric acid and binoxide of nitrogen. For this reason it cannot be made to unite directly with metallic oxides: nitrite of potassa may, however, be prepared by fusing nitrate of potassa, when part of its oxygen is evolved; and many other salts of nitrous acid may be obtained by indirect means.

Hyponitric Acid.—It has been doubted whether the term *acid* applied to this substance be correct, since it seems to possess the power of forming salts only in a very limited degree; the expression has, notwithstanding, been long sanctioned by use. Moreover, a beautiful crystalline lead-salt of this substance has been discovered by M. Péligot. It is formed by digesting nitrate of lead with metallic lead.

It is chiefly the vapour of hyponitric acid which forms the deep-red fumes always produced when binoxide of nitrogen escapes into the air.

When carefully-dried nitrate of lead is exposed to heat in a retort of hard glass, it is decomposed; protoxide of lead remains behind, while the acid is resolved into a mixture of oxygen and hyponitric acid. By surrounding the receiver with a very powerful freezing mixture, the latter is condensed to the liquid form. It is then nearly colourless, but acquires a yellow and ultimately a red tint, as the temperature rises. At 82° (27.8°C) it boils, giving off its well-known red vapour, the intensity of the colour of which is greatly augmented by elevation of temperature.

This substance, like the preceding, is decomposed by water, being resolved into binoxide of nitrogen and nitric acid. Its vapour is absorbed by strong nitric acid, which thereby acquires a yellow or red tint, passing into green, then into blue, and afterwards disappearing altogether on the addition of successive portions of water. The deep-

red fuming acid of commerce, called *nitrous acid*, is simply nitric acid impregnated with hyponitric acid gas.*

Nitrogen appears to combine, under favourable circumstances, with metals. When iron and copper are heated to redness in an atmosphere of ammonia, they become brittle and crystalline, but without sensible alteration of weight. M. Schrötter has shown that in the case of copper, at least, this effect is caused by the formation and subsequent destruction of a nitride, that is, a compound of nitrogen with copper. When ammonia is passed over protoxide of copper heated to 570° (298°C), water is formed, and a soft brown powder produced, which, when heated farther evolves nitrogen, and leaves metallie copper. The same effect is produced by the contact of strong acids. A similar compound of chromium with nitrogen appears to exist.

CARBON.

This substance occurs in a state of purity, and crystallized, in two distinct and very dissimilar forms, namely, as diamond, and as graphite or plumbago. It constitutes a large proportion of all organic structures, animal and vegetable; when these latter are exposed to destructive distillation in close vessels, a great part of their carbon remains, obstinately retaining some of the hydrogen and oxygen, and associated with the earthy and alkaline matter of the tissue, giving rise to the many varieties of charcoal, coke, &c.


The diamond is one of the most remarkable substances known: long prized on account of its brilliancy as an ornamental gem, the discovery of its curious chemical nature confers upon it a high degree of scientific interest. Several localities in India, the island of Borneo, and more especially Brazil, furnish this beautiful substance. It is always distinctly crystallized, often quite transparent and colourless, but now and then having a shade of yellow, pink, or blue. The origin and true geological position of the diamond are unknown; it is always found embedded in gravel and transported materials, whose history cannot be traced. The crystalline form of the diamond is that of the regular octahedron or cube, or some figure geometrically connected

* Much doubt yet hangs over the true nature and relations of these two acids. According to M. Peligot, the only product of the union of binoxide of nitrogen and oxygen is *hyponitric acid*, which, in the total absence of water is a white solid crystalline body, fusible at 16° (-8°C). At common temperatures it is an orange-yellow liquid. The same product is obtained by heating perfectly-dry nitrate of lead. From these experiments it would appear that nitrous acid in a separate state is unknown. Ann. Chim. et Phys. 3rd series, ii. 58.

with these. Many of the octahedral crystals exhibit a very peculiar appearance, arising from the faces being curved or rounded, which gives to the crystal an almost spherical figure.

The diamond is infusible and unalterable by a very intense heat, provided air be excluded; but when heated, thus protected, between the poles of a strong galvanic battery, it is converted into coke or graphite: heated to whiteness in a vessel of oxygen, it burns with facility, yielding carbonic acid gas.

Fig. 92.



This is the hardest substance known: it admits of being split or cleaved without difficulty in certain particular directions, but can only be cut or abraded by a second portion of the same material; the powder rubbed off in this process serves for polishing the new faces, and is also highly useful to the lapidary and seal-engraver. One very curious and useful application of the diamond is made by the glazier: a *fragment* of this mineral, like a bit of flint, or any other hard substance, scratches the surface of glass; a *crystal* of diamond, having the rounded octahedral figure spoken of, held in one particular position on the glass, namely, with an edge formed by the meeting of two adjacent faces presented to the surface, and then drawn along with gentle pressure, causes a deep split or cut, which penetrates to a considerable depth into the glass, and determines its fracture with perfect certainty.

Graphite or plumbago appears to consist essentially of pure carbon, although most specimens contain iron, the quantity of which varies from a mere trace up to five per cent. Graphite is a somewhat rare mineral: the finest and most valuable for pencils is brought from Borrowdale, in Cumberland, where a kind of irregular vein is found traversing the ancient slate-beds of that district. Crystals are not common: when they occur, they have the figure of a short six-sided prism;—a form bearing no geometric relation to that of the diamond.

Graphite is often formed artificially in certain metallurgic operations: the brilliant scales which sometimes separate from melted cast iron on cooling, called by the workmen “kish,” consist of graphite.

Lampblack, the soot produced by the imperfect combustion of oil or resin, is the best example that can be given of carbon in its uncrystallized or *amorphous* state. To the same class belong the different kinds

of charcoal. That prepared from wood, either by distillation in a large iron retort, or by the smothered combustion of a pile of fagots partially covered with earth, is the most valuable as fuel. Coke, the charcoal of pit-coal is much more impure; it contains a large quantity of earthy matter, and very often sulphur; the quality depending very much upon the mode of preparation. Charcoal from bones and animal matters in general is a very valuable substance, on account of the extraordinary power it possesses of removing colouring matters from organic solutions; it is used for this purpose by the sugar-refiners to a very great extent, and also by the manufacturing and scientific chemist. The property in question is possessed by all kinds of charcoal in a small degree.


Charcoal made from box, or other dense wood, has the property of condensing into its pores gases and vapours; of ammoniacal gas it is said to absorb not less than ninety times its volume, while of hydrogen it takes up less than twice its own bulk, the quantity being apparently connected with the property in the gas of suffering liquefaction. This effect, as well as that of the decolorizing power, no doubt depends in some way upon the same peculiar action of surface so remarkable in the case of platinum in a mixture of oxygen and hydrogen.

Compounds of Carbon and Oxygen.

There are two direct inorganic compounds of carbon and oxygen, called carbonic oxide and carbonic acid; their composition may be thus stated:—


		Composition by weight.	
		Carbon.	Oxygen.
Carbonic oxide	.	6	8
Carbonic acid	.	6	16

Carbonic Acid is always produced when charcoal burns in air or oxygen gas; it is most conveniently obtained, however, for study, by decomposing a carbonate with one of the stronger acids. For this purpose, the apparatus for generating hydrogen may again be employed; fragments of marble are put into the bottle with enough water to cover the extremity of the funnel-tube, and hydrochloric* or nitric acid added by the latter, until the gas is freely disengaged. Chalk-powder and dilute sulphuric acid may be used instead. The gas may be collected over water, although with some loss; or very



conveniently by displacement, if it be required dry, as shown in the figure. The long drying-tube is filled with fragments of chloride of calcium, and the heavy gas is conducted to the bottom of the vessel in which it is to be received, the mouth of the latter being lightly closed.*


Fig. 93.



Carbonic acid gas is colourless; it has an agreeable pungent taste and odour, but cannot be respired for a moment without insensibility following. Its specific gravity is 1.524,† 100 cubic inches weighing 47.26 grains.

This gas is very hurtful to animal life, even when largely diluted with air: it acts as a narcotic poison. Hence the danger arising from imperfect ventilation, the use of fire-places and stoves of all kinds unprovided with proper chimneys, and the crowding together of many

Fig. 94.



* In connecting tube-apparatus for conveying gases or cold liquids, not corrosive, little tubes of caoutchouc about an inch long, are *inexpressibly* useful. These are made by bending a piece of sheet India-rubber loosely round a glass tube or rod, and cutting off the superfluous portion with sharp scissors. The fresh-cut edges of the caoutchouc, pressed strongly together, cohere completely, and the tube is perfect, provided they have not been soiled by touching with the fingers. The connectors are secured by two or three turns of thin silk cord. The glass tubes are sold by weight, and are easily bent in the flame of a spirit-lamp, and, when, necessary, cut by scratching with a file, and break asunder.

† MM. Dulong and Berzelius.

individuals in houses and ships without efficient means for renewing the air; for carbonic acid is constantly disengaged during the process of respiration, which, as we have seen (page 109), is nothing but a process of slow combustion. This gas is sometimes emitted in large quantity from the earth in volcanic districts, and it is constantly generated where organic matter is in the act of undergoing fermentive decomposition. The fatal "after-damp" of the coal-mines contains a large proportion of carbonic acid.

A lighted taper plunged into carbonic acid is instantly extinguished, even to the red-hot snuff. When diluted with three times its volume of air, it still retains the power of extinguishing a light. The gas is easily known from nitrogen, which is also incapable of supporting combustion, by its rapid absorption by caustic alkali, or by lime-water; the turbidity communicated to the latter from the production of insoluble carbonate of lime is very characteristic.

Cold water dissolves about its own volume of carbonic acid, whatever be the density of the gas with which it is in contact; the solution temporarily reddens litmus paper. In common soda-water, and also in effervescent wines, examples may be seen of this solubility of the gas. Even boiling water absorbs a perceptible quantity.

Some of the interesting phenomena attending the liquefaction of carbonic acid have been already described; it requires for the purpose a pressure of between 27 and 28 atmospheres at 32° (0°C), according to Mr. Addams. The liquefied acid is colourless and limpid, lighter than water and four times more expansible than air; it mixes in all proportions with ether, alcohol, naphtha, oil of turpentine, and bisulphide of carbon, and is insoluble in water and fat oils. It is probably destitute when in this condition of all properties of an acid.

Carbonic acid exists, as already mentioned, in the air; relatively, its quantity is but small, but absolutely, taking into account the vast extent of the atmosphere, it is very great, and fully adequate to the purpose for which it is designed, namely, to supply to plants their carbon, these latter having the power, by the aid of their green leaves, of decomposing carbonic acid, retaining the carbon, and expelling the oxygen. The presence of light is essential to this extraordinary effect, but of the manner in which it is produced we are yet ignorant.

The carbonates form a very large and important group of salts, some of which occur in nature in great quantities, as the carbonates of lime and magnesia.

Carbonic Oxide.—When carbonic acid is passed over red-hot charcoal or metallic iron, one-half of its oxygen is removed, and it becomes converted into carbonic oxide. A very good method of preparing this gas is to introduce into a flask fitted with a bent tube some crystallized oxalic acid, or salt of sorrel, and pour upon it five or six times as

much strong oil of vitriol.* On heating the mixture the organic acid is resolved into water, carbonic acid, and carbonic oxide; by passing the gases through a strong solution of caustic potassa, the first is withdrawn by absorption, while the second remains unchanged. Another, and it may be preferable method, is to heat finely-powdered yellow ferrocyanide of potassium with eight or ten times its weight of concentrated sulphuric acid. The salt is entirely decomposed, yielding a most copious supply of perfectly pure carbonic oxide gas, which may be collected over water in the usual manner.†


Carbonic oxide is a combustible gas; it burns with a beautiful pale blue flame, generating carbonic acid. It has never been liquefied. It is colourless, has very little odour, and is extremely poisonous, even worse than carbonic acid. Mixed with oxygen it explodes by the electric spark, but with some difficulty. Its specific gravity is 0.973; 100 cubic inches weigh 30.21 grains.

The relation by volume of these oxides of carbon may thus be made intelligible:—carbonic acid contains its own volume of oxygen, that gas suffering no change of bulk by its conversion. One measure of carbonic oxide, mixed with half a measure of oxygen and exploded, yields one measure of carbonic acid; hence carbonic oxide contains half its volume of oxygen.

Carbonic oxide unites with chlorine under the influence of light, forming a pungent, suffocating compound, possessing acid properties, called phosgene gas, or chloro-carbonic acid. It is made by mixing equal volumes of carbonic oxide and chlorine, both perfectly dry, and exposing the mixture to sunshine; the gases unite quietly, the colour disappears, and the volume becomes reduced to one-half. It is decomposed by water.

SULPHUR.

This is an elementary body of great importance and interest. Sulphur is often found in a free state in connection with deposits of gypsum and rock-salt; its occurrence in volcanic districts is probably accidental. Sicily furnishes a large proportion of the sulphur employed in Europe. In a state of combination with iron and other metals, and as sulphuric acid, united to lime and magnesia, it is also abundant.



† See a paper by the author in *Memoirs of Chem. Soc. of London*, i. 251. 1 eq. crystallized ferrocyanide of potassium and 6 eq. oil of vitriol yield 6 eq. carbonic oxide, 2 eq. sulphate of potassa, 3 eq. sulphate of ammonia, and 1 eq. protosulphate of iron.

Pure sulphur is a pale-yellow brittle solid, of well-known appearance. It melts when heated, and distils over unaltered, if air be excluded. The crystals of sulphur exhibit two distinct and incompatible forms, namely, an octahedron with rhombic base, which is the figure of native sulphur, and that assumed when sulphur separates from solution at common temperatures, as when a solution of sulphur in bisulphide of carbon is exposed to slow evaporation in the air: and a lengthened prism, having no relation to the preceding: this happens when a mass of sulphur is melted, and, after partial cooling, the crust at the surface broken, and the fluid portion poured out. Fig. 96 shows the result of such an experiment.

Fig. 95.





Fig. 96.



The specific gravity of sulphur varies according to the form in which it is crystallized. The octahedral variety has a specific gravity 2.045; the prismatic variety a specific gravity 1.982.

Sulphur melts at 232° (111°C): at this temperature it is of the colour of amber, and thin and fluid as water; when farther heated, it begins to thicken, and to acquire a deeper colour; and between 430° (221°C) and 480° (249°C) it is so tenacious that the vessel in which it is contained may be inverted for a moment without the loss of its contents. If in this state it be poured into water, it retains for many hours its remarkable soft and flexible condition, which should be looked upon as the amorphous state of sulphur. After a while it again becomes brittle and crystalline. From the temperature last mentioned to the boiling-point about 792° (400°C), sulphur again becomes thin and liquid. In the preparation of commercial flowers of sulphur the vapour is conducted into a large cold chamber, where it condenses in minute crystals. The specific gravity of sulphur-vapour is 6.654.

Sulphur is insoluble in water and alcohol; oil of turpentine and the fat oils dissolve it, but the best substance for the purpose is bisulphide of carbon. In its chemical relations sulphur bears great resemblance to oxygen: to very many oxides there are corresponding sulphides, and these sulphides often unite among themselves, forming crystallizable compounds analogous to salts.

Compounds of Sulphur and Oxygen.

	Composition by weight.	
	Sulphur.	Oxygen.
Sulphurous acid	16	16
Sulphuric acid*	16	24
Hyposulphurous acid	32	16
Hyposulphuric acid	32	40
Sulphuretted hyposulphuric acid	48	40
Bisulphuretted hyposulphuric acid	64	40
Trisulphuretted hyposulphuric acid†.	80	40

Sulphurous Acid.—This is the only product of the combustion of sulphur in dry air or oxygen gas. It is most conveniently prepared by heating oil of vitriol with metallic mercury or copper clippings; a portion of the acid is decomposed, one-third of its oxygen being transferred to the metal, while the sulphuric acid becomes sulphurous. Sulphurous acid thus obtained is a colourless gas, having the peculiar suffocating odour of burning brimstone; it instantly extinguishes flame, and is quite irrespirable. Its density is 2.21; 100 cubic inches weighing 68.69 grains. At 0° (−17°·8C), under the pressure of the atmosphere, this gas condenses to a colourless, limpid liquid, very expansible by heat. Cold water dissolves more than thirty times its volume of sulphurous acid. The solution may be kept unchanged so long as air is excluded, but access of oxygen gradually converts the sulphurous into sulphuric acid, in the presence of water, although the dry gases may remain in contact for any length of time without change. When sulphurous acid and aqueous vapour are passed into a vessel cooled to below 17° or 21° (−6° or −8°C), a crystalline body forms, which contains about 24.2 acid to 75.8 water.

One volume of sulphurous acid gas contains one volume of oxygen and $\frac{1}{8}$ of a volume of sulphur-vapour, condensed into one volume.

Gases which, like the present, are freely soluble in water, must be

* The terminations *ous* and *ic*, applied to acids, signify degrees of oxidation, the latter being the highest; acids ending in *ous* form salts the names of which are made to end in *ite*, and those in *ic* terminate in *ate*—as *sulphurous acid*, *sulphite* of soda; *sulphuric acid*, *sulphate* of soda.

† The more advanced student will be glad to see these stated in equivalents by the use of symbols, their relations becoming thereby much more evident. The numbers given are really the equivalent numbers, but are intended only to show the proportions of sulphur and oxygen, without any reference to other bodies. The following are the quantities required to saturate one equivalent of a base:

Sulphurous acid	SO ₂
Sulphuric acid	SO ₃
Hyposulphurous acid	S ₂ O ₂
Hyposulphuric acid, <i>Dithionic acid</i>	S ₂ O ₃
Sulphuretted hyposulphuric acid, <i>Trithionic acid</i>	S ₃ O ₃
Bisulphuretted hyposulphuric acid, <i>Tetrathionic acid</i>	S ₄ O ₃
Bisulphuretted hyposulphuric acid, <i>Pentathionic acid</i>	S ₅ O ₃

collected by displacement, or by the use of the mercurial pneumatic trough. The manipulation with the latter is exactly the same in principle as with the ordinary water-trough, but rather more troublesome, from the great density of the mercury, and its opacity. The whole apparatus is on a much smaller scale. The trough is best constructed of hard, sound wood, and so contrived as to economise as much as possible the expensive fluid it is to contain.

Sulphurous acid has bleaching properties; it is used in the arts for bleaching woollen goods and straw-plait. A piece of blue litmus-paper plunged into the moist gas is first reddened and then slowly bleached.

The salts of sulphurous acid are not of much importance; those of the alkalies are soluble and crystallizable; they are easily formed by direct combination. Sulphites of baryta, strontia, and lime are insoluble in water, but soluble in hydrochloric acid. The strong acids decompose them; nitric acid converts them into sulphates.

Sulphuric Acid.—Hydrated sulphuric acid has been known since the fifteenth century. There are two distinct processes by which it is at the present time prepared, namely, by the distillation of green sulphate of iron, and by the oxidation of sulphurous acid by nitrous and hyponitric acids.

The first process is still carried on in some parts of Germany, especially in the neighbourhood of Nordhausen in Prussia. The sulphate of iron, derived from the oxidation of iron pyrites, is deprived by heat of the greater part of its water of crystallization, and subjected to a high red heat in earthen retorts, to which receivers are fitted as soon as the acid begins to distil over. A part gets decomposed by the very high temperature; the remainder is driven off in vapour, which is condensed by the cold vessel. The product is a brown oily liquid, of about 1.9 specific gravity, fuming in the air, and very corrosive. It is chiefly made for the purpose of dissolving indigo.


The second method, which is, perhaps, with the single exception mentioned, always followed as the more economical, depends upon the fact that, when sulphurous acid, hyponitric acid, and water are present in certain proportions, the sulphurous acid becomes oxidized at the expense of the hyponitric acid, which by the loss of one-half of its oxygen sinks to the condition of binoxide of nitrogen. The operation is thus conducted:—A large and very long chamber is built of sheet-lead supported by timber framing; on the outside, at one extremity, a small furnace or oven is constructed, having a wide tube leading into the chamber. In this, sulphur is kept burning, the flame of which heats a crucible containing a mixture of nitre and oil of vitriol. A shallow stratum of water occupies the floor of the chamber, and sometimes a jet of steam is also introduced. Lastly, an exit is provided at the remote end of the chamber for the spent and useless gases. The effect of these arrangements is to cause a constant supply of sulphurous acid, atmospheric air, nitric acid vapour, and water in

the state of steam, to be thrown into the chamber, there to mix and react upon each other. The nitric acid immediately gives up a part of its oxygen to the sulphurous acid, becoming hyponitric; it does not remain in this state, however, but suffers farther deoxidation until it becomes reduced to binoxide of nitrogen. That substance in contact with free oxygen absorbs a portion of the latter, and once more becomes hyponitric acid, which is again destined to undergo deoxidation by a fresh quantity of sulphurous acid. A very small portion of hyponitric acid, mixed with atmospheric air and sulphurous acid, may thus in time convert an indefinite amount of the latter into sulphuric acid, by acting as a kind of carrier between the oxygen of the air and the sulphurous acid. The presence of water is essential to this reaction.

We may thus represent the change :—*

Hyponitric acid	{ Nitrogen 14	—————	Binoxide of nitrogen
46	{ Oxygen 16	—————	30.
	{ Oxygen 16	—————	
Sulphurous acid	{ Sulphur 32	—————	
64	{ Oxygen 32	—————	Hydrated sulphuric
Water . . .	18	—————	acid 98.

Such is the simplest view that can be taken of the production of sulphuric acid in the leaden chamber; but it is too much to affirm that it is strictly true; it may be more complex. When a little water is put at the bottom of a large glass globe, so as to maintain a certain degree of humidity in the air within, and sulphurous and hyponitric acids are introduced by separate tubes, symptoms of chemical action become immediately evident, and after a little time a white crystalline matter is observed to condense on the sides of the vessel. This substance appears to be a compound of sulphuric acid, nitrous acid, and a little water.† When thrown into water, it is resolved into sul-



† M. Gaultier de Claubry assigned to this curious substance the composition expressed by the formula $4\text{HO}, 2\text{NO}_3 + 5\text{SO}_3$, and this view has generally been received by recent chemical writers. M. de la Provostaye has since shown that a compound, possessing all the essential properties of the body in question, may be formed by bringing together, in a sealed glass tube, liquid sulphurous acid and liquid hyponitric acid, both free from water. The white crystalline solid soon begins to form, and at the expiration of twenty-six hours the reaction appears complete. The new product is accompanied by an exceedingly volatile greenish liquid having the characters of nitrous acid. The white substance, on analysis, was found to contain the elements of two equivalents of sulphuric acid and one of nitrous acid, or $\text{NO}_3 + 2\text{SO}_3$. M. de la Provostaye very ingeniously explains the anomalies in the different analyses of the leaden-chamber product, by showing that the pure substance forms crystallizable combinations with different proportions of liquid sulphuric acid. (Ann. Chim. et Phys. lxxiii. 362.)

phuric acid, binoxide of nitrogen, and nitric acid. This curious body is certainly very often produced in large quantity in the leaden chambers; but that its production is indispensable to the success of the process, and constant when the operation goes on well, and the hyp-nitric acid is not in excess, may perhaps admit of doubt.

The water at the bottom of the chamber thus becomes loaded with sulphuric acid: when a certain degree of strength has been reached, it is drawn off and concentrated by evaporation, first in leaden pans, and afterwards in stills of platinum, until it attains a density (when cold) of 1·84, or thereabouts; it is then transferred to carboys, or large glass bottles fitted in baskets, for sale. In Great Britain this manufacture is one of great national importance, and is carried on to a vast extent. An inferior kind of acid is sometimes made by burning iron pyrites, or poor copper ore, as a substitute for Sicilian sulphur; this is chiefly used by the makers for their own consumption; it very frequently contains arsenic.

The most concentrated sulphuric acid, or *oil of vitriol*, as it is often called, is a definite combination of 40 parts real acid, and 9 parts water. It is a colourless, oily liquid, having a specific gravity of about 1·85, of intensely acid taste and reaction. Organic matter is rapidly charred and destroyed by this substance. At the temperature of -15° ($-26^{\circ}\cdot1\text{C}$) it freezes; at 620° ($326^{\circ}\cdot6\text{C}$) it boils, and may be distilled without decomposition. Oil of vitriol has a most energetic attraction for water; it withdraws aqueous vapours from the air, and when diluted with water, great heat is evolved, so that the mixture always requires to be made with caution. Oil of vitriol is not the only hydrate of sulphuric acid; three others are known to exist. When the fuming oil of vitriol of Nordhausen is exposed to a low temperature, a white crystalline substance separates, which is a hydrate containing half as much water as the common liquid acid. Then, again, a mixture of 49 parts of strong liquid acid and 9 parts of water, congeals or crystallizes at a temperature above 32° (0°C), and remains solid even at 45° ($7^{\circ}\cdot2\text{C}$). Lastly, when a very dilute acid is concentrated by evaporation *in vacuo* over a surface of oil of vitriol, the evaporation stops when the real acid and water bear to each other the proportion of 40 to 27.

When good Nordhausen oil of vitriol is exposed in a retort to a gentle heat, and a receiver cooled by a freezing mixture fitted to it, a volatile substance distils over in great abundance, which condenses into beautiful white, silky crystals, resembling those of asbestos; this bears the name of anhydrous sulphuric acid. When put into water it hisses like a hot iron, from the violence with which combination occurs; exposed to the air even for a few moments, it liquefies by absorption of moisture, forming common liquid sulphuric acid. It forms an exceedingly curious compound with dry ammoniacal gas, quite distinct from ordinary sulphate of ammonia, and which indeed possesses none of the characters of a sulphate. This interesting sub-


stance may also be obtained by distilling the most concentrated oil of vitriol with a sufficient quantity of anhydrous phosphoric acid.

Sulphuric acid, in all soluble states of combination, may be detected with the greatest ease by solution of nitrate of baryta, or chloride of barium. A white precipitate is produced, which does not dissolve in nitric acid.

Hyposulphurous Acid.—By digesting sulphur with a solution of sulphite of potassa or soda, a portion of that substance is dissolved, and the liquid, by slow evaporation, furnishes crystals of the new salt.* The acid cannot be isolated: when hydrochloric acid is added to a solution of a hyposulphite, the acid of the latter is almost instantly resolved into sulphur, which precipitates, and into sulphurous acid, easily recognized by its odour. The most remarkable feature of the alkaline hyposulphites is their property of dissolving certain insoluble salts of silver, as the chloride—a property which has lately conferred upon them a considerable share of importance in relation to the art of photogenic drawing.

Hyposulphuric Acid; Dithionic Acid.—This is prepared by suspending finely divided binoxide of manganese in water artificially cooled, and then transmitting a stream of sulphurous acid gas; the binoxide becomes protoxide, half its oxygen converting the sulphurous acid into hyposulphuric.† The hyposulphate of manganese thus prepared is decomposed by a solution of pure hydrate of baryta, and the barytic salt, in turn, by enough sulphuric acid to precipitate the base. The solution of hyposulphuric acid may be concentrated by evaporation *in vacuo*, until it acquires a density of 1.347; pushed farther, it decomposes into sulphuric and sulphurous acids. It has no odour, is very sour, and forms soluble salts with baryta, lime, and protoxide of lead.

Sulphuretted Hyposulphuric Acid; Trithionic Acid.—A substance accidentally formed by M. Langlois,‡ in the preparation of hyposulphite of potassa, by gently heating with sulphur a solution of carbonate of potassa, saturated with sulphurous acid. The salts bear a great resemblance to those of hyposulphurous acid, but differ completely in composition, while the acid itself is not quite so prone to change. It is obtained by decomposing the potassa salt by hydrofluosilicic acid; it may be concentrated under the receiver of the air-pump, but is gradually decomposed into sulphur, sulphurous and sulphuric acids.



‡ Ann. Chim. et Phys. 3rd series, iv. 77.

Bisulphuretted Hyposulphuric Acid ; Tetrathionic Acid.—This was discovered by MM. Fordos and Gelis.* When iodine is added to a solution of hyposulphite of soda, a large quantity of that substance is dissolved, and a clear colourless solution obtained, which, besides iodide of sodium, contains a salt of a peculiar acid, richer in sulphur than the preceding. By suitable means, the new substance can be eliminated, and obtained in a state of solution. It very closely resembles hyposulphuric acid. The same acid is produced by the action of sulphurous acid on subchloride of sulphur.

Trisulphuretted Hyposulphuric Acid ; Pentathionic Acid.—Another acid of sulphur has been announced by M. Wackenroder, who formed it by the action of sulphuretted hydrogen on sulphurous acid. It is described as colourless and inodorous, of acid and bitter taste, and capable of being concentrated to a considerable extent by cautious evaporation.

Under the influence of heat, it is decomposed into sulphur, sulphurous and sulphuric acid, and sulphuretted hydrogen. The salts of pentathionic acid are nearly all soluble. The baryta salt crystallizes from alcohol in square prisms. The acid is also formed when hyposulphate of lead is decomposed by sulphuretted hydrogen, and when protochloride of sulphur is heated with sulphurous acid.

Sulphurous acid unites, under peculiar circumstances, with chlorine, and also with iodine, forming compounds, which have been called chloro- and iodo-sulphuric acids. They are decomposed by water. It also combines with dry ammoniacal gas, giving rise to a remarkable compound ; and with nitric oxide also, in presence of an alkali.

SELENIUM.

This is a very rare substance, much resembling sulphur in its chemical relations, and found in association with that element in some few localities, or replacing it in certain metallic combinations, as in the selenide of lead of Clausthal, in the Hartz.

Selenium is a reddish-brown solid body, somewhat translucent, and having an imperfect metallic lustre. Its specific gravity, when rapidly cooled after fusion is 4.3. At 212° (100°C), or a little above, it melts, and at 650° ($343^{\circ}\cdot 3\text{C}$) boils. It is insoluble in water, and exhales, when heated in the air, a peculiar and disagreeable odour, which has been compared to that of decaying horseradish. There are three oxides of selenium, two of which correspond respectively to sulphurous and sulphuric acids, while the third has no known analogue in the sulphur-series.

* Ann. Chim. et Phys. 3rd series, vi. 454.

	Composition by weight.*	
	Selenium.	Oxygen.
Oxide of selenium	39.5	8
Selenous acid	39.5	16
Selenic acid	39.5	24

Oxide.—Formed by heating selenium in the air. It is a colourless gas, slightly soluble in water, and has the remarkable odour above described. It has no acid properties.

Selenous Acid.—This is obtained by dissolving selenium in nitric acid, and evaporating to dryness. It is a white, soluble, deliquescent substance, of distinctly acid properties, and may be sublimed without decomposition. Sulphurous acid decomposes it, precipitating the selenium.

Selenic Acid.—Prepared by fusing nitrate of potassa or soda with selenium, precipitating the selenate so produced by a salt of lead, and then decomposing the compound by sulphuretted hydrogen. The hydrated acid strongly resembles oil of vitriol; but, when very much concentrated, decomposes, by the application of heat, into selenous acid and oxygen. The selenates bear the closest analogy to the sulphates in every particular.

PHOSPHORUS.

Phosphorus in the state of phosphoric acid is contained in the ancient unstratified rocks, and in the lavas of modern origin. As these disintegrate and crumble down into fertile soil, the phosphates pass into the organism of plants, and ultimately into the bodies of the animals to which these latter serve for food. The earthy phosphates play a very important part in the structure of the animal frame, by communicating stiffness and inflexibility to the bony skeleton.

This element was discovered in 1669 by Brandt, of Hamhurg, who prepared it from urine. The following is an outline of the process now adopted. Thoroughly-calcined bones are reduced to powder, and mixed with two-thirds of their weight of sulphuric acid, diluted with a considerable quantity of water: this mixture, after standing some hours, is filtered, and the nearly-insoluble sulphate of lime washed. The liquid is then evaporated to a syrupy consistence, mixed with charcoal powder, and the desiccation completed in an iron vessel exposed to a high temperature. When quite dry it is transferred to a

* In symbols—

Oxide of Selenium	SeO
Selenous Acid	SeO ₂
Selenic Acid	SeO ₃

stoneware retort, to which a wide bent tube is luted, dipping a little way into the water contained in the receiver. A narrow tube serves to give issue to the gases, which are conveyed to a chimney. This manufacture is now conducted on a very great scale, the consumption of phosphorus, for the apparently-trifling article of instantaneous-light matches, being something prodigious.

Phosphorus, when pure, very much resembles in appearance imperfectly-bleached wax, and is soft and flexible at common temperatures. Its density is 1.77, and that of its vapour 4.35, air being unity. At 108° ($42^{\circ}\cdot2\text{C}$) it melts, and at 550° ($287^{\circ}\cdot7\text{C}$) boils. It is insoluble in water, and is usually kept immersed in that liquid, but dissolves in oils, in native naphtha, and especially in bisulphide of carbon. When set on fire in the air, it burns with a bright flame, generating phosphoric acid. Phosphorus is exceedingly inflammable; it sometimes takes fire by the heat of the hand, and demands great care in its management; a blow or hard rub will very often kindle it. A stick of phosphorus held in the air always appears to emit a whitish smoke, which in the dark is luminous. This effect is chiefly due to a slow combustion which the phosphorus undergoes by the oxygen of the air, and upon it depends one of the methods employed for the analysis of the atmosphere, as already described. It is singular that the slow oxidation of phosphorus may be entirely prevented by the presence of a small quantity of olefiant gas, or the vapour of ether, or some essential oil; it may even be distilled in an atmosphere containing vapour of oil of turpentine in considerable quantity. Neither does the action go on in pure oxygen, at least at the temperature of 60° ($15^{\circ}\cdot5\text{C}$), which is very remarkable; but if the gas be rarefied, or diluted with nitrogen, hydrogen, or carbonic acid, oxidation is set up.

A very remarkable modification of this element is known by the name of amorphous phosphorus. It was discovered by Schrötter, and may be made by exposing for fifty hours common phosphorus to a temperature of about 550° (240° to 250°C) in an atmosphere which is unable to act chemically upon it. At this temperature it becomes red and opaque, and insoluble in bisulphide of carbon, whereby it may be separated from ordinary phosphorus. It may be obtained in compact masses when common phosphorus is kept for eight days at a constant high temperature. It is a coherent reddish-brown, infusible substance, of specific gravity between 2.089 and 2.106. It does not become luminous in the dark until its temperature is raised

Fig. 97.



to about 393° (200°C), nor has it any tendency to combine with the oxygen of the air. When heated to 500° (260°C), it is reconverted into ordinary phosphorus.

Compounds of Phosphorus and Oxygen.—These are three in number, and have the composition indicated below :—

	Composition by weight.	
	Phosphorus.	Oxygen.
Hypophosphorous acid	31	8
Phosphorous acid	31	24
Phosphoric acid*	31	40


Oxide of Phosphorus.—When phosphorus is melted beneath the surface of hot water, and a stream of oxygen gas forced upon it from a bladder, combustion ensues, and the phosphorus is converted in great part into a brick-red powder, which was formerly believed to be a peculiar oxide of phosphorus. Schrötter has lately shown that it is a mixture, consisting chiefly of amorphous phosphorus.

Hypophosphorous Acid.—When phosphorus is boiled with a solution of potassa or baryta, water is decomposed, giving rise to phosphoretted hydrogen, phosphoric acid, and hypophosphorous acid, which combine with the baryta; the first escapes as gas, and the two acids remain in union with the baryta.† By filtration the soluble hypophosphite is separated from the insoluble phosphate. On adding to the liquid the quantity of sulphuric acid necessary to precipitate the base, the hypophosphorous acid is obtained in solution. By evaporation it may be reduced to a syrupy consistence.

The acid is very prone to absorb more oxygen, and is therefore a powerful deoxidizing agent. All its salts are soluble in water.

Phosphorous Acid.—Phosphorous acid is formed by the slow combustion of phosphorus in the atmosphere; or by burning that substance by means of a very limited supply of air, in which case it is anhydrous, and presents the aspect of a white powder. The hydrated acid is more conveniently prepared by adding water to the terechloride of phosphorus, when mutual decomposition takes place, the oxygen of the water being transferred to the phosphorus, generating phosphorous acid, and its hydrogen to the chlorine, giving rise to hydrochloric

* In symbols—Hypophosphorous acid P O
 Phosphorous acid P O₃
 Phosphoric acid P O₅
 Equivalent of phosphorus, 31.



acid.* By evaporating the solution to the consistence of syrup, the hydrochloric acid is expelled, and the residue on cooling crystallizes.

Hydrated phosphorous acid is very deliquescent and very prone to attract oxygen and pass into phosphoric acid. When heated in a close vessel, it is resolved into hydrated phosphoric acid and pure phosphoretted hydrogen gas. It is composed of 56 parts of real acid and 27 parts of water.†

The phosphites are of little importance.


Phosphoric Acid.—When phosphorus is burned under a bell-jar by the aid of a copious supply of dry air, snow-like anhydrous phosphoric acid is produced in great quantity. This substance exhibits as much attraction for water as anhydrous sulphuric acid; exposed to the air for a few moments it deliquesces to a liquid, and when thrown into water, combines with the latter with explosive violence. Once in the state of hydrate the water cannot again be separated.

When nitric acid of moderate strength is heated in a retort to which a receiver is connected, and fragments of phosphorus added singly, taking care to suffer the violence of the action to subside between each addition, the phosphorus is oxidized to its maximum, and converted into phosphoric acid. By distilling off the greater part of the acid, transferring the residue in the retort to a platinum vessel, and then cautiously raising the heat to redness, the hydrated acid may be obtained pure. This is the *glacial phosphoric acid* of the Pharmacopœia.

A third method consists in taking the acid phosphate of lime produced by the action of sulphuric acid on bone-earth, precipitating it with a slight excess of carbonate of ammonia, separating by a filter the insoluble lime-salt, and then evaporating and igniting in a platinum vessel the mixed phosphate and sulphate of ammonia. Hydrated phosphoric acid alone remains behind. The acid thus obtained is not remarkable for its purity. One of the most advantageous methods of preparing phosphoric acid on the large scale in a state of purity is to burn phosphorus in a stream of dry atmospheric air, by the aid of a proper apparatus, not difficult to contrive, in which the process may be carried on continuously. The anhydrous acid obtained may be preserved in that state, or converted into hydrate or glacial acid, by the addition of water and subsequent fusion in a platinum vessel. The hydrate of phosphoric acid is exceedingly deliquescent, and requires to be kept in a closely-stopped bottle. It contains 71 parts of real acid, and 9 parts of water.‡

Phosphoric acid is a powerful acid; its solution has an intensely sour taste, and reddens litmus paper; it is not poisonous.

There are few bodies that present a greater degree of interest to the



chemist than this substance : the extraordinary changes its compounds undergo by the action of heat, chiefly made known to us by the admirable researches of Prof. Graham, will be found described in connexion with the general history of saline compounds.


CHLORINE.

This substance is a member of a small natural group containing besides iodine, bromine, and fluorine. So great a degree of resemblance exists between these bodies in all their chemical relations, that the history of one will almost serve, with a few little alterations, for that of the rest.

Chlorine* is a very abundant substance ; in common salt it exists in combination with sodium. It is most easily prepared by pouring strong liquid hydrochloric acid upon finely-powdered black oxide of manganese, contained in a retort or flask, and applying a gentle heat ; a heavy yellow gas is disengaged, which is the substance in question.

It may be collected over warm water, or by displacement ; the mercurial trough cannot be employed, as the chlorine rapidly acts upon the metal, and becomes absorbed.


Fig. 98.



The reaction is very easily explained. Hydrochloric acid is a compound of chlorine and hydrogen : when this is mixed with a metallic protoxide, double interchange of elements takes place, water and chloride of the metal being produced. But when some of the *binoxides* are substituted, an additional effect ensues, namely, the decomposition of a second portion of hydrochloric acid by the oxygen in excess, the hydrogen of which is withdrawn and the chlorine set free.

Chlorine was discovered by Scheele in 1774, but its nature was long misunderstood. It is a yellow gaseous body, of intolerably suffocating properties, producing very violent cough and irritation when inhaled even in exceedingly small quantity. It is soluble to a considerable extent in water, that liquid absorbing at 60° (15°·5C) about twice its volume, and acquiring the colour and odour of the gas. When this solution is exposed to light, it is slowly changed by decomposition of water into hydrochloric acid, the oxygen being at the same time liberated. When moist chlorine gas is exposed to a cold of 32° (0°C), yellow crystals are formed, which consist of a definite compound of chlorine and water, containing 35·5 parts of the former to 90 of the latter.

* From *χλωρός*, yellowish-green, the name given to it by Sir H. Davy




Chlorine has a specific gravity of 2.47, 100 cubic inches weighing 76.6 grains. Exposed to a pressure of about four atmospheres, it condenses to a yellow limpid liquid.

This substance has but little attraction for oxygen, its chemical energies being principally exerted towards hydrogen and the metals. When a lighted taper is plunged into the gas, it continues to burn with a dull red light, and emits a large quantity of smoke, the hydrogen of the wax being alone consumed, and the carbon separated. If a piece of paper be wetted with oil of turpentine, and thrust into a bottle filled with chlorine, the chemical action of the latter upon the hydrogen is so violent as to cause inflammation, accompanied by a copious deposit of soot. Although chlorine can, by indirect means, be made to combine with carbon, yet this never occurs under the circumstances described.


Phosphorus takes fire spontaneously in chlorine; it burns with a pale and feebly-luminous flame. Several of the metals, as copper leaf, powdered antimony, and arsenic, undergo combustion in the same manner. A mixture of equal measures of chlorine and hydrogen explodes with violence on the passage of an electric spark, or on the application of a lighted taper, hydrochloric acid gas being formed. Such a mixture may be retained in the dark for any length of time without change: exposed to diffuse daylight, the two gases slowly unite, while the direct rays of the sun induce instantaneous explosion.

The most characteristic property of chlorine is its bleaching power; the most stable organic colouring principles are instantly decomposed and destroyed by this remarkable agent; indigo, for example, which resists the action of strong oil of vitriol, is converted by chlorine into a brownish substance, to which the blue colour cannot be restored. The presence of water is essential to these changes, for the gas in a state of perfect dryness is incapable even of affecting litmus.

Chlorine is largely used in the arts for bleaching linen and cotton goods, rags for the manufacture of paper, &c. For these purposes it is sometimes employed in the state of gas, sometimes in that of solution in water, but more frequently in combination with lime, forming the substance called bleaching-powder. When required in large quantities it is often made by pouring slightly diluted oil of vitriol upon



a mixture of common salt and oxide of manganese contained in a large leaden vessel. The decomposition which ensues may be thus represented:—






Chlorine is one of the best and most potent substances that can be used for the purpose of disinfection, but its employment requires care. Bleaching-powder mixed with water; and exposed to the air in shallow vessels, becomes slowly decomposed by the carbonic acid of the atmosphere, and the chlorine evolved; if a more rapid disengagement be wished, a little acid of any kind may be added. In the absence of bleaching-powder, either of the methods for the production of the gas described may be had recourse to, always taking care to avoid an excess of acid.

Chloride of Hydrogen; Hydrochloric, Chlorhydric or Muriatic Acid.—This substance, in a state of solution in water, has been long known. The gas is prepared with the utmost ease by heating in a flask, fitted with a cork and bent tube, a mixture of common salt and oil of vitriol, diluted with a small quantity of water; it must be collected by displacement, or over mercury. It is a colourless gas, which fumes strongly in the air from condensing the atmospheric moisture; it has an acid, suffocating odour, but is infinitely less offensive than chlorine. Exposed to a pressure of 40 atmospheres it liquefies.

Hydrochloric acid gas has a density of 1.269. It is exceedingly soluble in water, that liquid taking up at the temperature of the air about 418 times its bulk. The gas and solution are powerfully acid.

The action of oil of vitriol on common salt, or any analogous substance is thus easily explained:—†




The composition of this substance may be determined by synthesis : when a measure of chlorine and a measure of hydrogen are fired by the electric spark, two measures of hydrochloric acid gas result, the combination being unattended by change of volume. By weight it contains 35.5 parts of chlorine and 1 part of hydrogen.

Solution of hydrochloric acid, the liquid acid of commerce, is a very important preparation, and of extensive use in chemical pursuits ; it is best prepared by the following arrangement :—

A large glass flask, containing a quantity of common salt, is fitted with a cork and bent tube, in the manner represented in fig. 99 ; the latter passes through and below a second short tube into a wide-necked bottle, containing a little water, into which the open tube dips. A bent tube is adapted to another hole in the cork of the wash-bottle so as to convey the purified gas into a quantity of distilled water, by which it is instantly absorbed : the joints are made air-tight by melting over the corks a little yellow wax.

Fig. 99.



A quantity of oil of vitriol, about equal in weight to the salt, is then slowly introduced by the funnel ; the disengaged gas is at first wholly

absorbed by the water in the wash-bottle, but when this becomes saturated, it passes into the second vessel and there dissolves. When all the acid has been added, heat may be applied to the flask by a charcoal chauffer, until its contents appear nearly dry, and the evolution of gas almost ceases, when the process may be stopped. As much heat is given out during the condensation of the gas, it is necessary to surround the condensing-vessel with cold water.

The simple wash-bottle figured in the drawing will be found an exceedingly-useful contrivance in a great number of chemical operations. It serves in the present, and in many similar cases, to retain any liquid or solid matter mechanically carried over with the gas, and it may be always employed when a gas of any kind is to be passed through an alkaline or other solution. The open tube dipping into the liquid prevents the possibility of absorption, by which a partial vacuum would be occasioned, and the liquid of the second vessel lost by being driven into the first.

The arrangement by which the acid is introduced also deserves a moment's notice. The tube is bent twice upon itself, and a bulb blown in one portion, the liquid poured into the funnel rises upon the opposite side of the first bend until it reaches the second; it then flows over and runs into the flask. Any quantity can then be got into the latter without the introduction of air, and without the escape of gas from the interior. The funnel acts also as a kind of safety-valve, and in both directions; for if by any chance the delivery-tube should be stopped, and the issue of gas prevented, its increased elastic force soon drives the little column of liquid out of the tube, the gas escapes, and the vessel is saved. On the other hand, any absorption within is quickly compensated by the entrance of air through the liquid in the bulb. The plan employed on the large scale by the manufacturer is the same in principle as that described; he merely substitutes a large iron cylinder for the flask, and vessels of stoneware for those of glass.

Pure solution of hydrochloric acid is transparent and colourless: when strong, it fumes in the air by disengaging a little gas. It leaves no residue on evaporation, and gives no precipitate or opacity with diluted solution of chloride of barium. When saturated with the gas, it has a specific gravity of 1.21, and contains about 42 per cent. of real acid. The commercial acid has usually a yellow colour and is very impure, containing salts, sulphuric acid, chloride of iron, and organic matter. It may be rendered sufficiently pure for most purposes by diluting it to the density of 1.1, which happens when the strong acid is mixed with its own bulk or rather less of water, and then distilling it in a retort furnished with a Liebig's condenser.

Fig. 100.



A mixture of nitric and hydrochloric acids has long been known under the name of *aqua regia*, from its property of dissolving gold. When these two substances are heated together, they both undergo decomposition, hyponitric acid and chlorine being evolved. This at least appears to be the final result of the action; at a certain stage, however, two peculiar substances, consisting of nitrogen, oxygen, and chlorine (chlorohyponitric acid* and chloronitrous acid),† appear to be formed. It is chiefly the chlorine which attacks the metal.

The presence of hydrochloric acid, or any other soluble chloride, is easily detected by solution of nitrate of silver. A white curdy precipitate is produced, insoluble in nitric acid; freely soluble in ammonia, and subject to blacken by exposure to light.

Compounds of Chlorine and Oxygen.

Although these bodies never combine directly, they may be made to unite by circuitous means in five different proportions, as below:—

					Composition by weight.	
					Chlorine.	Oxygen.
Hypochlorous acid	35.5	8
Chlorous acid	35.5	24
Hypochloric acid	35.5	32
Chloric acid	35.5	40
Perchloric acid ‡	35.5	56


Hypochlorous and chloric acids are generated by the action of chlorine on certain metallic oxides; the former in the cold, the latter at a high temperature. Chlorous, hypochloric, and perchloric acids result from the decomposition of chloric acid.

Hypochlorous Acid.—This is best prepared by the action of chlorine gas upon red oxide of mercury. It is a pale-yellow gaseous body, containing, in every two measures, two measures of chlorine and one of oxygen. It is very freely soluble in water, and explodes, although with no great violence, by slight elevation of temperature. The odour of this gas is peculiar, and but remotely resembles that of chlorine. It bleaches powerfully, and acts upon certain of the metals in a manner which is determined by their respective attractions for oxygen and chlorine. It forms with the alkalis a series of bleaching salts.

The preparations called *chloride of*, or *chlorinated*, *lime* and *soda*, contain hypochlorous acid. A description of these will be found under the head of Salts of Lime.

* $\text{NO}_2 \text{Cl}_2$.	† $\text{NO}_2 \text{Cl}$.
‡ Hypochlorous acid	ClO
Chlorous acid	ClO_2
Hypochloric acid	ClO_3
Chloric acid	ClO_4
Perchloric acid	ClO_5
	ClO_7

The reaction by which hypochlorous acid is produced may thus be illustrated:—




The chloride of mercury, however, does not remain as such; it combines with another portion of the oxide, when the latter is in excess, forming a peculiar brown compound, an oxychloride of mercury.†

Chlorous Acid.—This substance is prepared by heating in a flask filled to the neck a mixture of 4 parts of chlorate of potassa and 3 parts of arsenious acid with 12 parts of nitric acid previously diluted by 4 parts of water. During the operation, which must be performed in a water-bath, a greenish-yellow gas is evolved, which is sparingly soluble in water, and cannot be condensed by exposure to a freezing mixture. It slowly combines with bases, producing a class of salts called chlorites. The process which gives rise to chlorous acid is rather complicated. The arsenious acid deprives the nitric acid of part of its oxygen, reducing it into nitrous acid, which is oxidized again at the expense of the chloric acid. This, by the loss of two-fifths of its oxygen, becomes chlorous acid.

Hypochloric Acid; Peroxide of Chlorine.—Chlorate of potassa is made into a paste with concentrated sulphuric acid, and cooled; this is introduced into a small glass retort, and very cautiously heated by warm water; a deep-yellow gas is evolved, which is the body in question; it can be collected only by displacement, since mercury decomposes, and water absorbs the gas.

Hypochloric acid has a powerful odour, quite different from that of the preceding compounds, and of chlorine itself. It is exceedingly explosive, being resolved with violence into its elements by a temperature short of the boiling-point of water. Its preparation is, there-



† A very convenient method of preparing hypochlorous acid has been described by M. Pelouze. Red oxide of mercury, prepared by precipitation, and dried by exposure to a strong heat, is introduced into a glass tube, kept cool, well washed, and dry chlorine gas is slowly passed over it. Chloride of mercury and hypochlorous acid are formed; the latter is collected by displacement. When the flask or bottle in which the gas is received is exposed to artificial cold by the aid of a mixture of ice and salt, the hypochlorous acid condenses to a deep-red liquid, slowly soluble in water, and very subject to explosion. It is remarkable that the *crystalline* oxide of mercury prepared by calcining the nitrate, or by the direct oxidation of the metal, is scarcely acted upon by chlorine under the circumstances described.—Ann. Chim. et. Phys. 3rd series, vii. 179.

fore, always attended by danger, and should be performed only on a small scale. It is composed by measure of one volume of chlorine and two volumes of oxygen, condensed into two volumes.* It may be liquefied by cold. The solution of the gas in water bleaches. Salts of this acid have not yet been obtained.




The *euchlorine* of Davy, prepared by gently heating chlorate of potassa with dilute hydrochloric acid, is probably a mixture of chlorous acid and free chlorine.

The production of hypochloric acid from chlorate of potassa and sulphuric acid depends upon the spontaneous splitting of the chloric acid into hypochloric acid and perchloric acid, which latter remains in union with the potassa.†

When a mixture of chlorate of potassa and sugar is touched with a drop of oil of vitriol, it is instantly set on fire; the hypochloric acid disengaged being decomposed by the combustible substance with such violence as to cause inflammation. If crystals of chlorate of potassa be thrown into a glass of water, a few small fragments of phosphorus added, and then oil of vitriol poured down a narrow funnel reaching to the bottom of the glass, the phosphorus will burn beneath the surface of the water by the assistance of the oxygen of the hypochloric acid disengaged. The liquid at the same time becomes yellow, and acquires the odour of that gas.

Chloric Acid.—This is the most important compound of the series. When chlorine is passed to saturation into a moderately strong hot solution of caustic potassa, or the carbonate of that base, and the liquid concentrated by evaporation, it furnishes, on cooling, flat tabular crystals of a colourless salt, consisting of potassa combined with chloric acid. The mother-liquor contains chloride of potassium. In this reaction a part of the potassa is decomposed; its oxygen combines with one portion of chlorine to form chloric acid, while the potassium is taken up by a second portion of the same substance.‡

* In equivalents, as already stated, ClO_4 .



From chlorate of potassa chloric acid may be obtained by boiling the salt with a solution of hydrofluosilicic acid, which forms an almost insoluble salt with potassa, decanting the clear liquid, and digesting it with a little silica, which removes the excess of the hydrofluosilicic acid. Filtration through paper must be avoided.

By cautious evaporation, the acid may be so far concentrated as to assume a syrupy consistence; it is then very easily decomposed. It sometimes sets fire to paper, or other dry organic matter, in consequence of the facility with which it is deoxidized by combustible bodies.

The chlorates are easily recognized; they give no precipitate when in solution with nitrate of baryta or silver; they evolve pure oxygen when heated, passing thereby into chlorides; and they afford, when treated with sulphuric acid, the characteristic explosive yellow gas already described. The dilute solution of the acid has no bleaching power.

Perchloric Acid.—Prof. Penny has shown that when powdered chlorate of potassa is thrown by small portions at a time into hot nitric acid a change of the same description as that which happens when sulphuric acid is used takes place, but with this important difference, that the chlorine and oxygen, instead of being evolved in a dangerous state of combination, are emitted in a state of *mixture*. The result of the reaction is a mixture of nitrate of potassa and perchlorate of potassa, which may be readily separated by their difference of solubility.

By treating the potassa-salt in the manner directed for chloric acid, the free acid may be obtained tolerably pure. It may be concentrated by evaporation, and even distilled without change. The solution fumes slightly in the air, and has a specific gravity of 1.65. It is very deliquescent or hygroscopic, and has no bleaching properties. The perchlorates much resemble the chlorates; they give off oxygen when heated to redness. This acid is the most stable of the compounds of chlorine and oxygen.

IODINE.

This remarkable substance was first noticed in 1812 by M. Courtois of Paris. Minute traces are found in combination with sodium or potassium in sea-water, and occasionally a much larger proportion in that of certain mineral springs. It seems to be in some way beneficial to many marine plants, as these latter have the power of abstracting it from the surrounding water, and accumulating it in their tissues. It is from this source that all the iodine of commerce

is derived. It has lately been found in minute quantity in some aluminous slates of Sweden, and in several varieties of coal and turf.


Kelp, or the half-vitrified ashes of sea-weeds, prepared by the inhabitants of the Western Islands and the northern shores of Scotland and Ireland, is treated with water, and the solution filtered. The liquid is then concentrated by evaporation until it is reduced to a very small volume, the chloride of sodium, carbonate of soda, chloride of potassium, and other salts, being removed as they successively crystallize. The dark-brown mother-liquor left contains very nearly the whole of the iodine, as iodide of sodium, magnesium, &c.; this is mixed with sulphuric acid and binoxide of manganese, and gently heated in a leaden retort, when the iodine distils over and condenses in the receiver.* The theory of the operation is exactly analogous to that of the preparation of chlorine; it requires in practice, however, careful management, otherwise the impurities present in the solution interfere with the general result.*

The manganese is not really essential; iodide of potassium or sodium, heated with an excess of sulphuric acid, evolves iodine. This effect is due to a secondary action between the hydriodic acid first produced, and the excess of the sulphuric acid, in which both suffer decomposition, yielding iodine, water, and sulphurous acid.

Iodine crystallizes in plates or scales of a bluish-black colour and imperfect metallic lustre, resembling that of plumbago; the crystals are sometimes very large and brilliant. Its density is 4.948. At 225° (107°·2C) it fuses, and at 347° (175°C) boils, the vapour having an exceedingly beautiful violet colour.† It is slowly volatile, however, at common temperatures, and exhales an odour much resembling that of chlorine. The density of the vapour is 8.716. Iodine requires for solution about 7000 parts of water, which nevertheless acquires a brown colour; in alcohol it is much more freely soluble. Solutions of hydriodic acid and the iodides of the alkaline metals also dissolve a large quantity: these solutions are not decomposed by water, which is the case with the alcoholic tincture.

This substance stains the skin, but not permanently; it has a very energetic action upon the animal system, and is much used in medicine.

One of the most characteristic properties of iodine is the production of a splendid blue colour by contact with the organic principle starch. The iodine for this purpose must be free or uncombined. It is easy, however, to make the test available for the purpose of recognizing the




† Whence the name, from *ιωδης*, violet-coloured.

presence of the element in question when a soluble iodide is suspected; it is only necessary to add a very small quantity of chlorine-water, when the iodine, being displaced from combination, becomes capable of acting upon the starch.

Hydriodic Acid.—The simplest process for preparing hydriodic acid gas is to introduce into a glass tube, sealed at one extremity, a little iodine, then a small quantity of roughly-powdered glass moistened with water, upon this a few little fragments of phosphorus, and lastly more glass: this order of iodine, glass, phosphorus, glass, is repeated until the tube is half or two-thirds filled. A cork and narrow bent tube are then fitted, and gentle heat applied. The gas is received over mercury. The experiment depends upon the formation of an iodide of phosphorus, and its subsequent decomposition by water, hydrated phosphorus acid and iodide of hydrogen being produced.* The glass merely serves to moderate the violence of the action of the iodine upon the phosphorus.


Fig. 101.



Hydriodic acid gas greatly resembles the corresponding chlorine compound; it is colourless, and highly acid; it fumes in the air, and is very soluble in water. Its density is about 4.4. By weight it is composed of 127 parts iodine and 1 part hydrogen; and by measure, of equal volumes of iodine-vapour and hydrogen united without condensation.

Solution of hydriodic acid may be prepared by a process much less troublesome than the above. Iodine in fine powder is suspended in water, and a stream of washed sulphuretted hydrogen passed through

the mixture; sulphur is deposited, and the iodine converted into hydriodic acid. When the liquid has become colourless, it is heated, to expel the excess of sulphuretted hydrogen, and filtered. This solution cannot long be kept, especially if it be strong; the oxygen of the air gradually decomposes the hydriodic acid, and iodine is set free, which, dissolving in the remainder, communicates to it a brown colour.



Compounds of Iodine and Oxygen.

The most important of these are the iodic and periodic acids.

	Composition by Weight.	
	Iodine.	Oxygen.
Iodic acid	127	40
Periodic acid*	127	56

Iodic acid may be prepared by the direct oxidation of iodine by nitric acid of specific gravity 1·5; 5 parts of dry iodine with 200 parts of nitric acid are kept at a boiling temperature for several hours, or until the iodine has disappeared. The solution is then cautiously distilled to dryness, and the residue dissolved in water and made to crystallize.

Iodic acid is a very soluble substance; it crystallizes in colourless, six-sided tables, which contain water. It is decomposed by heat, and its solution readily deoxidized by sulphurous acid. The iodates much resemble the chlorates; that of potassa is decomposed by heat into iodide of potassium and oxygen gas.


Periodic Acid.—When solution of iodate of soda is mixed with caustic soda, and a current of chlorine transmitted through the liquid, two salts are formed, namely, chloride of sodium and a combination of periodate of soda with hydrate of soda, which is sparingly soluble.† This is separated, converted into a silver-salt, and dissolved in nitric acid: the solution yields on evaporation crystals of yellow periodate of silver; from which the acid may be separated by the action of water, which resolves the salt into free acid and insoluble basic periodate.

The acid itself may be obtained in crystals. It is permanent in the air, and capable of being resolved into iodine and oxygen by a high temperature.

BROMINE.

Bromine ‡ dates back to 1826 only, having been discovered by M. Balard of Montpellier. It is found in sea-water, and is a frequent constituent of saline springs, chiefly as bromide of magnesium;—a

* IO_5 , and IO_7 .



‡ From *βρωμος*, a noisome smell; a very appropriate term.

celebrated spring of the kind exists near Kreuznach in Prussia. Bromine may be obtained pure by the following process, which depends upon the fact, that ether agitated with an aqueous solution of bromine, removes the greater part of that substance.

The mother-liquor, from which the less soluble salts have separated by crystallization, is exposed to a stream of chlorine, and then shaken up with a quantity of ether; the chlorine decomposes the bromide of magnesium, and the ether dissolves the bromine thus set free. On standing, the ethereal solution, having a fine red colour, separates, and may be removed by a funnel or pipette. Caustic potassa is then added in excess, and heat applied; bromide of potassium and bromate of potassa are formed. The solution is evaporated to dryness, and the saline matter, after ignition to redness to decompose the bromate of potassa, heated in a small retort with binocide of manganese and sulphuric acid diluted with a little water, the neck of the retort being plunged into cold water. The bromine volatilizes in the form of a deep-red vapour, which condenses into drops beneath the liquid.

Bromine is at common temperatures a red thin liquid of an exceedingly intense colour, and very volatile; it freezes at about 19° ($-7^{\circ} \cdot 2\text{C}$), and boils at $145^{\circ} \cdot 4$ (63°C). The density of the liquid is $2 \cdot 976$, and that of the vapour $5 \cdot 39$. The odour of bromine is very suffocating and offensive, much resembling that of iodine, but more disagreeable. It is slightly soluble in water, more freely in alcohol, and most abundantly in ether. The aqueous solution bleaches.

Hydrobromic Acid.*—This substance bears the closest resemblance in every particular to hydriodic acid; it has the same constitution by volume, very nearly the same properties, and may be prepared by means exactly similar, substituting the one body for the other. The solution of hydrobromic acid has also the power of dissolving a large quantity of bromine, thereby acquiring a red tint. Hydrobromic acid contains by weight 80 parts bromine, and 1 part hydrogen.

Bromic Acid.†—Caustic alkalis in presence of bromine undergo the same change as with chlorine, bromide of the metal and bromate of the oxide being produced; these may often be separated by the inferior solubility of the latter. Bromic acid, obtained from bromate of baryta, closely resembles chloric acid; it is easily decomposed. The bromates when heated lose oxygen and become bromides.

No other compound of bromine and oxygen has yet been described.

FLUORINE.

This element has never been isolated, at least in a state fit for examination; its properties are consequently in great measure unknown;

* HBr .

† BrO_3 .

from the observations made it is presumed to be gaseous, and to possess colour, like chlorine. The compounds containing fluorine can be easily decomposed, and the element transferred from one body to another; but its extraordinary chemical energies towards the metals and towards silicium, a component of glass, have hitherto baffled all attempts to obtain it pure in a separate state. As fluoride of calcium it exists in small quantities in many animal substances, such as bones. Several chemists have endeavoured to obtain it by decomposing fluoride of silver by means of chlorine in vessels of fluor-spar, but even these experiments have not led to a decisive result.

*Hydrofluoric Acid.**—When powdered fluoride of calcium (fluor-spar) is heated with concentrated sulphuric acid in a retort of platinum or lead connected with a carefully-cooled receiver of the same metal, a very volatile colourless liquid is obtained, which emits copious white and highly-suffocating fumes in the air. This was formerly believed to be the acid in an anhydrous state. M. Louyet, however, states that it still contains water, and that hydrofluoric acid, like hydrochloric acid, when anhydrous, is a gas.

When hydrofluoric acid is put into water, it unites with the latter with great violence: the dilute solution attacks glass with great facility. The concentrated acid dropped upon the skin occasions deep and malignant ulcers, so that great care is requisite in its management. Hydrofluoric acid contains 19 parts fluorine and 1 part hydrogen.

In a diluted state, this acid is occasionally used in the analysis of siliceous minerals, when alkali is to be estimated; it is employed also for etching on glass, for which purpose the acid may be prepared in vessels of lead, that metal being but slowly attacked under these circumstances. The vapour of the acid is also very advantageously applied to the same object in the following manner: the glass to be engraved is coated with etching-ground or wax, and the design traced in the usual way with a pointed instrument. A shallow basin made by beating up a piece of sheet-lead is then prepared, a little powdered fluor-spar placed in it, and enough sulphuric acid added to form with the latter a thin paste. The glass is placed upon the basin, with the waxed side downwards, and gentle heat applied beneath, which speedily disengages the vapour of hydrofluoric acid. In a very few minutes the operation is complete; the glass is then removed and cleaned by a little warm oil of turpentine. When the experiment is successful, the lines are very clear and smooth.

No combination of fluorine and oxygen has yet been discovered.

* HF.

SILICIUM.

Silicium, sometimes called silicon, in union with oxygen constituting silica, or the earth of flints, is a very abundant substance, and one of great importance. It enters largely into the composition of many of the rocks and mineral masses of which the surface of the earth is composed. The following process yields silicium most readily. The double fluoride of silicium and potassium is heated in a glass tube with nearly its own weight of metallic potassium; violent reaction ensues, and silicium is set free. When cold, the contents of the tube are put into cold water, which removes the saline matter and any residual potassium, and leaves the silicium untouched. So prepared, silicium is a dark-brown powder, destitute of lustre. Heated in the air, it burns, and becomes superficially converted into silica. It is also acted upon by sulphur and by chlorine. When silicium is strongly heated in a covered crucible, its properties are greatly changed; it becomes darker in colour, denser, and incombustible, refusing to burn even when heated by the flame of the oxyhydrogen blowpipe.

Silica.—This is the only known oxide; it contains 21·3 parts silicium, and 24 parts oxygen.* Colourless transparent rock-crystal consists of silica very nearly in a state of purity; common quartz, agate, calcedony, flint, and several other minerals, are also chiefly composed of this substance.

Fig. 102.



The experiment about to be described furnishes silica in a state of complete purity, and at the same time exhibits one of the most remarkable properties of silicium, namely, its attraction for fluorine. A mixture is made of equal parts fluor-spar and glass, both finely powdered, and introduced into a glass flask, with a quantity of oil of vitriol. A tolerably wide bent tube, fitted to the flask by a cork, passes to the bottom of a glass jar, into which enough mercury is poured to cover the extremity of the tube. The jar is then half filled with water, and heat is applied to the flask.

The first effect is the disengagement of hydrofluoric acid: this substance, however, finding itself in contact with the silica of the powdered glass, undergoes decomposition, water and fluoride of silicium being produced. The latter is a permanent gas, which escapes from the flask by the bent tube. By contact with a large quantity of water, it is in turn decomposed, yielding silica, which separates in a beautiful gelatinous condition,


* Or, SiO_2 .

and an acid liquid which is a double fluoride of silicium and hydrogen, commonly called hydrofluosilicic acid.* The silica may be collected on a cloth filter, well washed, dried, and heated to redness, to expel water.


The acid liquid is kept as a test for baryta and potassa, with which it forms nearly insoluble precipitates, the double fluoride of silicium and potassium being used, as was stated, in the preparation of silicium. The fluoride of silicium, instead of being conducted into water, may be collected over mercury; it is a permanent gas, destitute of colour, and very heavy. Admitted into the air, it condenses the moisture of the latter, giving rise to a thick white cloud. It is important in the experiment above described to keep the end of the delivery-tube from touching the water of the jar, otherwise it almost instantly becomes stopped; the mercury effects this object.

There is another method by which pure silica can be prepared, and which is also very instructive, inasmuch as it is the basis of the proceeding adopted in the analysis of all siliceous minerals. Powdered rock-crystal or fine sand is mixed with about three times its weight of dry carbonate of soda, and the mixture fused in a platinum crucible. When cold, the glassy mass is boiled with water, by which it is softened, and almost entirely dissolved. An excess of hydrochloric acid is then added to the filtered liquid, and the whole evaporated to complete dryness. By this treatment the gelatinous silica thrown down by the acid becomes completely insoluble, and remains behind when the dry saline mass is treated with acidulated water, by which the

* (1) Reaction of hydrofluoric acid upon silica :—



(2) Decomposition of fluoride of silicium by water :—



alkaline salts, alumina, sesquioxide of iron, lime, and many other bodies which may happen to be present, are removed. The silica is washed, dried, and heated to redness.

The most prominent characters of silica are the following: it is a very fine, white, tasteless powder, not sensibly soluble in water or dilute acids (with the exception of hydrofluoric) unless recently precipitated. It dissolves, on the contrary, freely in strong alkaline solutions. Its density is about 2.66, and it is only to be fused by the oxyhydrogen blowpipe.

Silica is in reality an acid, and a very powerful one; insolubility in water prevents the manifestation of acid properties under ordinary circumstances. When heated with bases, especially those which are capable of undergoing fusion, it unites with them and forms true salts, which are sometimes soluble in water, as in the case of the silicates of potassa and soda when the proportion of base is considerable. Common glass is a mixture of several silicates in which the reverse of this happens, the silica, or as it is more correctly called, silicic acid, being in excess. Even glass, however, is slowly acted upon by water.

Finely-divided silica is highly useful in the manufacture of porcelain.

BORON.

This substance is closely related to silicium; it is the basis of boracic acid.

Boron is prepared by a process very similar to that described in the case of silicium, the double fluoride of boron and potassium being substituted for the other salt, and the operation conducted in a small iron vessel instead of a glass tube. It is a dull greenish-brown powder, which burns in the air when heated, producing boracic acid. Nitric acid, alkalis in a fused condition, chlorine, and other agents, attack it readily.

There is but one oxide of boron, namely, *boracic acid*, containing 10.9 parts of boron and 24 parts of oxygen.*

Boracic acid is found in solution in the water of the hot volcanic lagoons of Tuscany, whence a large supply is at present derived. It is also easily made by decomposing with sulphuric acid a hot solution of borax, a salt brought from the East Indies, consisting of boracic acid combined with soda.

Boracic acid crystallizes in transparent colourless plates, soluble in about 25 parts of cold water, and in a much smaller quantity at a boiling heat; the acid has but little taste, and feebly affects vegetable colours. When heated, it loses water, and melts to a glassy transparent mass, which dissolves many metallic oxides with great ease. The crystals contain 34.9 parts of real acid, and 27 parts of water.† They dissolve in alcohol, and the solution burns with a green flame.

* BoO_3 .

† $3\text{HO}, \text{BoO}_3$.

Glassy boracic acid in a state of fusion requires for its dissipation in vapour a very intense and long-continued heat: the solution in water cannot, however, be evaporated without very appreciable loss by volatilization; hence it is probable that the hydrate is far more volatile than the acid itself.

By heating in a glass flask or retort one part of the vitrified boracic acid, 2 of fluor-spar, and 12 of oil of vitriol, a gaseous fluoride of boron may be obtained, and received in glass jars standing over mercury. It is a transparent gas, very soluble in water, and very heavy; it forms a dense fume in the air like the fluoride of silicium.*

* These two bodies are thus constituted :— SiF_3 , and BoF_3 .

ON CERTAIN IMPORTANT COMPOUNDS FORMED BY
THE UNION OF THE PRECEDING ELEMENTS
AMONG THEMSELVES.

COMPOUNDS OF CARBON AND HYDROGEN.

THE compounds of carbon and hydrogen already known are exceedingly numerous; perhaps all, in strictness, belong to the domain of organic chemistry, as they cannot be formed by the direct union of their elements, but always arise from the decomposition of a complex body of organic origin. It will be found convenient, notwithstanding, to describe two of them in this part of the volume, as they very well illustrate the important subjects of combustion, and the nature of flame.

Light Carbonetted or Carburetted Hydrogen; Marsh-gas; Fire-dump; Gas of the Acetates.—This gas is but too often found to be abundantly disengaged in coal-mines from the fresh-cut surface of the coal, and from remarkable apertures or “blowers,” which emit for a great length of time a copious stream or jet of gas, which probably existed in a state of compression, pent up in the coal.

The mud at the bottom of pools in which water-plants grow, on being stirred, suffers bubbles of gas to escape, which may be easily collected. This, on examination, is found to be chiefly a mixture of light carbonetted hydrogen and carbonic acid; the latter is easily absorbed by lime-water or caustic potassa.

Until recently, no method was known by which the gas in question could be produced in a state approaching to purity by artificial means; the various illuminating gases from pit-coal and oil, and that obtained by passing the vapour of alcohol through a red-hot tube, contain large quantities of light carbonetted hydrogen, associated, however, with other substances which hardly admit of separation. M. Dumas was so fortunate as to discover a method by which that gas can be produced at will, perfectly pure, and in any quantity.

A mixture is made of 40 parts crystallized acetate of soda, 40 parts solid hydrate of potassa, and 60 parts quicklime in powder. This mixture is transferred to a flask or retort, and strongly heated; the gas is disengaged in great abundance, and may be collected over water.*

* Ann. Chim. et Phys. lxxiii. 93. The reaction consists in the conversion of the acetic acid, by the aid of the elements of water, into carbonic acid and


Light carbonetted hydrogen is a colourless and nearly inodorous gas, which does not affect vegetable colours. It burns with a yellow flame, generating carbonic acid and water. It is not poisonous, and may be respired to a great extent without apparent injury. The density of this compound is about 0.559, 100 cubic inches weighing 17.41 grains; and it contains carbon and hydrogen associated in the proportion of 6 parts by weight of the former to 2 of the latter.*

When 100 measures of this gas are mixed with 200 of pure oxygen in the eudiometer, and the mixture exploded by the electric spark, 100 measures of a gas remain which is entirely absorbable by a little solution of caustic potassa. Now carbonic acid contains its own volume of oxygen; hence one half the oxygen added, that is 100 measures, must have been consumed in uniting with the hydrogen. Consequently, the gas must contain twice its own measure of hydrogen, and enough carbon to produce, when completely burned, an equal quantity of carbonic acid.


When chlorine is mixed with light carbonetted hydrogen over water, no change follows, provided light be excluded. The presence of light, however, brings about decomposition, hydrochloric acid, carbonic acid, and sometimes other products being produced. It is important to remember that the gas is not acted upon by chlorine in the dark.

Olefiant Gas.—Strong spirit of wine is mixed with five or six times its weight of oil of vitriol in a glass-flask, the tube of which passes into a wash-bottle containing caustic potassa. A second wash-bottle, partly filled with oil of vitriol, is connected with the first, and furnished with a tube dipping into the water of the pneumatic trough. On the first application of heat to the contents of the flask, alcohol, and afterwards ether, make their appearance; but, as the temperature rises, and the mixture blackens, the ether-vapour diminishes in quantity, and its place becomes in great part supplied by a permanent inflammable gas; carbonic acid and sulphurous acid are also generated at the same time, besides traces of other products. The two last-mentioned gases are absorbed by the alkali in the first bottle, and the ether-vapour by

light carbonetted hydrogen; the instability of the organic acid at a high temperature, and the attraction of the potassa for carbonic acid, being the determining causes. The lime prevents the hydrate of potassa from fusing and attacking the glass vessels. This decomposition is best understood by putting it in the shape of an equation.



* The two carbides of hydrogen here described are thus represented in equivalents:—



the acid in the second, so that the olefiant gas is delivered tolerably pure. The reaction is too complex to be discussed at the present moment; it will be found fully described in another part of the volume. Olefiant gas thus produced is colourless, neutral, and but slightly soluble in water. Alcohol, ether, oil of turpentine, and even olive oil, as Mr. Faraday has observed, dissolve it to a considerable extent. It has a faint odour of garlic. On the approach of a kindled taper it takes fire, and burns with a splendid white light, far surpassing in brilliancy that produced by light carbonetted hydrogen. This gas, when mixed with oxygen and fired, explodes with extreme violence. Its density is 0.981; 100 cubic inches weigh 30.57 grains.

By the use of the eudiometer, as already described, it has been found that each measure of olefiant gas requires for complete combustion exactly three of oxygen, and produces under these circumstances two measures of carbonic acid. Whence it is evident that it contains twice its own volume of hydrogen, combined with twice as much carbon as in marsh-gas.

By weight, these proportions will be 12 parts carbon, and 2 parts hydrogen.

Olefiant gas is decomposed by passing it through a tube heated to bright redness; a deposit of charcoal and tar takes place, and the gas becomes converted into light carbonetted hydrogen, or even into free hydrogen, if the temperature be very high. This latter change is of course attended by increase of volume.

Chlorine acts upon olefiant gas in a very remarkable manner. When the two bodies are mixed, even in the dark, they combine in equal measures, and give rise to a heavy oily liquid, of sweetish taste and ethereal odour, to which the name chloride of hydrocarbon, or Dutch liquid,* is given. It is from this peculiarity that the term *olefiant* gas is derived.

A pleasing and instructive experiment may also be made by mixing in a tall jar two measures of chlorine and one of olefiant gas, and then quickly applying a light to the mouth of the vessel. The chlorine and hydrogen unite with flame, which passes quickly down the jar, while the whole of the carbon is set free in the form of a thick black smoke.

Coal and Oil Gases.—The manufacture of coal-gas is at the present moment a branch of industry of great interest and importance in several points of view. The process is one of great simplicity of principle, but requires, in practice, some delicacy of management to yield a good result.

When pit-coal is subjected to destructive distillation, a variety of products show themselves; permanent gases, steam, and volatile oils, besides a not inconsiderable quantity of ammonia from the nitrogen always present in the coal. These substances vary very much in their proportions with the temperature at which the process

* C_2H_2Cl .

is conducted, the permanent gases becoming more abundant with increased heat, but at the same time losing much of their value for the purposes of illumination.

The coal is distilled in cast-iron retorts, maintained at a bright red heat, and the volatilized products conducted into a long horizontal pipe of large dimensions, always half filled with liquid, into which the extremity of each separate tube dips; this is called the hydraulic main. The gas and its accompanying vapours are next made to traverse a refrigerator, usually a series of iron pipes, cooled on the outside by a stream of water; here the condensation of the tar and ammoniacal liquid becomes complete, and the gas proceeds onwards to another part of the apparatus, in which it is to be deprived of the sulphuretted hydrogen and carbonic acid gases always present in the crude product. This is generally effected by hydrate of lime, which readily absorbs the compounds in question. The purifiers are large iron vessels, partly filled with a mixture of hydrate of lime and water,* in which a churning machine or agitator is kept in constant motion to prevent the subsidence of the lime. The gas is admitted at the bottom of the vessel by a great number of minute apertures, and is thus made to present a large surface of contact to the purifying liquid. The last part of the operation, which indeed is often omitted, consists in passing the gas through dilute sulphuric acid, in order to remove ammonia. The quantity thus separated is very small, relatively to the bulk of the gas, but in an extensive work becomes an object of importance.

Coal-gas thus manufactured and purified is preserved for use in immense cylindrical receivers, closed at the top, suspended in tanks of water by chains to which counterpoises are attached, so that the gas-holders rise and sink in the liquid as they become filled from the purifiers or emptied by the mains. These latter are made of large diameter, to diminish as much as possible the resistance experienced by the gas in passing through such a length of pipe. The joints of these mains are still made in such an imperfect manner, that immense loss is experienced by leakage when the pressure upon the gas at the works exceeds that exerted by a column of water an inch in height.†

Coal-gas varies very much in composition, judging from its variable density and illuminating power, and from the analyses which have

* A mixture of sulphate of lime and hydrated sesquioxide of iron is likewise frequently employed.

† It may give some idea of the extent of this species of manufacture, to mention, that in the year 1838, for lighting London and the suburbs alone, there were eighteen public gas-works, and £2,800,000 invested in pipes and apparatus. The yearly revenue amounted to £450,000, and the consumption of coal in the same period to 180,000 tons, 1,460 millions of cubic feet of gas being made in the year. There were 134,300 private lights, and 30,400 street lamps. 890 tons of coal were used in the retorts in the space of twenty-four hours at mid-winter, and 7,120,000 cubic feet of gas consumed in the longest night.—Dr. Ure, Dictionary of Arts and Manufactures. Since that time the production of gas has been very considerably increased.

been made. The difficulties of such investigations are very great, and unless particular precaution be taken, the results are merely approximative. The purified gas is believed to contain the following substances, of which the first is most abundant, and the second most valuable :—

Light carbonetted hydrogen.
Olefiant gas.
Hydrogen.
Carbonic oxide.
Nitrogen.
Vapours of volatile liquid carbides of hydrogen.*
Vapour of bisulphide of carbon.

Separated by Condensation and by the Purifiers.

Tar and volatile oils.
Sulphate of ammonia, chloride and sulphide of ammonium.
Sulphuretted hydrogen.
Carbonic acid.
Hydrocyanic acid, or cyanide of ammonium.

A very far better illuminating gas may be prepared from oil, by dropping it into a red-hot iron retort filled with coke; the liquid is in great part decomposed and converted into permanent gas, which requires no purification, as it is quite free from the ammoniacal and sulphur compounds which vitiate the gas from coal. A few years ago this article was prepared in London; it was compressed for the use of the consumer into strong iron vessels, to the extent of 30 atmospheres; these were furnished with a screw-valve of peculiar construction, and exchanged for others when exhausted. The comparative high price of the material, and other circumstances, led to the abandonment of the undertaking.

COMBUSTION, AND THE STRUCTURE OF FLAME.

When any solid substance, capable of bearing the fire, is heated to a certain point, it emits light, the character of which depends upon the temperature. Thus, a bar of platinum or a piece of porcelain raised to a particular temperature, become what is called red-hot, or emissive of red light: at a higher degree of heat this light becomes whiter and more intense, and when urged to the utmost, as in the case of a piece of lime placed in the flame of the oxyhydrogen blowpipe, the light becomes exceedingly powerful, and acquires a tint of violet. Bodies in these states are said to be *incandescent* or *ignited*.

Again, if the same experiment be made on a piece of charcoal,

* These bodies increase the illuminating power, and confer on the gas its peculiar odour.

similar effects will be observed, but something in addition; for whereas the platinum or porcelain, when removed from the fire, or the lime from the blowpipe flame, begin immediately to cool, and emit less and less light, until they become completely obscure, the charcoal maintains to a great extent its high temperature. Unlike the other bodies, too, which suffer no change whatever, either of weight or substance, the charcoal gradually wastes away until it disappears. This is what is called *combustion*, in contradistinction to mere ignition; the charcoal burns, and its temperature is kept up by the heat evolved in the act of union with the oxygen of the air.

In the most general sense, a body in a state of combustion is one in the act of undergoing intense chemical action: any chemical action whatsoever, if its energy rise sufficiently high, may produce the phenomenon of combustion, by *heating the body to such an extent that it becomes luminous*.

In all ordinary cases of combustion, the action lies between the burning body and the oxygen of the air; and since the materials employed for the economical production of heat and light consist of carbon chiefly, or that substance conjoined with a certain proportion of hydrogen and oxygen, all common effects of this nature are cases of the rapid and violent oxidation of carbon and hydrogen by the aid of the free oxygen of the air. The heat must be referred to the act of chemical union, and the light to the elevated temperature.

By this principle it is easy to understand the means which must be adopted to increase the heat of ordinary fires to the point necessary to melt refractory metals, and to bring about certain desired effects of chemical decomposition. If the rate of consumption of the fuel can be increased by a more rapid introduction of air into the burning mass, the intensity of the heat will of necessity rise in the same ratio, there being reason to believe that the quantity of heat evolved is fixed and definite for the same constant quantity of chemical action. This increased supply of air may be effected by two distinct methods: it may be forced into the fire by bellows or blowing machines, as in the common forge, and in the blast and cupola-furnaces of the iron-worker, or it may be drawn through the burning materials by the help of a tall chimney, the fireplace being closed on all sides, and no entrance of air allowed, save between the bars of the grate. Such is the kind of furnace generally employed by the scientific chemist in assaying and in the reduction of metallic oxides by charcoal; the principle will be at once understood by the aid of the sectional drawing, in which a crucible is represented, arranged in the fire for an operation of the kind mentioned. (Fig. 103.)


The "reverberatory" furnace is one very much used in the arts when substances are to be exposed to heat without contact with the fuel. The fire-chamber is separated from the bed or hearth of the furnace by a low wall or *bridge* of brick-work, and the flame and heated air are reflected downwards by the arched form of the roof.

Any degree of heat can be obtained in a furnace of this kind, from the temperature of dull redness, to that required to melt very large quantities of cast-iron. The fire is urged by a chimney, provided with a sliding-plate or damper to regulate the draught.

Fig. 103.



Fig. 104.



Solids and liquids, as melted metal, enjoy, when sufficiently heated, the faculty of emitting light; the same power is possessed by gaseous bodies, but the temperature required to render a gas luminous is incomparably higher than in the cases already described. Gas or vapour in this condition constitutes *flame*, the actual temperature of which generally exceeds that of the white heat of solid bodies.

The light emitted from pure flame is exceedingly feeble; illuminating power is almost entirely dependent upon the presence of solid matter. The flame of hydrogen, or of the mixed gases, is scarcely visible in full daylight; in a dusty atmosphere, however, it becomes much more luminous by igniting to intense whiteness the floating particles with which it comes in contact. The piece of lime in the blowpipe flame cannot have a higher temperature than that of the flame itself; yet the light it throws off is infinitely greater.

Flames burning in the air, and not supplied with oxygen from

another source, are, as already stated, hollow; the chemical action is necessarily confined to the spot where the two bodies unite. That of a lamp or candle, when carefully examined, is seen to consist of three separate portions. The dark central part, easily rendered evident by depressing upon the flame a piece of fine wire-gauze, consists of combustible matter drawn up by the capillarity of the wick, and volatilized by the heat. This is surrounded by a highly-luminous cone or envelope, which, in contact with a cold body, deposits soot. On the outside a second cone is to be traced, feeble in its light-giving power, but having an exceedingly high temperature. The explanation of these appearances is easy: carbon and hydrogen are very unequal in their attraction for oxygen, the latter greatly exceeding the former in this respect; consequently, when both are present, and the supply of oxygen limited, the hydrogen takes all, to the exclusion of a great part of the carbon. Now this happens in the case under consideration at some little distance within the outer surface of the flame, namely, in the luminous portion; the little oxygen which has penetrated thus far inwards is entirely consumed by the hydrogen, and the particles of deposited charcoal, which would, were they cooler, form smoke, become intensely ignited by the burning hydrogen, and evolve a light whose whiteness marks a very elevated temperature. In the exterior and scarcely-visible cone, these particles of carbon undergo combustion.

A jet of coal-gas exhibits these phenomena; but, if the gas be previously mingled with air, or if air be forcibly mixed with, or driven into the flame, no such separation of carbon occurs, the hydrogen and carbon burn *together*, and the illuminating power almost disappears.

The common mouth blowpipe is a little instrument of great utility; it is merely a brass tube fitted with an ivory mouth-piece, and terminated by a jet, having a small aperture by which a current of air is driven across the flame of a candle. The best form is perhaps that contrived by Mr. Pepys, and figured in the margin. The flame so produced is very peculiar.

Instead of the double envelope just described, two long pointed cones are observed, which, when the blowpipe is good, and the aperture smooth and round, are very well defined, the outer cone

Fig. 105.




Fig. 106.



being yellowish, and the inner blue. A double combustion is, in fact, going on, by the blast in the inside, and by the external air.

Fig. 107.



The space between the inner and outer cones is filled with exceedingly hot combustible matter, possessing strong reducing or deoxidizing-powers, while the highly-heated air just beyond the point of the exterior cone oxidizes with great facility. A small portion of matter, supported on a piece of charcoal, or fixed in a ring at the end of a fine platinum wire, can thus in an instant be exposed to a very high degree of heat under these contrasted

circumstances, and observations of great value made in a very short time. The use of the instrument requires an even and uninterrupted blast of some duration, by a method easily acquired with a little patience; it consists in employing for the purpose the muscles of the cheeks alone, respiration being conducted through the nostrils, and the mouth from time to time replenished with air without intermission of the blast.

The Argand lamp, adapted to burn either oil or spirit, but especially the latter, is a very useful piece of chemical apparatus. In this lamp the wick is cylindrical, the flame being supplied with air both inside and outside: the combustion is greatly aided by the chimney, which is made of copper when the lamp is used as a source of heat.

Fig. 108.




Fig. 109.



The accompanying drawing exhibits, in section, an excellent lamp of this kind for burning alcohol or wood-spirit. It is constructed of thin copper, and furnished with ground caps to the wick-holder and aper-

ture* by which the spirit is introduced, in order to prevent loss when the lamp is not in use. Glass spirit-lamps, fitted with caps to prevent evaporation, are very convenient for occasional use, being always ready and in order.

In London, and other large towns, where coal-gas is to be had, it is constantly used with the greatest economy and advantage in every respect as a source of heat. Retorts, flasks, capsules, and other vessels, can be thus exposed to an easily-regulated and invariable temperature for many successive hours. Small platinum crucibles may be ignited to redness by placing them over the flame on a little wire triangle. The arrangement shown consisting of a common Argand gas-burner fixed on a heavy and low foot, and connected with a flexible tube of caoutchouc or other material, leaves nothing to desire.


The kindling-point, or temperature at which combustion commences, is very different with different substances: phosphorus will sometimes take fire in the hand; sulphur requires a temperature exceeding that of boiling water, charcoal must be heated to redness. Among gaseous bodies the same fact is observed: hydrogen is inflamed by a red-hot wire; carbonetted hydrogen requires a white heat to effect the same thing. When flame is cooled by any means below the temperature at which the rapid oxidation of the combustible gas occurs, it is at once extinguished. Upon this depends the principle of Sir H. Davy's invaluable safety-lamp.

Mention has already been made of the frequent disengagement of great quantities of light carbonetted hydrogen gas in coal-mines. This gas, mixed with seven or eight times its volume of atmospheric air, becomes highly explosive, taking fire at a light, and burning with a pale-blue flame; and many fearful accidents have occurred from the ignition of large quantities of mixed gas and air occupying the extensive galleries and workings of a mine. Sir H. Davy undertook an investigation with a view to discover some remedy for this constantly-occurring calamity: his labours resulted in some exceedingly-important discoveries respecting flame, of which the substance has been given, and which led to the construction of the lamp which bears his name.

When two vessels filled with a gaseous explosive mixture are connected by a narrow tube, and the contents of one fired by the electric spark, or otherwise, the flame is not communicated to the other, pro-

* When in use this aperture must always be open, otherwise an accident is sure to happen; the heat expands the air in the lamp, and the spirit is forced out in a state of inflammation.

Fig. 110.



vided the diameter of the tube, its length, and the conducting power for heat of its material, bear a certain proportion to each other; the flame is extinguished by cooling, and its transmission rendered impossible.

In this experiment high conducting power and diminished diameter compensate for diminution of length; and to such an extent can this be carried, that metallic gauze, which may be looked upon as a series of very short square tubes arranged side by side, arrests in the most complete manner the passage of flame in explosive mixtures, when of sufficient degree of fineness, depending upon the inflammability of the gas. Most providentially the fire-damp mixture has an exceedingly high kindling point; a red heat does not cause inflammation; consequently, the gauze will be safe for this substance, when flame would pass in almost any other case.

The miner's safety-lamp is merely an ordinary oil-lamp, the flame of which is enclosed in a cage of wire-gauze; made double at the upper part, containing about 400 apertures to the square inch. The tube for supplying oil to the reservoir reaches nearly to the bottom of the latter, while the wick admits of being trimmed by a bent wire passing with friction through a small tube in the body of the lamp; the flame can thus be kept burning for any length of time, without the necessity of unscrewing the cage. When this lamp is taken into an explosive atmosphere, although the fire-damp may burn within the cage with such energy as sometimes to heat the metallic tissue to dull redness, the flame is not communicated to the mixture on the outside.

Fig. 111.



These effects may be conveniently studied by suspending the lamp in a large glass jar, and gradually admitting coal-gas below. The oil-flame is at first elongated, and then, as the proportion of gas increases, extinguished, while the interior of the gauze cylinder becomes filled with the burning mixture of gas and air. As the atmosphere becomes purer, the wick is once more relighted. These appearances are so remarkable, that the lamp becomes an admirable indicator of the state of the air in different parts of the mine.*

The same great principle has been ingeniously applied by Mr.

* This is the true use of the lamp, namely, to permit the viewer or superintendent, without risk to himself, to examine the state of the air in every part of the mine; not to enable workmen to continue their labours in an atmosphere habitually explosive, which must be unfit for human respiration, although the evil effects may be slow to appear. Owners of coal-mines should be compelled either to adopt efficient means of ventilation, or to close workings of this dangerous character altogether.

Hemming to the construction of the oxyhydrogen safety-jet before-mentioned. This is a tube of brass about four inches long, filled with straight pieces of fine brass wire, the whole being tightly wedged together by a pointed rod, forcibly driven into the centre of the bundle. The arrangement thus presents a series of metallic tubes, very long in proportion to their diameter, the cooling powers of which are so great as to prevent the possibility of the passage of flame, even with oxygen and hydrogen. The jet may be used, as before mentioned, with a common bladder, without a chance of explosion. The fundamental fact of flame being extinguished by contact with a cold body, may be elegantly shown by twisting a copper wire into a short spiral, about 0.1 inch in diameter, and then passing it *cold* over the flame of a wax candle; the latter is extinguished. If the spiral be now heated to redness by a spirit-lamp, and the experiment repeated, no such effect follows.

Fig. 113.



Fig. 112.



NITROGEN AND HYDROGEN; AMMONIA.

When powdered sal-ammoniac is mixed with moist hydrate of lime, and gently heated in a gas-flask, a large quantity of gaseous matter is disengaged, which must be collected over mercury, or by displacement, advantage being taken of its low specific gravity.

Ammoniacal gas thus obtained is colourless; it has a very powerfully-pungent odour, and a strongly-alkaline reaction to test-paper, by which it may be at once distinguished from nearly all other bodies possessing the same physical characters. Under a pressure of 6.5 atmospheres at 60° (15°.5C), ammonia condenses to the liquid form. Water dissolves about 700 times its volume of this remarkable gas, forming a solution which in a more dilute state has long been known under the name of *liquor ammoniæ*; by heat, a great part is again expelled. The solution is decomposed by chlorine, sal-ammoniac being formed, and nitrogen set free.

Ammonia has a density of 0.589; 100 cubic inches weigh 18.26 grains. It cannot be formed by the direct union of its elements, although it is sometimes produced under rather remarkable circumstances by the deoxidation of nitric acid. The great sources of am-

monia are the feebly-compounded azotized principles of the animal and vegetable kingdoms, which, when left to putrefactive change, or subjected to destructive distillation, almost invariably give rise to an abundant production of this substance.


The analysis of ammoniacal gas is easily effected. When a portion is confined in a graduated tube over mercury, and electric sparks passed through it for a considerable time, the volume of the gas gradually increases until it becomes doubled. On examination, the tube is found to contain a mixture of 3 measures hydrogen gas and 1 measure nitrogen. Every two volumes of the ammonia, therefore, contained three volumes of hydrogen and one of nitrogen, the whole being condensed to the extent of one-half. The weight of the two constituents will be in the proportion of 3 parts hydrogen to 14 parts nitrogen.

Ammonia may also be decomposed into its elements by transmission through a red-hot tube.

Solution of ammonia is a very valuable reagent, and is employed in a great number of chemical operations, for some of which it is necessary to have it perfectly pure. The best mode of preparation is the following :—

Equal weights of sal-ammoniac and quicklime are taken ; the lime is slaked in a covered basin, and the salt reduced to powder. These are mixed and introduced into the flask employed in preparing solution of hydrochloric acid, together with just enough water to damp the mixture, and cause it to aggregate into lumps ; the rest of the apparatus is arranged exactly as in the former case, with an ounce or two of water in the wash-bottle, or enough to cover the ends of the tubes, and the gas conducted afterwards into pure distilled water, artificially cooled as before. The cork-joints are made tight with wax, a little water is put into the safety-funnel, heat cautiously applied to the flask, and the whole left to itself. The disengagement of ammonia is very regular and uniform. Chloride of calcium, with excess of hydrate of lime, remains in the flask.

The decomposition of the salt is usually represented in the manner shown by the following diagram :—



* See Fig. 99, p. 153.



Solution of ammonia should be perfectly colourless, leave no residue on evaporation, and when supersaturated by nitric acid, give no cloud or muddiness with nitrate of silver. Its density diminishes with its strength, that of the most concentrated being about 0.875: the value in alkali of any sample of liquor ammoniæ is most safely inferred, not from a knowledge of its density, but from the quantity of acid a given amount will saturate. The mode of conducting this experiment will be found described under *Alkalimetry*.

When solution of ammonia is mixed with acids of various kinds, salts are generated, which resemble in the most complete manner the corresponding compounds of potassa and soda: these are best discussed in connexion with the latter. Any ammoniacal salt can at once be recognized by the evolution of ammonia when it is heated with hydrate of lime, or solution of carbonate of potassa or soda.


NITROGEN AND BORON.

A combination of nitrogen with boron was first obtained by Balmain. Wöehler prepared it by mixing one part of pure dry borax with two parts of dry sal-ammoniac, heating to redness, boiling with water and hydrochloric acid, filtering and washing with hot water, when the compound remained in the form of a white powder. As yet it has not been obtained quite free from oxygen.


SULPHUR, SELENIUM, AND PHOSPHORUS WITH HYDROGEN.

Sulphuretted Hydrogen ; Hydrosulphuric Acid.—There are two methods by which this important compound can be readily prepared, namely, by the action of dilute sulphuric acid upon sulphide of iron, and by the decomposition of sulphide of antimony by hydrochloric acid. The first method yields it most easily, and the second in the purest state.

Protosulphide of iron is put into the apparatus for hydrogen, already several times mentioned, together with some water, and oil of vitriol is added by the funnel, until a copious disengagement of gas takes place. This is to be collected over tepid water. The reaction is thus explained:—



By the other plan, finely-powdered sulphide of antimony is put into a flask, to which a cork and bent tube can be adapted, and strong liquid hydrochloric acid poured upon it. On the application of heat, a double interchange occurs between the bodies present, sulphuretted hydrogen being formed and chloride of antimony. The action only lasts while the heat is maintained.



Sulphuretted hydrogen is a colourless gas, having the odour of putrid eggs; it is most offensive when in small quantity, when a mere trace is present in the air. It is not irritating, but, on the contrary, powerfully narcotic. When set on fire, it burns with a blue flame, producing water and sulphurous acid when the supply of air is abundant; and depositing sulphur when the oxygen is deficient. Mixed with chlorine, it is instantly decomposed, with separation of the whole of the sulphur.

This gas has a specific gravity of 1.171; 100 cubic inches weigh 36.33 grains.


A pressure of 17 atmospheres at 50° (10°C) reduces it to the liquid form. Cold water dissolves its own volume of sulphuretted hydrogen, and the solution is often directed to be kept as a test; it is so prone to decomposition, however, by the oxygen of the air, that it speedily spoils. A much better plan is to keep a little apparatus for

Fig. 114.



generating the gas always at hand, and ready for use at a moment's notice. A small bottle or flask, to which a bit of bent tube is fitted by a cork, is supplied with a little sulphide of iron and water; when required for use, a few drops of oil of vitriol are added, and the gas is at once evolved. The experiment completed, the liquid is poured from the bottle, replaced by a little clean water, and the apparatus is again ready for use.

When potassium is heated in sulphuretted hydrogen, the metal burns with great energy, becoming converted into sulphide, while pure hydrogen remains, equal in volume to the original gas. Taking



this fact into account, and comparing the density of the gas with those of hydrogen and sulphur-vapour, it appears that every volume of sulphuretted hydrogen contains one volume of hydrogen and $\frac{1}{8}$ of a volume of sulphur-vapour, the whole condensed into one volume. This corresponds very nearly with its composition by weight, determined by other means, namely, 16 parts sulphur and 1 part hydrogen.

When a mixture is made of 100 measures of sulphuretted hydrogen and 150 measures of pure oxygen, and exploded by the electric spark, complete combustion ensues, and 100 measures of sulphurous acid gas result.

Sulphuretted hydrogen is a frequent product of the putrefaction of organic matter, both animal and vegetable; it occurs also in certain mineral springs, as at Harrowgate, and elsewhere. When accidentally present in the atmosphere of an apartment, it may be instantaneously destroyed by a small quantity of chlorine gas.

There are few reagents of greater value to the practical chemist than this substance: when brought in contact with many metallic solutions, it gives rise to precipitates, which are often exceedingly characteristic in appearance, and it frequently affords the means also of separating metals from each other with the greatest precision and certainty. The precipitates spoken of are insoluble sulphides, formed by the mutual decomposition of the metallic oxides or chlorides and sulphuretted hydrogen, water or hydrochloric acid being produced at the same time. All the metals are, in fact, precipitated whose sulphides are insoluble in water and in dilute acids.

Sulphuretted hydrogen possesses itself the properties of an acid; its solution in water reddens litmus paper.

The best test for the presence of this compound is paper wetted with solution of acetate of lead. This salt is blackened by the smallest trace of the gas.

Persulphide of Hydrogen.—This substance corresponds in constitution and instability to the binoxide of hydrogen; it is prepared by the following means:—

Equal weights of slaked lime and flowers of sulphur are boiled with 5 or 6 parts of water for half an hour, when a deep orange-coloured solution is produced, containing among other things persulphide of calcium. This is filtered, and slowly added to an excess of dilute sulphuric acid, with constant agitation. A white precipitate of separated sulphur and sulphate of lime makes its appearance, together with a quantity of yellow oily-looking matter, which collects at the bottom of the vessel: this is persulphide of hydrogen.*

If the experiment be conducted by pouring the *acid* into the solu-

* The reaction which ensues when hydrate of lime, sulphur, and water are boiled together, is rather complex, bisulphide or pentasulphide of calcium being formed, together with hyposulphite of lime, arising from the transfer of the oxygen of the decomposed lime to another portion of sulphur.



tion of sulphide, then nothing but finely-divided precipitated sulphur is obtained.

The persulphide is a yellow, viscid, insoluble liquid, exhaling the odour of sulphuretted hydrogen: its specific gravity is 1.769. It is slowly decomposed even in the cold into sulphur and sulphuretted hydrogen, and instantly by a higher temperature, or by contact with many metallic oxides. This compound probably contains twice as much sulphur in relation to the other elements as sulphuretted hydrogen.*



Hydrogen and Selenium; Selenetted Hydrogen.—This substance is produced by the action of dilute sulphuric acid upon selenide of potassium or iron: it very much resembles sulphuretted hydrogen, being a colourless gas, freely soluble in water, and decomposing metallic solutions like that substance; insoluble selenides are thus produced. This gas is said to act very powerfully upon the lining membrane of the uose, exciting catarrhal symptoms, and destroying the sense of smell. It contains 39.5 parts selenium, and 1 part hydrogen.

Phosphorus and Hydrogen; Phosphoretted Hydrogen.—This body bears a slight analogy in some of its chemical relations to ammoniacal gas; it is, however, destitute of alkaline properties.

Phosphoretted hydrogen may be obtained in a state of purity by heating in a small retort hydrated phosphorous acid, which is by such



* The bisulphide of calcium, decomposed by an acid under favourable circumstances, yields a salt of lime and bisulphide (persulphide) of hydrogen.




When the acid is poured into the sulphide, sulphuretted hydrogen, water, and sulphate of lime are produced, while the excess of sulphur is thrown down as a fine white powder, the "precipitated sulphur" of the Pharmacopœia. When the object is to prepare the latter substance, hydrochloric acid must be used in the place of sulphuric.

treatment decomposed into phosphoretted hydrogen and hydrated phosphoric acid.*




Thus obtained, the gas has a density of 1.24. It contains 32 parts phosphorus and 3 parts hydrogen, and is so constituted that every two volumes contain 3 volumes of hydrogen and half a volume of phosphorous vapour, condensed into two volumes. It possesses a highly-disagreeable odour of garlic, is slightly soluble in water, and burns with a brilliant white flame, forming water and phosphoric acid.

Phosphoretted hydrogen may also be produced by boiling together in a retort of small dimensions caustic potassa or hydrate of lime, water, and phosphorus; the vessel should be filled to the neck, and the extremity of the latter made to dip into the water of the pneumatic trough. In the reaction which ensues the water is decomposed, and both its elements combine with the phosphorus. The alkali acts by *its presence* determining the decomposition of the water, in the same manner as sulphuric acid determines the decomposition of water when in contact with zinc.



The phosphoretted hydrogen prepared by the latter process has the singular property of spontaneous inflammability when admitted into the air or into oxygen gas: with the latter, the experiment is very beautiful, but requires caution; the bubbles should be singly admitted. When kept over water for some time, the gas loses this property, with-

* Decomposition of hydrated phosphorous acid by heat:—



out otherwise suffering any appreciable change; but if dried by chloride of calcium, it may be kept unaltered for a much longer period. M. Paul Thénard has shown that the spontaneous combustibility of the gas arises from the presence of the vapour of a liquid phosphide of hydrogen, which can be procured in small quantity, by conveying the gas produced by the action of water on phosphide of calcium through a tube cooled by a freezing mixture. This substance forms a colourless liquid of high refractive power and very great volatility. It does not freeze at 0° ($-17^{\circ}\cdot8\text{C}$). In contact with air it inflames instantly, and its vapour in very small quantity communicates spontaneous inflammability to pure phosphoretted hydrogen, and to all other combustible gases. It is decomposed by light into gaseous phosphoretted hydrogen, and a solid phosphide which is often seen on the inside of jars containing gas which has lost the property of spontaneous inflammation by exposure to light. Strong acids occasion its instantaneous decomposition. Its instability is equal to that of binoxide of hydrogen. It is to be observed that the pure phosphoretted hydrogen gas itself becomes spontaneously inflammable if heated to the temperature of boiling water.*

Phosphoretted hydrogen decomposes several metallic solutions, giving rise to precipitates of insoluble phosphides. With hydriodic acid it forms a crystalline compound somewhat resembling sal-ammoniac.


NITROGEN WITH CHLORINE AND IODINE.

Chloride of Nitrogen.—When sal-ammoniac or nitrate of ammonia is dissolved in water, and a jar of chlorine gas inverted into the solution, the gas is absorbed, and a deep-yellow oily liquid is observed to collect upon the surface of the solution, which ultimately sinks in globules to the bottom. This is chloride of nitrogen, the most dangerously-explosive substance known. The following is the safest method of conducting the experiment:—

A somewhat dilute and tepid solution of pure sal-ammoniac in distilled water is poured into a clean basin, and a bottle of chlorine, the neck of which is quite free from grease, inverted into it. A shallow and heavy leaden cup is placed beneath the mouth of the bottle to collect the product. When enough has been obtained, the leaden vessel may be withdrawn with its dangerous contents, the chloride remaining covered with a stratum of water. The operator should protect his face with a strong wire-gauze mask when experimenting upon this substance.

* Ann. Chim. et Phys. 3rd series, xiv. 5. According to M. P. Thénard the new liquid phosphide of hydrogen contains PH_2 and the solid P_2H_4 . The gas is represented by the formula PH_3 .


The change is explained by the following diagram :—



Chloride of nitrogen is very volatile, and its vapour is exceedingly irritating to the eyes. It has a specific gravity of 1.653. It may be distilled at 160° (71°C), although the experiment is attended with great danger. Between 200° (93°C) and 212° (105°C) it explodes with the most fearful violence. Contact with almost any combustible matter, as oil or fat of any kind, determines the explosion at common temperatures: a vessel of porcelain, glass, or even of cast-iron is broken to pieces, and the leaden cup receives a deep indentation. This body has usually been supposed to contain nitrogen and chlorine in the proportion of 14 parts of the former to 106.5 parts of the latter, but recent experiments upon the corresponding iodine-compound induce a belief that it contains hydrogen.†

Iodide of Nitrogen.—When finely-powdered iodine is put into caustic ammonia it is in part dissolved, giving a deep-brown solution, and the residue is converted into a black powder, which is the substance in question. The brown liquid consists of hydriodic acid holding iodine in solution, and is easily separated from the solid product by a filter. The latter while still wet is distributed in small quantities upon separate pieces of bibulous paper, and left to dry in the air.

Iodide of nitrogen is a black insoluble powder, which, when dry, explodes with the slightest touch, even that of a feather; and sometimes without any obvious cause. The explosion is not nearly so violent as that of the compound last described, and is attended with the production of violet fumes of iodine. According to Dr. Gladstone this substance contains hydrogen, and it may be viewed as ammonia, in which two-thirds of the hydrogen are replaced by iodine;‡ according to recent researches of Bunsen it must be viewed as a combination of teriodide of nitrogen with ammonia.§



† Instead of NCl_3 , it may in reality be NH Cl_2 .

‡ NH_2I .

§ $\text{NHI}^3 + \text{NH}_3$.

OTHER COMPOUNDS OF NON-METALLIC ELEMENTS.

Chlorine with Sulphur and Phosphorus.—*Chloride of Sulphur.*—The subchloride is easily prepared by passing dry chlorine over the surface of sulphur kept melted in a small glass retort connected with a good condensing arrangement. The chloride distils over as a deep orange-yellow mobile liquid, of peculiar and disagreeable odour, which boils at 280° ($137^{\circ}\cdot 8\text{C}$). As this substance dissolves both sulphur and chlorine, it is not easy to obtain it in a pure and definite state. It contains 32 parts sulphur and $35\cdot 5$ chlorine.*

Subchloride of sulphur is instantly decomposed by water; hydrochloric and hyposulphurous acids are formed, and sulphur separated. The hyposulphurous acid in its turn decomposes into sulphur and sulphurous acid. Protochloride of sulphur is formed by exposing the above compound for a considerable time to the action of chlorine, and then distilling it in a stream of the gas. It has a deep-red colour, is heavier than water, boils at 147° ($63^{\circ}\cdot 9\text{C}$), and contains twice as much chlorine as the subchloride.†

Chlorides of Phosphorus.—*Trichloride.*‡—This is prepared in the same manner as subchloride of sulphur, by gently heating phosphorus in dry chlorine gas, the phosphorus being in excess. Or, by passing the vapour of phosphorus over fragments of calomel (subchloride of mercury) contained in a glass tube and strongly heated. It is a colourless, thin liquid, which fumes in the air, and possesses a powerful and offensive odour. Its specific gravity is $1\cdot 45$. Thrown into water, it sinks to the bottom of that liquid, and becomes slowly decomposed, yielding phosphorous acid and hydrochloric acid. This compound contains 32 parts phosphorus and $106\cdot 5$ parts chlorine.

Pentachloride of Phosphorus.§—The compound formed when phosphorus is burned in excess of chlorine. Into a large retort, fitted with a cap and stop-cock, pieces of phosphorus are introduced; the retort is then exhausted, and filled with dry chlorine gas. The phosphorus takes fire, and burns with a pale flame, forming a white, volatile crystalline sublimate, which is the pentachloride. It may be obtained in larger quantity by passing a stream of dry chlorine gas into the preceding liquid trichloride, which becomes gradually converted into a solid crystalline mass. Pentachloride of phosphorus is decomposed by water, yielding phosphoric and hydrochloric acids.

Two bromides of phosphorus are known, closely corresponding in properties and constitution with the chlorides. Several compounds of iodine and phosphorus appear to exist, they are fusible crystalline substances, which decompose by contact with water, and yield hydriodic acid and phosphorus, or phosphoric acid.

* S_2Cl .† SCl .‡ PCl_3 .§ PCl_5 .

Chlorine and Carbon.—Several compounds of chlorine and carbon are known. They are obtained indirectly by the action of chlorine upon certain organic compounds, and are described in connexion with the history of alcohol, &c.

Iodine with Sulphur and Phosphorus.—These compounds are formed by gently heating together the materials in vessels from which the air is excluded. They present few points of interest.

Chlorine with Iodine.—Iodine readily absorbs chlorine gas, forming, when the chlorine is in excess, a solid yellow compound, and when the iodine preponderates, a brown liquid. The solid iodide is decomposed by water, yielding hydrochloric and iodic acids.*

Another definite compound is formed by heating in a retort a mixture of 1 part iodine and 4 parts chlorate of potassa; oxygen gas and chloride of iodine are disengaged, and the latter may be condensed by suitable means. Iodate and perchlorate of potassa remain in the retort.

This chloride of iodine is a yellow, oily liquid, of suffocating smell and astringent taste; it is soluble in water and alcohol without decomposition. It probably consists of 127 parts iodine and 35.5 parts chlorine.†

Carbon and Sulphur.—*Bisulphide of Carbon.*‡—A wide porcelain tube is filled with pieces of charcoal which have been recently heated to redness in a covered crucible, and fixed across a furnace in a slightly-inclined position. Into the lower extremity a tolerably wide tube is secured by the aid of a cork: this tube bends downwards, and passes nearly to the bottom of a bottle filled with fragments of ice and a little water. The porcelain tube being heated to bright redness, fragments of sulphur are thrown into the open end, which is immediately afterwards stopped by a cork. The sulphur melts, and becomes converted into vapour, which at that high temperature, combines with the carbon, forming an exceedingly volatile compound, which is condensed by the ice and collects at the bottom of the vessel. This is collected and redistilled with a very gentle heat in a retort connected with a good condenser. Bisulphide of carbon is a transparent colourless liquid of great refractive and dispersive power. Its density is 1.272. It boils at 110° (43° .3C), and emits vapour of considerable elasticity at common temperatures. The odour of this substance is very repulsive. When set on fire in the air it burns with a blue flame, forming carbonic acid and sulphurous acid gases; and when its vapour is mixed with oxygen it becomes explosive.

It freely dissolves sulphur, and by spontaneous evaporation deposits the latter in beautiful crystals, it also dissolves phosphorus.

Chlorides of Silicium and Boron.—Both silicium and boron combine directly with chlorine. The chloride of silicium is obtained by mixing

* Hence it doubtless contains 1 eq. iodine, and 5 eq. chlorine, or ICl_5 .

† Or single equivalents.

‡ CS_2 .

finely-divided silica with charcoal-powder and oil, strongly heating the mixture in a covered crucible, and then exposing the mass so obtained in a porcelain tube, heated to full redness, to the action of perfectly-dry chlorine gas. A good condensing arrangement, supplied with ice-cold water, must be connected with the porcelain tube. The product is a colourless and very volatile liquid, boiling at 122° (50°C), of pungent, suffocating odour. In contact with water it yields hydrochloric acid and gelatinous silica. This substance contains 21.3 parts silicium, and 106.5 chlorine.*

Bromide of Silicium† may be obtained by a similar proceeding, the vapour of bromine being substituted for chlorine: it resembles the chloride, but is less volatile.

Chloride of Boron‡ is a permanent gas, decomposed by water, with production of boracic and hydrochloric acids, and fuming strongly in the air. It may be most easily obtained by exposing to the action of dry chlorine at a very high temperature an intimate mixture of glassy boracic acid and charcoal. It resembles in constitution chloride of silicium.

* Or SiCl_3 .

† SiBr_3 .

‡ BoCl_3 .

ON THE GENERAL PRINCIPLES OF CHEMICAL PHILOSOPHY.

THE study of the non-metallie elements can be pushed to a very considerable extent, and a large amount of precise and exceedingly important information aquired, without much direct reference to the great fundamental laws of chemical union. The subject cannot be discussed in this manner completely, as will be obvious from frequent cases of anticipation in many of the foregoing foot-notes ; still much may be done by this simple method of proceeding. The bodies themselves, in their combinations, furnish admirable illustrations of the general laws referred to ; but the study of their leading characters and relations does not of necessity involve a previous knowledge of these laws themselves.

It is thought that by such an arrangement the comprehension of these very important general principles may become, in some measure, facilitated by constant references to examples of combinations, the elements and products of which have been already described. So much more difficult is it to gain a clear and distinct idea of any proposition of great generality from a simple enunciation, than to understand the bearing of the same law when illustrated by a single good and familiar instance.

Before proceeding farther, however, it is absolutely necessary that these matters should be discussed : the metallie compounds are so numerous and complicated, that the establishment of some general principle, some connecting link, becomes indispensable. The doctrine of equivalents, and the laws which regulate the formation of saline compounds, supply this deficiency.

In the organic department of the science, the most interesting perhaps of all, a knowledge of these principles, and, farther, an acquaintance or even familiarity with the beautiful system of chemical notation now in use, are absolutely required. This latter is found of very great service in the study of salts and other complex inorganic compounds, but in that of organic chemistry it cannot be dispensed with.

It will be proper to commence with a notice of the principles which regulate the modern nomenclature in use in chemical writings.

NOMENCLATURE.

In the early days of chemistry the arbitrary and fanciful names which were conferred by each experimenter on the new compounds he discovered sufficed to distinguish these from each other, and to render intelligible the description given of their production. Such terms as

oil of vitriol, spirit of salt, oil of tartar, butter of antimony, sugar of lead, flowers of zinc, sal enixum, sal mirabile, &c., were then quite admissible. In process of time, however, when the number of known substances became vastly increased, the confusion of language produced by the want of a more systematic kind of nomenclature became quite intolerable, and the evil was still farther increased by the frequent use of numerous synonyms to designate the same substance.

In the year 1787 Lavoisier and his colleagues published the plan of the remarkable system of nomenclature, which, with some important extensions since rendered necessary, has up to the present time to a great extent satisfied the wants of the science. It is in organic chemistry that the deficiencies of this plan are chiefly felt, and that something like a return to the old method has been rendered inevitable. Organic chemistry is an entirely new science which has sprung up since the death of these eminent men, and has to deal with bodies of a constitution or *type* differing completely from that of the inorganic acids, bases, and salts, which formed the subjects of the chemical studies of that period. The rapid progress of discovery by which new compounds, and new classes of compounds, often of the most unexpected nature, are continually brought to light, sufficiently proves that the time to attempt the construction of a permanent systematic plan of naming organic bodies has not yet arrived.

The principle of the nomenclature in use may be thus explained:—Elementary substances still receive arbitrary names, generally, but not always, referring to some marked peculiarity of the body; an uniformity in the termination of the word has generally been observed, as in the case of new metals whose names are made to end in *ium*.

Compounds formed by the union of non-metallic elements with metals, or with other non-metallic elements, are collected into groups having a kind of generic name derived from the non-metallic element, or that most opposed in characters to a metal, and made to terminate in *ide*.* Thus we have oxides, chlorides, iodides, bromides, &c., of hydrogen and of the several metals; oxides of chlorine; chlorides of iodine and sulphur; sulphides and phosphides of hydrogen and the metals.

The nomenclature of oxides has been already described (p. 110). They are divided into three classes, namely, alkaline or basic oxides, neutral oxides, and oxides possessing acid characters. In practice the term oxide is usually restricted to bodies belonging to the first two groups, those of the third being simply called acids. Generally speaking these acids are derived from the non-metallic elements, which yield no basic oxides: many of the metals, however, yield acids of a more or less energetic description.

The same element in combining with oxygen in more than one proportion may yield more than one acid: in this case it has been usual

* Formerly the termination *uret* was likewise frequently used.

to apply to the acid containing most oxygen the termination *ic*, and to the one containing the lesser quantity the termination *ous*. When more members of the same group came to be known, recourse was had to a prefix, *hypo* or *hyper*, (or *per*,) signifying deficiency or excess. Thus, the two earliest-known acids of sulphur were named respectively *sulphurous* and *sulphuric* acids; subsequently two more were discovered, the one containing less oxygen than sulphurous acid, the other intermediate in composition between sulphurous and sulphuric acids. These were called *hyposulphurous* and *hyposulphuric* acids. The names of the new acids of sulphur of still more recent discovery are not yet permanently fixed; Lavoisier's system, even in its extended form, fails to furnish names for such a lengthened series. Other examples of the nomenclature of acids with increasing proportions of oxygen are easily found; as *hypophosphorous*, *phosphorous*, and *phosphoric* acids; *hypochlorous*, *chlorous*, *hypochloric*, *chloric*, and *perchloric* acids; *nitrous*, *hyponitric*, and *nitric* acids, &c.

The nomenclature of salts is derived from that of the acid they contain; if the name of the acid terminate in *ic*, that of the salt is made to end in *ate*; if in *ous*, that of the saline compound ends in *ite*. Thus, sulphuric acid forms *sulphates* of the various bases; sulphurous acid, *sulphites*; hyposulphurous acid, *hyposulphites*; hyposulphuric acid, *hyposulphates*, &c. The rule is here very simple and obvious.

The want of uniformity in the application of the systematic nomenclature is chiefly felt in the class of oxides not possessing acid characters, and in that of some analogous compounds. The old rule was to apply the word *protoxide* to the oxide containing least oxygen, to call the next in order *binoxide*, the third *tritoxide* or *teroxide*; &c. But latterly this rule has been broken through, and the term *protoxide* given to that oxide of a series in which the basic characters are most strongly marked. Any compound containing a smaller proportion of oxygen than this is called a *suboxide*. An example is to be found in the two oxides of copper; that which was once called *binoxide* is now *protoxide*, being the more basic of the two, while the former *protoxide* is degraded into *suboxide*.

The Latin prefix *per*, or rarely *hyper*, is sometimes used to indicate the highest oxide of a series destitute of acidity, as *peroxide* of iron, chromium, manganese, lead, &c. Other Latin prefixes, as *sesqui*, *bi* or *bin*, and *quad*, applied to the names of binary compounds or salts have reference to the constitution of these latter expressed in chemical equivalents.* Thus, an oxide in which the proportion of oxygen and metal are in equivalents, as 1.5 to 1, or 3 to 2, is often called a *sesquioxide*; if in the proportion of 2 to 1, a *binoxide*, &c. The same terms are applied to salts: thus we have *neutral* sulphate of potassa, *sesquisulphate* of potassa, and *bisulphate* of potassa; the first containing 1 equivalent of acid to 1 of base, the second 1.5 of acid to 1 of

* See a few pages forward.

base, and the third 2 equivalents of acid to 1 equivalent of base. In like manner we have *neutral oxalate*, *binoxalate*, and *quadroxalate* of potassa, the latter having 4 eq. of acid to 1 eq. of base. Many other cases might be cited.

The student will soon discover that the rules of nomenclature are often loosely applied, as when a Latin numeral prefix is substituted for one of Greek origin. We speak of *tersulphide* instead of *tritrosulphide* of antimony, and *pentasulphide* of antimony. These and other small irregularities are not found in practice to cause serious confusion.

THE LAWS OF COMBINATION BY WEIGHT.

The great general laws which regulate all chemical combinations admit of being laid down in a manner at once simple and concise. They are four in number, and to the following effect:—

1. All chemical compounds are definite in their nature, the ratio of the elements being constant.
2. When any body is capable of uniting with a second in several proportions, these proportions bear a simple relation to each other.
3. If a body, A, unite with other bodies, B, C, D, the quantities of B, C, D, which unite with A, represent the *relations in which they unite among themselves*, in the event of union taking place.
4. The combining quantity of a compound is the sum of the combining quantities of its components.

(1.) *Constancy of Composition*.—That the same chemical compound invariably contains the same elements united in unvarying proportions, is a proposition almost axiomatic; it is involved in the very idea of identity itself. The converse, however, is very far from being true; the same elements combining in the same proportions do not of necessity generate the same substance.

Organic chemistry furnishes numerous instances of this very remarkable fact, in which the greatest diversity of properties is associated with identity of chemical composition. These cases seem to be nearly confined to organic chemistry; only a few well-established and undoubted examples being known in the inorganic or mineral division of the science.

(2.) *Multiple Proportions*.—Illustrations of this simple and beautiful law abound on every side: let the reader take for example the compounds of nitrogen and oxygen, five in number, containing the proportions of the two elements so described that the quantity of one of them shall remain constant:—

	Nitrogen.	Oxygen.
Protoxide	14	8
Binoxide	14	16
Nitrous acid	14	24
Hyponitric acid	14	32
Nitric acid	14	40

It will be seen at a glance, that while the nitrogen remains the same, the quantities of oxygen increase by *multiples* of 8, or the number representing the quantity of that substance in the first compound; thus, $8, 8 \times 2, 8 \times 3, 8 \times 4$, and 8×5 , give respectively the oxygen in the protoxide, the binoxide, nitrous acid, hyponitric acid, and lastly, nitric acid. Again, carbonic acid contains exactly twice as much oxygen in proportion to the other constituent as carbonic oxide; the binoxide of hydrogen is twice as rich in oxygen as water; the corresponding sulphides exhibit the same phenomena, while the metallic compounds offer one continued series of illustrations of the law, although the ratio is not always so simple as that of 1 to 2.

It often happens that one or more members of a series are yet deficient: the oxides of chlorine afford an example.

	Chlorine.	Oxygen.
Hypochlorous acid	35.5	8
Chlorous acid	35.5	24
Hypochloric acid	35.5	32
Chloric acid	35.5	40
Perchloric acid	35.5	56

Here the quantities of oxygen progress in the following order:— $8, 8 \times 3, 8 \times 4, 8 \times 5, 8 \times 7$; gaps are manifest between the first and second, and also between the fourth and fifth substances; these remain to be filled up by future researches. The existence of a simple relation among the numbers in the second column is however not the less evident. Even when difficulties seem to occur in applying this principle, they are only apparent, and vanish when closely examined. In the highly-complex sulphur series, given at p. 135, the numbers placed in each column are multiples of the lowest among them; and, by making the assumption, which is not at all extravagant, that certain of the last-named bodies are intermediate combinations, we may arrange the four direct compounds in such a manner that the sulphur shall remain a constant quantity.

	Sulphur.	Oxygen,
Hyposulphurous acid	32	16
Sulphurous acid	32	32
Hyposulphuric acid	32	40
Sulphuric acid	32	48

Compound bodies of all kinds are also subject to the law of mul-

tiples when they unite among themselves, or with elementary substances. There are two sulphates of potassa and soda: the second contains twice as much acid in relation to the alkaline base as the first. There are three oxalates of potassa, namely, the simple oxalate, the binoxalate, and the quadroxalate; the second has equally twice as much acid as the first; and the third twice as much as the second. Many other cases might be cited, but the student, once in possession of the principle, will easily notice them as he proceeds.

(3.) *Law of Equivalents*.—It is highly important that the subject now to be discussed should be completely understood.

Let a substance be chosen whose range of affinity and powers of combination are very great, and whose compounds are susceptible of rigid and exact analysis; such a body is found in oxygen, which is known to unite with all the elementary substances, with the single exception of fluorine. Now, let a series of exact experiments be made to determine the proportions in which the different elements combine with one and the same constant quantity of oxygen, which, for reasons hereafter to be explained, may be assumed to be 8 parts by weight; and let these numbers be arranged in a column opposite the names of the substances. The result is a table or list like the following, but of course much more extensive when complete.

Oxygen	8
Hydrogen	1
Nitrogen	14
Carbon	6
Sulphur	16
Phosphorus	32
Chlorine	35.5
Iodine	127
Potassium	39
Iron	28
Copper	31.7
Lead	103.7
Silver	108
&c. &c.		

Now the law in question is to this effect:—If such numbers represent the proportions in which the different elements combine with the arbitrarily-fixed quantity of the starting-substance, the oxygen, they also represent the *proportions in which they unite among themselves*, or at any rate bear some exceedingly simple ratio to these proportions.

Thus, hydrogen and chlorine combine invariably in the proportions 1 and 35.5; hydrogen and sulphur, 1 to 16; chlorine and silver, 35.5 to 108; iodine and potassium, 127 parts of the former to 39 of the latter, &c. This rule is never departed from in any one instance.

The term *equivalent* is applied to these numbers for a reason which will now be perfectly intelligible; they represent quantities capable of exactly replacing each other in combination: 1 part of hydrogen goes as far in combining with or saturating a certain amount of oxygen as 28 parts of iron, 39 of potassium, or 108 of silver; for the same reasons, the numbers are said to represent *combining quantities*, or *proportionals*.

Nothing is more common than to speak of so many equivalents of this or that substance being united to one or more equivalents of a second; by this expression, quantities are meant just so many times greater than these relative numbers. Thus, sulphuric acid is said to contain 1 equivalent of sulphur and 3 equivalents of oxygen; that is, a quantity of the latter represented by three times the combining number of oxygen: phosphoric acid is made up of 1 equivalent of phosphorus and 5 of oxygen; the red oxide of iron contains, as will be seen hereafter, 3 equivalents of oxygen to every 2 equivalents of metal, &c. It is an expression which will henceforward be freely and constantly employed; it is hoped, therefore, that it will be understood.

The nature of the law will easily show that the choice of the body destined to serve for a point of departure is perfectly arbitrary, and regulated by considerations of convenience alone.

A body might be chosen which refuses to unite with a considerable number of the elements, and yet the equivalents of the latter would admit of being determined by indirect means, in virtue of the very peculiar law under discussion. Oxygen does not unite with fluorine, yet the equivalent of the latter can be found by observing the quantity which combines with the *equivalent* quantity of hydrogen or calcium, already known. We may rest assured that if an oxide of fluorine be ever discovered, its elements will be associated in the ratio of 8 to 19, or in numbers which are either multiples or submultiples of these.

The number assigned to the starting-substance is also equally arbitrary; if, in the table given, oxygen instead of 8 were made 10, or 100, or even a fractional number, it is quite obvious that although the other numbers would all be different, the *ratio*, or proportion among the whole, would remain unchanged, and the law would still be maintained in all its integrity.

There are in fact two such tables in use among chemists; one in which oxygen is made = 8, and a second in which it is made = 100; the former is generally used in this country, and the latter still to a certain extent on the Continent. The only reason for giving, as in the present volume, a preference to the first is, that the numbers are smaller and more easily remembered.

The number 8 has been chosen in this table to represent oxygen, from an opinion long held by the late Dr. Prout, and recently to appearance substantiated in some remarkable instances by very elaborate investigation, that the equivalents of all bodies are multiples of that of hydrogen; and consequently, by making the

latter unity, the numbers would be all integers. The question must be considered as altogether unsettled. A great obstacle to such a view is presented by the case of chlorine, which certainly seems to be a fractional number; and one single well-established exception will be fatal to the hypothesis.

As all experimental investigations are attended with a certain amount of error, the results contained in the following table must be looked upon merely as good approximations to the truth. For the same reason, small differences are often observed in the determination of the equivalents of the same bodies by different experimenters.

TABLE OF ELEMENTARY SUBSTANCES, WITH THEIR EQUIVALENTS.

	Oxy.=8.	Oxy.=100.		Oxy.=8.	Oxy.=100.
Aluminium	13.7	171.25	Nickel .	29.6	370
Antimony	129	1612.5	Niobium		
Arsenic .	75	937.5	Nitrogen	14	175
Barium .	68.5	856.25	Norium		
Beryllium	6.9	86.25	Osmium .	99.6	1245
Bismuth	213	2662.5	Oxygen .	8	100
Boron .	10.9	136.25	Palladium	53.3	666.25
Bromine	80	1000	Pelopium		
Cadmium	56	700	Phosphorus	31	387.5
Calcium .	20	250	Platinum	98.7	1233.75
Carbon .	6	75	Potassium	39	487.5
Cerium .	47 (?)	587.5	Rhodium	52.2	652.5
Chlorine .	35.5	443.75	Ruthenium	52.2	652.5
Chromium	26.7	333.75	Selenium	39.5	493.75
Cobalt .	29.5	368.75	Silicium .	21.3	266.25
Copper .	31.7	396.25	Silver .	108	1350
Didymium	50 (?)	625	Sodium .	23	287.5
Erbium			Strontium	43.8	547.5
Fluorine	19	237.5	Sulphur .	16	200
Gold .	197	2462.5	Tantalum	184	2300
Hydrogen	1	12.5	Tellurium	64	802.5
Iodine .	127	1587.5	Terbium		
Iridium .	99	1237.5	Thorium	59.6	745
Iron .	28	350	Tin .	58	725
Lanthanum	47 (?)	587.5	Titanium	25	312.5
Lead .	103.7	1296.25	Tungsten	92	1150
Lithium .	6.5	81.25	Uranium	60	750
Magnesium	12	150	Vanadium	68.6	857.5
Manganese	27.6	345	Yttrium		
Mereury .	100	1250	Zinc .	32.6	407.5
Molybdenum	46	575	Zirconium	33.6	420

(4.) *Combining Numbers of Compounds.*—The law states that the equivalent or combining number of a compound is always the sum of the equivalents of its components. This is also a great fundamental truth, which it is necessary to place in a clear and conspicuous light. It is a separate and independent law, established by direct experimental evidence, and not deducible from either of the preceding.

The method of investigation by which the equivalent of a simple body is determined, has been already explained; that employed in the case of a compound is in nowise different. The example of the acids and alkalis may be taken as the most explicit, and at the same time most important. An acid and a base, combined in certain definite proportions, *neutralize*, or mask each other's properties completely, and the result is a salt: these proportions are called the equivalents of the bodies, and they are very variable. Some acids have very high capacities of saturation, of others a much larger quantity must be employed to neutralize the same amount of base; the bases themselves present also similar phenomena. Thus, to saturate 47 parts of potassa, or 116 parts of oxide of silver, there are required

40 parts	sulphuric acid,
54 „	nitric acid,
75.5 „	chloric acid,
167 „	iodic acid,
51 „	acetic acid.

Numbers very different, but representing quantities which replace each other in combination. Now, if a quantity of some base, such as potassa, be taken, which is represented by the sum of the equivalents of potassium and oxygen, then the quantity of any acid requisite for its neutralization, as determined by direct experiment, will always be found equal to the sum of the equivalents of the different components of the acid itself.

39 = equivalent of potassium.

8 = „ oxygen.

—

47 = assumed equivalent of potassa.

47 parts of potassa are found to be exactly neutralized by 40 parts of real sulphuric acid, or by 54 parts of real nitric acid. These quantities are evidently made up by adding together the equivalents of their constituents:—

1 equivalent of sulphur = 16
3 „ oxygen = 24

—
1 „ sulphuric acid = 40

1 equivalent of nitrogen = 14
5 „ oxygen = 40

—
1 „ nitric acid = 54

And the same is true if any acid be taken, and the quantities of different bases required for its neutralization determined; the combining number of the compound will always be found to be the sum of the combining numbers of its components, however complex the substance may be. Even among such bodies as the vegetable-alkalis of organic chemistry, the same universal rule holds good. When salts combine, which is a thing of very common occurrence, as will hereafter be seen, it is always in the ratio of the equivalent numbers. Apart from hypothetical considerations, no *a priori* reason can be shown why such should be the case: it is, as before remarked, an independent law, established like the rest by experiment.

A curious observation was very early made to this effect:—If two neutral salts which decompose each other when mixed, be brought in contact, the new compounds resulting from their mutual decomposition will also be neutral. For example, when solution of nitrate of baryta and sulphate of potassa are mingled, they both suffer decomposition, sulphate of baryta and nitrate of potassa being simultaneously formed, both of which are perfectly neutral. The reason of this will be at once evident; interchange of elements can only take place by the displacement of equivalent quantities of matter on either side. For every 54 parts of nitric acid set free by the decomposition of the barytic salt, 47 parts of potassa are abandoned by the 40 parts of sulphuric acid with which they were previously in combination, now transferred to the baryta. But 54 and 47 are the representatives of combining quantities; hence the new compound must be neutral.

COMBINATION BY VOLUME.

Many years ago M. Gay-Lussac made the very important and interesting discovery that when gases combine chemically union invariably takes place either between equal volumes, or between volumes which bear a simple relation to each other. This is not only true of elementary gases, but of compound bodies of this description, as it is invariably observed that the contraction of bulk which so frequently follows combination itself also bears a simple relation to the volumes of the combining gases. The consequence of this is that compound gases and the vapours of complex volatile liquids (which are truly gases to all intents and purposes) follow the same law as elementary bodies when they unite with these latter or combine among themselves.

The ultimate reason of the law in question is to be found in the very remarkable relation established by the hand of Nature between

the specific gravity of a body in the gaseous state and its chemical equivalent;—a relation of such a kind that quantities by weight of the various gases expressed by their equivalents, or in other words quantities by weight which combine, occupy under similar circumstances of pressure and temperature either equal volumes or volumes bearing a simple proportion to each other. In the example cited below, equivalent weights of hydrogen, chlorine, and iodine-vapour occupy equal volumes, while the equivalent of oxygen occupies exactly half that measure.

	Cubic inches.
8.0 grains of oxygen occupy at 60° (15°·5C) and 30 in. barom.	23.3
1.0 grain of hydrogen	46.7
35.5 grains of chlorine	46.2
127.0 grains of iodine-vapour (would measure)	46.7

If both the specific gravity and the chemical equivalent of a gas be known, its equivalent or combining volume can be easily determined, since it will be represented by the number of times the weight of an unit of volume (the specific gravity) is contained in the weight of one chemical equivalent of the substance. In other words, the equivalent volume is found by dividing the chemical equivalent by the specific gravity. The following table exhibits the relations of specific gravity, equivalent weight, and equivalent volume of the principal elementary substances.

	Sp. gravity.	Equiv. weight.	Equiv. volume.
Hydrogen	0.0693 . .	1.0 . .	14.43 or 1
Nitrogen	0.972 . .	14.0 . .	14.37 „ 1
Chlorine	2.470 . .	35.5 . .	14.33 „ 1
Bromine-vapour	5.395 . .	80.0 . .	14.82 „ 1
Iodine-vapour	8.716 . .	127.0 . .	14.57 „ 1
Carbon-vapour*	0.418 . .	6.0 . .	14.34 „ 1
Mercury-vapour	7.000 . .	100.0 . .	14.29 „ 1
Oxygen	1.106 . .	8.0 . .	7.23 „ $\frac{1}{2}$
Phosphorus-vapour	4.350 . .	32.0 . .	7.35 „ $\frac{1}{2}$
Arsenic-vapour	10.420 . .	75.0 . .	7.19 „ $\frac{1}{2}$
Sulphur-vapour	6.654 . .	16.0 . .	2.40 „ $\frac{1}{6}$

Thus it appears that hydrogen, nitrogen, chlorine, bromine, iodine, carbon, and mercury, in the gaseous state, have the same equivalent volume; oxygen, phosphorus, and arsenic, one-half of this; and sulphur one-sixth. The slight discrepancies in the numbers in the third column result chiefly from errors in the determination of the specific gravities.

Compound bodies exhibit exactly similar results:—

* See farther on.

	Sp. gravity.	Equiv. weight.	Equiv. volume.
Water-vapour . . .	0·625	9·0	14·40 or 1
Protoxide of nitrogen . .	1·525	22·0	14·43 „ 1
Sulphuretted hydrogen . .	1·171	17·0	14·51 „ 1
Sulphurous acid . . .	2·210	32·0	14·52 „ 1
Carbonic oxide . . .	0·973	14·0	14·39 „ 1
Carbonic acid . . .	1·524	22·3	14·43 „ 1
Light carbouetted hydrogen	0·559	8·0	14·31 „ 1
Olefiant gas . . .	0·981	14·0	14·27 „ 1
Binoxide of nitrogen . .	1·039	30·0	28·87 „ 2
Hydrochloric acid . . .	1·269	36·5	28·70 „ 2
Phosphoretted hydrogen	1·240	35·0	28·22 „ 2
Ammonia . . .	0·589	17·0	28·86 „ 2
Ether-vapour . . .	2·586	37·0	14·31 „ 1
Acetone-vapour . . .	2·022	29·0	14·34 „ 1
Benzol-vapour . . .	2·738	78·0	28·49 „ 2
Alcohol-vapour . . .	1·613	46·0	28·52 „ 2

In the preceding tables the ordinary standard of specific gravity for gases, atmospheric air, has been taken. It is, however, a matter of perfect indifference what substance be chosen for this purpose; the numbers representing the combining volumes will change with the divisor, but the proportions they bear to each other will remain unaltered. And the same remark applies to the equivalent weights; either of the scales in use may be taken, provided that it be adhered to throughout.

The law of volumes often serves in practice to check and corroborate the results of experimental investigation, and is often of great service in this respect.

There is an expression sometimes made use of in chemical writings which it is necessary to explain, namely, the meaning of the words *hypothetical density of vapour*, applied to a substance which has never been volatilized, such as carbon, whose real specific gravity in that state must of course be unknown. It is easy to understand the origin of this term. Carbonic acid contains a volume of oxygen equal to its own; consequently, if the specific gravity of the latter be subtracted from that of the former gas, the residue will express the proportion borne by the weight of the carbon, certainly then in a vaporous state, to that of the two gases.

The specific gravity of carbonic acid is . . .	1·5240
That of oxygen is	1·1057
	<hr/>
	0·4183

On the supposition that carbonic acid contains equal volumes of oxygen and this vapour of carbon, condensed to one-half, the latter

will have the specific gravity represented by 0.4183 and the combining volume given in the table. But this is merely a supposition, a guess; no proof can be given that carbonic acid gas is so constituted. All that can be safely said is contained in the prediction, that, should the specific gravity of the vapour of carbon ever be determined, it will be found to coincide with this number, or to bear some simple and obvious relation to it.

For many years past attempts have been made to extend to solids and liquids the results of Gay-Lussac's discovery of the law of gaseous combination by volume, the combining or equivalent volumes of the bodies in question being determined by the method pursued in the case of gases, namely, by dividing the chemical equivalent by the specific gravity. The numbers obtained in this manner representing the combining volumes of the various solid and liquid elementary substances, present far more cases of discrepancy than of agreement. The latter are, however, sufficiently numerous to excite great interest in the investigation. Some of the results pointed out are exceedingly curious as far as they go, but are not as yet sufficient to justify any general conclusion. The inquiry is beset with many great difficulties, chiefly arising from the unequal expansion of solids and liquids by heat, and the great differences of physical state, and consequently of specific gravity, often presented by the former.

Such is a brief account of the great laws by which chemical combinations, of every kind, are governed and regulated; and it cannot be too often repeated, that the discovery of these beautiful laws has been the result of pure experimental inquiry. They have been established on this firm and stable foundation by the joint labours of very many illustrious men; they are the expression of fact, and are totally independent of all hypotheses or theories whatsoever.

CHEMICAL NOTATION; SYMBOLS.

For convenience in communicating ideas respecting the composition and supposed constitution of chemical compounds, and explaining in a clear and simple manner the results of changes they may happen to undergo, recourse is had to a kind of written symbolical language, the principle of which must now be explained. To represent compounds by symbols is no novelty, as the works of the Alchemists will show, but these have been mere arbitrary marks or characters invented for the sake of brevity, or sometimes perhaps for that of obscurity.

The plan about to be described is due to Berzelius: it has been adopted, with slight modifications, wherever chemistry is pursued.

Every elementary substance is designated by the first letter of its Latin name, in capital, or by the first letter conjoined with a second small one, the most characteristic in the word, as the names of many bodies begin alike. The single letter is usually confined to the earliest discovered, or most important elements. Farther, by a most

ingenious idea, the symbol is made to represent not the substance in the abstract, but *one equivalent of that substance*.

Table of Symbols of the Elementary Bodies.

Aluminium Al	Nickel Ni
Antimony (Stibium). . . . Sb	Niobium Nb
Arsenic As	Nitrogen. N
Barium Ba	Norium No
Beryllium Be	Osmium Os
Bismuth Bi	Oxygen O
Boron Bo	Palladium Pd
Bromine Br	Pelopium Pe
Cadmium Cd	Phosphorus P
Calcium Ca	Platinum Pt
Carbon C	Potassium (Kalium) K
Cerium Ce	Rhodium R
Chlorine Cl	Ruthenium Ru
Chromium Cr	Selenium Se
Cobalt Co	Silicium Si
Copper (Cuprum) Cu	Silver (Argentum) Ag
Didymium Dy	Sodium (Natrium) Na
Erbium Er	Strontium Sr
Fluorine F	Sulphur S
Gold (Aurum). Au	Tantalum Ta
Hydrogen H	Tellurium Te
Iodine I	Terbium Tb
Iridium Ir	Thorium Th
Iron (Ferrum). Fe	Tin (Stannum) Sn
Lanthanum Ln	Titanium Ti
Lead (Plumbum) Pb	Tungsten (Wolframium) . . . W
Lithium L	Vanadium V
Magnesium Mg	Uranium U
Manganese Mn	Yttrium Y
Mereury (Hydrargyrum) . . Hg	Zinc Zn
Molybdenum Mo	Zirconium Zr

Combination between bodies in the ratio of the equivalents is expressed by mere juxtaposition of the symbols, or sometimes by interposing the sign of addition. For example :—

Water HO, or H+O
 Hydrochloric acid HCl, or H+Cl
 Protoxide of iron FeO, or Fe+O

When more than one equivalent is intended, a suitable number is added, sometimes being placed before the symbol, like a coefficient in

algebra, sometimes appended after the manner of an exponent, but more commonly placed a little below on the right.

Binoxide of hydrogen $H + 2O$, or HO^2 , or HO_2

Sulphuric acid $S + 3O$, or SO^3 , or SO_3

Hyposulphuric acid $2S + 5O$, or S^2O^5 , or S_2O_5

Combination between bodies themselves compound is indicated by the sign of addition, or by a comma. When both are used in the same formula, the latter may be very conveniently applied, as Professor Graham has suggested, to indicate the closest and most intimate union. A number standing before symbols, enclosed within a bracket, signifies that the whole of the latter are to be multiplied by that number. Occasionally the bracket is omitted, when the number affects all the symbols between itself and the next sign. A few examples will serve to illustrate these several points.

Sulphate of soda $NaO + SO_3$, or NaO, SO_3

Nitrate of potassa $KO + NO_3$, or KO, NO_3

The base being always placed first.

Double sulphate of copper and potassa $CuO, SO_3 + KO, SO_3$

The same in a crystallized state $CuO, SO_3 + KO, SO_3 + 6HO$

Common crystallized alum, or double sulphate of alumina and potassa, is thus written :—



In expressing organic compounds, where three or more elements exist, the same plan is used.

Sugar . . . $C_{12}H_{11}O_{11}$

Alcohol . . . $C_4H_6O_2$

Acetic Acid . . . $HO, C_4H_3O_3$

Morphine . . . $C_{34}H_{19}NO_6$

Acetate of morphine $C_{34}H_{19}NO_6, C_4H_3O_3$

Acetate of soda . . . $NaO, C_4H_3O_3$

By such a system, the eye is enabled to embrace the whole at a glance, and gain a distinct idea of the composition of the body, and its relations to others similarly described.

Some authors are in the habit of making use of contractions, which, however, are by no means generally adopted. Thus, two equivalents of a substance are indicated by the symbol with a short line drawn through or below it; an equivalent of oxygen is signified by a dot,

and one of sulphur by a comma. These alterations are sometimes convenient for abbreviating a long formula, but easily liable to mistakes. Thus,

Sesquioxide of iron $\underline{\text{FeO}^3}$, or FeO^3 , or $\underline{\text{Fe}}$, instead of Fe_2O_3

Bisulphide of Carbon $\underline{\text{C}}''$, instead of CS_2

Crystallized alum as before $\underline{\text{Al}}\text{S}_3$, $\text{K}\text{S} + 24\text{H}$.

THE ATOMIC THEORY.

That no attempt should have been made to explain the reason of the very remarkable manner in which combination occurs in the production of chemical compounds, and to point out the nature of the relations between the different modifications of matter which fix and determine these peculiar and definite changes, would have been unlikely, and in contradiction to the speculative tendency of the human mind. Such an attempt, and a very ingenious and successful one it is, has been made, namely, the atomic hypothesis of Dr. Dalton.

From very ancient times, the question of the constitution of matter with respect to divisibility has been debated, some adopting the opinion that this divisibility is infinite, and others, that when the particles become reduced to a certain degree of tenuity, far indeed beyond any state that can be reached by mechanical means, they cease to be farther diminished in magnitude; they become, in short, *atoms*.* Now, however the imagination may succeed in figuring to itself the condition of matter on either view, it is hardly necessary to mention that we have absolutely no means at our disposal for deciding such a question, which remains at the present day in the same state as when it first engaged the attention of the Greek philosophers, or perhaps that of the sages of Egypt and Hindostan long before them.

Dr. Dalton's hypothesis sets out by assuming the existence of such atoms or indivisible particles, and states, that compounds are formed by the union of atoms of different bodies one to one, one to two, &c. The compound atom joins itself in the same manner to a compound atom of another kind, and a combination of the second order results. Let it be granted, farther, that the relative weights of the atoms are in the proportions of the equivalent numbers, and the hypothesis becomes capable of rendering consistent and satisfactory reasons for all the consequences of those beautiful laws of combination lately discussed.


Chemical compounds must always be definite; they must always

* *ἄτομος*, that which cannot be cut.

contain the same number of atoms, of the same kind, arranged in a similar manner. The same kind and number of atoms need not, however, of necessity produce the same substance, for they may be differently arranged; and much depends upon this circumstance.

Again, the law of multiple proportions is perfectly well explained; an atom of nitrogen unites with one of oxygen to form laughing gas; with two, to form binoxide of nitrogen; with three, to produce nitrous acid; with four, hyponitric acid; and with five, nitric acid,—perhaps something after the manner below represented, in which the circle with a cross represents the atom of nitrogen, and the plain circle that of oxygen.

Fig. 115.



Two atoms of one substance may unite themselves with three or even with seven of another, as in the case of one of the acids of manganese; but such combinations are rare.

The mode in which bodies replace, or may be substituted for, each other, is also perfectly intelligible, as a little consideration will show.

Finally, the law which fixes the equivalent of a compound at the sum of the equivalents of the components, receives an equally satisfactory explanation.

The difficulties in the general application of the atomic hypothesis are chiefly felt in attempting to establish some wide and universal relation between combining number and combining volume, among gases and vapours, and in the case of the highly-complex products of organic chemistry. These obstacles have grown up in comparatively recent times. On the other hand, the remarkable observations of the specific capacities for heat of equivalent quantities of the solid elementary substances, might be urged in favour of this or some similar molecular hypothesis. But even here serious discrepancies exist: we may not take liberties with equivalent numbers determined by exact chemical research, and, in addition, a simple relation is generally found to be wanting between the capacity for heat of the compound and that of its elements.

The theory in question has rendered great service to chemical science; it has excited a vast amount of inquiry and investigation, which have contributed very largely to define and fix the laws of com-

bination themselves. In more recent days it is not impossible, that without some such hypothetical guide the exquisitely-beautiful relations which Mitscherlich and others have shown to exist between crystalline form and chemical composition, might never have been brought to light, or, at any rate, their discovery might have been greatly delayed. At the same time, it is indispensable to draw the broadest possible line of distinction between this, which is at the best but a graceful, ingenious, and, in its place, useful hypothesis, and those great general laws of chemical action which are the pure and unmixed result of inductive research.*

Chemical Affinity.

The term chemical affinity, or chemical attraction, has been invented to describe that particular power or force, in virtue of which, union, often of a very intimate and permanent nature, takes place between two or more bodies, in such a way as to give rise to a *new* substance, having, for the most part, properties completely in discordance with those of its components.

The attraction thus exerted between different kinds of matter is to be distinguished from other modifications of attractive force which are exerted indiscriminately between all descriptions of substances, sometimes at enormous distances, and sometimes at intervals quite inappreciable. Examples of the latter are to be seen in cases of what is called *cohesion*, when the particles of solid bodies are immovably bound together into a mass. Then there are other effects of, if possible, a still more obscure kind; such as the various actions of surface, the adhesion of certain liquids to glass, the repulsion of others, the ascent of water in narrow tubes, and a multitude of curious phenomena which are described in works on Natural Philosophy, under the head of *molecular actions*. From all these true chemical attraction may be at once distinguished by the deep and complete change of characters which follows its exertion: we might define affinity to be a force by which new substances are generated.

It seems to be a general law that bodies most opposed to each other in chemical properties evince the greatest tendency to enter into combination, and, conversely, bodies between which strong analogies and resemblances can be traced, manifest a much smaller amount of mutual attraction. For example, hydrogen and the metals tend very strongly indeed to combine with oxygen, chlorine, and iodine. The attraction between the different members of these two groups is incomparably more feeble. Sulphur and phosphorus stand, as it were, mid-way: they combine with substances of one and the other class, their properties separating them sufficiently from both. Acids are drawn towards

* The expression *atomic weight* is very often substituted for that of *equivalent weight*, and is, in fact, in almost every case to be understood as such: it is, perhaps, better avoided.

alkalis, and alkalis towards acids, while union among themselves rarely, if ever, takes place.

Nevertheless, chemical combination graduates so imperceptibly into mere mechanical mixture, that it is often impossible to mark the limit. Solution is the result of a weak kind of affinity existing between the substance dissolved and the solvent: an affinity so feeble as completely to lose one of its most prominent features when in a more exalted condition, namely, power of causing elevation of temperature, for in the act of mere solution the temperature falls, the heat of combination being lost and overpowered by the effects of change of state.

The force of chemical attraction thus varies greatly with the nature of the substances between which it is exerted; it is influenced, moreover, to a very large extent by external or adventitious circumstances. An idea formerly prevailed that the relations of affinity were fixed and constant between the same substances, and great pains were taken in the preparation of tables exhibiting what was called the precedence of affinities. The order pointed out in these lists is now acknowledged to represent the order of precedence *for the circumstances* under which the experiments were made, but nothing more: so soon as these circumstances become changed, the order is disturbed. The ultimate effect, indeed, is not the result of the exercise of one single force, but rather the joint effect of a number, so complicated and so variable in intensity, that it is but seldom possible to predict the consequences of any yet untried experiment. The following may serve as examples of the tables alluded to; the first illustrates the relative affinities of a number of bases for sulphuric acid, each decomposing the combination of the acid with the base below it: thus magnesia decomposes sulphate of ammonia; lime displaces the acid from sulphate of magnesia, &c. The salts are supposed to be dissolved in water. The second table exhibits the order of affinity for oxygen of several metals, mercury reducing a solution of silver, copper one of mercury, &c.

Sulphuric Acid.		Oxygen.	
Baryta,	Lime,	Zinc,	Mercury,
Strontia,	Magnesia,	Lead,	Silver.
Potassa,	Ammonia.	Copper,	
Soda,			

It will be proper to examine shortly some of these extraneous causes to which allusion has been made, which modify to so great an extent the direct and original effects of the specific attractive force.

Alteration of temperature may be reckoned among these. When metallic mercury is heated nearly to its boiling point, and in that state exposed for a lengthened period to the air, it absorbs oxygen, and becomes converted into a dark-red crystalline powder. This very same substance, when raised to a still higher temperature, spon-

taneously separates into metallic mercury and oxygen gas. It may be said, and probably with truth, that the latter change is greatly aided by the tendency of the metal to assume the vaporous state; but precisely the same fact is observed with another metal, palladium, which is not volatile at all, but which oxidizes superficially at a red-heat, and again becomes reduced when the temperature rises to whiteness.

Insolubility and the power of vaporization are perhaps, beyond all other disturbing causes, the most potent; they interfere in almost every reaction which takes place, and very frequently turn the scale when the opposed forces do not greatly differ in energy. It is easy to give examples. When a solution of lime in hydrochloric acid is mixed with a solution of carbonate of ammonia, double interchange ensues, carbonate of lime and hydrochlorate of ammonia being generated. Here the action can be shown to be in a great measure determined by the insolubility of the carbonate of lime. Again, dry carbonate of lime, powdered and mixed with hydrochlorate of ammonia, and the whole, heated in a retort, gives a sublimate of carbonate of ammonia, while chloride of calcium remains behind. In this instance, it is no doubt the great volatility of the new ammoniacal salt which chiefly determines the kind of decomposition.

When iron-filings are heated to redness in a porcelain tube, and vapour of water passed over them, the water undergoes decomposition with the utmost facility, hydrogen is rapidly disengaged, and the iron converted into oxide. On the other hand, oxide of iron heated in a tube through which a stream of dry hydrogen is passed, suffers almost instantaneous reduction to the metallic state, while the vapour of water, carried forward by the current of gas, escapes as a jet of steam from the extremity of the tube. In these experiments the affinities between the iron and oxygen and the hydrogen and oxygen are so nearly balanced, that the difference of *atmosphere* is sufficient to settle the point. An atmosphere of steam offers little resistance to the escape of hydrogen; one of hydrogen bears the same relation to steam; and this apparently trifling difference of circumstances is quite enough for the purpose.

The decomposition of vapour of water by white-hot platinum, pointed out by Mr. Grove, will probably be referred in great part to this influence of atmosphere, the steam offering great facilities for the assumption of the elastic condition by the oxygen and hydrogen. The decomposition ceases as soon as these gases amount to about $\frac{1}{3000}$ of the bulk of the mixture, and can only be renewed by their withdrawal. The attraction of oxygen for hydrogen is probably much weakened by the very high temperature. The recombination of the gases by the heated metal is rendered impossible by their state of dilution.

What is called the nascent state is one very favourable to chemical combination. Thus, carbon and nitrogen refuse to combine with gaseous hydrogen; yet when these substances are simultaneously libe-

rated from some previous combination, they unite with great ease, as when organic matters are destroyed by heat, or by spontaneous putrefactive change. There is a strange and extraordinary, and at the same time very extensive class of actions, grouped together under the general title of cases of *disposing* affinity. The preparation of hydrogen from zinc and sulphuric acid is one of the most familiar. A piece of polished zinc or iron, put into pure water, manifests no power of decomposing the latter to the smallest extent; it remains perfectly bright for any length of time. On the addition, however, of a little sulphuric acid, hydrogen is at once freely disengaged, and the metal becomes oxidized and dissolved. Now, the only intelligible function of the acid is to dissolve off the oxide as fast as it is produced; but why is the oxide produced when acid is present, and not otherwise? The question is very difficult to answer.

Great numbers of examples of this curious indirect action might be adduced. Metallic silver does not oxidize at any temperature; nay more, its oxide is easily decomposed by simple heat; yet if the finely-divided metal be mixed with siliceous matter and alkali, and ignited, the whole fuses to a yellow transparent glass or silicate of silver. Platinum is attacked by fused hydrate of potassa; hydrogen is probably disengaged while the metal is oxidized: this is an effect which never happens to silver under the same circumstances, although silver is a much more oxidable substance than platinum. The fact is, that potassa forms with the oxide of the last-named metal a kind of saline combination, in which the oxide of platinum acts as an acid; and hence its formation under the *disposing* influence of the powerful base.

In the remarkable decompositions suffered by various organic bodies when heated in contact with caustic alkali or lime, we have other examples of the same fact. Products are generated which are never formed in the absence of the base; the reaction is invariably less complicated, and its results fewer in number and more definite, than in the event of simple destruction by a graduated heat. The preparation of light carbonetted hydrogen by the new artificial process, already described, is an excellent example.

There is yet a still more obscure class of phenomena, in which effects are brought about by the mere *presence* of a substance, which itself undergoes no change whatever: the experiment mentioned in the article on oxygen, in which that gas is obtained, with the greatest facility, by heating a mixture of chlorate of potassa and binoxide of manganese, is an excellent case in point. The salt is decomposed at a very far lower temperature than would otherwise be required. The oxide of manganese, however, is not in the slightest degree altered; it is found, after the experiment, in the same state as before. The name *katalysis* is sometimes given to those peculiar actions of contact: the expression is not significant, and may be for that reason the more admissible, as it suggests no explanation.

It is proper to remark that the contact decompositions alluded to are sometimes mixed up with other effects, which are, in reality, much more intelligible, as the action of finely-divided platinum upon certain gaseous mixtures, in which the solid really seems to have the power of condensing the gas upon its greatly-extended surface, and thereby inducing combination by bringing the particles within the sphere of their mutual attractions.

ELECTRO-CHEMICAL DECOMPOSITION ; CHEMISTRY OF THE VOLTAIC PILE.

WHEN a voltaic current of considerable power is made to traverse various compound liquids, a separation of the elements of these liquids ensues : provided that the liquid be capable of conducting a current of a certain degree of energy, its decomposition almost always follows.

The elements are disengaged solely at the limiting surfaces of the liquid ; where, according to the common mode of speech, the current enters and leaves the latter, all the intermediate portions appearing perfectly quiescent. In addition, the elements are not separated indifferently and at random at these two surfaces ; but, on the contrary, make their appearance with perfect uniformity and constancy at one or the other, according to their chemical character—namely, oxygen, chlorine, iodine, acids, &c., at the surface connected with the *copper* or *positive* end of the battery ; hydrogen, the metals, &c , at the surface in connection with the *zinc* or *negative* extremity of the arrangement.

The terminations of the battery itself, usually, but by no means necessarily, of metal, are designated poles or *electrodes*,* as by their intervention the liquid to be experimented on is made a part of the circuit. The process of decomposition by the current is called *electrolysis*,† and the liquids, which, when thus treated, yield up their elements, are denominated *electrolytes*.

When a pair of platinum plates are plunged into a glass of water to which a few drops of oil of vitriol have been added, and the plates connected by wires with the extremities of an active battery, oxygen is disengaged at the positive electrode, and hydrogen at the negative, in the proportion of one measure of the former to two of the latter nearly. This experiment has before been described.‡

A solution of hydrochloric acid mixed with a little Saxon blue (indigo), and treated in the same manner, yields hydrogen on the negative side and chlorine on the positive, the indigo there becoming bleached.

Iodide of potassium dissolved in water is decomposed in a similar manner, and with still greater ease : the free iodine at the positive side can be recognized by its brown colour, or by the addition of a little gelatinous starch.

* From *ἤλεκτρον*, and *ὁδός*, a way.

† From *ἤλεκτρον*, and *λύω*, I loose.

‡ Page 118.

Every liquid is not an electrolyte ; many refuse to conduct, and no decomposition can then occur ; alcohol, ether, numerous essential oils, and other products of organic chemistry, besides a few saline inorganic compounds act in this manner, and completely arrest the current of a very powerful battery. It is a very curious fact, and well deserves attention, that very nearly, if not all the substances acknowledged to be susceptible of electrolytic decomposition belong to one class ; they are all binary compounds, containing single equivalents of their components, the latter being strongly opposed to each other in their chemical relations, and held together by very powerful affinities.

The amount of power required to effect decomposition varies greatly ; solution of iodide of potassium, melted chloride of lead, solution of hydrochloric acid, water mixed with a little oil of vitriol, and pure water, demand in this respect very different degrees of electrical force, the resistance to decomposition increasing from the first-mentioned substance to the last.

One of the most important and indispensable conditions of electrolysis is fluidity : bodies which when reduced to the liquid condition freely conduct and as freely suffer decomposition, become absolute insulators to the electricity of the battery when they become solid. Chloride of lead offers a good illustration of this fact : when fused in a little porcelain crucible it gives up its elements with the utmost ease, and a galvanometer, interposed somewhere in the circuit, is strongly affected. But when the source of heat is withdrawn, and the salt suffered to solidify, all signs of decomposition cease, and at the same moment the magnetic needle reassumes its natural position. In the same manner the thinnest film of ice completely arrests the current of a powerful voltaic apparatus ; the instant the ice is liquefied at any one point, so that water-communication may be restored between the electrodes, the current again passes, and decomposition occurs. Fusion by heat, and solution in aqueous liquids, answer the purpose equally well.

Generally speaking, compound fluids cannot conduct the electric current without being decomposed ; but still there are a few exceptions to this statement, which perhaps are more apparent than real. Thus Hittorf has shown, that fluid sulphide of silver, which was formerly considered to be one of the exceptions, cannot be considered to be so.

When a fluid, which can be decomposed, and a galvanometer are included in the circuit of an electric current, if the needle of the galvanometer be deflected, it may be always assumed as certain that a portion of fluid, bearing a proportion to the strength of the current, is decomposed, notwithstanding it may be impossible in many cases, without special contrivances, to detect the products of the decomposition, on account of their minuteness.


The metallic terminations of the battery, the poles or electrodes, have, in themselves, nothing in the shape of attractive or repulsive power for the elements so often separated at their surfaces. Finely-

divided metal suspended in water, or chlorine held in solution in that liquid, shows not the least symptom of a tendency to accumulate around them; a single element is altogether unaffected, directly at least; severance from previous combination is required, in order that this appearance should be exhibited.

It is necessary to examine the process of electrolysis a little more closely. When a portion of water, for example, is subjected to decomposition in a glass vessel with parallel sides, oxygen is disengaged at the positive electrode, and hydrogen at the negative: the gases are perfectly pure and unmixed. If, while the decomposition is rapidly proceeding, the intervening water be examined by a beam of light, or by other means, not the slightest disturbance or movement of any kind will be perceived; nothing like currents in the liquid or bodily transfer of gas from one part to another can be detected; and yet two portions of water, separated perhaps by an interval of four or five inches, may be respectively evolving pure oxygen and pure hydrogen.

There is, it would seem, but one mode of explaining this and all similar cases of regular electrolytic decomposition; this is by assuming that *all* the particles of water between the electrodes, and by which the current is conveyed, simultaneously suffer decomposition, the hydrogen travelling in one direction, and the oxygen in the other. The neighbouring elements, thus brought into close proximity, unite and reproduce water, again destined to be decomposed by a repetition of the same change. In this manner each particle of hydrogen may be made to travel in one direction, by becoming successively united to each particle of oxygen between itself and the negative electrode: when it reaches the latter, finding no disengaged particle of oxygen for its reception, it is rejected as it were from the series, and thrown off in a separate state. The same thing happens to each particle of oxygen, which at the same time passes continually in the opposite direction, by combining successively with each particle of hydrogen

Fig. 116.




Water in usual state.

that moment separated, with which it meets, until at length it arrives at the positive plate or wire, and is disengaged. A succession of particles of hydrogen are thus continually thrown off from the decomposing mass at one extremity, and a corresponding succession of particles of oxygen at the other. The power of the current is exerted with equal energy in every part of the liquid conductor, although its *effects* only become manifest at the very extremities. The action is one of a

purely molecular or internal nature, and the metallic terminations of the battery merely serve the purpose of completing the connection between the latter and the liquid to be decomposed. The figures 116 and 117 are intended to assist the imagination of the reader, who must at the same time avoid regarding them in any other light than that of a somewhat figurative mode of representing the curious phenomena described. The circles are intended to indicate the elements, and are distinguished by their respective symbols.

Fig. 117.



Water undergoing electrolysis.

A distinction is to be carefully drawn between true and regular electrolysis, and what is called secondary decomposition, brought about by the reaction of the bodies so eliminated upon the surrounding fluid, or upon the substance of the electrodes : hence the advantage of platinum for the latter purpose when electrolytic actions are to be studied in their greatest simplicity, that metal being scarcely attacked by any ordinary agents. When, for example, a solution of nitrate or acetate of lead is decomposed by the current between platinum plates, metallic lead is deposited at the negative side, and a brown powder, binoxide of lead, at the positive : the latter substance is the result of a secondary action ; it proceeds, in fact, from the nascent oxygen at the moment of its liberation reacting upon the protoxide of lead present in the salt, and converting it into binoxide, which is insoluble in the dilute acid. There is every reason to believe that when sulphuric and nitric acids seem to be decomposed by the current, the effect is really due to the water they contain becoming decomposed, and reacting by its hydrogen upon the acid, for these bodies do not belong to the class of electrolytes, as already specified, and would probably refuse to conduct could they be examined in an anhydrous condition.

If a number of different electrolytes, such as acidulated water, sulphate of copper, iodide of potassium, fused chloride of lead, &c., be arranged in a series, and the same current be made to traverse the whole, all will suffer decomposition at the same time, but by no means to the same amount. If arrangements be made by which the quantities of the eliminated elements can be accurately ascertained, it will be found, when the decomposition has proceeded to some extent, that these latter will have been disengaged exactly in the *ratio of the chemical equivalents*. The same current which decomposes 9 parts of water, will separate into their elements 166 parts of iodide of potas-

sium, 139.2 parts of chloride of lead, &c. Hence the very important conclusion :—The action of the current is perfectly definite in its nature, producing a fixed and constant amount of decomposition, expressed in each electrolyte by the value of its chemical equivalent.

From a very extended series of experiments, based on this and other methods of research, Mr. Faraday was enabled to draw the general inference that effects of chemical decomposition were always proportionate to the quantity of circulating electricity, and might be taken as an accurate and trustworthy measure


of the latter. Guided by this highly-important principle, he constructed his *voltameter*, an instrument which has rendered the greatest service to electrical science. This is merely an arrangement by which a little acidulated water is decomposed by the current, the gas evolved being collected and measured. By placing such an instrument in any part of the circuit, the quantity of electric force necessary to produce any given effect can be at once estimated; or, on the other hand, any required amount of the latter can be, as it were, measured out and adjusted to the object in view. The voltameter has received

many different forms; one of the most extensively useful is that figured, in which the platinum plates are separated by a very small interval, and the gas is collected in a graduated jar standing on the shelf of the pneumatic trough, the tube of the instrument, which is filled to the neck with dilute sulphuric acid, being passed beneath the jar.

The decomposition of the voltaic battery can be effected by the electricity of the common machine, by that developed by magnetic action, and by that of animal origin, but to an extent incomparably more minute. This arises from the very small *quantity* of electricity set in motion by the machine, although its *tension*, that is, power of overcoming obstacles, and passing through imperfect conductors, is exceedingly great. A pair of small wires of zinc and platinum, dipping into a single drop of dilute acid, develop far more electricity, to judge from the chemical effects of such an arrangement, than very many turns of a large plate electrical machine in powerful action. Nevertheless, polar or electrolytic decomposition can be distinctly and satisfactorily effected by the latter, although on a minute scale.

With a knowledge of the principles laid down, the study of the voltaic battery may be resumed and completed. In the first place, two very different views have been held concerning the source of the electrical disturbance in that apparatus. Volta himself ascribed it to mere contact of dissimilar metals; to what was denominated an *electro-motive*

Fig. 118.



force, called into being by such contact ; the liquid merely serving the purpose of a conductor between one pair of metals and that succeeding. Proof was supposed to be given of the fundamental position by an experiment in which discs of zinc and copper attached to insulating handles, after being brought into close contact, were found, by the aid of a very delicate gold-leaf electroscope, to be in opposite electrical states. It appears, however, that the more carefully this experiment is made, the smaller is the effect observed ; and hence it is judged highly probable that the whole may be due to accidental causes, against which it is almost impossible to guard.

On the other hand, the observation was soon made that the power of the battery always bore some kind of proportion to the chemical action upon the zinc ; that, for instance, when pure water was used the effect was extremely feeble ; with a solution of salt, it became much greater ; and, lastly, with dilute acid, greatest of all ; so that some relation evidently existed between the chemical effect upon the metal, and the evolution of electrical force.

The experiments of Mr. Faraday and Professor Daniell have given very great support to the chemical theory, by showing that the contact of dissimilar metals is *not* necessary in order to call into being powerful electrical currents, and that the development of electrical force is not only in some way connected with the chemical action of the liquid of the battery, but that it is always in direct proportion to the latter.

Fig. 119.



One very beautiful experiment, in which decomposition of iodide of potassium by real electrolysis is performed by a current generated without any contact of dissimilar metals, can be thus made :— A plate of zinc is bent at a right angle, and cleaned by rubbing with sand-paper. A plate of platinum has a wire of the same metal attached to it by careful riveting, and the latter bent into an arch. A piece of folded filter-paper is wetted with solution of iodide of potassium, and placed upon the zinc ; the platinum plate is arranged opposite to the latter, with the end of its wire resting upon the paper, and then the pair plunged into a glass of dilute sulphuric acid, mixed with a few drops of nitric. A brown spot of iodine becomes in a moment evident beneath

the extremity of the platinum wire ; that is, at the positive side of the arrangement.

A strong argument in favour of the chemical view is founded on the easily-proved fact, that the direction of the current is determined by the kind of action upon the metals, the one least attacked being always positive. Let two polished plates, the one iron and the other copper, be connected by wires with a galvanometer, and then immersed in a solution of an alkaline sulphide. The needle in a moment indicates a powerful current, passing from the copper through

the liquid, to the iron, and back again through the wire. Let the plates be now removed, cleaned, and plunged into dilute acid; the needle is again driven round, but in the opposite direction, the current now passing from the iron, through the liquid, to the copper. In the first instance the copper is acted upon, and not the iron; in the second, these conditions are reversed, and with them the direction of the current.

The metals employed in the practical construction of voltaic batteries are zinc for the active metal, and copper, silver, or, still better, platinum for the inactive one: the greater the difference of oxidability, the better the arrangement. The liquid is either dilute sulphuric acid, sometimes mixed with a little nitric, or occasionally, where very slow and long-continued action is wanted, salt and water. To obtain the maximum effect of the apparatus with the least expenditure of zinc, that metal must be employed in a pure state, or its surface must be covered by an amalgam of mercury, which in its electrical relations closely resembles the pure metal. The zinc is easily brought into this condition by wetting it with dilute sulphuric acid, and then rubbing a little mercury over it, by means of a piece of rag tied to a stick.

The principle of the compound battery is, perhaps, best seen in the crown of cups: by each alternation of zinc, fluid, and copper, the current is urged forwards with increased energy; its intensity is augmented, but the actual amount of electrical force thrown into the current form is not increased. The quantity, estimated by its decomposing power, is, in fact, determined by that of the smallest and least active pair of plates, the quantity of electricity in every part or section of the circuit being exactly equal. Hence large and small plates, batteries strongly and weakly charged, can never be connected without great loss of power.

When a battery, either simple or compound, constructed with pure or with amalgamated zinc, is charged with dilute sulphuric acid, a number of highly-interesting phenomena may be observed. While the circuit remains broken the zinc is perfectly inactive, no water is decomposed, no hydrogen liberated; but the moment the connection is completed, torrents of hydrogen arise, not from the zinc, but from the copper or platinum surfaces alone, while the zinc undergoes tranquil and imperceptible oxidation and solution. Thus, exactly the same effects are seen to occur in every active cell of a closed circuit, which are witnessed in a portion of water undergoing electrolysis: the oxygen appears at the positive side, with respect to the current, and the hydrogen at the negative; but with this difference, that the oxygen, instead of being set free, combines with the zinc. It is, in fact, a real case of electrolysis, and electrolytes alone are available as exciting liquids.

Common zinc is very readily attacked and dissolved by dilute sulphuric acid; and this is usually supposed to arise from the formation of a multitude of little voltaic circles, by the aid of particles of foreign

metals or plumbago, partially imbedded in the zinc. This gives rise in the battery to what is called local action, by which in the common forms of apparatus three-fourths or more of the metal are often consumed, without contributing in the least to the general effect, but, on the contrary, injuring the latter to some extent. This evil is got rid of by amalgamating the surface.

From experiments very carefully made with a "dissected" battery of peculiar construction, in which local action was completely avoided, it has been distinctly proved that the quantity of electricity set in motion by the battery varies exactly with the zinc dissolved. Coupling this fact with that of the definite action of the current, it will be seen, that when a perfect battery of this kind is employed to decompose water, in order to evolve 1 grain of hydrogen from the latter, 33 grains of zinc must be oxidized and its equivalent quantity of hydrogen disengaged in each active cell of the battery. That is to say, that the electrical force generated by the oxidation of an equivalent of zinc in the battery, is capable of effecting the decomposition of an equivalent of water, or any other electrolyte *out* of it.


This is an exceedingly important discovery ; it serves to show, in the most striking manner, the intimate nature of the connection between chemical and electrical forces, and their remarkable quantitative or equivalent relations. It almost seems, to use an expression of Mr. Faraday, as if a transfer of chemical force took place through the substance of solid metallic conductors ; that chemical actions, called into play in one portion of the circuit, could be made at pleasure to exhibit their effects without loss or diminution in any other. There is an hypothesis, not of recent date, long countenanced and supported by the illustrious Berzelius, which refers all chemical phenomena to electrical forces : which supposes that bodies combine because they are in opposite electrical states : even the heat and light accompanying chemical union may be, to a certain extent, accounted for in this manner. In short, we are in such a position, that either may be assumed as cause or effect : it may be that electricity is merely a form or modification of ordinary chemical affinity ; or, on the other hand, that all chemical action is a manifestation of electrical force.

One of the most useful forms of the common voltaic battery is that contrived by Dr. Wollaston (fig. 120). The copper is made completely to encircle the zinc plate, except at the edges, the two metals being kept apart by pieces of cork or wood. Each zinc is soldered to the preceding copper, and the whole screwed to a bar of dry mahogany, so that the plates can be lifted into or out of the acid, which is contained in an earthenware trough, divided into separate cells. The liquid consists of a mixture of 100 parts water, $2\frac{1}{2}$ parts oil of vitriol, and 2 parts commercial nitric acid, all by measure. A number of such batteries are easily connected together by straps of sheet copper, and admit of being put into action with great ease.

The great objection to this and to all the older forms of the voltaic

battery is, that the power rapidly decreases, so that, after a short time, scarcely the tenth part of the original action remains. This loss of power depends partly on the gradual change of the sulphuric acid into sulphate of zinc, but still more on the coating of hydrogen, and, at a later stage, on the precipitation of metallic zinc on the copper plates.

Fig. 120.



It is self-evident that if the copper plate in the fluid became covered with zinc, it would electrically act like a zinc plate. This is precisely the action of the hydrogen, whereby a decrease of electrical power is produced. This effect, produced by the substances separated from the liquid, is commonly called polarization.

An instrument of immense value for purposes of electro-chemical research, in which it is desired to maintain powerful and equable currents for many successive hours, has been contrived by Professor Daniell (fig. 121). Each cell of this "constant" battery consists of a copper cylinder $3\frac{1}{2}$ inches in diameter, and of a height varying from 6 to 18 inches. The zinc is employed in the form of a rod $\frac{3}{4}$ of an inch in diameter, carefully amalgamated, and suspended in the centre of the cylinder. A second cell of porous earthenware or animal membrane intervenes between the zinc and the copper; this is filled with a mixture of 1 part by measure of oil of vitriol and 8 of water, and the exterior space with the same liquid, saturated with sulphate of copper. A sort of little colander is fitted to the top of the cell, in which crystals of the sulphate of copper are placed, so that the strength of the solution may remain unimpaired. When a communication is made by a wire between the rod and the cylinder, a powerful current is produced, the power of which may be increased to any extent, by connecting a sufficient number of such cells into a series, on the principle of the crown of cups, the copper of the first being attached to the

zinc of the second. Ten such alternations constitute a very powerful apparatus, which has the great advantage of retaining its energy undiminished for a lengthened period.

Fig. 121.



By this arrangement of the electric battery, the polarization of the copper plate is altogether avoided; the zinc in the porous cell, whilst it dissolves in the sulphuric acid indeed decomposes + water, but does not liberate any hydrogen, for by the progress of the decomposition (see p. 216) up to the boundary of the copper solution, the hydrogen takes the place of the copper, and thus ultimately the copper is precipitated on the copper plate. The copper plate therefore remains in its original state, so long as a sufficient quantity of sulphate of copper is present in the solution.

By increasing the generative and reducing the antagonizing chemical affinities, Mr. Grove succeeded in forming the constant nitric acid battery, which bears his name. This instrument is capable of producing a far greater degree of power than the battery previously mentioned, and hence, it has become one of the most important means of promoting electrical science in the present day. The zinc dips into dilute sulphuric acid; and instead of a solution of copper, concentrated nitric acid is used which surrounds a platinum plate. It is evident

Fig. 122.



that the electrolytic action which begins at the zinc, passes through the sulphuric acid, and in precisely similar way through the contiguous nitric acid. Hydrogen would thus be liberated on the platinum plate. This action is not perceptible by the evolution of gas, but only gradually by the change of colour in the nitric acid, for the hydrogen liberated by the electrical action, again forms water at the expense of the oxygen yielded with a minimum resistance by the nitric acid; and by this means, so long as sufficient nitric acid is present, the purity of the surface of the platinum plate is maintained.

One of the cells in this battery is represented in the margin, in section (fig. 122). The zinc plate is bent round, so as to present a double surface, and well amalgamated; within it stands a thin flat cell of porous earthenware, filled with strong nitric acid, and the whole is immersed in a mixture of 1 part by measure of oil of vitriol and 6 of water, contained either in one of the cells of Wollaston's trough, or

in a separate cell of glazed porcelain, made for the purpose. The apparatus is completed by a plate of platinum foil which dips into the nitric acid, and forms the positive side of the arrangement. With ten such pairs, experiments of decomposition, ignition of wires, the light between charcoal points, &c., can be exhibited with great brilliancy, while the battery itself is very compact and portable, and, to a great extent, constant in its action. The zinc, as in the case of Professor Daniell's battery, is only consumed while the current passes, so that the apparatus may be arranged an hour or two before it is required for use, which is often a matter of great convenience; and local action from the precipitation of copper on the zinc is avoided.


Professor Bunsen has modified the Grove battery by substituting for the platinum dense charcoal or coke, which is an excellent conductor of electricity. By this alteration, at a very small expense, a battery may be made as powerful and useful as that of Grove. On account of its cheapness any one may put together one hundred or more of Bunsen's cells; by which the most magnificent phenomena of heat and light may be obtained.

The accompanying figure shows the form of the round carbon cylinder, which is used in these cells. It is hollowed so as to receive a porous earthenware cell, in which a round plate of zinc is placed. The upper edge of the cylinder of carbon is well saturated with wax, and is surrounded by a copper ring, by means of which it may be put in connection with the zinc of the adjoining pair.

Mr. Smee has contrived an ingenious battery, in which silver covered with a thin coating of finely-divided metallic platinum is employed in association with amalgamated zinc and dilute sulphuric acid. The rough surface appears to permit the ready disengagement of the bubbles of hydrogen.

Within the last ten or twelve years several very beautiful and successful applications of voltaic electricity have been made, which may be slightly mentioned. Mr. Spencer and Professor Jacobi have employed it in copying, or rather in multiplying, engraved plates and medals, by depositing upon their surfaces a thin coating of metallic copper, which, when separated from the original, exhibits, in reverse, a most faithful representation of the latter. By using this in its turn as a mould or matrix, an absolutely-perfect *fac-simile* of the plate or medal is obtained. In the former case, the impressions taken on paper are quite indistinguishable from those directly derived from the work of the artist; and as there is no limit to the number of *electrotype* plates which can be thus produced, engravings of the most beautiful description may be multiplied indefinitely. The copper is very tough, and bears the action of the press perfectly well.

Fig. 123.



The apparatus used in this and many similar processes is of the simplest possible kind. A trough or cell of wood is divided by a porous diaphragm, made of a very thin piece of sycamore, into two parts; dilute sulphuric acid is put on one side, and a saturated solution of sulphate of copper, sometimes mixed with a little acid, on the other. A plate of zinc is soldered to a wire or strap of copper, the other end of which is secured by similar means to the engraved copper plate. The latter is then immersed in the solution of sulphate, and the zinc in the acid. To prevent deposition of copper on the back of the copper plate, that portion is covered with varnish. For medals and small works a porous earthenware cell, placed in a jelly-jar, may be used.

Fig. 124.



Other metals may be precipitated in the same manner, in a smooth and compact form, by the use of certain precautions which have been gathered by experience. Electro-gilding and plating are now carried on very largely and in great perfection by Messrs. Elkington and others. Even non-conducting bodies, as sealing-wax and plaster of Paris, may be coated with metal; it is only necessary, as Mr. Murray has shown, to rub over them the thinnest possible film of plumbago. Seals may thus be copied in a very few hours with unerring truth.

M. Becquerel, several years ago, published an exceedingly interesting account of certain experiments, in which crystallized metals, oxides, and other insoluble substances had been produced by the slow and continuous action of feeble electrical currents, kept up for months, or even years. These products exactly resemble natural minerals, and, indeed, the experiments threw great light on the formation of the latter within the earth.*

Fig. 125.



The common but very pleasing experiment of the *lead tree* is greatly dependent on electro-chemical action. When a piece of zinc is suspended in a solution of acetate of lead, the first effect is the decomposition of a portion of the latter, and the deposition of metallic lead upon the surface of the zinc; it is simply a displacement of a metal by a more oxidable one. The change does not, however, stop here; metallic lead is still deposited in large and beautiful plates upon that first thrown down, until the solution becomes exhausted, or the zinc entirely disappears. The first portions of lead form with the zinc a voltaic arrangement of sufficient power to decompose the salt; under the peculiar circumstances in which the latter is placed, the metal is

* *Traité de l'Electricité et du Magnétisme*, iii. 239.

precipitated upon the negative portion, that is, the lead, while the oxygen and acid are taken up by the zinc.

Mr. Grove has contrived a battery in which an electrical current, of sufficient intensity to decompose water, is produced by the reaction of oxygen upon hydrogen. Each *element* of this interesting apparatus consists of a pair of glass tubes to contain the gases, dipping into a vessel of acidulated water. Both tubes contain platinum plates, covered with a rough deposit of finely-divided platinum, and furnished with conducting wires, which pass through the tops or sides of the tubes, and are hermetically sealed into the latter. When the tubes are charged with oxygen on the one side and hydrogen on the other, and the wires connected with a galvanoscope, the needle of the instrument becomes instantly affected; and when ten or more are combined in a series, the oxygen-tube of the one with the hydrogen-tube of the next, &c., while the terminal wires dip into acidulated water, a rapid stream of minute bubbles from either wire indicates the decomposition of the liquid; and when the experiment is made with a small voltmeter, it is found that the oxygen and hydrogen disengaged exactly equal in amount the quantities absorbed by the act of combination in each tube of the battery.

CHEMISTRY OF THE METALS.

THE metals constitute the second and larger group of elementary bodies. A great number of these are of very rare occurrence, being found only in a few scarce minerals; others are more abundant, and some few almost universally diffused throughout the whole globe. Some of these bodies are of most importance when in the metallic state; others, when in combination, chiefly as oxides, the metals themselves being almost unknown. Many are used in medicine and in the arts, and are essentially connected with the progress of civilization.

If arsenic and tellurium be included, the metals amount to forty-nine in number.

Physical Properties.—One of the most remarkable and striking characters possessed by the metals is their peculiar lustre: this is so characteristic, that the expression *metallic lustre* has passed into common speech. This property is no doubt connected with the extraordinary degree of opacity which the metals present in every instance. The thinnest leaves or plates, the edges of crystalline laminæ, arrest the passage of light in the most complete manner. An exception to this rule is usually made in favour of gold-leaf, which when held up to the daylight exhibits a greenish colour, as if it were really endued with a certain degree of translucency; the metallic film is, however, always so imperfect that it becomes difficult to say whether the observed effect may not be in some measure due to multitudes of little holes, many of which are visible to the naked eye.

In point of *colour*, the metals present a certain degree of uniformity: with two exceptions, viz. copper, which is red, and gold, which is yellow, all these bodies are included between the pure white of silver, and the bluish-grey tint of lead; bismuth, it is true, has a pinkish colour, but it is very feeble.

The differences of *specific gravity* are very wide, passing from potassium and sodium, which are lighter than water, to platinum, which is nearly twenty-one times heavier than an equal bulk of that fluid.

*Table of the Specific Gravities of Metals at 60° (15°·5C).**

Platinum	20·98
Gold	19·26
Tungsten	17·60
Mercury	13·57
Palladium	11·30 to 11·8
Lead	11·35
Silver	10·47
Bismuth	9·82
Uranium	9·00
Copper	8·89
Cadmium	8·60
Cobalt	8·54
Nickel	8·28
Iron	3·79
Molybdenum	7·40
Tin	7·29
Zinc	7·86 to 7·1
Manganese	6·85
Antimony	6·70
Tellurium	6·11
Arsenic	5·88
Aluminium	2·60†
Magnesium	1·70
Sodium	0·972
Potassium , . . .	0·865

The property of *malleability*, or power of extension under the hammer, or between the rollers of the flatting-mill, is enjoyed by certain of the metals to a very great extent. Gold-leaf is a remarkable example of the tenuity to which a malleable metal may be brought by suitable means. The gilding on silver wire used in the manufacture of gold lace is even thinner, and yet presents an unbroken surface. Silver may be beaten out very thin; copper also, but to an inferior extent; tin and platinum are easily rolled out into foil: iron, palladium, lead, nickel, cadmium, the metals of the alkalis, and mercury, when solidified, are also malleable. Zinc may be placed mid-way between the malleable and brittle division; then perhaps bismuth, and, lastly, such metals as antimony and arsenic, which are altogether destitute of malleability.

The specific gravity of malleable metals is usually very sensibly increased by pressure or blows, and the metals themselves rendered

* Dr. Turner's Elements, eighth edition, p. 345.

† Wöbler.

much harder, with a tendency to brittleness. This condition is destroyed and the former soft state restored by the operation of *annealing*, which consists in heating the metal to redness out of contact with air (if it will bear that temperature without fusion), and cooling it quickly or slowly according to the circumstances of the case. After this operation, it is found to possess its original specific gravity.

Ductility is a property distinct from the last, inasmuch as it involves the principle of tenacity, or power of resisting tension. The art of wire-drawing is one of great antiquity; it consists in drawing rods of metal through a succession of trumpet-shaped holes in a steel

Fig. 126.



plate, each being a little smaller than its predecessor, until the requisite degree of fineness is attained. The metal often becomes very hard and rigid in this process, and is then liable to break; this is remedied by annealing. The order of tenacity among the metals susceptible of being easily drawn into wire is the following: it is determined by observing the weights required to break asunder wires drawn through the same orifice of the plate:

Iron	Gold
Copper	Zinc
Platinum	Tin
Silver	Lead.

Metals differ as much in *fusibility* as in density; the following table, extracted from the late Dr. Turner's excellent work, will give an idea of their relations to heat. The melting-points of the metals which only fuse at a temperature above ignition, and that of zinc, are on the authority of Mr. Daniell, having been observed by the help of the pyrometer before described:

		Melting points.	
		F.	C.
Fusible below a red heat.	Mercury	—39°	—39°·44
	Potassium	136	57·77
	Sodium	194	90
	Tin	442	227·77
	Cadmium (about)	442	227·77
	Bismuth	497	258·33
	Lead	612	322·77
	Tellurium—rather less fusible than lead		
	Arsenic—unknown		
	Zinc	773	411·66
Antimony—just below redness.			

		Melting points.	
		F.	C.
Infusible below a red heat.	Silver	1873°	1022°·77
	Copper	1996	1091·11
	Gold	2016	1102·22
	Cast iron	2786	1530
	Pure iron	Fusible only in an excellent wind-furnace.	
	Nickel		
	Cobalt		
	Manganese		
	Palladium	Imperfectly melted in wind- furnace.	
	Molybdenum		
	Uranium		
	Tungsten		
	Chromium	Infusible in furnace ; fusible by oxyhydrogen blowpipe.	
	Titanium		
	Cerium		
	Osmium		
	Iridium		
	Rhodium		
	Platinum		
	Tantalum		

Some metals acquire a pasty or adhesive state before becoming fluid: this is the case with iron and platinum, and also with the metals of the alkalis. It is this peculiarity which confers the very valuable property of welding, by which pieces of iron and steel are united without solder, and the finely-divided metallic sponge of platinum converted into a solid and compact bar.

Volatility is possessed by certain members of this class, and perhaps by all, could temperatures sufficiently elevated be obtained. Mercury boils and distils below a red heat; potassium, sodium, zinc, and cadmium rise in vapour when heated to a bright redness; arsenic and tellurium are volatile.

CHEMICAL RELATIONS OF THE METALS ; CONSTITUTION OF SALTS.

Metallic combinations are of two kinds, namely, those formed by the union of metals among themselves, which are called alloys, or where mercury is concerned, amalgams, and those generated by combination with the non-metallic elements, as oxides, chlorides, sulphides, &c. In this latter case, the metallic characters are very frequently lost. The alloys themselves are really true chemical compounds, and are not mere mixtures of the constituent metals; their properties often differ completely from those of the latter.

The oxides of the metals may be divided, as already pointed out, into three classes; namely, those which possess basic characters more or less marked, those which refuse to combine with either acids or alkalis,

and those which have distinctly acid properties. The strong bases are all protoxides; they contain single equivalents of metal and oxygen; the weaker bases are usually sesquioxides, containing metal and oxygen in the proportion of two equivalents of the former to three of the latter; the peroxides or neutral compounds are still richer in oxygen, and, lastly, the metallic acids contain the maximum proportion of that element.


The gradual change of properties by increasing proportions of oxygen is well illustrated by the case of manganese.

	Metal.	Oxygen.	Symbols.	Characters.
Protoxide . . .	1 eq.	1 eq.	MnO	Strongly basic.
Sesquioxide . . .	2 eq.	3 eq.	Mn ₂ O ₃	Feebly basic.
Binoxide . . .	1 eq.	2 eq.	MnO ₂	Neutral.
Manganic acid . .	1 eq.	3 eq.	MnO ₃	} Strongly acid.
Permanganic acid .	2 eq.	7 eq.	Mn ₂ O ₇	

The oxides of iron and chromium present similar, but less numerous gradations.

When a powerful oxygen-acid and a powerful metallic base are united in such proportions that they exactly destroy each other's properties, the resulting salt is said to be neutral; it is incapable of affecting vegetable colours. Now, in all these well-characterized neutral salts, a constant and very remarkable relation is observed to exist between the quantity of oxygen in the base and the quantity of *acid* in the salt. This relation is expressed in the following manner:—To form a neutral combination, as many equivalents of acid must be present in the salt as there are of oxygen in the base itself. In fact, this has become the very definition of neutrality, as the action on vegetable colours is sometimes an unsafe guide.


It is easy to see the application of this law. When a base is a protoxide, a single equivalent of acid suffices to neutralize it; when a sesquioxide, not less than three are required. Hence, if by any chance the base of a salt should pass by oxidation from the one state to the other, the acid will be insufficient in quantity by one-half to form a neutral combination. Sulphate of the protoxide of iron offers an example: when a solution of this substance is exposed to the air, it absorbs oxygen, and a yellow insoluble *sub-salt*, or *basic-salt* is produced, which contains an excess of base. Four equivalents of the green compound absorb from the air two equivalents of oxygen, and give rise to one equivalent of neutral and one equivalent of basic sulphate of the sesquioxide, as indicated by the diagonal zigzag line of division.



Such sub-salts or basic salts are very frequently insoluble.

The combinations of chlorine, iodine, bromine, and fluorine with the metals possess in a very high degree the saline character. If, however, the definition formerly given of a salt be rigidly adhered to, these bodies must be excluded from the class, and with them the very substance from which the name is derived, that is, common salt, which is a chloride of sodium. To obviate this anomaly, it has been found necessary to create two classes of salts: in the first division will stand those constituted after the type of common salt, which contain a metal and a *salt-radical*, as chlorine, iodine, &c.; and in the second, those which, like sulphate of soda and nitrate of potassa, are generally supposed to be combinations of an acid with an oxide. The names *haloid** salts, and *oxygen-acid*, or *oxy-salts*, are given to these two kinds.


When a haloid salt is dissolved in water, it might be regarded as a combination of a metallic oxide with a hydrogen-acid, the water being supposed to undergo decomposition, its hydrogen being transferred to the salt-radical, and its oxygen to the metal. This view is unsupported by evidence of any value: it is much more probable, indeed, that no truly saline compounds of hydrogen-acids exist, at any rate in inorganic chemistry. When a solution of any hydrogen-acid is poured upon a metallic oxide, we may rather suppose that both are decomposed, water and a haloid salt of the metal being produced. Take hydrochloric acid and potassa by way of example.



On evaporating the solution, the chloride of potassium crystallizes out.

When hydrochloric acid and ammoniacal gases are mixed, they combine with some energy, and form a white solid salt, sal-ammoniac. Now this substance bears such a strong resemblance in many important particulars to chloride of potassium and common salt, that the ascription to it of a similar constitution is well warranted.

If chloride of potassium, therefore, contain chlorine and metal, sal-ammoniac may also contain chlorine in combination with a substance having the chemical relations of a metal, formed by the addition of the hydrogen of the acid to the elements of the ammonia.





The term *ammonium* is given to this hypothetical body, NH_4 ; it

* ἅλς, sea-salt, and εἶδος, form.

is supposed to exist in all the ammoniacal salts. Thus we have chloride of ammonium, sulphate of the oxide of ammonium, &c. This view is very strongly supported by the peculiarities of the salts themselves, and by the existence of a series of substances intimately related to these salts in organic chemistry, as will hereafter be seen.


Many of the sulphides also possess the saline character and are soluble in water, as those of potassium and sodium. Sometimes a pair of sulphides will unite in definite proportions, and form a crystallizable compound. Such bodies bear a very close resemblance to oxygen-acid salts; they usually contain a protosulphide of an alkaline metal, and a higher sulphide of a non-metallic substance or of a metal which has little tendency to form a basic oxide, the two sulphides having exactly the same relation to each other as the oxide and acid of an ordinary salt. Hence the expressions *sulphur-salt*, *sulphur-acid*, and *sulphur-base*, which Berzelius applies to such compounds: they contain sulphur in the place of oxygen. Thus, bisulphide of carbon is a sulphur-acid; it forms a crystallizable compound with protosulphide of potassium, which is a sulphur-base. Were oxygen substituted for the sulphur in this product, we should have carbonate of potassa.



These remarkable compounds are very numerous and interesting; they have been studied by Berzelius with great care.

Salts often combine together, and form what are called *double salts*, in which the same acid is in combination with two different bases. When sulphate of copper and sulphate of potassa, or chloride of zinc and sal-ammoniac, are mixed in the ratio of the equivalents, dissolved in water, and the solution made to crystallize, double salts are obtained. These latter are often more beautiful, and crystallize better than their constituent salts.

Many of the compounds called *super*, or *acid salts*, such as bisulphate of potassa, which have a sour taste and acid reaction to test-paper, ought strictly to be considered in the light of double salts, in which one of the bases is water. Strange as it may at first sight appear, water possesses considerable basic powers, although it is unable to mask acid reaction on vegetable colours; hydrogen, in fact, very much resembles a metal in its chemical relations. Bisulphate of potassa will, therefore, be a double sulphate of potassa and water, while oil of vitriol must be assimilated to neutral sulphate of potassa.



Water is a weak base; it is for the most part easily displaced by a metallic oxide; yet cases occur now and then in which the reverse happens, and water is seen to decompose a salt, in virtue of its basic power.

There are a few acid salts which contain no water; as the bichromate of potassa, and a new anhydrous sulphate of potassa discovered by M. Jacquelin.* It will be necessary, of course, to adopt some other view in these cases. The simplest will be to consider them as really containing two equivalents of acid to one of base.

By *water of crystallization* is meant water in a somewhat loose state of combination with a salt, or other compound body, from which it can be disengaged by the mere application of heat, or by exposure to a dry atmosphere. Salts which contain water of crystallization have their crystalline form greatly influenced by the proportion of the latter. Green sulphate of iron crystallizes in two different forms, and with two different proportions of water, according to the temperature at which the salt separates from the solution.

Many salts containing water *effloresce* in a dry atmosphere, crumbling to powder, and losing a part or the whole of their water of crystallization; while in a moist atmosphere they may be preserved unchanged. The opposite effect to this, or *deliquescence*, results from a strong attraction of the salt for water, in virtue of which it absorbs the latter from the air, often to such an extent as to produce liquefaction.

Crystallization; Crystalline Forms.—Almost every substance, simple and compound, capable of existence in the solid state, assumes, under favourable circumstances, a distinct geometrical form or figure, usually bounded by plane surfaces, and having angles of fixed and constant value. The faculty of crystallization seems to be denied only to a few bodies, chiefly highly complex organic principles, which stand, as it were, upon the very verge of organization, and which, when in a solid state, are frequently characterized by a kind of beady or globular appearance, well known to microscopical observers.

The most beautiful examples of crystallization are to be found among natural minerals, the results of exceedingly slow changes constantly occurring within the earth. It is invariably found that artificial crystals of salts, and other soluble substances, which have been slowly and quietly deposited, always surpass in size and regularity those of more rapid formation.

Solution in water or some other liquid is one very frequent method of effecting crystallization. If the substance be more soluble at a high than at a low temperature, then a hot and saturated solution by slow cooling will generally be found to furnish crystals: this is a very common case with salts and various organic principles. If it be equally soluble, or nearly so, at all temperatures, then slow spontaneous evaporation in the air, or over a surface of oil of vitriol, often proves very effective.

Fusion and slow cooling may be employed in many cases; that of sulphur is a good example; the metals usually afford traces of crystalline figure when thus treated, which sometimes become very beautiful

* Ann. Chim. et Phys. lxx. 311.

and distinct, as with bismuth. A third condition under which crystals very often form is in passing from a gaseous to a solid state, of which iodine affords a good instance. When by any of these means time is allowed for the symmetrical arrangement of the particles of matter at the moment of solidification, crystals are produced.


That crystals owe their figure to a certain regularity of internal structure, is shown both by their mode of formation and also by the peculiarities attending their fracture. A crystal placed in a slowly-evaporating saturated solution of the same substance grows or increases by a continued deposition of fresh matter upon its sides, in such a manner that the angles formed by the meeting of the latter remain unaltered.

The tendency of most crystals to split in particular directions, called by mineralogists *cleavage*, is a certain indication of regular structure, while the curious optical properties of many among them, and their remarkable mode of expansion by heat, point to the same conclusion.

It may be laid down as a general rule that every substance has its own crystalline form, by which it may very frequently be recognized at once; not that each substance has a different figure, although very great diversity in this respect is to be found. Some forms are much more common than others, as the cube and six-sided prism, which are very frequently assumed by a number of bodies, not in any way related.

The same substance may have, under different sets of circumstances, as high and low temperatures, two different crystalline forms, in which case it is said to be *dimorphous*. Sulphur and carbon furnish, as already noticed, examples of this curious fact; another case is presented by carbonate of lime in the two modifications of calcareous spar and aragonite, both chemically the same, but physically different. A fourth

Fig. 127.




example might be given in the iodide of mercury, which also has two distinct forms, and even two distinct colours, offering as great a contrast as those of diamond and plumbago.

The angles of crystals are measured by means of instruments called *goniometers*, of which there are two kinds in use, namely, the old or common goniometer, and the reflective goniometer of Dr. Wollaston.

The common goniometer consists of a pair of steel blades moving with friction upon a centre, as shown in the cut (fig. 127). The edges *a a* are carefully adjusted to the faces of the crystal, whose inclination to each other it is required to ascertain, and then the instrument being applied to the divided semicircle, the contained angle is at once read off. An approximative measurement, within one or two degrees, can be easily obtained by this instrument, provided the planes of the crystal be tolerably perfect, and large enough for the purpose. Some practice is of course required before even this amount of accuracy can be attained.

The reflective goniometer is a very superior instrument, its indications being correct within a fraction of a degree; it is applicable also to the measurement of the angles of crystals of very small size, the only condition required being that their planes be smooth and brilliant. The subjoined sketch will convey an idea of its nature and mode of use.


Fig. 128.



a is a divided circle or disc of brass, the axis of which passes stiffly and without shake through the support *b*. This axis is itself pierced to admit the passage of a round rod or wire, terminated by the milled-edged head *c*, and destined to carry the crystal to be measured by means of the jointed arm *d*. A vernier, *e*, immovably fixed to the upright support, serves to measure with great accuracy the angular motion of the divided circle. The crystal at *f* can thus be turned round, or adjusted in any desired position, without the necessity of moving the disc.

The principle upon which the measurement of the angle rests is very simple. If the two adjacent plaues of a crystal be successively brought into the same position, the angle through which the crystal will have moved will be *the supplement to that contained between the two planes*. This will be easily intelligible by reference to the subjoined diagram, in which a crystal having the form of a triangular prism* is shown in the two positions, the angle to be measured being that indicated by the letters *e d f*.

Fig. 129.



The lines *a c*, *b c*, are perpendicular to the respective faces of the crystal, consequently the internal angles *d g c*, *d h c*, are right angles. Now, since the sum of the internal angles of a four-sided rectilinear figure, as *d g c h*, equal *four* right angles, or 360° , the angle *g d h* (or *e d f*) must of necessity be the supplement to the angle *g c h*, or that through which the crystal moves. All that is required to be done, therefore, is to measure the latter angle with accuracy, and subtract its value from 180° ; and this the goniometer effects.

One method of using the instrument is the following :—The goniometer is placed at a convenient height upon a steady table in front of a well-illuminated window. Horizontally across the latter, at the height of eight or nine feet from the ground, is stretched a narrow black ribbon, while a second similar ribbon, adjusted parallel to the first, is fixed beneath the window, a foot or eighteen inches above the floor. The object is to obtain two easily-visible black lines, perfectly parallel. The crystal to be examined is attached to the arm of the goniometer at *f* by a little wax, and adjusted in such a manner that the edge joining the two planes whose inclination is to be measured shall nearly coincide with, or be parallel to, the axis of the instrument. This being done, the adjustment is *completed* in the following manner :—The divided circle is turned until the zero of the vernier comes to

* The triangular prism has been chosen for the sake of simplicity; but a moment's consideration will show that the rule applies equally well to any other figure.

180°; the crystal is then moved round by means of the inner axis *c* (fig. 128) until the eye placed near it perceives the image of the upper black line reflected from the surface of one of the planes in question. Following this image, the crystal is still cautiously turned until the upper black line seen by reflection approaches and overlaps the lower black line seen *directly* by another portion of the pupil. It is obvious, that if the plane of the crystal be quite parallel to the axis of the instrument (the latter being horizontal), the two lines will coincide completely. If, however, this should not be the case, the crystal must be moved upon the wax until the two lines fall in one when superposed. The second face of the crystal must then be adjusted in the same manner, care being taken not to derange the position of the first. When by repeated observation it is found that both have been correctly placed, so as to bring the edge into the required condition of parallelism with the axis of motion, the measurement of the angle may be made.

For this purpose the crystal is moved as before by the inner axis until the image of the upper line, reflected from the first face of the crystal, covers the lower line seen directly. The great circle, carrying the whole with it, is then cautiously turned until the same coincidence of the upper with the lower line is seen by means of the second face of the crystal; that is, the second face is brought into exactly the same position as that previously occupied by the first. Nothing then remains but to read off by the vernier the angle through which the circle has been moved in this operation. The division upon the circle itself is very often made *backwards*, so that the angle of motion is not obtained, but its supplement, or the angle of the crystal required.

It may be necessary to remark, that, although the principle of the operation described is in the highest degree simple, its successful practice requires considerable skill and experience.


If a crystal of tolerably simple form be attentively considered, it will become evident that certain directions can be pointed out in which straight lines may be imagined to be drawn, passing through the central point of the crystal from side to side, from end to end, or from one angle to that opposed to it, &c., about which lines the particles of matter composing the crystal may be conceived to be symmetrically built up. Such lines or *axes* are not always purely imaginary, however, as may be inferred from the remarkable optical properties of many crystals: upon their number, relative lengths, position, and inclination to each other, depends the outward figure of the crystal itself.

All crystalline forms may upon this plan be arranged in six classes or *systems*; these are as follows:—

1. *The regular system*.—The crystals of this division have three equal axes, all placed at right angles to each other. The most important forms are the *cube* (1), the *regular octahedron* (2), and the *rhombic dodecahedron* (3).

The letters a — a show the termination of the three axes, placed as stated.


Fig. 130.



Very many substances, both simple and compound, assume these forms, as most of the metals, carbon in the state of diamond, common salt, iodide of potassium, the alums, fluor-spar, bisulphide of iron, garnet, spinelle, &c.

2. *The square prismatic system.*—Three axes are here also observed, at right angles to each other. Of these, however, two only are of equal length, the third being usually longer or shorter. The most important forms are: a *right square prism*, in which the lateral axes terminate in the central point of each side (1); a *second right square prism*, in which the axes terminate in the edges (2); a corresponding pair of *right, square-based octahedra* (3 and 4).

Fig. 131.




a — a . Principal or verticle axis.
 b — b . Secondary, or lateral axes.

Examples of these forms are to be found in zircon, native binocide of tin, apophyllite, yellow ferrocyanide of potassium, &c.

3. *The right prismatic system.*—This is characterized by three axes of unequal lengths, placed at right angles to each other, as in the *right*

rectangular prism (1), the *right rhombic prism* (2), the *right rectangular-based octahedron* (3), and the *right rhombic-based octahedron* (4).

Fig. 132.




a — a . Principal axis.
 b — b , c — c . Secondary axes.

The system is exemplified in sulphur crystallized at a low temperature, arsenical iron pyrites, nitrate and sulphate of potassa, sulphate of baryta, &c.

4. *The oblique prismatic system*.—Crystals belonging to this group have also three axes which may be all unequal, two of these (the secondary) are placed at right angles, the third being so inclined as to be oblique to one and perpendicular to the other. To this system may be referred the four following forms:—*The oblique rectangular*

Fig. 133.




a — a . Principal axis.
 b — b , c — c . Secondary axes.

prism (1), the *oblique rhombic prism* (2), the *oblique rectangular-based octahedron* (3), the *oblique rhombic-based octahedron* (4).

Such forms are taken by sulphur crystallized by fusion and cooling, realgar, sulphate, carbonate and phosphate of soda, borax, green vitriol, and many other salts.

5. *The doubly-oblique prismatic system.*—The crystalline forms comprehended in this division are, from their great apparent irregularity, exceedingly difficult to study and understand. In them are traced three axes, which may be all unequal in length, and are all oblique to each other, as in the two *doubly-oblique prisms* (1 and 2), and in the corresponding *doubly-oblique octahedrons* (3 and 4).

Fig. 134.




a — a . Principal axis, as before.
 b — b , c — c . Secondary axes.

Sulphate of copper, nitrate of bismuth, and quadroxalate of potassa afford illustrations of these forms.

6. *The rhombohedral system.*—This is very important and extensive; it is characterized by the presence of *four* axes, three of which are

Fig. 135.



a — a . Principal axis.
 b — b . Secondary axes.

equal, in the same plane, and inclined to each other at angles of 60° , while the fourth or principal axis is perpendicular to all. The *regular six-sided prism* (1), the *quartz-dodecahedron* (2), the *rhombododecahedron* (3), and a *second dodecahedron*, whose faces are scalene triangles (4), belong to the system in question.

Examples are readily found; as in ice, calcareous spar, nitrate of soda, beryl, quartz or rock crystal, and the semi-metals, arsenic, antimony, and tellurium.

If a crystal increase in magnitude by equal additions on every part, it is quite clear that its figure must remain unaltered; but, if from some cause this increase should be partial, the newly-deposited matter being distributed unequally, but still in obedience to certain definite laws, then alterations of form are produced, giving rise to figures which have a direct geometrical connection with that from which they are derived. If, for example, in the cube, a regular omission of successive rows of particles of matter in a certain order be made at each solid angle, while the crystal continues to increase elsewhere, the result will be the production of small triangular planes, which, as the process advances, gradually usurp the whole of the surface of the crystal, and convert the cube into an octahedron. The new planes are called *secondary*, and their production is said to take place by regular *decrements* upon the solid angles. The same thing may happen on the edges of the cube; a new figure, the rhombic dodecahedron, is then generated. The modifications which can thus be produced of the original or *primary* figure (all of which are subject to exact geometrical laws) are very numerous. Several distinct modifications may be present at the same time, and thus render the form exceedingly complex.

Fig. 136.




Passage of cube to octahedron.

It is important to observe, that in all these deviations from what may be regarded as the primary or fundamental figure of the crystal, the modifying planes are in fact *the planes of figures belonging to the same natural group or crystallographical system as the primary form, and having their axes coincident with those of the latter*. The crystals of each system are thus subject to a peculiar and distinct set of modifications, the observation of which very frequently constitutes an excellent guide to the discovery of the primary form itself.

Crystals often cleave parallel to all the planes of the primary figure, as in calcareous spar, which offers a good illustration of this perfect cleavage. Sometimes one or two of these planes have a kind of preference over the rest in this respect, the crystal splitting readily in these directions only.

A very curious modification of the figure sometimes occurs by the excessive growth of each alternate plane of the crystal; the rest become at length obliterated, and the crystal assumes the character called *hemihedral* or *half-sided*. This is well seen in the production of the tetrahedron from the regular octahedron, and of the rhombohedral form by a similar change from the quartz-dodecahedron already figured.

Fig. 137.



Passage of octahedron to tetrahedron.

Relations of Form and Constitution ; Isomorphism.—Certain substances, to which a similar chemical constitution is ascribed, possess the remarkable property of exactly replacing each other in crystallized compounds without alteration of the characteristic geometrical figure. Such bodies are said to be *isomorphous*.*

For example, magnesia, oxide of zinc, oxide of copper, protoxide of iron, and oxide of nickel, are allied by isomorphic relations of the most intimate nature. The salts formed by these substances with the same acid and similar proportions of water of crystallization, are identical in their form, and, when of the same colour, cannot be distinguished by the eye; the sulphates of magnesia and zinc may be thus confounded. The sulphates, too, all combine with sulphate of potassa and sulphate of ammonia, giving rise to double salts, whose figure is the same, but quite different from that of the simple sulphates. Indeed this connection between identity of form and parallelism of constitution runs through all their combinations.

In the same manner alumina and sesquioxide of iron replace each other continually without change of crystalline figure; the same remark may be made of potassa, soda, and ammonia with an equivalent of water, or oxide of ammonium, these bodies being strictly isomorphous. The alumina in common alum may be replaced by sesquioxide of iron, the potassa by ammonia or by soda, and still the figure of the crystal remains unchanged. These replacements may be partial only; we may

* From *ἴσος*, equal, and *μόρφη*, shape or form.

have an alum containing both potassa and ammonia, or alumina and sesquioxide of chromium. By artificial management—namely, by transferring the crystal successively to different solutions—we may have these isomorphous and mutually-replacing compounds distributed in different layers upon the same crystal.

For these reasons mixtures of isomorphous salts can never be separated by crystallization, unless their difference of solubility is very great. A mixed solution of sulphate of protoxide of iron and sulphate of copper, isomorphous salts, yields on evaporation crystals containing both iron and copper. But if before evaporation the protoxide of iron be converted into sesquioxide by chlorine or other means, then the crystals obtained are free from iron, except that of the mother-liquor which wets them. The salt of sesquioxide of iron is no longer isomorphous with the copper salt, and easily separates from the latter.

When compounds are thus found to correspond, it is inferred that the elements composing them are also isomorphous. Thus, the metals magnesium, zinc, iron, and copper are presumed to be isomorphous: arsenic and phosphorus should present the same crystalline form, because arsenic and phosphoric acids give rise to combinations which agree most completely in figure and constitution. The chlorides, iodides, bromides, and fluorides agree, whenever they can be observed, in the most perfect manner; hence the elements themselves are believed to be also isomorphous. Unfortunately, for obvious reasons, it is very difficult to observe the crystalline figure of most of the elementary bodies, and this difficulty is increased by the frequent dimorphism they exhibit.

Absolute identity of value in the angles of crystals is not always exhibited by isomorphous substances. In other words, small variations often occur in the magnitude of the angles of crystals of compounds which in all other respects show the closest isomorphic relations. This should occasion no surprise, as there are reasons why such variations might be expected, the chief perhaps being the unequal effects of expansion by heat, by which the angles of the same crystal are changed by alteration of temperature. A good example is found in the case of the carbonates of lime, magnesia, manganese, iron, and zinc, which are found native crystallized in the form of obtuse rhombohedra (fig. 135, 3) not distinguishable from each other by the eye, or even by the common goniometer, but showing small differences when examined by the more accurate instrument of Dr. Wollaston. These compounds are isomorphous, and the measurements of the obtuse angles of their rhombohedra as follows:—

Carbonate of lime	.	.	105° 5'
„ magnesia	.	.	107° 25'
„ protox. manganese	.	.	107° 20'
„ „ iron	.	.	107°
„ zinc	.	.	107° 40'

Anomalies in the composition of various earthy minerals, which formerly threw much obscurity upon their chemical nature, have been in great measure explained by these discoveries.

Specimens of the same mineral from different localities were found to afford very discordant results on analysis. But the proof once given of the extent to which substitution of isomorphous bodies may go without destruction of what may be called the primitive type of the compound, these difficulties vanish.

Another benefit conferred on science by the discoveries in question, is that of furnishing a really philosophical method of classifying elementary and compound substances, so as to exhibit their natural relationships; it would be perhaps more proper to say that such will be the case when the isomorphic relations of all the elementary bodies become known,—at present only a certain number have been traced.

Decision of a doubtful point concerning the constitution of a compound may now and then be very satisfactorily made by a reference to this same law of isomorphism. Thus, alumina, the only known oxide of aluminum, is judged to be a sesquioxide of the metal from its relation to sesquioxide of iron, which is certainly so; the black oxide of copper is inferred to be really the protoxide, although it contains twice as much oxygen as the red oxide, because it is isomorphous with magnesia and zinc, both undoubted protoxides.

The subjoined table will serve to convey some idea of the most important families of isomorphous elements; it is taken from Professor Graham's systematic work,* to which the pupil is referred for fuller details on this interesting subject.

Isomorphous Groups.

(1.)	(3.)	(7.)
Sulphur	Barium	Sodium
Selenium	Strontium	Silver
Tellurium.	Lead.	Gold
(2.)	(4.)	Potassium
Magnesium	Tin	<i>Ammonium.</i>
Calcium	Titanium.	(8.)
Manganese	(5.)	Chlorine
Iron	Platinum	Iodine
Cobalt	Iridium	Bromine
Nickel	Osmium.	Fluorine
Zinc	(6.)	<i>Cyanogen.</i>
Cadmium	Tungsten	(9.)
Copper	Molybdenum	Phosphorus
Chromium	Tantalum.	Arsenic
Aluminum		Antimony
Beryllium		Bismuth.
Vanadium		
Zirconium.		

* Second edition, p. 175.



There is a law concerning the formation of double salts which may now be mentioned; the two bases are never taken from the same isomorphous family. Sulphate of copper or of zinc may unite in this manner with sulphate of soda or potassa, but not with sulphate of iron or cobalt; chloride of magnesium may combine with chloride of ammonium, but not with chloride of zinc or nickel, &c. It will be seen hereafter that this is a matter of some importance in the theory of the organic acids.



Polybasic Acids.—There is a particular class of acids in which a departure occurs from the law of neutrality formerly described: these are acids requiring two or more equivalents of a base for neutralization. The phosphoric and arsenic acids present the best examples yet known in mineral chemistry; but in the organic department of the science cases very frequently occur.

Phosphoric acid is capable of existing in three different states or modifications, forming three separate classes of salts which differ completely in properties and constitution. They are distinguished by the names *tribasic*, *bibasic*, and *monobasic* acids, according to the number of equivalents of base required to form neutral salts.

Tribasic or Common Phosphoric Acid.—When commercial phosphate of soda is dissolved in water, and the solution mixed with acetate of lead, an abundant white precipitate of phosphate of lead falls, which may be collected on a filter, and well washed. While still moist, this compound is suspended in distilled water, and an excess of sulphuretted hydrogen gas passed into it. The protoxide of lead is converted into sulphide, which subsides as a black insoluble precipitate, while phosphoric acid remains in solution, and is easily deprived of the residual sulphuretted hydrogen by a gentle heat.

The soda-salt employed in this experiment contains the tribasic modification of phosphoric acid. Of the three equivalents of base, two consist of soda and one of water: when mixed with solution of lead, a tribasic phosphate of the oxide of that metal falls, which, when decomposed by sulphuretted hydrogen, yields sulphide of lead and a hydrate of the acid containing three equivalents of water in intimate combination.






The solution of tribasic hydrate may be concentrated by evaporation *in vacuo* over sulphuric acid until it crystallizes in thin deliquescent plates. The same compound in beautiful crystals, resembling those of sugar-candy, has been accidentally formed.* It undergoes no change by boiling with water, but when heated alone to 400° ($204^\circ\cdot4\text{C}$) loses some of its combined water, and becomes converted into a mixture of the bibasic and monobasic hydrates. At a red heat it becomes entirely changed to monohydrate, which at a still higher temperature, sublimes.

Tribasic phosphoric acid is characterized by the yellow insoluble salt it forms with protoxide of silver.


Bibasic Phosphoric Acid, or *Pyrophosphoric Acid*.—When common phosphate of soda, containing



is gently heated, the 24 equivalents of water of crystallization are expelled, and the salt becomes anhydrous; but if the heat be raised to a higher point, the basic water is also driven off, and the acid passes into the second or bibasic modification. If the altered salt be now dissolved in water, this new compound, the bibasic phosphate of soda, crystallizes out. When mixed with solution of acetate of lead, bibasic phosphate of lead is thrown down, which, decomposed by sulphuretted hydrogen, furnishes a solution of the bibasic hydrate. This solution may be preserved without change at common temperatures; but when heated, an equivalent of water is taken up, and the substance passes back again into the tribasic modification.

Crystals of this hydrate have also been observed by M. Péligot. Their production was accidental. The bibasic phosphates soluble in water give a white precipitate with solution of silver.

Monobasic, or *Metaphosphoric Acid*.—When common tribasic phosphate of soda is mixed with solution of tribasic hydrate of phosphoric acid, and exposed, after proper concentration, to a low temperature, prismatic crystals are obtained, which consist of a phosphate of soda having two equivalents of basic water.



* Peligot, Ann. Chim. et Phys. lxxiii. 286.

When this salt is very strongly heated, both the water of crystallization and that contained in the base are expelled, and monobasic phosphate of soda remains. This may be dissolved in cold water, precipitated with acetate of lead, and the lead-salt as before decomposed by sulphuretted hydrogen.

The solution of the monobasic hydrate is decomposed rapidly by heat, becoming converted into tribasic hydrate. It possesses the property of coagulating albumen, which is not enjoyed by either of the preceding modifications. Monobasic alkaline phosphates precipitate nitrate of silver white.

The glacial phosphoric acid of pharmacy is, when pure, hydrate of monobasic phosphoric acid: it contains HO, PO_5 .

Anhydrous phosphoric acid, prepared by burning phosphorus in dry air, when thrown into water, forms a variable mixture of the three hydrates. When heated, a solution of the tribasic hydrate alone remains.* See also phosphates of soda.

Binary Theory of Salts.—The great resemblance in properties between the two classes of saline compounds, the haloid and oxy-salts, has very naturally led to the supposition that both might possibly be alike constituted, and that the latter, instead of being considered compounds of an oxide and an acid, might with greater propriety be considered to contain a metal in union with a compound salt-radical, having the chemical relations of chlorine and iodine.

On this supposition sulphate and nitrate of potassa will be constituted in the same manner as chloride of potassium, the compound radical replacing the simple one.

Old view.	New view.
$\text{KO} + \text{S O}_3$	$\text{K} + \text{S O}_4$
$\text{KO} + \text{NO}_5$	$\text{K} + \text{N O}_6$

Hydrated sulphuric acid will be, like hydrochloric acid, a hydride of a salt-radical,



When the latter acts upon metallic zinc, the hydrogen is simply displaced, and the metal substituted; no decomposition of water is supposed to occur, and, consequently, the difficulty of the old hypothesis is at an end. When the acid is poured upon a metallic oxide, the same reaction occurs as in the case of hydrochloric acid, water

* The three modifications of phosphoric acid possess properties so dissimilar that they might really be considered three distinct, although intimately related bodies. It is exceedingly remarkable, that when their salts are subjected to electro-chemical decomposition, the acids travel unaltered, a tribasic salt giving at the positive electrode a solution of common phosphoric acid; a bibasic salt, one of pyrophosphoric acid; and a monobasic salt, one of metaphosphoric acid (Professor Daniell and Dr. Miller, Phil. Trans. for 1844, p. 1).

and a haloid salt are produced. All acids must be, in fact, hydrogen acids, and all salts haloid salts, with either simple or compound radicals.

This simple and beautiful theory is not by any means new; it was suggested by Davy, who proposed to consider hydrogen as the acidifying principle in the common acids, and lately revived and very happily illustrated by Liebig. It is supported by a good deal of evidence derived from various sources, and has received great help from a series of exceedingly interesting experiments on the electrolysis of saline solutions, by the late Professor Daniell.* The necessity of creating a great number of non-soluble compounds is often urged as an objection to the new view; but the same objection applies to the old mode of considering the subject. Hyposulphurous acid and hyposulphuric acid are unknown in their free states. The compounds S_2O_2 and S_2O_4 are as hypothetical as the substances S_2O_3 and S_2O_6 . The same remark applies to almost every one of the organic acids; and, what is well worthy of notice, those acids which, like sulphuric, phosphoric, and carbonic acids, may be obtained in a separate state, are *destitute of all acid properties so long as the anhydrous condition is retained.*

The general application of the binary theory still presents a few difficulties. But it is very probable that the progress of discovery will ultimately lead to its universal adoption, which would greatly simplify many parts of the science. One great inconvenience will be the change of nomenclature involved.

CLASSIFICATION OF METALS.

1.

Metals of the Alkalis.

Potassium	Lithium
Sodium	Ammonium.†

2.

Metals of the Alkaline Earths.

Barium	Calcium
Strontium	Magnesium.

* See Daniell's Introduction to Chemical Philosophy, 2nd edition, p. 533.

† This hypothetical substance is merely placed with the metals for the sake of convenience, as will be apparent in the sequel.

3.

Metals of the Earths Proper.

Aluminum	Norium
Beryllium	Thorium
Yttrium	Cerium
Erbium	Lanthanum
Terbium	Didymium.
Zirconium	

4.

Oxidable Metals Proper, whose Oxides form powerful Bases.

Manganese	Zinc
Iron	Cadmium
Chromium	Bismuth
Nickel	Lead
Cobalt	Uranium.
Copper	

5.

Oxidable Metals Proper, whose Oxides form weak Bases, or Acids.

Vanadium	Titanium
Tungsten	Tin
Molybdenum	Antimony
Tantalum	Arsenic
Niobium	Tellurium
Pelopium	Osmium.

6.

Metals Proper, whose Oxides are reduced by Heat ; Noble Metals.

Gold	Palladium
Mercury	Iridium
Silver	Ruthenium
Platinum	Rhodium.

SECTION I.

METALS OF THE ALKALIS.

POTASSIUM.

POTASSIUM was discovered by Sir H. Davy in 1807, who obtained it in very small quantity by exposing a piece of moistened hydrate of potassa to the action of a powerful voltaic battery, the alkali being placed between a pair of platinum plates put into connection with the apparatus. Processes have since been devised for obtaining this curious metal in almost any quantity that can be desired.

An intimate mixture of carbonate of potassa and charcoal is prepared by calcining, in a covered iron pot, the crude tartar of commerce; when cold, it is rubbed to powder, mixed with one-tenth part of charcoal in small lumps, and quickly transferred to a retort of stout hammered iron; the latter may be one of the iron bottles in which mercury is imported, a short and somewhat wide iron tube having been fitted to the aperture. The retort is placed upon its side, in a furnace so constructed that the flame of a very strong fire, fed with dry wood, may wrap round it, and maintain every part at a uniform degree of heat, approaching to whiteness. A copper receiver, divided in the centre by a diaphragm, is connected with the iron pipe, and kept cool by the application of ice, while the receiver itself is partly filled with naphtha or rock-oil, in which the potassium is to be preserved. Arrangements being thus completed, the fire is gradually raised until the requisite temperature is reached, when decomposition of the alkali by the charcoal commences, carbonic oxide gas is abundantly disengaged, and potassium distils over, and falls in large melted drops into the liquid. The pieces of charcoal are introduced for the purpose of absorbing the melted carbonate of potassa, and preventing its separation from the finely-divided carbonaceous matter.

If the potassium be wanted absolutely pure, it must be afterwards re-distilled in an iron retort, into which some naphtha has been put, that its vapour may expel the air, and prevent oxidation of the metal.

Potassium is a brilliant white metal, with a high degree of lustre; at the common temperature of the air it is soft, and may be easily cut with a knife, but at 32° (0°C) it is brittle and crystalline. It melts completely at 136° ($57^{\circ}\cdot77\text{C}$), and distils at a low red heat. The density of this remarkable metal is only 0.865, water being unity.

Exposed to the air, potassium oxidizes instantly, a tarnish covering the surface of the metal, which quickly thickens to a crust of caustic

potassa. Thrown upon water, it takes fire spontaneously, and burns with a beautiful purple flame, yielding an alkaline solution. When brought into contact with a little water in a jar standing over mercury, the liquid is decomposed with great energy, and hydrogen liberated. Potassium is always preserved under the surface of naphtha.

The equivalent of potassium (kalium) is 39; and its symbol, K.

There are two compounds of this metal with oxygen,—potassa and teroxide of potassium.

POTASSA, POTASH, or PROTOXIDE OF POTASSIUM, KO, is produced when potassium is heated in dry air; the metal burns, and becomes entirely converted into a volatile, fusible, white substance, which is anhydrous potassa. Moistened with water, it evolves great heat, and forms the hydrate.

The hydrate of potassa, KO.HO, is a very important substance, and one of great practical utility. It is always prepared for use by decomposing the carbonate by hydrate of lime, as in the following process, which is very convenient:—10 parts of carbonate of potassa are dissolved in 100 parts of water, and heated to ebullition in a clean untinned iron, or still better, silver vessel; 8 parts of good quicklime are meanwhile slaked in a covered basin, and the resulting hydrate of lime added, little by little, to the boiling solution of carbonate, with frequent stirring. When all the lime has been introduced, the mixture is suffered to boil for a few minutes, and then removed from the fire, and covered up. In the course of a very short time, the solution will have become quite clear, and fit for decantation, the carbonate of lime, with the excess of hydrate, settling down as a heavy, sandy precipitate. The solution should not effervesce with acids.

It is essential in this process that the solution of carbonate of potassa be dilute, otherwise the decomposition becomes imperfect; the proportion of lime recommended is much greater than that required by theory, but it is always proper to have an excess.

The solution of hydrate, or, as it is commonly called, caustic potassa, may be concentrated by quick evaporation in the iron or silver vessel to any desired extent: when heated until vapour of water ceases to be disengaged, and then suffered to cool, it furnishes the solid hydrate, containing single equivalents of potassa and water.

Pure hydrate of potassa is a white solid substance, very deliquescent and soluble in water; alcohol also dissolves it freely, which is the case with comparatively few of the compounds of this base: the solid hydrate of commerce, which is very impure, may thus be purified. The solution of this substance possesses, in the very highest degree, the properties termed alkaline: it restores the blue colour to litmus which has been reddened by an acid; neutralizes completely the most powerful acids; has a nauseous and peculiar taste, and dissolves the skiu, and many other organic matters, when the latter are subjected

to its action. It is frequently used by surgeons as a cauter, being moulded into little sticks for that purpose.

Hydrate of potassa, both in the solid state and in solution, rapidly absorbs carbonic acid from the air; hence it must be kept in closely-stopped bottles. When imperfectly prepared, or partially altered by exposure, it effervesces with an acid.

The water in this compound cannot be displaced by heat, the hydrate volatilizing as such at a very high temperature.

The following table of the densities and value in real alkali of different solutions of hydrate of potassa is given on the authority of Dr. Dalton:—

Density.	Percentage of real alkali.	Density.	Percentage of real alkali.
1.68 . . .	51.2	1.33 . . .	26.3
1.60 . . .	46.7	1.28 . . .	23.4
1.52 . . .	42.9	1.23 . . .	19.5
1.47 . . .	39.6	1.19 . . .	16.2
1.44 . . .	36.8	1.15 . . .	13.0
1.42 . . .	34.4	1.11 . . .	9.5
1.39 . . .	32.4	1.06 . . .	4.7
1.36 . . .	29.4		

TEROXIDE OF POTASSIUM, KO_3 .—This is an orange-yellow fusible substance, generated when potassium is burned in excess of dry oxygen gas, and also formed, to a small extent, when hydrate of potassa is long exposed, in a melted state, to the air. When nitre is decomposed by a strong heat, peroxide of potassium is also produced. It is decomposed by water into potassa, which unites with the latter, and into oxygen gas.

CARBONATE OF POTASSA, $\text{KO}, \text{CO}_2 + 2\text{HO}$.—Salts of potassa containing a vegetable acid are of constant occurrence in plants, where they perform important, but not yet perfectly understood, functions in the economy of those beings. The potassa is derived from the soil, which, when capable of supporting vegetable life, always contains that substance. When plants are burned, the organic acids are destroyed, and the potassa left in the state of carbonate.

It is by these indirect means that carbonate, and, in fact, nearly all the salts of potassa, are obtained: the great natural depository of the alkali is the felspar of granitic and other unstratified rocks, where it is combined with silica, and in an insoluble state. Its extraction thence is attended with too many difficulties to be attempted on the large scale; but when these rocks disintegrate into soils, and the alkali acquires solubility, it is gradually taken up by plants, and accumulates in their substance in a condition highly favourable to its subsequent applications.

Potassa-salts are always most abundant in the green and tender parts of plants, as may be expected, since from these evaporation of

nearly pure water takes place to a large extent; the solid timber of forest trees contains comparatively little.

In preparing the salt on an extensive scale, the ashes are subjected to a process called *lixivation*: they are put into a large cask or tun, having an aperture near the bottom, stopped by a plug, and a quantity of water is added. After some hours the liquid is drawn off, and more water added, that the whole of the soluble matter may be removed. The weakest solutions are poured upon fresh quantities of ash, in place of water. The solutions are then evaporated to dryness, and the residue calcined, to remove a little brown organic matter; the product is the crude potash or *pearlash* of commerce, of which very large quantities are obtained from Russia and America.

This salt is very impure; it contains silicate and sulphate of potassa, chloride of potassium, &c.

The purified carbonate of potassa of pharmacy is prepared from the crude article by adding an equal weight of cold water, agitating, and filtering; most of the foreign salts are, from their inferior degree of solubility, left behind. The solution is then boiled down to a very small bulk, and suffered to cool, when the carbonate separates in small crystals containing 2 equiv. of water, which are drained from the mother-liquor, and then dried in a stove.

A still purer salt may be obtained by exposing to a red-heat purified cream of tartar (acid tartrate of potassa), and separating the carbonate by solution in water and crystallization, or evaporation to dryness.

Carbonate of potassa is extremely deliquescent, and soluble in less than its own weight of water; the solution is highly alkaline to test paper. It is insoluble in alcohol. By heat the water of crystallization is driven off, and by a temperature of full ignition the salt is fused, but not otherwise changed. This substance is largely used in the arts, and is a compound of great importance.

BICARBONATE OF POTASSA, $\text{KO}, \text{CO}_2 + \text{HO}, \text{CO}_2$.—When a stream of carbonic acid gas is passed through a cold solution of carbonate of potassa, the gas is rapidly absorbed, and a white, crystalline, and less soluble substance separated, which is the new compound. It is collected, pressed, re-dissolved in warm water, and the solution left to crystallize.

Bicarbonate of potassa is much less soluble than simple carbonate; it requires for that purpose 4 parts of cold water. The solution is nearly neutral to test-paper, and has a much milder taste than the preceding salt. When boiled, carbonic acid is disengaged. The crystals, which are large and beautiful, derive their form from a right rhombic prism; they are decomposed by heat, water and carbonic acid being extricated, and simple carbonate left behind.

NITRATE OF POTASSA; **NITRE**; **SALTPETRE**, KO, NO_3 .—This important compound is a natural product, being disengaged by a kind

of efflorescence from the surface of the soil in certain dry and hot countries. It may also be produced by artificial means, namely, by the oxidation of ammonia in presence of a powerful base.

In France, large quantities of artificial nitre are prepared by mixing animal refuse of all kinds with old mortar or hydrate of lime and earth, and placing the mixture in heaps, protected from the rain by a roof, but freely exposed to the air. From time to time the heaps are watered with putrid urine, and the mass turned over, to expose fresh surfaces to the air. When much salt has been formed, the mixture is lixiviated, and the solution, which contains nitrate of lime, mixed with carbonate of potassa; carbonate of lime is formed, and the nitric acid transferred to the alkali. The filtered solution is then made to crystallize, and the crystals purified by re-solution and crystallization several times repeated.

All the nitre used in this country comes from the East Indies; it is dissolved in water, a little carbonate of potassa added to precipitate lime, and then the salt purified as above.

Nitrate of potassa crystallizes in anhydrous six-sided prisms, with dihedral summits; it is soluble in 7 parts of water at 60° ($15^{\circ}5C$), and in its own weight of boiling water. Its taste is saline and cooling, and it is without action on vegetable colours. At a temperature below redness it melts, and by a strong heat is completely decomposed.

When thrown on the surface of many metals in a state of fusion, or when mixed with combustible matter and heated, rapid oxidation ensues, at the expense of the oxygen of the nitric acid. Examples of such mixtures are found in common gunpowder, and in nearly all pyrotechnic compositions, which burn in this manner independently of the oxygen of the air, and even under water. Gunpowder is made by very intimately mixing together nitrate of potassa, charecoal, and sulphur, in proportions which approach 1 eq. nitre, 3 eq. carbon, and 1 eq. sulphur.

These quantities give, reckoned to 100 parts, and compared with the proportions used in the manufacture of the English government powder,* the following results:—

	Theory.	Proportions in practice.
Nitrate of potassa	74.8	75
Charecoal	13.3	15
Sulphur	11.9	10
	<hr/> 100.	<hr/> 100

The nitre is rendered very pure by the means already mentioned, freed from water by fusion, and ground to fine powder; the sulphur and charcoal, the latter being made from light wood, as dogwood or

* Dr. McCulloch, Ency. Brit.

elder, are also finely ground, after which the materials are weighed out, moistened with water, and thoroughly mixed, by grinding under an edge-mill. The mass is then subjected to great pressure, and the mill-cake thus produced broken in pieces, and placed in sieves made of perforated vellum, moved by machinery, each containing, in addition, a round piece of heavy wood. The grains of powder broken off by attrition fall through the holes in the skin, and are easily separated from the dust by sifting. The powder is, lastly, dried by exposure to steam-heat, and sometimes glazed or polished by agitation in a kind of cask mounted on an axis.

When gunpowder is fired, the oxygen of the nitrate of potassa is transferred to the carbon, forming carbonic acid; the sulphur combines with the potassium, and the nitrogen is set free. The large volume of gas thus produced, and still farther expanded by the very exalted temperature, sufficiently accounts for the explosive effects.

SULPHATE OF POTASSA, KO, SO_3 .—The acid residue left in the retort when nitric acid is prepared is dissolved in water, and neutralized with crude carbonate of potassa. The solution furnishes, on cooling, hard transparent crystals of the neutral sulphate, which may be re-dissolved in boiling water, and re-crystallized.

Sulphate of potassa is soluble in about 10 parts of cold, and in a much smaller quantity of boiling water; it has a bitter taste, and is neutral to test-paper. The crystals much resemble those of quartz in figure and appearance; they are anhydrous, and deerepitate when suddenly heated, which is often the case with salts containing no water of crystallization. They are quite insoluble in alcohol.

BISULPHATE OF POTASSA, $\text{KO}, \text{SO}_3 + \text{HO}, \text{SO}_3$.—The neutral sulphate in powder is mixed with half its weight of oil of vitriol, and the whole evaporated quite to dryness in a platinum vessel, placed under a chimney; the fused salt is dissolved in hot water, and left to crystallize. The crystals have the figure of flattened rhombic prisms, and are much more soluble than the neutral salt, requiring only twice their weight of water at 60° ($15^\circ\cdot5\text{C}$), and less than half that quantity at 212° (100°C). The solution has a sour taste and strongly acid reaction.

BISULPHATE OF POTASSA, ANHYDROUS, $\text{KO}, 2\text{SO}_3$.—Equal weights of neutral sulphate of potassa and oil of vitriol are dissolved in a small quantity of warm distilled water, and set aside to cool. The anhydrous sulphate crystallizes out in long delicate needles, which if left several days in the mother-liquor disappear, and give place to crystals of the ordinary hydrated bisulphate above described. This salt is decomposed by a large quantity of water.*

SESQUISULPHATE OF POTASSA, $2(\text{KO}, \text{SO}_3) + \text{HO}, \text{SO}_3$.—A salt, crystallizing in fine needles resembling those of asbestos, and having the composition stated, was obtained by Mr. Phillips from the nitric

* Jacquelin, *Ann. Chim. et Phys.* vol. vii. p. 311.

acid residue. M. Jacquelin was unsuccessful in his attempts to reproduce this compound.

CHLORATE OF POTASSA, KO, ClO_3 .—The theory of the production of chloric acid, by the action of chlorine gas on a solution of caustic potassa, has been already described (p. 157).

Chlorine gas is conducted by a wide tube into a strong and warm solution of carbonate of potassa, until absorption of the gas ceases. The liquid is, if necessary, evaporated, and then allowed to cool, in order that the slightly-soluble chlorate may crystallize out. The mother-liquor affords a second crop of crystals, but they are much more contaminated by chloride of potassium. It may be purified by one or two re-crystallizations.

Chlorate of potassa is soluble in about 20 parts of cold and 2 of boiling water; the crystals are anhydrous, flat, and tabular; in taste it somewhat resembles nitre. Heated, it disengages oxygen gas from both acid and base, and leaves chloride of potassium. By arresting the decomposition when the evolution of gas begins, and re-dissolving the salt, perchlorate of potassa and chloride of potassium may be obtained.

This salt deflagrates violently with combustible matter, explosion often occurring by friction or blows. When about one grain weight of chlorate and an equal quantity of sulphur are rubbed in a mortar, the mixture explodes with a loud report; hence it cannot be used in the preparation of gunpowder instead of nitrate of potassa. Chlorate of potassa is now a large article of commerce, being employed, together with phosphorus, in making instantaneous light matches.

PERCHLORATE OF POTASSA, KO, ClO_4 .—This has been already noticed under the head of perchloric acid. It is best prepared by projecting powdered chlorate of potassa into warm nitric acid, when the chloric acid is resolved into perchloric acid, chlorine and oxygen gases. The salt is separated by crystallization from the nitrate. Perchlorate of potassa is a very feebly-soluble salt; it requires 55 parts of cold water, but is more freely taken up at a boiling heat. The crystals are small, and have the figure of an octahedron, with square base. It is decomposed by heat, in the same manner as chlorate of potassa.

SULPHIDES OF POTASSIUM.—There are not less than five or six distinct compounds of potassium and sulphur, of which, however, only three are of sufficient importance to be noticed here; these are the compounds, containing KS , KS_3 , and KS_5 .


Simple or protosulphide of potassium is formed by directly combining the metal with sulphur, or by reducing sulphate of potassa at a red-heat by hydrogen or charcoal powder. Another method is to take a strong solution of hydrate of potassa, and after dividing it into two equal portions, saturate the one with sulphuretted hydrogen gas, and then add the remainder. The whole is then evaporated to dryness in a retort, and the residue fused.

The protosulphide is a crystalline cinnabar-red mass, very soluble in water. The solution has an exceedingly offensive and caustic taste, and is decomposed by acids, even carbonic acid, with evolution of sulphuretted hydrogen, and formation of a salt of the acid used. This compound is a strong sulphur-base, and unites with the sulphides of hydrogen, carbon, arsenic, &c., forming crystallizable saline compounds. One of these, $KS + HS$, is produced when hydrate of potassa is saturated with sulphuretted hydrogen, as before mentioned.


The higher sulphides are obtained by fusing the protosulphide with different proportions of sulphur. They are soluble in water, and decomposed by acids, in the same manner as the foregoing compound, with this addition, that the excess of sulphur is precipitated as a fine white powder.

Hepar sulphuris is a name given to a brownish substance, sometimes used in medicine, made by fusing together different proportions of carbonate of potassa and sulphur. It is a variable mixture of the two higher sulphides with hyposulphite and sulphate of potassa.

When equal parts of sulphur and dry carbonate of potassa are melted together at a temperature not exceeding 482° ($250^{\circ}C$), the decomposition of the salt is quite complete, and all the carbonic acid is expelled. The fused mass dissolves in water, with the exception of a little mechanically-mixed sulphur, with dark-brown colour, and the solution is found to contain nothing besides pentasulphide of potassium and hyposulphite of potassa.



When the mixture has been exposed to a temperature approaching that of ignition, it is found, on the contrary, to contain sulphate of potassa, arising from the decomposition of the hyposulphite which then occurs.



From both these mixtures the pentasulphide of potassium may be extracted by alcohol, in which it dissolves.

When the carbouate is fused with half its weight of sulphur only, then the tersulphide, KS_3 , is produced instead of that above indicated; 3 eq. of potassa and 8 eq. of sulphur containing the elements of 2 eq. sulphide and 1 eq. hyposulphite.

The effects described happen in the same manner when hydrate of potassa is substituted for the carbonate; and, also, when a solution of the hydrate is boiled with sulphur, a mixture of sulphide and hyposulphite always results.


CHLORIDE OF POTASSIUM, KCl .—This salt is obtained in large quantity in the manufacture of chlorate of potassa; it is easily purified from any portions of the latter by exposure to a dull red-heat. It is also contained in kelp, and is separated for the use of the alum-maker.

Chloride of potassium closely resembles common salt in appearance, assuming, like that substance, the cubic form of crystallization. The crystals dissolve in three parts of cold, and in a much less quantity of boiling water; they are anhydrous, have a simple saline taste, with slight bitterness, and fuse when exposed to a red-heat. Chloride of potassium is volatilized by a very high temperature.

IODIDE OF POTASSIUM, KI .—There are two different methods of preparing this important medicinal compound.

(1.) When iodine is added to a strong solution of caustic potassa free from carbonate, it is dissolved in large quantity, forming a colourless solution containing iodide of potassium and iodate of potassa; the reaction is the same as in the analogous case with chlorine. When the solution begins to be permanently coloured by the iodine, it is evaporated to dryness, and cautiously heated to redness; by which the iodate of potassa is entirely converted into iodide of potassium. The mass is then dissolved in water, and, after filtration, made to crystallize.

(2.) Iodine, water, and iron-filings or scraps of zinc, are placed in a warm situation until the combination is complete, and the solution colourless. The resulting iodide of iron or zinc is then filtered, and exactly decomposed with solution of pure carbonate of potassa, great care being taken to avoid excess of the latter. Iodide of potassium and carbonate of protoxide of iron, or zinc, are obtained; the former is separated by filtration, and evaporated until the solution is sufficiently concentrated to crystallize on cooling, the washings of the filter being added to avoid loss.



The second method is on the whole to be preferred.

Iodide of potassium crystallizes in cubes, which are often, from some unexplained cause, milk-white and opaque; they are anhydrous, and fuse readily when heated. The salt is very soluble in water, but not deliquescent, when pure, in a moderately-dry atmosphere; it is dissolved by alcohol.

Solution of iodide of potassium, like those of all the soluble iodides, dissolves a large quantity of free iodine, forming a deep-brown liquid, not decomposed by water.

BROMIDE OF POTASSIUM, KBr.—This compound may be obtained by processes exactly similar to those just described, substituting bromine for the iodine. It is a colourless and very soluble salt, quite indistinguishable in appearance and general characters from the iodide.

The salts of potassa are colourless, when not associated with a coloured metallic oxide or acid. They are all more or less soluble in water, and may be distinguished by the following characters:—

(1.) Solution of tartaric acid added to a moderately-strong solution of a potassa-salt, gives, after some time, a white, crystalline precipitate of cream of tartar; the effect is greatly promoted by strong agitation.

(2.) Solution of bichloride of platinum, with a little hydrochloric acid, if necessary, gives, under similar circumstances, a crystalline yellow precipitate, which is a double salt of bichloride of platinum and chloride of potassium. Both this compound and cream of tartar are, however, soluble in about 60 parts of cold water. An addition of alcohol increases the delicacy of both tests.

(3.) Perchloric acid, and hydrofluosilicic acid, give rise to slightly-soluble white precipitates when added to a potassa-salt.

(4.) Salts of potassa usually colour the outer blowpipe flame purple or violet; this reaction is clearly perceptible only when the potassa-salts are pure.

SODIUM.

This metal was obtained by Davy very shortly after the discovery of potassium, and by similar means. It may be prepared in large quantity by decomposing carbonate of soda by charcoal at a high temperature.

Six parts of anhydrous carbonate of soda are dissolved in a little hot water, and mixed with two parts of finely-powdered charcoal and one part of charcoal in lumps. The whole is then evaporated to dryness, transferred to the iron retort before described, and heated in the same manner to whiteness. A receiver containing rock-oil is adapted to the tube, and the whole operation carried on in the same way as when potassium is made. The process, when well conducted, is easier and more certain than that of making potassium.

Sodium is a silver-white metal, greatly resembling potassium in every respect; it is soft at common temperatures, melts at 194° (90°C), and oxidizes very rapidly in the air. Its specific gravity is 0.972.

Placed upon the surface of cold water, sodium decomposes that liquid with great violence, but seldom takes fire unless the motion of the fragment be restrained, and its rapid cooling diminished, by adding gum or starch to the water. With hot water it takes fire at once, burning with a bright-yellow flame, and giving rise to a solution of soda.

The equivalent of sodium is 23, and its symbol Na (Natrium).

There are two well-defined compounds of sodium and oxygen; the protoxide, anhydrous soda, NaO, and the binoxide, NaO₂, or perhaps, teroxide NaO₃; they are formed by burning sodium in air or oxygen gas, and resemble in every respect the corresponding compounds of potassium.

HYDRATE OF SODA, NaO, HO.—This substance is prepared in practice by decomposing a somewhat dilute solution of carbonate of soda by hydrate of lime; the description of the process employed in the case of hydrate of potassa, and the precautions necessary, apply word for word to that of soda.

The solid hydrate is a white, fusible substance, very similar in properties to hydrate of potassa. It is deliquescent, but dries up again after a time in consequence of the absorption of carbonic acid. The solution is highly alkaline, and a powerful solvent for animal matter: it is used in large quantity for making soap.

The strength of a solution of caustic soda may be roughly determined from a knowledge of its density, by the aid of the following table drawn up by Dr. Dalton.

TABLE OF PERCENTAGE OF SODA IN SOLUTIONS OF DIFFERENT DENSITY.

Density.	Percentage of real soda.	Density.	Percentage of real soda.
2·00	77·8	1·40	29·0
1·85	63·6	1·36	26·0
1·72	53·8	1·32	23·0
1·63	46·6	1·29	19·0
1·55	41·2	1·23	16·0
1·50	36·8	1·18	13·0
1·47	34·0	1·12	9·0
1·44	31·0	1·06	4·7



CARBONATE OF SODA, NaO, CO₂ + 10HO.—Carbonate of soda was once exclusively obtained from the ashes of sea-weeds, and of plants, such as the *Salsola soda*, which grew by the sea-side, or, being cultivated in suitable localities for the purpose, were afterwards subjected to incineration. The *barilla*, yet employed to a small extent in soap-making, is thus produced in several places on the coast of Spain, as Alicante, Carthageua, &c. That made in Brittany is called *varec*.

Carbonate of soda is now manufactured on a stupendous scale from common salt, or rather from sulphate of soda, by a process of which the following is an outline :—

A charge of 600lbs. of common salt* is placed upon the hearth of a well-heated reverberatory furnace, and an equal weight of sulphuric acid of sp. gr. 1·6 poured upon it through an opening in the roof, and thoroughly mingled with the salt; hydrochloric acid gas is disengaged, which is either allowed to escape by the chimney, or condensed by suitable apparatus, and the salt is converted into sulphate of soda. This part of the process takes for completion about four hours, and requires much care and skill.

The sulphate is next reduced to powder, and mixed with an equal weight of chalk or limestone, and half as much small coal, both ground or crushed. The mixture is thrown into a reverberatory furnace, and heated to fusion; with constant stirring; 2 cwts. are about the quantity operated on at once. When the decomposition is judged complete, the melted matter is raked from the furnace into an iron trough, where it is allowed to cool. When cold, it is broken up into little pieces, and lixiviated with cold or tepid water. The solution is evaporated to dryness, and the salt calcined with a little saw-dust in a suitable furnace. The product is the soda-ash, or British alkali of commerce, which, when of good quality, contains from 48 to 52 per cent. of pure soda, partly in the state of carbonate, and partly as hydrate, the remainder being chiefly sulphate of soda and common salt, with occasional traces of sulphite or hyposulphite, and also cyanide of sodium. By dissolving soda-ash in hot water, filtering the solution, and then allowing it to cool slowly, the carbonate is deposited in large transparent crystals.

The reaction which takes place in the calcination of the sulphate with chalk and coal-dust seems to consist, first, in the conversion of the sulphate of soda into sulphide of sodium by the aid of the combustible matter, and, secondly, in the double interchange of elements between that substance and the carbonate of lime.



The sulphide of calcium combines with another proportion of lime to form a peculiar compound, which is insoluble in cold or slightly warm water.

* Graham, Elements, p. 558, vol. i.

Other processes have been proposed, and even carried into execution, but the above, which was originally proposed by M. Leblanc, is found most advantageous.

The ordinary crystals of carbonate of soda contain ten equivalents of water, but by particular management the same salt may be had with fifteen, nine, seven, equivalents, or sometimes with only one. The common form of the crystal is derived from an oblique rhombic prism; they effloresce in dry air, and crumble to a white powder. Heated, they fuse in their water of crystallization; when the latter has been expelled, and the dry salt exposed to a full red-heat, it melts without undergoing change. The common crystals dissolve in two parts of cold, and in less than their own weight of boiling water; the solution has a strong, disagreeable, alkaline taste, and a powerfully alkaline reaction.

BICARBONATE OF SODA, $\text{NaO}, \text{CO}_2 + \text{HO}, \text{CO}_2$.—This salt is prepared by passing carbonic acid gas into a cold solution of the neutral carbonate, or by placing the crystals in an atmosphere of the gas, which is rapidly absorbed, while the crystals lose the greater part of their water, and pass into the new compound.

Bicarbonate of soda, prepared by either process, is a crystalline white powder, which cannot be re-dissolved in warm water without partial decomposition. It requires 10 parts of water at 60° (15°C) for solution; the liquid is feebly alkaline to test-paper, and has a much milder taste than that of the simple carbonate. It does not precipitate a solution of magnesia. By exposure to heat, the salt is converted into neutral carbonate.

A sesquicarbonate of soda containing $2\text{NaO}, 3\text{CO}_2 + 4\text{HO}$ has been described by Mr. Phillips; like the sesquicarbonate of potassa, it is formed at pleasure only with difficulty. This salt occurs native on the banks of the soda-lakes of Sokeua in Africa, whence it is exported under the name of *trona*.

Alkalimetry; Analysis of Hydrates and Carbonates of the Alkalis.—The general principle of these operations consists in ascertaining the quantity of real alkali in a given weight of the substance examined, by finding how much of the latter is required to neutralize a known quantity of an acid, as sulphuric acid.

The first step is the preparation of a stock of dilute sulphuric acid of determinate strength; containing, for example, 100 grains of real acid in every 1,000 grain-measures of liquid: * a large quantity, as a gallon or more, may be prepared at once by the following means. The oil of vitriol is first examined; if it be good and of the sp. gr. 1.85 or

* The capacity of 1,000 grains of distilled water at 60° (15°C). The grain-measure of water is often found a very convenient and useful unit of volume in chemical researches. Vessels graduated on this plan bear simple comparison with the imperial gallon and pint, and frequently also enable the operator to measure out a liquid of known density instead of weighing it.

near it, the process is extremely simple; every 49 grains of the liquid acid contains 40 grains of absolute acid; the quantity of the latter required in the gallon, or 70,000 grain-measures of dilute acid, will be of course 7,000 grains. This is equivalent to 8·571 grains of the oil of vitriol, for

$$\begin{array}{ccccccc} \text{Real acid.} & & \text{Oil of vitriol.} & & & & \\ 40 & : & 49 & = & 7000 & : & 8575. \end{array}$$

All that is required to be done, therefore, is to weigh out 8,575 grains of oil of vitriol, and dilute it with so much water, *that the mixture, when cold, shall measure exactly one gallon.*

It very often happens, however, that the oil of vitriol to be used is not so strong as that above mentioned; in which case it is necessary to discover its real strength, as estimated from its saturating power. Pure anhydrous carbonate of soda is prepared by heating to dull redness, without fusion, the bicarbonate; of this salt 53 grains, or 1 eq., correspond to 31 grains of soda, and neutralize 40 grains of real sulphuric acid.

A convenient quantity is carefully weighed out, and added, little by little, to a known weight, say 100 grains, of the oil of vitriol to be tried, diluted with four or five times its weight of water, until the liquid, after warming, becomes quite neutral to test-paper. By weighing again the residue of the carbonate, it is at once known how much of the latter has been employed; the amount of real acid in the hundred parts of oil of vitriol is then easily calculated. Thus, suppose the quantity of carbonate of soda used to be 105 grains; then,


$$\begin{array}{ccccccc} \text{Carb. soda.} & & \text{Sulph. acid.} & & & & \\ 53 & : & 40 & = & 105 & : & 79\cdot24; \end{array}$$

79·24 grains of real acid are consequently contained in 100 grains of oil of vitriol; consequently,

$$79\cdot24 : 100 = 7000 : 8833\cdot82;$$

the weight in grains of the oil of vitriol required to make one gallon of the dilute acid.

The "alkalimeter" is next to be constructed. This is merely a 1000-grain measure, made of a piece of even cylindrical glass tube, about 15 inches long and 0·6 inch internal diameter, closed at one extremity, and moulded into a spout or lip at the other. A strip of paper is pasted on the tube and suffered to dry, after which the instrument is graduated



by counterpoising it in a nearly-upright position in the pan of a balance of moderate delicacy, and weighing into it, in succession, 100, 200, 300, &c., grains of distilled water at 60° ($15^{\circ}\cdot5\text{C}$), until the whole quantity, amounting to 1,000 grains, has been introduced, the level of the water in the tube being, after each addition, carefully marked with a pen upon the strip of paper, while the tube is held quite upright, and the mark made between the top and bottom of the curve formed by the surface of the water. The smaller divisions of the scale, of 10 grains each, may then be made by dividing by compasses each of the spaces into ten equal parts. When the graduation is complete, and the operator is satisfied with its accuracy, the marks may be transferred to the tube itself by a sharp file, and the paper removed by a little warm water. The numbers are scratched on the glass with the hard end of the same file, or with a diamond. When this alkalimeter is used with the dilute acid described, every division of the glass will correspond to one grain of real sulphuric acid.

Let it be required, by way of example, to test the commercial value of soda-ash, or to examine it for scientific purposes: 50 grains of the sample are weighed out, dissolved in a little warm water, and, if necessary, the solution filtered; the alkalimeter is then filled to the top of the scale with the test-acid, and the latter poured from it into the alkaline solution, which is tried from time to time with red litmus-paper. The addition of acid must of course be made very cautiously as neutralization advances. When the solution, after being heated a few minutes, no longer affects either blue or red test-paper, the measure of liquid employed is read off, and the quantity of soda present in the state of carbonate or hydrate in the 50 grains of salt found by the rule of proportion. Suppose 33 measures, consequently 33 grains of acid, have been taken; then

Sulph. acid.		Soda.				
40	:	31	=	33	:	25.57;

the sample contains, therefore, 51.2 per cent. of available alkali.

It will be easily seen that the principle of the process described admits of very wide application, and that, by the aid of the alkalimeter and carefully-prepared test-acid, the hydrates and carbonates of potassa, soda, and ammonia, both in the solid state and in solution, can be examined with great ease and accuracy. The quantity of real alkali in a solution of caustic ammonia may thus be determined, the equivalent of that substance, and the amount of acid required to neutralize a known weight, being inserted as the second and third terms in the above rule-of-three statement. The same acid answers for all.

The alkalimeter represented in fig. 138, is the simplest form of this instrument. The pouring out of minute quantities is greatly facilitated by providing the measure with a narrow dropping tube,

fig. 139, the lower extremity of which is soldered into the measure, whilst the upper one is bent outward and sharply cut off. This kind of burette, which is known as Gay-Lussac's, is chiefly used in France.

Fig. 139.




Fig. 140.




Fig. 141.



The liquid may be very conveniently poured from it; but it is rather easily broken, so that its manipulation requires a good deal of care. This defect is greatly obviated in the burette, fig. 140, in which the graduated tube is provided with a spout at the top, there being at the same time an orifice for pouring in the liquid.

A very elegant instrument has lately been contrived by Dr. Mohr of Coblenz. It is a graduated tube, at one end drawn out to a point, to which is attached, by means of a narrow vulcanized caoutchouc tube, a short glass tube, likewise drawn out to a point, fig. 141. There is a small space (about $\frac{1}{4}$ inch) between the two tubes, upon which is fixed a metallic clamp, *a*, represented in its actual dimensions in fig. 142. This clamp shuts off the connection between this graduated cylinder and the small glass tube. But by pressing with the fingers upon the ends, *b b*, of this clamp, it opens, and allows the

Fig. 142.



liquid to flow out of the lower tube. It is evident that by this arrangement the amount of liquid may be regulated with the greatest nicety.

It is often desirable, in the analysis of carbonates, to determine directly the proportion of carbonic acid: the following methods leave nothing to be desired in point of precision:—


A small light glass flask of three or four ounces capacity, with lipped edge, is chosen, and a cork fitted to it. A piece of tube about

Fig. 143.



three inches long is drawn out at one extremity, and fitted, by means of a small cork and a bit of bent tube, to the cork of the flask. This tube is filled with fragments of chloride of calcium, prevented from escaping by a little cotton at either end; the joints are secured by sealing-wax. A short tube, closed at one extremity, and small enough to go into the flask, is also provided, and the apparatus is complete. Fifty grains of the carbonate to be examined are carefully weighed out and introduced into the flask, together with a little water; the small tube is then filled with oil of vitriol, and placed in the flask in a nearly upright position, and leaning against its side in such a manner that the acid does not escape. The cork and chloride of calcium tube are then adjusted, and the whole apparatus accurately counterpoised on the balance. This done, the flask is slightly inclined, so that the oil of vitriol may slowly mix with the other substances and decompose the carbonate, the gas from which escapes in a dry state from the extremity of the tube. When the action has entirely ceased, the liquid is heated until it boils, and the steam begins to condense in the drying-tube; it is then left to cool, and weighed, when the loss indicates the quantity of carbonic acid. The acid must

Fig. 144.



whilst a second tube reaching to the bottom of B establishes a com-

be in excess after the experiment. When carbonate of lime is thus analysed, strong hydrochloric acid must be substituted for the oil of vitriol.

Instead of the above apparatus a neat arrangement may be used which was first suggested by Will and Fresenius. It consists of two small glass flasks, A and B, the latter being somewhat smaller than the former. Both the flasks are provided with a doubly-perforated cork. A tube, open at both ends, but closed at the upper extremity by means of a small quantity of wax, passes through the cork of A to the very bottom of the flask,

munication between the two flasks. The cork of B is provided, moreover, with a short tube *d*. In order to analyse a carbonate, a suitable quantity (fifty grains) is put into A, together with some water. B is half filled with concentrated sulphuric acid, the apparatus tightly fitted and weighed. A small quantity of air is now sucked out of flask B by means of the tube *d*, whereby the air in A is likewise rarefied. Immediately a portion of sulphuric acid ascends in the tube *c*, and flows over into flask A, causing a disengagement of carbonic acid, which escapes at *d*, after having been perfectly dried by passing through the bottle B. This operation is repeated until the whole of the carbonate is decomposed, and the process terminated by opening the wax stopper, and drawing a quantity of air through the apparatus. The apparatus is now re-weighed. The difference of the two weighings expresses the quantity of carbonic acid in the compound analysed.

SULPHATE OF SODA, GLAUBER'S SALT, $\text{NaO}, \text{SO}_3 + 10\text{HO}$.—This is a by-product in several chemical operations; it may of course be prepared directly, if wanted pure, by adding dilute sulphuric acid, to saturation, to a solution of carbonate of soda. It crystallizes in a figure derived from an oblique rhombic prism; the crystals contain 10 eq. of water, are efflorescent, and undergo watery fusion when heated, like those of the carbonate; they are soluble in twice their weight of cold water, and rapidly increase in solubility as the temperature of the liquid rises to $91^{\circ}5$ (33°C), when a maximum is reached, 100 parts of water dissolving 322 parts of the salt. Heated beyond this point, the solubility diminishes, and a portion of sulphate is deposited. A warm saturated solution, evaporated at a high temperature, deposits opaque prismatic crystals, which are anhydrous. This salt has a slightly-bitter taste, and is purgative. Mineral springs sometimes contain it, as at Cheltenham.

BISULPHATE OF SODA, $\text{NaO}, \text{SO}_3 + \text{HO}, \text{SO}_3 + 3\text{HO}$.—This is prepared by adding to 10 parts of anhydrous neutral sulphate, 7 of oil of vitriol, evaporating the whole to dryness, and gently igniting. The bisulphate is very soluble in water, and has an acid reaction. It is not deliquescent. When very strongly heated, the fused salt gives up anhydrous sulphuric acid, and becomes simple sulphate; a change which necessarily supposes the previous formation of a true anhydrous bisulphate, $\text{NaO}, 2\text{SO}_3$.

HYPOSULPHITE OF SODA, $\text{NaO}, \text{S}_2\text{O}_2$.—There are several modes of procuring this salt, which is now used in considerable quantity for photographic purposes. One of the best is to form neutral *sulphite* of soda, by passing a stream of well-washed sulphurous acid gas into a strong solution of carbonate of soda, and then to digest the solution with sulphur at a gentle heat during several days. By careful evaporation at a moderate temperature the salt is obtained in large and regular crystals, which are very soluble in water.

NITRATE OF SODA; CUBIC NITRE, NaO, NO_3 .—Nitrate of soda occurs native, and in enormous quantity, at Atacama in Peru, where

it forms a regular bed, of great extent, covered with clay and alluvial matter. The pure salt commonly crystallizes in rhombohedra, resembling those of calcareous spar, but is probably dimorphous. It is deliquescent, and very soluble in water. Nitrate of soda is employed for making nitric acid, but cannot be used for gunpowder, as the mixture burns too slowly, and becomes damp in the air. It has been lately used with some success in agriculture as a superficial manure or top-dressing.

PHOSPHATES OF SODA; COMMON TRIBASIC PHOSPHATE, 2NaO , HO , $\text{PO}_5 + 24\text{HO}$.—This beautiful salt is prepared by precipitating the acid phosphate of lime obtained by decomposing bone-earth by sulphuric acid, with a slight excess of carbonate of soda. It crystallizes in oblique rhombic prisms, which are efflorescent. The crystals dissolve in 4 parts of cold water, and undergo the aqueous fusion when heated. The salt is bitter and purgative; its solution is alkaline to test-paper. Crystals containing 14 equivalents of water, and having a form different from that above mentioned, have been obtained.

A second tribasic phosphate, sometimes called subphosphate, 3NaO , $\text{PO}_5 + 24\text{HO}$, is obtained by adding a solution of caustic soda to the preceding salt. The crystals are slender six-sided prisms, soluble in 5 parts of cold water. It is decomposed by acids, even carbonic, but suffers no change by heat, except the loss of its water of crystallization. Its solution is strongly alkaline. A third tribasic phosphate often called superphosphate or biphosphate, NaO , 2HO , $\text{PO}_5 + 2\text{HO}$, may be obtained by adding phosphoric acid to the ordinary phosphate, until it ceases to precipitate chloride of barium, and exposing the concentrated solution to cold. The crystals are prismatic, very soluble, and have an acid reaction. When strongly heated, the salt becomes changed into monobasic phosphate of soda.

Tribasic phosphate of soda, ammonia, and water; microcosmic salt, NaO , NH_4O , HO , $\text{PO}_5 + 8\text{HO}$.—Six parts of common phosphate of soda are heated with 2 of water until the whole is liquefied, when 1 part of powdered sal-ammoniac is added; common salt separates, and may be removed by a filter, and from the solution, duly concentrated, the new salt is deposited in prismatic crystals, which may be purified by one or two re-crystallizations. Microcosmic salt is very soluble. When gently heated, it parts with the 8 eq. of water of crystallization, and, at a higher temperature, the water acting as base is expelled, together with the ammonia, and a very fusible compound, metaphosphate of soda, remains, which is valuable as a flux in blowpipe experiments. This salt is said to occur in the urine.

BIBASIC PHOSPHATE OF SODA; PYROPHOSPHATE OF SODA, 2NaO , $\text{PO}_5 + 10\text{HO}$. Prepared by strongly heating common phosphate of soda, dissolving the residue in water, and re-crystallizing. The crystals are very brilliant, permanent in the air, and less soluble than the original phosphate; their solution is alkaline. A bibasic phos-

phate, containing an equivalent of basic water, has been obtained ; it does not, however, crystallize.

MONOBASIC PHOSPHATE OF SODA ; METAPHOSPHATE OF SODA, NaO,PO_5 .—Obtained by heating either the acid tribasic phosphate, or microcosmic salt. It is a transparent glassy substance, fusible at a dull red-heat, deliquescent, and very soluble in water. It refuses to crystallize, but dries up into a gum-like mass.

If this glassy phosphate be cooled very slowly it separates as a beautifully crystalline mass. It may be purified by means of boiling water from the vitreous metaphosphate which will not crystallize. Another metaphosphate has been obtained by adding sulphate of soda to an excess of phosphoric acid, evaporating and heating to upwards of 600° ($315^\circ\cdot5\text{C}$). Possibly these several metaphosphates may be represented by the formulæ NaO,PO_5 ; $2\text{NaO},2\text{PO}_5$; $3\text{NaO},3\text{PO}_5$. (Graham.)

The tribasic phosphates give a bright-yellow precipitate with solution of nitrate of silver ; the bibasic and monobasic phosphates, afford white precipitates with the same substance. The salts of the two latter classes, fused with excess of carbonate of soda, yield the tribasic modification of the acid.

Phosphates intermediate between the monobasic and bibasic phosphates of soda, $3\text{NaO},2\text{PO}_5$ and $6\text{NaO},5\text{PO}_5$.—The first is produced by fusing 100 parts of anhydrous pyrophosphate of soda, and 76·87 parts of metaphosphate of soda. The white crystalline mass is reduced to powder, and quickly exhausted with water. The solution on exposure to the atmosphere yields small plates which are very soluble in water.

The second is produced by fusing 100 parts of pyrophosphate of soda, and 307·5 of metaphosphate ; it crystallizes with more difficulty than the preceding compound.

MM. Fleitmann and Henneberg, the discoverers of these new phosphates, represent the different phosphates thus—

Common phosphate	$6\text{NaO},2\text{PO}_5$
Pyrophosphate	$6\text{NaO},3\text{PO}_5$
New phosphates	$\begin{cases} 6\text{NaO},4\text{PO}_5 \\ 6\text{NaO},5\text{PO}_5 \end{cases}$
Metaphosphate	$6\text{NaO},6\text{PO}_5$

In each of which six equivalents of the base are combined with a different polymeric acid.

BIBORATE OF SODA ; BORAX, $\text{NaO},2\text{BO}_3+10\text{HO}$.—This compound occurs in the waters of certain lakes in Thibet and Persia ; it is imported in a crude state from the East Indies under the name of *tincal*. When purified it constitutes the borax of commerce. Much borax is now, however, manufactured from the native boracic acid of Tuscany. Borax crystallizes in six-sided prisms, which effloresce in dry air, and require 20 parts of cold, and 6 of boiling water for solution.

Exposed to heat, the 10 eq. of water of crystallization are expelled, and at a higher temperature the salt fuses, and assumes a glassy appearance on cooling; in this state it is much used for blowpipe experiments, the metallic oxides dissolving in it to transparent beads, many of which are distinguished by characteristic colours. By particular management, crystals of borax can be obtained with 5 eq. of water; they are very hard, and permanent in the air. Although by constitution an acid salt, borax has an alkaline reaction to test-paper. It is used in the arts for soldering metals, its action consisting in rendering the surfaces to be joined metallic, by dissolving the oxides, and it sometimes enters into the composition of the glaze with which stoneware is covered.

Neutral borate of soda may be formed by fusing together borax and carbonate of soda in equivalent proportions, and then dissolving the mass in water. The crystals are large, and contain $\text{NaO}, \text{BO}_3 + 8\text{HO}$.

SULPHIDE OF SODIUM, NaS .—Prepared in the same manner as the protosulphide of potassium; it separates from a concentrated solution in octahedral crystals, which are rapidly decomposed by contact of air into a mixture of hydrate and hyposulphite of soda. It forms double sulphur-salts with sulphuretted hydrogen, bisulphide of carbon, and other sulphur-acids.

Sulphide of sodium is supposed to enter into the composition of the beautiful pigment *ultramarine*, prepared from the *lapis lazuli*, and which is now imitated by artificial means.*

CHLORIDE OF SODIUM; COMMON SALT, NaCl .—This very important substance is found in many parts of the world in solid beds or irregular strata of immense thickness, as in Cheshire, for example, in Spain, Galicia, and many other localities. An inexhaustible supply exists also in the waters of the ocean, and large quantities are annually obtained from saline springs.

The rock-salt is almost always too impure for use; if no natural brine-spring exist, an artificial one is formed by sinking a shaft into the rock-salt, and, if necessary, introducing water. This when saturated is pumped up, and evaporated more or less rapidly in large iron pans. As the salt separates, it is removed from the bottom of the vessels by means of a scoop, pressed while still moist into moulds, and then transferred to the drying stove. When large crystals are required, as for the coarse-grained *bay-salt* used in curing provisions, the evaporation is slowly conducted. Common salt is apt to be contaminated with chloride of magnesium.

When pure, this substance is not deliquescent in moderately-dry air. It crystallizes in anhydrous cubes, which are often grouped together into pyramids, or steps. It requires about $2\frac{1}{2}$ parts of water at 60° ($15\cdot5\text{C}$) for solution, and its solubility is not sensibly increased

* See Pharmaceutical Journal, ii. 53.

by heat; it dissolves to some extent in spirit of wine, but is nearly insoluble in absolute alcohol. Chloride of sodium fuses at a red-heat, and is volatile at a still higher temperature. The economical uses of common salt are well known.

The *iodide* and *bromide of sodium* much resemble the corresponding potassium-compounds: they crystallize in cubes which are anhydrous, and are very soluble in water.

There is no good precipitant for soda, all the salts being very soluble with the exception of antimoniate of soda, the use of which is attended with difficulties; its presence is often determined by purely negative evidence. The yellow colour imparted by soda-salts to the outer flame of the blowpipe, and to combustible matter, is a character of some importance.

AMMONIUM.

In connection with the compounds of potassium and sodium, those formed by ammonia are most conveniently studied. Ammoniacal salts correspond in every respect in constitution with those of potassa and soda; in all cases the substance which replaces those alkalis is hydrate of ammonia, or, as it is now almost generally considered, the oxide of a hypothetical substance called ammonium, capable of playing the part of a metal, and isomorphous with potassium and sodium. All attempts to isolate this substance have failed, apparently from its tendency to separate into ammonia and hydrogen gas.

When a globule of mercury is placed on a piece of moistened caustic potassa, and connected with the negative side of a voltaic battery of very moderate power, while the circuit is completed through the platinum plate upon which rests the alkali, decomposition of the latter takes place, and an amalgam of potassium is rapidly formed.

If this experiment be now repeated with a piece of sal-ammoniac instead of hydrate of potassa, a soft, solid, metalline mass is also produced, which has been called the *ammoniacal amalgam*, and considered to contain ammonium in combination with mercury. A still simpler method of preparing this extraordinary compound is the following:—A little mercury is put into a test-tube with a grain or two of potassium or sodium, and gentle heat applied; combination ensues, attended by heat and light. When cold, the fluid amalgam is put into a capsule, and covered with a strong solution of sal-ammoniac. The production of an ammoniacal amalgam instantly commences, the mercury increases prodigiously in volume, and becomes quite pasty. The increase of weight is, however, quite trifling: it varies from $\frac{1}{1800}$ th to $\frac{1}{12000}$ part.

Left to itself, the amalgam quickly decomposes into fluid mercury, ammonia, and hydrogen.

It is difficult to offer any opinion concerning the real nature of this compound : something analogous occurs when pure silver is exposed to a very high temperature, much above its melting-point, in contact with air or oxygen gas ; the latter is absorbed in very large quantity, amounting, according to the observation of Gay-Lussac, to 20 times the volume of the silver, and is again disengaged on lessening the heat. The metal loses none of its lustre, and is not sensibly altered in other respects.

The great argument in favour of the existence of ammonium is founded on the perfect comparison which the ammoniacal salts bear with those of the alkaline metals.

The equivalent of ammonium is 18 ; its symbol is NH_4 .

CHLORIDE OF AMMONIUM ; SAL-AMMONIAC, NH_4Cl .—Sal-ammoniac was formerly obtained from Egypt, being extracted by sublimation from the soot of camels' dung ; it is now largely manufactured from the ammoniacal liquid of the gas-works, and from the condensed products of the distillation of bones, and other animal refuse, in the preparation of animal charcoal.

These impure and highly-offensive solutions are treated with a slight excess of hydrochloric acid, by which the free alkali is neutralized, and the carbonate and sulphide decomposed with evolution of carbonic acid and sulphuretted hydrogen gases. The liquid is evaporated to dryness, and the salt carefully heated, to expel or decompose the tarry matter ; it is then purified by sublimation in large iron vessels lined with clay, surmounted with domes of lead.

Sublimed sal-ammoniac has a fibrous texture ; it is tough, and difficult to powder.

When crystallized from water it separates, under favourable circumstances, in distinct cubes or octahedra ; but the crystals are usually small, and aggregated together in rays. It has a sharp saline taste, and is soluble in $2\frac{3}{4}$ parts of cold, in a much smaller quantity of hot water. By heat, it is sublimed without decomposition. The crystals are anhydrous. Chloride of ammonium forms double salts with the chlorides of magnesium, nickel, cobalt, manganese, zinc, and copper.

SULPHATE OF OXIDE OF AMMONIUM ; SULPHATE OF AMMONIA, $\text{NH}_4\text{O}, \text{SO}_3 + \text{HO}$.—Prepared by neutralizing carbonate of ammonia by sulphuric acid, or on a large scale, by adding sulphuric acid in excess to the coal-gas liquor just mentioned, and purifying the product by suitable means. It is soluble in 2 parts of cold water, and crystallizes in long, flattened, six-sided prisms, which lose an equivalent of water when heated. It is entirely decomposed, and driven off by ignition, and, even to a certain extent, by long boiling with water, ammonia being expelled and the liquid rendered acid.

CARBONATES OF AMMONIA.—These compounds have been carefully examined by Professor Rose, of Berlin,* and appear very nume-

* *Annalen der Pharmacie*, xxx. 45.

rous. The *neutral, anhydrous carbonate*, NH_3CO_2 , is prepared by the direct union of carbonic acid with ammoniacal gas, both being carefully dried and cooled. The gases combine in the proportions of one measure of the first to two of the second, and give rise to a pungent, and very volatile compound, which condenses in white flocks. It is very soluble in water. The pungent, transparent, carbonate of ammonia of pharmacy, which is prepared by subliming a mixture of sal-ammoniac and chalk, always contains less base than that required to form a neutral carbonate. Its composition varies a good deal, but in freshly-prepared specimens approaches that of a sesquicarbonate of oxide of ammonium, $2\text{NH}_4\text{O}, 3\text{CO}_2$.—When heated in a retort, the neck of which dips into mercury, it is decomposed, with disengagement of pure carbonic acid, into neutral hydrated carbonate of ammonia, and several other compounds. Exposed to the air at common temperatures, it disengages neutral carbonate of ammonia, loses its pungency, and crumbles down to a soft, white powder, which is a bicarbonate, containing $\text{NH}_4\text{O}, \text{CO}_2 + \text{HO}, \text{CO}_2$. This is a permanent combination, although still volatile. When a strong solution of the commercial sesquicarbonate is made with tepid water, and filtered, warm, into a close vessel, large and regular crystals of bicarbonate, having the above composition, are sometimes deposited after a few days. These are inodorous, quite permanent in the air, and resemble in the closest manner, crystals of bicarbonate of potassa.

NITRATE OF AMMONIA, $\text{NH}_4\text{O}, \text{NO}_3$, is easily prepared by adding carbonate of ammonia to slightly-diluted nitric acid until neutralization has been reached. By slow evaporation at a moderate temperature it crystallizes in six-sided prisms, like those of nitrate of potassa; but, as usually prepared for making nitrous oxide, by quick boiling, until a portion solidifies completely on cooling, it forms a fibrous and indistinct crystalline mass.

Nitrate of ammonia dissolves in two parts of cold water, is but feebly deliquescent, and deflagrates like nitre on contact with heated combustible matter. Its decomposition by heat has been already explained.*

SULPHIDES OF AMMONIUM.—Several of these compounds exist, and may be formed by distilling with sal-ammoniac the corresponding sulphides of potassium or sodium.

The *double sulphide of ammonium and hydrogen*, $\text{NH}_4\text{S} + \text{HS}$, commonly called hydrosulphate of ammonia, or, more correctly, hydrosulphate of sulphide of ammonium, is a compound of great practical utility: it is obtained by saturating a solution of ammonia with well-washed sulphuretted hydrogen gas, until no more of the latter is absorbed. The solution is nearly colourless at first, but becomes yellow after a time, without, however, suffering material injury, unless it has been exposed to the air. It gives precipitates with most

* Page 130.

metallic solutions, which are very often characteristic, and is of great service in analytical chemistry.

When dry ammoniacal gas is brought in contact with anhydrous sulphuric acid, a white crystalline compound is produced, which is soluble in water. In a freshly-prepared cold solution of this substance neither sulphuric acid nor ammonia can be found; but after standing some time, and especially if heat be applied, it passes into ordinary sulphate of ammonia.

A compound of dry ammoniacal gas and sulphurous acid also exists; it is a yellow soluble substance, altogether distinct from sulphite of ammonia. Dry carbonic acid and ammonia also unite to form a volatile white powder, as already mentioned.

When certain salts, especially chlorides in an anhydrous state, are exposed to ammoniacal gas, the latter is absorbed with great energy, and the combinations formed are not always easily decomposed by heat. The chlorides of copper and silver absorb, in this manner, large quantities of the gas. All these compounds must be carefully distinguished from the true ammoniacal salts containing ammonium or its oxide.

There is supposed to be yet another compound of hydrogen and nitrogen to which the term *amidogen* has been given. When potassium is heated in the vapour of water, this substance is decomposed, hydrogen is evolved, and the metal converted into oxide. When the same experiment is made with dry ammoniacal gas, hydrogen is also set free, and an olive-green crystalline compound produced, supposed to contain potassium in union with a new body, NH_2 , having an equivalent of hydrogen less than ammonia.

When ammonia is added to a solution of corrosive sublimate, a white precipitate is obtained, which has been long known in pharmacy. Sir R. Kane infers, from his experiments, that this substance should be looked upon as a compound of chloride of mercury with amide of mercury. The latter salt has not been obtained separately; still less has amidogen itself been isolated.

It has been thought that ammonia may be considered an amide of hydrogen, analogous to water or oxide of hydrogen, capable of entering into combination with salts, and other substances, in a similar manner, yielding unstable and easily-decomposed compounds, which offer a great contrast to those of the energetic *quasi*-metal ammonium: the views of chemists upon this subject are, however, still divided.

The ammoniacal salts are easily recognised; they are all decomposed or volatilized by a high temperature; and when heated with hydrate of lime, or solution of alkaline carbonate, evolve ammonia,

which may be known by its odour and alkaline reaction. The salts are all more or less soluble, the acid tartrate of ammonia and the double chloride of ammonium and platinum being among the least so; hence the salts of ammonia cannot be distinguished from those of potassa by the tests of tartaric acid and platinum-solution.

LITHIUM.

A connecting link between this class of metals and the next succeeding. Lithium is obtained by electrolyzing, in contact with mercury, the hydrate of lithia, and then decomposing the amalgam by distillation. It is a white metal like sodium, and very oxidable. The equivalent of lithium is 6.5, and its symbol L.

The oxide, lithia, Li_2O , is found in petalite, spodumene, lepidolite, triphylite, and a few other minerals, and sometimes occurs in minute quantities in mineral springs. From petalite it may be obtained, on the small scale, by the following process:—The mineral is reduced to an exceedingly fine powder, mixed with five or six times its weight of pure carbonate of lime, and the mixture heated to whiteness, in a platinum crucible, placed within a well-covered earthen one, for twenty minutes or half an hour. The shrunken coherent mass is digested in dilute hydrochloric acid, the whole evaporated to dryness, acidulated water added, and the silica separated by a filter. The solution is then mixed with carbonate of ammonia in excess, boiled, and filtered; the clear liquid is evaporated to dryness, and gently heated in a platinum crucible, to expel the sal-ammoniac. The residue is then wetted with oil of vitriol, gently evaporated once more to dryness, and ignited: pure fused sulphate of lithia remains.

This process will serve to give a good idea of the general nature of the operation by which alkalis are extracted in mineral analysis, and their quantities determined.

The hydrate of lithia is much less soluble in water than those of potassa and soda; the carbonate and phosphate are also sparingly soluble salts. The chloride crystallizes in anhydrous cubes which are deliquescent. Sulphate of lithia is a very beautiful salt; it crystallizes in lengthened prisms containing one equivalent of water. It gives no double salt with sulphate of alumina.

The salts of lithia colour the outer flame of the blowpipe carmine-red.

SECTION II.

METALS OF THE ALKALINE EARTHS.

BARIUM.

BARIUM was obtained by Sir H. Davy by means similar to those mentioned in the case of lithium: it is procured more advantageously by strongly heating baryta in an iron tube, through which the vapour of potassium is conveyed. The reduced barium is extracted by quicksilver, and the amalgam distilled in a small green glass retort.

Barium is a white metal, having the colour and lustre of silver; it is malleable, melts below a red heat, decomposes water, and gradually oxidizes in the air.

The equivalent of this metal has been fixed at 68.5; its symbol is Ba.

PROTOXIDE OF BARIUM; BARYTA, BaO .—Baryta,* or barytes, occurs in nature in considerable abundance as carbonate and sulphate, forming the *veinstone* in many lead-mines; from both these sources it may be extracted with facility. The best method of preparing pure baryta is to decompose the crystallized nitrate by heat in a capacious crucible of porcelain until red vapours are no longer disengaged; the nitric acid is resolved into nitrous acid and oxygen, and the baryta remains behind in the form of a greyish spongy mass, fusible at a high degree of heat. When moistened with water it combines to a hydrate with great elevation of temperature.

The hydrate is a white, soft powder, having a great attraction for carbonic acid, and soluble in 20 parts of cold and 2 of boiling water; a hot saturated solution deposits crystals on cooling, which contain $BaO, HO + 9HO$. Solution of hydrate of baryta is a valuable reagent; it is highly alkaline to test-paper, and instantly rendered turbid by the smallest trace of carbonic acid.

BINOXIDE OF BARIUM, BaO_2 .—This may be formed, as already mentioned, by exposing baryta, heated to full redness in a porcelain tube, to a current of pure oxygen gas. The binoxide is grey, and forms a white hydrate with water, which is not decomposed by that liquid in the cold, but dissolves in small quantity. The binoxide may also be made by heating pure baryta to redness in a platinum crucible, and then gradually adding an equal weight of chlorate of

* From *βαρύς*, heavy, in allusion to the great specific gravity of the native carbonate and sulphate.

potassa: binoxide of barium and chloride of potassium are produced. The latter may be extracted by cold water, and the binoxide left in the state of hydrate. It is interesting chiefly in its relation to bin-oxide of hydrogen. When dissolved in dilute acid, it is decomposed by bichromate of potassa, oxide of silver, chloride of silver, sulphate and carbonate of silver.

CHLORIDE OF BARIUM, $\text{BaCl} + 2\text{HO}$.—This valuable salt is prepared by dissolving the native carbonate in hydrochloric acid, filtering the solution, and evaporating until a pellicle begins to form at the surface; the solution on cooling deposits crystals. When native carbonate cannot be procured, the native sulphate may be employed in the following manner:—The sulphate is reduced to fine powder, and intimately mixed with one-third of its weight of powdered coal; the mixture is pressed into an earthen crucible to which a cover is fitted, and exposed for an hour or more to a high red-heat, by which the sulphate is converted into sulphide at the expense of the combustible matter of the coal. The black mass obtained is powdered and boiled in water, by which the sulphide is dissolved; the solution is filtered hot, and mixed with a slight excess of hydrochloric acid; chloride of barium and sulphuretted hydrogen are produced; the latter escaping with effervescence. Lastly, the solution is filtered to separate any little insoluble matter, and evaporated to the crystallizing point.

The crystals of chloride of barium are flat, four-sided tables, colourless and transparent. They contain 2 equivalents of water, easily driven off by heat; 100 parts of water dissolve 43.5 parts at 60° ($15^\circ\cdot5\text{C}$), and 78 parts at 223° ($104^\circ\cdot5\text{C}$), which is the boiling-point of the saturated solution.

NITRATE OF BARYTA, BaO, NO_5 .—The nitrate is prepared by methods exactly similar to the above, nitric acid being substituted for the hydrochloric. It crystallizes in transparent colourless octahedrons, which are anhydrous. They require for solution 8 parts of cold, and 3 parts of boiling water. This salt is much less soluble in dilute nitric acid than in pure water; errors sometimes arise from such a precipitate of crystalline nitrate of baryta being mistaken for sulphate. It disappears on heating, or by large effusion of water.

SULPHATE OF BARYTA; HEAVY-SPAR; BaO, SO_3 .—Found native, often beautifully crystallized. This compound is always produced when sulphuric acid or a soluble sulphate is mixed with a solution of a barytic salt. It is not sensibly soluble in water or in any dilute acid, even nitric; hot oil of vitriol dissolves a little, but the greater part separates again on cooling. Sulphate of baryta is used as a pigment, but often for the purpose of adulterating white-lead; the native salt is ground to fine powder and washed with dilute sulphuric acid, by which its colour is improved, and a little oxide of iron probably dissolved out. The specific gravity of the natural sulphate is as high as 4.4 to 4.8.

SULPHIDE OF BARIUM, BaS .—The protosulphide of barium is

obtained in the manner already described; the higher sulphides may be formed by boiling this compound with sulphur. Protosulphide of barium crystallizes in thin and nearly colourless plates from a hot solution, which contain water, and are not very soluble: they are rapidly altered by the air. A strong solution of sulphide may be employed in the preparation of hydrate of baryta, by boiling it with small successive portions of black oxide of copper, until a drop of the liquid ceases to precipitate a salt of lead black; the liquid being filtered, yields on cooling crystals of hydrate. In this reaction, besides hydrate of baryta, hyposulphite of that base, and sulphide of copper are produced; the latter is insoluble, and is removed by the filter, while most of the hyposulphite remains in the mother-liquor.

CARBONATE OF BARYTA, BaO, CO_2 .—The natural carbonate is called *witherite*; the artificial is formed by precipitating the chloride or nitrate with an alkaline carbonate, or carbonate of ammonia. It is a heavy, white powder, very sparingly soluble in water, and chiefly useful in the preparation of the rarer baryta-salts.

Solutions of hydrate and nitrate of baryta and of chloride of barium are constantly kept in the laboratory as chemical tests, the first being employed to effect the separation of carbonic acid from certain gaseous mixtures, and the two latter to precipitate sulphuric acid from solution.

The soluble salts of baryta are poisonous, which is not the case with those of the base next to be described.

STRONTIUM.

The metal strontium may be obtained from its oxide by means similar to those described in the case of barium: it is a white metal, heavy, oxidizable in the air, and capable of decomposing water at common temperatures.

The equivalent of strontium is 43.8, and its symbol is Sr.

PROTOXIDE OF STRONTIUM; STRONTIA; SrO .—This compound is best prepared by decomposing the nitrate by the aid of heat; it resembles in almost every particular the earth baryta, forming, like that substance, a white hydrate, soluble in water. A hot saturated solution deposits crystals on cooling, which contain 10 equivalents of water. The hydrate has a great attraction for carbonic acid.

BINOXIDE OF STRONTIUM, SrO_2 .—The binoxide is prepared in the same manner as binoxide of barium; it may be substituted for the latter in making binoxide of hydrogen.

The native carbonate and sulphate of strontia, met with in lead-mines and other localities, serve for the preparation of the various

salts by means exactly similar to those already described in the case of baryta; they have a very feeble degree of solubility in water.

CHLORIDE OF STRONTIUM, SrCl .—The chloride crystallizes in colourless needles or prisms, which are slightly deliquescent, and soluble in 2 parts of cold and still less of boiling water; they are also soluble in alcohol, and the solution, when kindled, burns with a crimson flame. The crystals contain 6 equivalents of water, which they lose by heat; at a higher temperature the chloride fuses.

NITRATE OF STRONTIA, SrO, NO^3 .—This salt crystallizes in anhydrous octahedrons, which require for solution 5 parts of cold, and about half their weight of boiling water. It is principally of value to the pyrotechnist, who employs it in the composition of the well-known “red-fire.”*

CALCIUM.

This is a silver-white and extremely oxidable metal, obtained with great difficulty by means analogous to those by which barium and strontium are procured.

The equivalent of calcium is 20; its symbol is Ca .

PROTOXIDE OF CALCIUM; LIME; CaO .—This extremely important compound may be obtained in a state of considerable purity by heating to full redness for some time fragments of the black bituminous marble of Derbyshire or Kilkenny. If required absolutely pure, it must be made by igniting to whiteness, in a platinum crucible, an artificial carbonate of lime, procured by precipitating the nitrate by carbonate of ammonia. Lime in an impure state is prepared for building and agricultural purposes by calcining, in a kiln of suitable construction, the ordinary limestones which abound in many districts; a red heat, continued for some hours, is sufficient to disengage the whole of the carbonic acid. In the best-contrived limekilns the process is carried on continuously, broken limestone and fuel being constantly thrown in at the top, and the burned lime raked out at intervals from beneath. Sometimes, when the limestones contain silica, and the heat has been very high, the lime refuses to slake, and is said to be *over-burned*; in this case a portion of silicate has been formed.

Pure lime is white, and often of considerable hardness; it is quite infusible and phosphoresces, or emits a pale light at a high temperature.

* RED-FIRE :—	Grns.	GREEN-FIRE :—	Grns.
Dry nitrate of strontia . . .	800	Dry nitrate of baryta . . .	450
Sulphur	225	Sulphur	150
Chlorate of potassa . . .	200	Chlorate of potassa . . .	100
Lampblack	50	Lampblack	25

The strontia or baryta-salt, the sulphur, and the lampblack, must be finely powdered and intimately mixed, after which the chlorate of potassa should be added in rather coarse powder, and mixed without much rubbing with the other ingredients. The red-fire composition has been known to ignite spontaneously.

When moistened with water, it slakes with great violence, evolving heat, and crumbling to a soft, white, bulky powder, which is a hydrate containing a single equivalent of water; the latter can be again expelled by a red-heat. This hydrate is soluble in water, but far less so than either the hydrate of baryta or of strontia, and what is very remarkable, the *colder* the water, the larger the quantity of the compound which is taken up. A pint of water at 60° ($15^{\circ}\cdot5\text{C}$) dissolves about 11 grains, while at 212° (100°C) only 7 grains are retained in solution. The hydrate has been obtained in thin delicate crystals by slow evaporation under the air-pump. Lime-water is always prepared for chemical and pharmaceutical purposes by agitating cold water with excess of hydrate of lime in a closely-stopped vessel, and then, after subsidence, pouring off the clear liquid, and adding a fresh quantity of water, for another occasion; there is not the least occasion for filtering the solution. Lime-water has a strong alkaline reaction, a nauseous taste, and when exposed to the air becomes almost instantly covered with a pellicle of carbonate, by absorption of carbonic acid from the atmosphere. It is used, like baryta-water, as a test for that substance, and also in medicine. Lime-water prepared from some varieties of limestone may contain potassa.

The hardening of mortars and cements is in a great measure due to the gradual absorption of carbonic acid; but even after a very great length of time, this conversion into carbonate is not complete. Mortar is known, under favourable circumstances, to acquire extreme hardness with age. Lime-cements which resist the action of water contain the oxides of iron, silica, and alumina; they require to be carefully prepared, and the stone not over-heated. When ground to powder and mixed with water, solidification speedily ensues, from causes not yet thoroughly understood, and the cement, once in this condition, is unaffected by wet. Parker's or Roman cement is made in this manner from the nodular masses of calcareo-argillaceous iron-stone found in the London clay. Lime is of great importance in agriculture; it is found more or less in every fertile soil, and is often very advantageously added by the cultivator. The decay of vegetable fibre in the soil is promoted, and other important objects, as the destruction of certain hurtful compounds of iron in marsh and peat-land, is often attained. The addition of lime probably serves likewise to liberate potassa from the insoluble silicate of that base contained in the soil.

BINOXIDE OF CALCIUM, CaO_2 .—This is stated to resemble bin-oxide of barium, and to be obtainable by a similar process.

CHLORIDE OF CALCIUM, CaCl .—Usually prepared by dissolving marble in hydrochloric acid; also a by-product in several chemical manufactures. The salt separates from a strong solution in colourless, prismatic, and exceedingly deliquescent crystals, which contain 6 equivalents of water. By heat this water is expelled, and by a temperature of strong ignition the salt is fused. The crystals reduced to

powder are employed in the production of artificial cold by being mixed with snow or powdered ice; and the chloride, strongly dried or in a fused condition, is of great practical use in desiccating gases, for which purpose the latter are slowly transmitted through tubes filled with fragments of the salt. Chloride of calcium is also freely soluble in alcohol, which, when anhydrous, forms with it a definite crystallizable compound.

SULPHIDE OF CALCIUM.—The simple sulphide is obtained by reducing sulphate of lime at a high temperature by charcoal or hydrogen; it is nearly colourless, and but little soluble in water. By boiling together hydrate of lime, water, and flowers of sulphur, a red solution is obtained, which, on cooling, deposits crystals of bisulphide, which contain water. When the sulphur is in excess, and the boiling long continued, a pentasulphide is generated; hyposulphurous acid is, as usual, formed in these reactions.

PHOSPHIDE OF CALCIUM.—When the vapour of phosphorus is passed over fragments of lime heated to redness in a porcelain tube, a chocolate-brown compound, the so-called *phosphide of lime*, is produced. This substance is probably a mechanical mixture of phosphide of calcium, and phosphate of lime. It yields spontaneously inflammable phosphoretted hydrogen when put into water.*

SULPHATE OF LIME; GYPSUM; SELENITE; CaO, SO_3 .—Native sulphate of lime in a crystalline condition, containing 2 equivalents of water, is found in considerable abundance in some localities; it is often associated with rock-salt. When regularly crystallized, it is termed *selenite*. Anhydrous sulphate of lime is also occasionally met with. The salt is formed by precipitation when a moderately-concentrated solution of chloride of calcium is mixed with sulphuric acid. Sulphate of lime is soluble in about 500 parts of cold water, and its solubility is a little increased by heat. It is more soluble in water containing chloride of ammonium or nitrate of potassa. The solution is precipitated by alcohol. Gypsum, or native hydrated sulphate, is largely employed for the purpose of making casts of statues and medals, and also for moulds in the porcelain and earthenware manufactures, and for other applications. It is exposed to heat in an oven where the temperature does not exceed 260° ($126^\circ\text{.}6\text{C}$), by which the water of crystallization is expelled, and afterwards reduced to fine powder. When mixed with water, it solidifies after a short time from the re-formation of the same hydrate; but this effect does not happen if the gypsum has been over-heated. It is often called plaster of Paris. Artificial coloured marbles, or *scagliola*, are fre-

* According to M. Paul Thénard, the phosphide of calcium existing in this mixture, has the composition PCa_2 . By coming in contact with water, it yields liquid phosphoretted hydrogen, $\text{PCa}_2 + 2\text{HO} = 2\text{CaO} + \text{PH}_2$.—(Page 172.)

The greater portion of the liquid phosphide is immediately decomposed into solid and gaseous phosphoretted hydrogen.— $5\text{PH}_2 = 3\text{PH}_3 + \text{P}_2\text{H}$.

quently prepared by inserting pieces of natural stone in a soft stucco containing this substance, and polishing the surface when the cement has become hard. Sulphate of lime is one of the most common impurities of spring water.

The peculiar property water acquires by the presence in it of lime is termed *hardness*. It manifests itself by the effect such waters have upon the palate, and particularly by its peculiar behaviour with soap. Hard waters yield a lather with soap only after the whole of the lime-salts have been thrown down from the water in the form of an insoluble lime-soap. Upon this principle Prof. Clark's soap-test for the hardness of waters is based.* The hardness produced by sulphate of lime is called *permanent hardness*, since it cannot be remedied.

CARBONATE OF LIME ; CHALK ; LIMESTONE ; MARBLE ; CaO, CO_2 . —Carbonate of lime, often more or less contaminated by protoxide of iron, clay, and organic matter, forms rocky beds, of immense extent and thickness, in almost every part of the world. These present the greatest diversities of texture and appearance, arising, in a great measure, from changes to which they have been subjected since their deposition. The most ancient and highly-crystalline limestones are destitute of visible organic remains, while those of more recent origin are often entirely made up of the shelly exuviae of once-living beings. Sometimes these latter are of such a nature as to show that the animals inhabited fresh water ; marine species and corals are, however, most abundant. Cavities in limestone and other rocks are very often lined with magnificent crystals of carbonate of lime or calcareous spar, which have evidently been slowly deposited from a watery solution. Carbonate of lime is always precipitated when an alkaline carbonate is mixed with a solution of that base.

Although this substance is not sensibly soluble in pure water, it is freely taken up when carbonic acid happens at the same time to be present. If a little lime-water be poured into a vessel of that gas, the turbidity first produced disappears on agitation, and a transparent solution of carbonate of lime in excess of carbonic acid is obtained. This solution is decomposed completely by boiling, the carbonic acid being expelled, and the carbonate precipitated. Since all natural waters contain dissolved carbonic acid, it is to be expected that lime in this condition should be of very common occurrence ; and such is really found to be the fact ; river, and more especially spring water, almost invariably containing carbonate of lime thus dissolved. In limestone districts, this is often the case to a great extent. The *hardness* of water, which is owing to the presence of carbonate of lime, is called *temporary*, since it is diminished to a very considerable extent by boiling, and may be nearly removed by mixing the hard water with lime-water, when both the dissolved carbonate and the dissolved lime, which becomes thus carbonated, are precipitated.

* Journal of the Pharmaceutical Society, vol. vi. p. 526.

Upon this principle Prof. Clark's process of softening water is based. This process is of considerable importance, since a supply of hard water to towns is in many respects a source of great inconvenience. As has been already mentioned, the use of such water, for the purposes of washing, is attended with a great loss of soap. Boilers, in which such water is heated, speedily become lined with a thick stony incrustation.* The beautiful stalactitic incrustations of limestone caverns, and the deposits of calc-sinter or travertin upon various objects, and upon the ground in many places, are thus explained by the solubility of carbonate of lime in water containing carbonic acid.

Crystallized carbonate of lime exhibits the curious property of dimorphism; calcareous spar and arragonite, although possessing the same chemical composition, both containing single equivalents of lime and carbonic acid, and nothing besides, have different crystalline forms, different densities, and different optical properties.

The former occurs very abundantly in crystals derived from an obtuse rhomboid, whose angles measure $105^{\circ} 5'$ and $74^{\circ} 55'$; its density varies from 2.5 to 2.8. The rarer variety, or arragonite, is found in crystals whose primary form is a right rhombic prism; a figure having no geometrical relation to the preceding; it is besides, heavier and harder.

PHOSPHATES OF LIME.—A number of distinct compounds of lime and phosphoric acid probably exist. Two *tribasic phosphates*, 2CaO , HO , PO_5 , and 3CaO , PO_5 , are produced when the corresponding soda-salts are added in solution to chloride of calcium; the first is slightly crystalline, and the second gelatinous. When the first phosphate is digested with ammonia, or dissolved in acid and re-precipitated by that alkali, it is converted into the second. The earth of bones consists principally of what appears to be a combination of these two salts. Another phosphate, containing 2 equivalents of basic water, has been described, which completes the series: it is formed by dissolving either of the preceding in phosphoric, hydrochloric, or nitric acid, and evaporating until the salt separates on cooling in small platy crystals. It is the substance which yields phosphorus, when heated with charcoal, in the ordinary process of manufacture, before described. *Bibasic* and *monobasic phosphates of lime* also exist. These phosphates, although insoluble in water, dissolve readily in dilute acids, even acetic acid.

FLUORIDE OF CALCIUM; FLUOR-SPAR; CaF .—This substance is important as the most abundant natural source of hydrofluoric acid and the other fluorides. It occurs beautifully crystallized, of various



* Many proposals have been made to prevent the formation of boiler-deposits. The most efficient appears to be the method of Dr. Ritterband, which consists in throwing into the boiler a small quantity of sal-ammoniac, when carbonate of ammonia is formed, which is volatilized with the steam, chloride of calcium remaining in solution. It need scarcely be mentioned that this plan is inapplicable in the case of permanently-hard waters.

colours, in lead-veins, the crystals having commonly the cubic, but sometimes the octahedral form, parallel to the faces of which latter figure they always cleave. Some varieties, when heated, emit a greenish phosphorescent light. The fluoride is quite insoluble in water, and is decomposed by oil of vitriol in the manner already mentioned, vide p. 158.

CHLORIDE OF LIME; BLEACHING-POWDER.—When hydrate of lime, very slightly moist, is exposed to chlorine gas, the latter is eagerly absorbed, and a compound produced which has attracted a great deal of attention; this is the bleaching-powder of commerce, now manufactured on an immense scale, for bleaching linen and cotton goods. It is requisite, in preparing this substance, to avoid with the greatest care all elevation of temperature, which may be easily done by slowly supplying the chlorine in the first instance. The product, when freshly and well prepared, is a soft, white powder, which attracts moisture from the air, and exhales an odour sensibly different from that of chlorine. It is soluble in about 10 parts of water, the unaltered hydrate being left behind; the solution is highly alkaline, and bleaches feebly. When hydrate of lime is suspended in cold water, and chlorine gas transmitted through the mixture, the lime is gradually dissolved, and the same peculiar bleaching compound produced; the alkalis also, either caustic or carbonated, may by similar means be made to absorb a large quantity of chlorine, and give rise to corresponding compounds; such are the “disinfecting solutions” of M. Labarraque.

The most consistent view of the constitution of these curious compounds is that which supposes them to contain salts of hypochlorous acid, a substance as remarkable for bleaching powers as chlorine itself; and this opinion seems borne out by a careful comparison of the properties of the bleaching salts with those of the true hypochlorites. Hypochlorous acid can be actually obtained from good bleaching-powder, by distilling it with dilute sulphuric or nitric acid, in quantity insufficient to decompose the whole: when the acid is used in excess, chlorine is disengaged.*

If this view be correct, chloride of calcium must be formed simultaneously with the hypochlorite, as in the following diagram:



When the temperature of the hydrate of lime has risen during the absorption of the chlorine, or when the compound has been subse-

* M. Gay-Lussac, Ann. Chim. et Phys. 3rd series, v. 296.

quently exposed to heat, its bleaching properties are impaired or altogether destroyed; it then contains chlorate of lime and chloride of calcium; oxygen, in variable quantity, is usually set free. The same change seems to ensue by long keeping, even at the common temperature of the air. In an open vessel it is speedily destroyed by the carbonic acid of the atmosphere. Commercial bleaching-powder thus constantly varies in value with its age, and with the care originally bestowed upon its preparation: the best may contain about 30 per cent. of available chlorine, easily liberated by an acid, which is, however, far short of the theoretical quantity.

The general method in which this substance is employed for bleaching is the following:—the goods are first immersed in a dilute solution of chloride of lime and then transferred to a vat containing dilute sulphuric acid. Decomposition ensues; both the lime of the hypochlorite and the calcium of the chloride are converted into sulphate of lime, while the free hypochlorous and hydrochloric acids yield water and free chlorine.

The chlorine thus disengaged in contact with the cloth causes the destruction of the colouring matter. This process is often repeated, it being unsafe to use strong solutions. White patterns are on this principle imprinted upon coloured cloth, the figures being stamped with tartaric acid thickened with gum-water, and then the stuff immersed in the chloride bath, when the parts to which no acid has been applied remain unaltered, while the printed portions are bleached.

For purifying an offensive or infectious atmosphere, *as an aid to proper ventilation*, the bleaching-powder is very convenient. The solution is exposed in shallow vessels, or cloths steeped in it are suspended in the apartment, when the carbonic acid of the air slowly decomposes it in the manner above described. An addition of a strong acid causes rapid disengagement of chlorine.

The value of any sample of bleaching-powder may be easily determined by the following method, in which the feebly-combined chlorine is estimated by its effect in peroxidizing a protosalt of iron, of which two equivalents require one of chlorine; the latter acts by decomposing water and liberating a corresponding quantity of oxygen—78 (more correctly 78.16) grains of green sulphate of iron are dissolved in about two ounces of water, and acidulated by a few drops of sulphuric or hydrochloric acid; this quantity will require for peroxidation 10 grains of chlorine. Fifty grains of the chloride of lime to be examined are next rubbed up with a little tepid water, and the whole transferred to the alkalimeter* before described, which is then filled up to 0 with water, after which the contents are well mixed by agitation. The liquid is next gradually poured into the solution of iron, with constant stirring until the latter has become peroxidized, which may be known by a drop ceasing to give a deep blue precipitate

* Vide p. 262.

with ferrieyanide of potassium. The number of grain-measures of the ehloride solution employed may then be read off: since these must contain 10 grains of serviceable ehlorine, the quantity of the latter in the 50 grains may be easily reckoned. Thus, suppose 72 such measures have been taken, then

Measures.	Grs. chlorine.	Measures.	Grs. chlorine.
72	: 10	= 100	: 13.89

The bleaching-powder contains, therefore, 27.78 per cent.*

Baryta, strontia, and lime are thus distinguished from all other substanees, and from each other.

Caustic potassa, when free from carbonate, and caustic ammonia, occasion no precipitates in dilute solutions of the earths, especially of the first two, the hydrates being soluble in water.

Alkaline carbonates, and carbonate of ammonia, give white precipitates, insoluble in excess of the precipitant, with all three.

Sulphuric acid, or a sulphate, added to very dilute solutions of the earths in question, gives an immediate white precipitate with baryta, a similar precipitate after a short interval with strontia, and occasions no change with the lime-salt. The precipitates with baryta and strontia are quite insoluble in nitric acid.

Solution of sulphate of lime gives an instantaneous cloud with baryta, and one with strontia after a little time. Sulphate of strontia is itself sufficiently soluble to occasion turbidity when mixed with chloride of barium.

Lastly, the soluble oxalates give a white precipitate in the most dilute solutions of lime, which is not dissolved by a drop or two of hydrochloric or by an excess of acetic acid. This is an exceedingly characteristic test.

The chlorides of strontium and calcium dissolved in alcohol colour the flame of the latter red or purple; salts of baryta communicate to the flame a pale green tint.

MAGNESIUM.

A few pellets of sodium are placed at the bottom of a test-tube of hard German glass, and covered with fragments of fused chloride of magnesium. The heat of a spirit-lamp is then applied until reaction has been induced: this takes place with great violence and elevation of temperature, chloride of sodium being formed, and metallic magnesium set free. When the tube and its contents are completely cold, it is broken up, and the fragments put into cold water, by which the metal is separated from the salt.

Bunsen has lately succeeded in reducing the magnesium by the decomposition of fused chloride of magnesium, by means of the electric battery.

* Graham's Elements, vol. i. p. 593.

Magnesium is a white, malleable metal, fusible at a red-heat, and not sensibly acted upon by cold water; it is oxidized by hot water. Heated in the air, it burns and produces magnesia, which is the only oxide. Sulphuric and hydrochloric acids dissolve it readily, evolving hydrogen.

The equivalent of this metal is 12, and its symbol Mg.

MAGNESIA; CALCINED MAGNESIA; MgO .—This is prepared with great ease by exposing the *magnesia alba* of pharmacy to a full red-heat in an earthen or platinum crucible. It forms a soft, white powder, which slowly attracts moisture and carbonic acid from the air, and unites quietly with water to a hydrate which possesses a feeble degree of solubility, requiring about 5,000 parts of water at 60° ($15^\circ\cdot5\text{C}$) and 36,000 parts at 212° (100°C). The alkalinity of magnesia can only be observed by placing a small portion in a moistened state upon test-paper; it neutralizes acids, however, in the most complete manner. It is infusible.

CHLORIDE OF MAGNESIUM, MgCl .—When magnesia, or its carbonate, is dissolved in hydrochloric acid, there can be no doubt respecting the simultaneous production of chloride of magnesium and water; but when this solution comes to be evaporated to dryness, the last portions of water are retained with such obstinacy, that decomposition of the water is brought about by the concurring attractions of magnesium for oxygen, and of chlorine for hydrogen; hydrochloric acid is expelled, and magnesia remains. If, however, sal-ammoniac or chloride of potassium happen to be present, a double salt is produced, which is easily rendered anhydrous. The best mode of preparing the chloride is to divide a quantity of hydrochloric acid into two equal portions, to neutralize one with magnesia, and the other with ammonia, or carbonate of ammonia; to mix these solutions, evaporate them to dryness, and then expose the salt to a red-heat in a loosely-covered porcelain crucible. Sal-ammoniac sublimes, and chloride of magnesium in a fused state remains; the latter is poured out upon a clean stone, and when cold, transferred to a well-stopped bottle.

The chloride so obtained is white and crystalline. It is very deliquescent and highly soluble in water, from which it cannot again be recovered by evaporation, for the reasons just mentioned. When long exposed to the air in a melted state, it is converted into magnesia. It is soluble in alcohol.

SULPHATE OF MAGNESIA; EPSOM SALT; $\text{MgO}, \text{SO}_3 + 7\text{HO}$.—This salt occurs in sea-water, and in that of many mineral springs, and is now manufactured in large quantities by acting on magnesian limestone by diluted sulphuric acid, and separating the sulphate of magnesia from the greater part of the slightly-soluble sulphate of lime by the filter. The crystals are derived from a right rhombic prism; they are soluble in an equal weight of water at 60° ($15^\circ\cdot5\text{C}$), and in a still smaller quantity at 212° (100°C). The salt has a nauseous

bitter taste, and like many other neutral salts, purgative properties. When exposed to heat, 6 equivalents of water readily pass off, the seventh being energetically retained. Sulphate of magnesia forms beautiful double salts with the sulphates of potassa and ammonia, which contains 6 equivalents of water of crystallization.

CARBONATE OF MAGNESIA.—The *neutral carbonate*, MgO, CO_2 , occurs native in rhombohedral crystals, resembling those of calcareous spar, embedded in talc-slate; a soft earthy variety is sometimes met with.

When *magnesia alba* is dissolved in carbonic acid water, and the solution left to evaporate spontaneously, small prismatic crystals are deposited, which consist of carbonate of magnesia, with 3 equivalents of water.

The *magnesia alba* itself, although often called carbonate of magnesia, is not so in reality; it is a compound of carbonate with hydrate. It is prepared by mixing hot solutions of carbonate of potassa or soda, and sulphate of magnesia, the latter being kept in slight excess, boiling the whole a few minutes, during which time much carbonic acid is disengaged, and then well washing the precipitate so produced. If the solution be very dilute, the *magnesia alba* is exceedingly light and bulky; if otherwise, it is denser. The composition of this precipitate is not perfectly constant. In most cases it contains $4(\text{MgO}, \text{CO}_2) + \text{MgO}, \text{HO} + 6\text{HO}$.

Magnesia alba is slightly soluble in water, especially when cold.

PHOSPHATE OF MAGNESIA, $2\text{MgO}, \text{HO}, \text{PO}_5 + 14\text{HO}$.—This salt separates in small colourless prismatic crystals when solutions of phosphate of soda and sulphate of magnesia are mixed and suffered to stand some time. Prof. Graham states that it is soluble in about 1,000 parts of cold water, but Berzelius describes a phosphate which only requires 15 parts of water for solution: this can hardly be the same substance. Phosphate of magnesia exists in the grain of the cereals, and can be detected in considerable quantity in beer.

PHOSPHATE OF MAGNESIA AND AMMONIA, $2\text{MgO}, \text{NH}_4\text{O}, \text{PO}_5 + 12\text{HO}$.—When a soluble phosphate is mixed with a salt of magnesia, and ammonia or its carbonate added, a crystalline precipitate, having the above composition, subsides, immediately if the solutions are concentrated, and after some time if very dilute; in the latter case, the precipitation is promoted by stirring. This salt is slightly soluble in pure water, but scarcely so in saline liquids. When heated, it is resolved into bibasic phosphate (pyrophosphate) of magnesia, containing 35.71 per cent. of magnesia. At a strong red-heat it fuses to a white enamel-like mass. The phosphate of magnesia and ammonia sometimes forms an urinary calculus.

In practical analysis, magnesia is often separated from solutions by bringing it into this state. The liquid, free from alumina, lime, &c., is mixed with phosphate of soda and excess of ammonia, and gently heated for a short time. The precipitate is collected upon a filter and

thoroughly washed with water containing a little sal-ammoniac, after which it is dried, ignited to redness, and weighed. The proportion of magnesia is then easily calculated.

SILICATES OF MAGNESIA.—The following natural compounds belong to this class:—*Stealite* or *soap-stone*, MgO, SiO_2 , a soft, white, or pale-coloured, amorphous substance, found in Cornwall and elsewhere;—*Meerschaum*, $\text{MgO}, \text{SiO}_2 + \text{HO}$, from which pipe-bowls are often manufactured;—*Chrysolite*, $3\text{MgO}, \text{SiO}_2$, a crystallized mineral, sometimes employed for ornamental purposes; a portion of magnesia is commonly replaced by protoxide of iron, which communicates a green colour;—*Serpentine* is a combination of silicate and hydrate of magnesia;—*Jade*, an exceedingly-hard stone, brought from New Zealand, contains silicate of magnesia combined with silicate of alumina; its green colour is due to sesquioxide of chromium;—*Augite* and *hornblende* are essentially double salts of silicic acid, magnesia, and lime, in which the magnesia is more or less replaced by its isomorphous substitute, protoxide of iron.

The salts of magnesia are strictly isomorphous with those of the protoxides of zinc, of iron, of copper, &c.; they are usually colourless, and are easily recognized by the following characters:—

- A gelatinous white precipitate with caustic alkalis, including ammonia, insoluble in excess, but soluble in solution of sal-ammoniac.
- A white precipitate with the carbonates of potassa and soda, but none with carbonate of ammonia in the cold.
- A white crystalline precipitate with soluble phosphates, on the addition of a little ammonia.

SECTION III.

METALS OF THE EARTHS PROPER.

ALUMINUM OR ALUMINIUM.

ALUMINA, the only known oxide of this metal is a substance of very abundant occurrence in nature in the state of silicate, as in felspar and its associated minerals, and in the various modifications of clay thence derived. Aluminium is prepared in the same manner as magnesium, but with rather more difficulty; a platinum or iron tube closed at one extremity may be employed. Sesquichloride of aluminium is first introduced, and upon that about an equal bulk of potassium loosely wrapped in platinum foil. The lower part of the tube is then heated so as to sublime the chloride and bring its vapours in contact with the melted potassium. The reduction takes place with great disengagement of heat. The metal, separated by cold water from the alkaline chloride, has a tin-white colour and perfect lustre. It is obtained in small fused globules by the heat attained in the reduction, which are malleable, and have a specific gravity of 2.6. When heated in the air or in oxygen, it takes fire and burns with brilliancy, producing alumina.

Aluminium has for its equivalent the number 13.7; its symbol is Al.

ALUMINA, Al_2O_3 .—This substance is inferred to be a sesquioxide, from its isomorphism with the red oxide of iron. It is prepared by mixing solution of alum with excess of ammonia, by which an extremely bulky, white, gelatinous precipitate of hydrate of alumina is thrown down. This is washed, dried, and ignited to whiteness. Thus obtained, alumina constitutes a white, tasteless, coherent mass, very little acted upon by acids. The hydrate, on the contrary, when simply dried in the air, or by gentle heat, dissolves freely in dilute acid, and in caustic potassa or soda, from which it is precipitated by the addition of sal-ammoniac. Alumina is fusible before the oxy-hydrogen blowpipe. The mineral called *corundum*, of which the ruby and sapphire are transparent varieties, consists of nearly pure alumina in a crystallized state, with a little colouring oxide; emery, used for polishing glass and metals, is a coarse variety of corundum. Alumina is a very feeble base, and its salts have often an acid reaction.

SESEQUICHLORIDE OF ALUMINIUM, Al_2Cl_3 .—The solution of alumina in hydrochloric acid behaves, when evaporated to dryness, like that of magnesia, the chloride being decomposed by the water, and alumina

and hydrochloric acid produced. The chloride may be thus prepared :—Pure precipitated alumina is dried and mixed with lampblack, and the mixture strongly calcined in a covered crucible. It is then transferred to a porcelain tube fixed across a furnace, and heated to redness in a stream of chlorine gas, when the alumina, yielding to the attraction of the chlorine on the one hand and the carbon on the other, for each of its constituents, suffers decomposition, carbonic oxide being disengaged, and sesquichloride of aluminium formed; the latter sublimes, and condenses in the cool part of the tube.

Sesquichloride of aluminium is a crystalline yellowish substance, excessively greedy of moisture, and very soluble. Once dissolved, it cannot be again recovered. It is said to combine with sulphuretted and phosphoretted hydrogen, and with ammonia.

SULPHATE OF ALUMINA, $\text{Al}_2\text{O}_3, 3\text{SO}_3 + 18\text{HO}$.—Prepared by saturating dilute sulphuric acid with hydrate of alumina, and evaporating. It crystallizes in thin, pearly plates, soluble in 2 parts of water; it has a sweet and astringent taste, and an acid reaction. Heated to redness, it is decomposed, leaving pure alumina. Two other sulphates of alumina, with excess of base, are also described, one of which is insoluble in water.

Sulphate of alumina combines with the sulphates of potassa, soda, and ammonia, forming double salts of great interest, the *alums*. Common alum, the source of all the preparations of alumina, contains $\text{Al}_2\text{O}_3, 3\text{SO}_3 + \text{KO}, \text{SO}_3 + 24\text{HO}$. It is manufactured, on a very large scale, from a kind of slaty clay, loaded with bisulphide of iron, which abounds in certain parts. This is gently roasted, and then exposed to the air in a moistened state; oxygen is absorbed, the sulphur becomes acidified, sulphate of protoxide of iron and sulphate of alumina are produced, and afterwards separated by lixiviation with water. The solution is next concentrated, and mixed with a quantity of chloride of potassium, which decomposes the iron-salt, forming protochloride of iron and sulphate of potassa, which latter combines, with the sulphate of alumina, to form alum. By crystallization, the alum is separated from the highly-soluble chloride of iron, and afterwards easily purified by a repetition of that process. Other methods of alum-making exist, and are sometimes employed. Potassa-alum crystallizes in colourless, transparent octahedrons, which often exhibit the faces of the cube. It has a sweetish and astringent taste, reddens litmus paper, and dissolves in 18 parts of water at 60° ($15^\circ\text{.}5\text{C}$), and in its own weight of boiling water. Exposed to heat, it is easily rendered anhydrous, and, by a very high temperature, decomposed. The crystals have little tendency to change in the air. Alum is largely used in the arts, in preparing skins, dyeing, &c.; it is occasionally contaminated with oxide of iron, which interferes with some of its applications. The celebrated Roman alum, made from *alum-stone*, a felspathic rock, altered by sulphurous vapours, was once much prized on account of its freedom from this impurity.

A mixture of dried alum and sugar, carbonized in an open pan, and then heated to redness, out of contact of air, furnishes the *pyrophorus of Homberg*, which ignites spontaneously on exposure to the atmosphere. The essential ingredient is, in all probability, finely-divided sulphide of potassium.

Soda-alum, in which sulphate of soda replaces sulphate of potassa, has a form and constitution similar to that of the salt described: it is, however, much more soluble, and difficult to crystallize.

Ammonia-alum, containing $\text{NH}_4\text{O}, \text{SO}_3$, instead of KO, SO_3 , very closely resembles common potassa-alum, having the same figure, appearance, and constitution, and nearly the same degree of solubility as that substance. It is sometimes manufactured for commercial use. When heated to redness, it yields pure alumina.

Few of the other salts of alumina, except the silicates, present points of interest: these latter are of great importance. Silicates of alumina enter into the composition of a number of crystallized minerals, among which felspar occupies, by reason of its abundant occurrence, a prominent place. Granite, porphyry, trachyte, and other ancient unstratified rocks, consist in great part of this mineral, which, under peculiar circumstances, by no means well understood, and particularly by the action of the carbonic acid of the air, suffer complete decomposition, becoming converted into a soft, friable mass of earthy matter. This is the origin of clay: the change itself is seen in great perfection in certain districts of Devonshire and Cornwall, the felspar of the fine white granite of those localities being often disintegrated to an extraordinary depth, and the rock altered to a substance resembling soft mortar. By washing, this finely-divided matter is separated from the quartz and mica, and the milk-like liquid, being collected in tanks and suffered to stand, deposits the suspended clay, which is afterwards dried, first in the air and afterwards in a stove, and employed in the manufacture of porcelain. The composition assigned to unaltered felspar is $\text{Al}_2\text{O}_3, 3\text{SiO}_3 + \text{KO}, \text{SiO}_3$, or alum, having silicic acid in the place of sulphuric. The exact nature of the change by which it passes into porcelain clay is unknown, although it evidently consists in the abstraction of silica and alkali.

When the decomposing rock contains oxide of iron, the clay produced is coloured. The different varieties of shale and slate result from the alteration of ancient clay-beds, apparently in many instances by the infiltration of water holding silica in solution: the dark appearance of some of these deposits is due to bituminous matter.

It is a common mistake to confound clay with alumina; all clays are essentially silicates of that base; they often vary a good deal in composition. Dilute acids exert little action on these compounds; but by boiling with oil of vitriol, alumina is dissolved out, and finely-divided silica left behind. Clays containing an admixture of carbonate of lime are termed *marls*, and are recognized by effervescing with acids.

A basic silicate of alumina, $2\text{Al}_2\text{O}_3, \text{SiO}_3$, is found crystallized, constituting the beautiful mineral called *cyanite*. The compounds formed by the union of the silicates of alumina with other silicates are almost innumerable; a soda-felspar, *albite*, containing that alkali in place of potassa, is known, and there are two somewhat similar lithia-compounds *spodumene* and *petalite*. The *zeolites* belong to this class: *analcime*, *nepheline*, *mesotype*, &c., are double silicates of soda and alumina, with water of crystallization. *Stilbite*, *heulandite*, *laumontite*, *prehnite*, &c., consist of silicate of lime, combined with silicate of alumina. The *garnets*, *axinite*, *mica*, &c., have a similar composition, but are anhydrous. Sesquioxide of iron is very often substituted for alumina in these minerals.

Alumina, when in solution, is distinguished without difficulty.

Caustic potassa and soda occasion white gelatinous precipitates of hydrate of alumina, freely soluble in excess of the alkali.

Ammonia produces a similar precipitate, insoluble in excess of the reagent.

The alkaline carbonates and carbonate of ammonia precipitate the hydrate, with escape of carbonic acid. The precipitates are insoluble in excess.

BERYLLIUM (GLUCINUM).

This metal is prepared from the chloride in the same manner as aluminium. It is fusible with great difficulty, not acted upon by cold water, and burns when heated in the air, producing berylla.

The equivalent of beryllium is 6.9, and the symbol Be.

BERYLLA, Be_2O_3 , is a rare earth found in the *emerald*, *beryl*, and *euclase*, from which it may be extracted by a tolerably simple process. It very much resembles alumina, but is distinguished from that substance by its solubility, when freshly precipitated, in a cold solution of carbonate of ammonia, from which it is again thrown down on boiling. The salts of berylla have a sweet taste, whence its former name glucina ($\gamma\lambda\upsilon\kappa\acute{\iota}\varsigma$).

YTTRIUM.

The metal of a very rare earth, *yttria*, contained in a few scarce minerals. The name is derived from Ytterby, a place in Sweden, where one of these, *gadolinite*, is found. It is obtained from the chloride by the process already described; it resembles in character the preceding metal.

Ordinary yttria is stated by Professor Mosander to be a mixture of the oxides of not less than three metals, namely, *yttrium*, *erbium*, and

terbium, which differ in the characters of their salts, and in other particulars. The first is a very powerful base, the two others are weak ones. They are separated with extreme difficulty.

CERIUM, LANTHANUM, AND DIDYMIUM.

The oxides of these very rare metals are found associated in the Swedish mineral *cerite*; the equivalent of cerium is about 47, and its symbol Ce. This metal forms a protoxide CeO , and a sesquioxide Ce_2O_3 .

The crude sesquioxide of cerium obtained by precipitating the double sulphate of cerium and potassa directly derived from *cerite* by carbonate of potassa, has been shown by Mosander to contain in addition to sesquioxide of cerium, the oxides of two other metals, to which the above names were given. After ignition it is red-brown. The complete separation of these three bodies is attended with the greatest difficulty, and has indeed been only partially accomplished.* Oxide of cerium may be obtained pure by heating the mixture of the three oxides first with diluted and afterwards with concentrated nitric acid, which gradually removes the whole of the oxides of lanthanum and didymium.

The yellow oxide of cerium, obtained by igniting the nitrate, is a mixture of proto- and sesqui-oxide, which are extremely difficult to obtain in a separate state. The salts of the former are colourless, and are completely precipitated by sulphate of potassa; the sulphate of the sesquioxide is yellow, and forms a beautiful double salt with sulphate of potassa, which is decomposed by water. The metal cerium has been obtained from the chloride by the action of sodium.

Oxide of lanthanum, as pure as it has been obtained, forms a very pale salmon-coloured powder, unchanged by ignition in open or close vessels. In contact with water it gives a snow-white bulky hydrate which has an alkaline reaction, and decomposes ammoniacal salts by boiling. Its salts are crystallizable, colourless, sweet, and astringent, and are precipitated by sulphate of potassa.

A tolerably pure lanthanum-salt may be obtained by slowly crystallizing an acid solution containing the sulphates of lanthanum and didymium, picking out the rose-coloured crystals (containing didymium), and the violet ones (containing lanthanum and didymium), adding the solution of the latter to the mother-liquor, and repeating the process. In this manner the whole of the didymium-salt may be finally separated by crystallization. Metallic lanthanum is prepared like cerium.

The occasional brown colour of crude oxide of cerium is due to

* A synopsis of the various methods for the separation of cerium, lanthanum, and didymium has been given by Mr. H. Watts. Chem. Soc. Quar. Jour. ii. 140.

oxide of didymium. In a pure state, it forms a brown powder, soluble in acids, and generating a series of red crystallizable salts, from which caustic potassa precipitates a violet-blue hydrate, quickly changing by exposure to the air. It communicates to glass an amethystine colour.*

ZIRCONIUM.

Prepared by heating the double fluoride of zirconium and potassium with potassium, and separating the salt with cold water. The metal is black, and acquires a feeble lustre when burnished. It takes fire when heated in the air.

The equivalent of zirconium is 33·6, and its symbol Zr.

ZIRCONIA, Zr_2O_3 , is a rare earth, very closely resembling alumina, found together with silica, in the mineral *zircon*. The salts are colourless and have an astringent taste.

Svanberg has rendered it probable that an undescribed metallic oxide exists in certain varieties of zircon, for the metal of which he proposes the name of *norium*.

THORIUM.

The metal of an earth from a very rare mineral, *thorite*; it agrees in character with aluminium, and is obtained by similar means.

The equivalent of thorium is 59·6, and its symbol Th.

THORIA, ThO , is remarkable for its great specific gravity, and is otherwise distinguished by peculiar properties which separate it from all other substances.

Manufacture of Glass, Porcelain, and Earthenware.

GLASS.—Glass is a mixture of various insoluble silicates, with excess of silica, altogether destitute of crystalline structure: the simple silicates, formed by fusing the bases with silicic acid in equivalent proportions, very often crystallize, which happens also with the greater number of the natural silicates included among the earthy minerals. Compounds identical with some of these are also occasionally formed in artificial processes, where large masses of melted glassy matter are suffered to cool slowly. The alkaline silicates, when in a state of fusion, have the power of dissolving a large quantity of silica.

Two principal varieties of glass are met with in commerce, namely, glass composed of silica, alkali, and lime, and glass containing a large proportion of silicate of lead; *crown* and *plate glass* belong to the former division; *flint-glass*, and the material of artificial gems to

* *Annalen der Chemie und Pharmacie*, xlviii. 210.

the latter. The lead promotes fusibility, and confers also density and lustre. Common green bottle-glass contains no lead, but much silicate of black oxide of iron, derived from the impure materials. The principle of the glass manufacture is very simple. Silica, in the shape of sand, is heated with carbonate of potassa or soda, and slaked lime or oxide of lead; at a high temperature, fusion and combination occur, and the carbonic acid is expelled. When the melted mass has become perfectly clear and free from air-bubbles, it is left to cool until it assumes the peculiar tenacious condition proper for working.

The operation of fusion is conducted in large crucibles of refractory fire-clay, which in the case of lead-glass are covered by a dome at the top, and have an opening at the side by which the materials are introduced, and the melted glass withdrawn. Great care is exercised in the choice of the sand, which must be quite white and free from oxide of iron. Red-lead, one of the higher oxides, is preferred to litharge, although immediately reduced to protoxide by the heat, the liberated oxygen serving to destroy any combustible matter which might accidentally find its way into the crucible, and stain the glass by reducing a portion of the lead. Potassa gives a better glass than soda, although the latter is very generally employed, from its lower price. A certain proportion of broken and waste glass of the same kind is always added to the other materials.

Articles of blown glass are thus made:—The workman begins by collecting a proper quantity of soft, pasty glass at the end of his *blow-pipe*, an iron tube, five or six feet in length, terminated by a mouth-piece of wood; he then commences blowing, by which the lump is expanded into a kind of flask, susceptible of having its form modified by the position in which it is held, and the velocity of rotation continually given to the iron tube. If an open-mouthed vessel is to be made, an iron rod, called a *pontil* or *puntil*, is dipped into the glass-pot and applied to the bottom of the flask, to which it thus serves as a handle, the blowpipe being removed by the application of a cold iron to the neck. The vessel is then re-heated at a hole left for the purpose in the wall of the furnace, and the aperture enlarged, and the vessel otherwise altered in figure by the aid of a few simple tools, until completed. It is then detached, and carried to the annealing oven, where it undergoes slow and gradual cooling during many hours, the object of which is to obviate the excessive brittleness always exhibited by glass which has been quickly cooled. The large circular *tables* of crown-glass are made by a very curious process of this kind; the globular flask at first produced, transferred from the blowpipe to the pontil, is suddenly made to assume the form of a flat disc by the centrifugal force of the rapid rotatory movement given to the rod. Plate-glass is cast upon a flat metal table, and after very careful annealing, ground true and polished by suitable machinery. Tubes are made by rapidly drawing out a hollow cylinder; and from these a great variety of useful small apparatus may be constructed with the

help of a lamp and blowpipe, or still better, the bellows-table of the barometer-maker. Small tubes may be bent in the flame of a spirit-lamp or gas-jet, and cut with great ease by a file, a scratch being made, and the two portions pulled or broken asunder in a way easily learned by a few trials.

Specimens of the two chief varieties of glass gave the following results on analysis:—

Bohemian plate-glass (excellent).*		English flint-glass.†	
Silica	60·0	Silica	51·93
Potassa	25·0	Potassa	13·77
Lime	12·5	Oxide of lead . .	33·28
	<hr/> 97·5		<hr/> 98·98

The difficultly-fusible white Bohemian tube, so invaluable in organic chemistry, has been found to contain, in 100 parts—

Silica	72·80
Lime, with trace of alumina . . .	9·68
Magnesia	·40
Potassa	16·80
Traces of manganese, &c., and loss	·32

Different colours are often communicated to glass by metallic oxides. Thus, oxide of cobalt gives deep blue; oxide of manganese, amethyst; suboxide of copper, ruby-red; black oxide of copper, green; the oxides of iron, dull green or brown, &c. These are either added to the melted contents of the glass-pot, in which they dissolve, or applied in a particular manner to the surface of the plate or other object, which is then re-heated, until fusion of the colouring matter occurs: such is the practice of enamelling and glass-painting. An opaque white appearance is given by oxide of tin; the enamel of watch faces is thus prepared.

When silica is melted with twice its weight of carbonate of potassa or soda, and the product treated with water, the greater part dissolves, yielding a solution from which acids precipitate gelatinous silica. This is the *soluble glass* sometimes mentioned by chemical writers; its solution has been used for rendering muslin and other fabrics of cotton or linen less combustible.

PORCELAIN AND EARTHENWARE.—The plasticity of natural clays, and their hardening when exposed to heat, are properties which suggested in very early times their application to the making of vessels for the various purposes of daily life: there are few branches of industry of higher antiquity than that exercised by the potter.

True porcelain is distinguished from earthenware by very obvious

* Mitscherlich, Lehrbuch, ii. 187.

† Faraday.

characters. In porcelain the *body* of the ware is very compact and translucent, and breaks with a conchoidal fracture, symptomatic of a commencement of fusion. The glaze, too, applied for giving a perfectly smooth surface, is closely adherent, and in fact graduates by insensible degrees into the substance of the body. In earthenware, on the contrary, the fracture is open and earthy, and the glaze detachable with greater or less facility. The compact and partly glassy character of porcelain is the result of the admixture with the clay of a small portion of some substance, fusible at the temperature to which the ware is exposed when baked or fired, and which, absorbed by the more infusible portion, binds the whole into a solid mass on cooling; such substances are found in felspar, and in a small admixture of silicate of lime, or alkali. The clay employed in porcelain-making is always directly derived from decomposed felspar, none of the clays of the secondary strata being pure enough for the purpose; it must be white, and free from oxide of iron. To diminish the contraction which this substance undergoes in the fire, a quantity of finely-divided silica, carefully prepared by crushing and grinding calcined flints or chert, is added, together with a proper proportion of felspar or other fusible material, also reduced to impalpable powder. The utmost pains are taken to effect perfect uniformity of mixture, and to avoid the introduction of particles of grit, or other foreign bodies. The ware itself is fashioned either on the potter's wheel;—a kind of vertical lathe;—or in moulds of plaster of Paris, and dried, first in the air, afterwards by artificial heat, and at length completely hardened by exposure to the temperature of ignition. The porous *biscuit* is now fit to receive its glaze, which may be either ground felspar, or a mixture of gypsum, silica, and a little porcelain clay, diffused through water. The piece is dipped for a moment into this mixture, and withdrawn; the water sinks into its substance, and the powder remains evenly spread upon its surface; it is once more dried, and lastly, fired at an exceedingly-high temperature.

The porcelain-furnace is a circular structure of masonry, having several fire-places, and surmounted by a lofty dome. Dry wood or coal is consumed as fuel, and its flame directed into the interior, and made to circulate around and among the earthen cases, or *seggars* in which the articles to be fired are packed. Many hours are required for this operation, which must be very carefully managed. After the lapse of several days, when the furnace has completely cooled, the contents are removed in a finished state, so far as regards the ware.

The ornamental part, consisting of gilding and painting in enamel, has yet to be executed, after which the pieces are again heated, in order to flux the colours. This operation has sometimes to be repeated more than once.

The manufacture of porcelain in Europe is of modern origin: the Chinese have possessed the art from the commencement of the seventh century, and their ware is, in some respects, altogether unequalled.

The materials employed by them are known to be *kaolin*, or decomposed felspar; *petuntze*, or quartz reduced to fine powder; and the ashes of fern, which contain carbonate of potassa.

STONEWARE.—This is a coarse kind of porcelain, made from clay, containing oxide of iron and a little lime, to which it owes its partial fusibility. The glazing is performed by throwing common salt into the heated furnace; this is volatilized, and decomposed by the joint agency of the silica of the ware, and of the vapour of water always present; hydrochloric acid and soda are produced, the latter forming a silicate, which fuses over the surface of the ware, and gives a thin, but excellent glaze.

EARTHENWARE.—The finest kind of earthenware is made from a white secondary clay, mixed with a considerable quantity of silica. The articles are thoroughly dried and fired, after which they are dipped into a readily-fusible glaze mixture, of which oxide of lead is usually an important ingredient, and, when dry, re-heated to the point of fusion of the latter. The whole process is much easier of execution than the making of porcelain, and demands less care. The ornamental designs in blue and other colours, so common upon plates and household articles, are printed upon paper in enamel pigment, mixed with oil, and transferred, while still wet, to the unglazed ware. When the ink becomes dry, the paper is washed off, and the glazing completed.

The coarser kinds of earthenware are sometimes covered with a whitish opaque glaze, which contains the oxides of lead and tin: such glaze is very liable to be attacked by acids, and is dangerous for culinary vessels.

Crucibles, when of good quality, are very valuable to the practical chemist. They are made of clay free from lime, mixed with sand or ground ware of the same description. The Hessian and Cornish crucibles are among the best. Sometimes a mixture of plumbago and clay is employed for the same purpose; and powdered coke has been also used with the earth: such crucibles bear rapid changes of temperature with impunity.

SECTION IV.

OXIDABLE METALS PROPER, WHOSE OXIDES FORM
POWERFUL BASES.

MANGANESE.

MANGANESE is tolerably abundant in nature in an oxidized state, forming, or entering into the composition of, several interesting minerals. Traces of this substance are very frequently found in the ashes of plants.

Metallic manganese, or perhaps, strictly, carbide of manganese, may be best prepared by the following process. The carbonate is calcined in an open vessel, by which it becomes converted into a dense brown powder: this is intimately mixed with a little charcoal, and about one-tenth of its weight of anhydrous borax. A charcoal crucible is next prepared by filling a Hessian or Cornish crucible with moist charcoal powder, introduced a little at a time, and rammed as hard as possible. A smooth cavity is then scooped in the centre, into which the above-mentioned mixture is compressed, and covered with charcoal-powder. The lid of the crucible is then fixed, and the whole arranged in a very powerful wind-furnace. The heat is slowly raised until the crucible becomes red-hot, after which it is urged to its maximum for an hour or more. When cold, the crucible is broken up, and the metallic button of manganese extracted.

Manganese is a greyish-white metal, resembling some varieties of cast-iron; it is hard and brittle, and destitute of magnetic properties. Its specific gravity is about 8. It is fusible with great difficulty, and, when free from iron, oxidizes in the air so readily that it requires to be preserved in naphtha. Water is not sensibly decomposed by manganese in the cold. Dilute sulphuric acid dissolves it with great energy, evolving hydrogen.

The equivalent of manganese is 27.6; its symbol is Mu.

Oxides of Manganese.—Seven different oxides of this metal are

described, but two out of the number are, probably, secondary compounds.

Protoxide	MnO
Sesquioxide	Mn_2O_3
Binoxide	MnO_2
Proto-sesquioxide (red oxide)	$\text{Mn}_3\text{O}_4 = \text{MnO}, \text{Mn}_2\text{O}_3$
Varvicite	$\text{Mn}_4\text{O}_7 = \text{Mn}_2\text{O}_3, 2\text{MnO}_2$
Manganic acid	MnO_3
Permanganic acid	Mn_2O_7

PROTOXIDE, MnO .—When carbonate of manganese is heated in a stream of hydrogen gas, or of vapour of water, the carbonic acid is disengaged, and a green-coloured powder left behind, which is the protoxide. Prepared at a dull red-heat only, the protoxide is so prone to absorb oxygen from the air, that it cannot be removed from the tube without change; but when made at a higher temperature, it appears more stable. This oxide is a very powerful base, being isomorphous with magnesia and zinc; it dissolves quietly in dilute acids, neutralizing them completely and forming salts, which have often a beautiful pink colour. When alkalis are added to solutions of these compounds the white hydrated oxide first precipitated speedily becomes brown by passing into a higher state of oxidation.

SESQUIOXIDE, Mn_2O_3 .—This compound occurs in nature in the state of hydrate; a very beautiful crystallized variety is found at Ilfeld, in the Hartz. It is produced artificially, by exposing to the air the hydrated protoxide, and forms the principal part of the residue left in the iron retort when oxygen gas is prepared by exposing the native binoxide to a moderate red-heat. The colour of the sesquioxide is brown or black, according to its origin or mode of preparation. It is a feeble base, isomorphous with alumina; for, when gently heated with diluted sulphuric acid, it dissolves to a red liquid, which, on the addition of sulphate of potassa or of ammonia, deposits octahedral crystals having the constitution of common alum; these are, however, decomposed by water. Strong nitric acid resolves this oxide into a mixture of protoxide and binoxide, the former dissolving, and the latter remaining unaltered; while hot oil of vitriol destroys it by forming sulphate of the protoxide, and liberating oxygen gas. Heated with hydrochloric acid, chlorine is evolved, as with the binoxide, but to a smaller extent.

BINOXIDE, MnO_2 .—The most common ore of manganese; it is found both massive and crystallized. It may be obtained artificially in the anhydrous state by gently calcining the nitrate, or in combination with water, by adding solution of bleaching powder to a salt of the protoxide. Binoxide of manganese has a black colour, is insoluble in water, and refuses to unite with acids. It is decomposed by

hot hydrochloric acid and by oil of vitriol in the same manner as the sesquioxide.

As this substance is an article of commerce of considerable importance, being used in very large quantity for making chlorine, and as it is subject to great alteration of value from an admixture of the sesquioxide and several impurities, it becomes desirable to possess means of assaying different samples that may be presented, with a view of testing their fitness for the purposes of the manufacturer. One of the best and most convenient methods is the following:—50 grains of the mineral, reduced to very fine powder, are put into the little vessel employed in the analysis of carbonates,* together with about half an ounce of cold water, and 100 grains of strong hydrochloric acid; 50 grains of crystallized oxalic acid are then added, the cork carrying the chloride of calcium tube is fitted, and the whole quickly weighed or counterpoised. The application of a gentle heat suffices to determine the action; the disengaged chlorine converts the oxalic acid into carbonic acid, with the help of the elements of water, two equivalents of carbonic acid representing one of chlorine, and consequently one of binoxide of manganese. Now, the equivalent of the latter substance, 43·6, is so nearly equal to twice that of carbonic acid, 22, that the loss of weight suffered by the apparatus when the reaction has become complete, and the residual gas has been driven off by momentary ebullition, may be taken to represent the quantity of real binoxide in the 50 grains of the sample. It is obvious that the little apparatus of Will and Fresenius, described at page 266, may be used with the same advantage.

RED OXIDE, Mn_3O_4 , or probably $\text{MnO} + \text{Mn}_2\text{O}_3$.—This oxide is also found native, and is produced artificially by heating to whiteness the binoxide or sesquioxide, or by exposing the protoxide or carbonate to a red-heat in an open vessel. It is a reddish-brown substance, incapable of forming salts, and acted upon by acids in the same manner as the two higher oxides already described. Borax and glass in a fused state dissolve this substance, and acquire the colour of the amethyst.

VARVICITE, Mn_4O_7 , or $\text{Mn}_2\text{O}_3 + 2\text{MnO}_2$.—A natural production, discovered by Mr. Phillips, among certain specimens of manganese-ore from Warwickshire: it has also been found at Ilfeld. It much resembles the binoxide, but is harder and more brilliant, and contains water. By a strong heat, varvicite is converted into red oxide, with disengagement of aqueous vapour and oxygen gas.

CHLORIDE OF MANGANESE, MnCl .—This salt may be prepared in a state of purity from the dark-brown liquid residue of the preparation of chlorine from binoxide of manganese and hydrochloric acid, which often accumulates in the laboratory to a considerable extent in the course of investigation: from the pure chloride, the

* See page 266.

carbonate and all other salts can be conveniently obtained. The liquid referred to consists chiefly of the mixed chlorides of manganese and iron; it is filtered, evaporated to perfect dryness, and then slowly heated to dull ignition in an earthen vessel, with constant stirring. The chloride of iron is thus either volatilized or converted by the remaining water into insoluble sesquioxide, while the manganese-salt is unaffected. On treating the greyish-looking powder thus obtained with water, the chloride of manganese is dissolved out, and may be separated by filtration from the sesquioxide of iron. Should a trace of the latter yet remain, it may be got rid of by boiling the liquid for a few minutes with a little carbonate of manganese. The solution of chloride has usually a delicate pink colour, which becomes very manifest when the salt is evaporated to dryness. A strong solution deposits rose-coloured tabular crystals, which contain 4 equivalents of water; these are very soluble and deliquescent. The chloride is fusible at a red-heat, is decomposed slightly at that temperature by contact of air, and is dissolved by alcohol, with which it forms a crystallizable compound.

SESQUICHLORIDE, Mn_2Cl_3 .—When precipitated sesquioxide of manganese is put into cold dilute hydrochloric acid, it dissolves quietly, forming a red solution of sesquichloride. Heat disengages chlorine, and occasions the production of protochloride.

SULPHATE OF PROTOXIDE OF MANGANESE, $MnO, SO_3 + 7HO$.—A beautiful rose-coloured and very soluble salt, isomorphous with sulphate of magnesia. It is prepared on a large scale for the use of the dyer, by heating, in a close vessel, binoxide of manganese and coal, and dissolving the impure protoxide thus obtained in sulphuric acid, with the addition of a little hydrochloric acid towards the end of the process. The solution is evaporated to dryness, and again exposed to a red-heat, by which the sulphate of sesquioxide of iron is decomposed. Water then dissolves out the pure sulphate of manganese, leaving the sesquioxide of iron behind. The salt is used to produce a permanent brown dye, the cloth steeped in the solution being afterwards passed through a solution of bleaching-powder, by which the protoxide is changed to insoluble hydrate of the binoxide. Sulphate of manganese sometimes crystallizes with five equivalents of water. It forms a double salt with sulphate of potassa.

CARBONATE OF MANGANESE.—Prepared by precipitating the protochloride by an alkaline carbonate. It is insoluble and buff-coloured, or sometimes nearly white. Exposed to heat, it loses carbonic acid and absorbs oxygen.

MANGANIC ACID, MnO_3 .—When an oxide of manganese is fused with an alkali, an additional quantity of oxygen is taken up from the air, and a deep-green saline mass results, which contains a salt of the new acid, thus formed under the influence of the base. The addition

of nitre, or chlorate of potassa, facilitates the productions of manganic acid. Water dissolves this compound very readily, and the solution, concentrated by evaporation in *vacuo*, yields green crystals.

PERMANGANIC ACID, Mn_2O_7 .—When manganate of potassa, free from any great excess of alkali, is put into a large quantity of water, it is resolved into hydrated binoxide of manganese, which subsides, and a deep-purple liquid, containing permanganate of potassa. This effect is accelerated by heat. The changes of colour accompanying this decomposition are very remarkable, and have procured for the substance the name *mineral chameleon*; excess of alkali hinders, in some measure, the reaction, by conferring greater stability on the manganate. Permanganate of potassa is easily prepared on a considerable scale. Equal parts of very finely-powdered binoxide of manganese and chlorate of potassa are mixed with rather more than one part of hydrate of potassa dissolved in a little water, and the whole exposed, after evaporation to dryness, to a temperature just short of ignition. The mass is treated with hot water, the insoluble oxide separated by decantation, and the deep-purple liquid concentrated by heat, until crystals form upon its surface; it is then left to cool. The crystals have a dark-purple colour, and are not very soluble in cold water. The manganates and permanganates are decomposed by contact with organic matter; the former are said to be isomorphous with the sulphates, and the latter with the perchlorates.

Salts of the protoxide of manganese are very easily distinguished by reagents.

The fixed caustic alkalis, and ammonia, give white precipitates, insoluble in excess, quickly becoming brown.

The carbonates of the fixed alkalis, and carbonate of ammonia, give white precipitates, but little subject to change, and insoluble in excess of carbonate of ammonia.

Sulphuretted hydrogen gives no precipitate, but sulphide of ammonium throws down insoluble, flesh-coloured sulphide of manganese, which is very characteristic.

Ferrocyanide of potassium gives a white precipitate.

Manganese is also easily detected by the blowpipe; it gives with borax an amethystine bead in the outer or oxidizing flame, and a colourless one in the inner flame. Heated upon platinum foil with carbonate of soda, it yields a green mass of manganate of soda.

IRON.

This is by very far the most important member of the group of metals under discussion: there are few substances to which it yields in interest, when it is considered how very intimately the knowledge of the properties and uses of iron is connected with human civilization.

Metallic iron is of exceedingly rare occurrence; it has been found at Canaan, in Connecticut,* forming a vein about two inches thick in mica-slate, but it invariably enters into the composition of those extraordinary stones known to fall from the air, called *meteorites*. Isolated masses of soft malleable iron also, of large dimensions, lie loose upon the surface of the earth in South America and elsewhere, and are presumed to have had a similar origin: these latter contain, in common with the iron of the undoubted meteorites, nickel. In an oxidized condition, the presence of iron may be said to be universal: it constitutes a great part of the common colouring matter of rocks and soils; it is contained in plants, and forms an essential component of the blood of the animal body. In the state of bisulphide it is also very common. Pure iron may be prepared, according to Mitscherlich, by introducing into a Hessian crucible 4 parts of fine iron wire cut small, and 1 part of black oxide of iron. This is covered with a mixture of white sand, lime, and carbonate of potassa, in the proportions used for glass-making, and a cover being closely applied, the crucible is exposed to a very high degree of heat. A button of pure metal is thus obtained, the traces of carbon and silicium present in the wire having been removed by the oxygen of the oxide.

Pure iron has a white colour and perfect lustre; it is extremely soft and tough, and has a specific gravity of 7.8. The crystalline form is probably the cube, to judge from appearances now and then exhibited. In good bar-iron or wire a distinct fibrous texture may always be observed when the metal has been attacked by rusting or by the application of an acid, and upon the perfection of this fibre much of its strength and value depends. Iron is the most tenacious of all the metals, a wire $\frac{1}{32}$ of an inch in diameter bearing a weight of 60 lbs. It is very difficult of fusion, and before becoming liquid passes through a soft or pasty condition. Pieces of iron pressed or hammered together in this state cohere into a single mass: the operation is termed *welding*, and is usually performed by sprinkling a little sand over the heated metal, which combines with the superficial film of oxide, forming a fusible silicate, which is subsequently forced out from between the pieces of iron by the pressure applied; clean surfaces of

* Phillip's Mineralogy, fourth edit., p. 208.

metal are thus presented to each other, and union takes place without difficulty.

Iron does not oxidize in dry air at common temperatures: heated to redness, it becomes covered with a scaly coating of black oxide, and at a high white-heat burns brilliantly, producing the same substance. In oxygen gas the combustion occurs with still greater ease. The finely-divided spongy metal, prepared by reducing the red oxide by hydrogen gas, takes fire spontaneously in the air. Pure water, free from air and carbonic acid, does not tarnish a surface of polished iron, but the combined agency of free oxygen and moisture speedily leads to the production of rust, which is a hydrate of the sesquioxide. The rusting of iron is wonderfully promoted by the presence of a little acid vapour. At a red-heat iron decomposes water, evolving hydrogen, and passing into the black oxide. Dilute sulphuric and hydrochloric acids dissolve it freely with separation of hydrogen. Iron is strongly magnetic up to a red-heat, when it loses all traces of that remarkable property.

The equivalent of iron is 28, and its symbol Fe.

Four compounds of iron and oxygen are described.

Protoxide	.	.	.	Fe O
Sesquioxide (peroxide)	.	.	.	Fe ₂ O ₃
Protos sesquioxide (black oxide)	.	.	.	Fe ₃ O ₄ = FeO, Fe ₂ O ₃
Ferrie acid	.	.	.	Fe O ₃ .

PROTOXIDE, FeO.—This is a very powerful base, neutralizing acids completely, and isomorphous with magnesia, oxide of zinc, &c. It is almost unknown in a separate state, from its extreme proneness to absorb oxygen and pass into the sesquioxide. When a salt of this substance is mixed with caustic alkali or ammonia, a bulky whitish precipitate of hydrate of the protoxide falls, which becomes nearly black when boiled, the water being separated. This hydrate exposed to the air, very rapidly changes, becoming green and ultimately red-brown. The soluble salts of protoxide of iron have commonly a delicate pale-green colour, and a nauseous *metallic* taste.

SESQUIOXIDE, Fe₂O₃.—A feeble base, isomorphous with alumina. Sesquioxide of iron occurs native, most beautifully crystallized as specular iron ore in the island of Elba, and elsewhere; also as red and brown *hematites*, the latter being a hydrate. It is artificially prepared by precipitating a solution of sulphate of the sesquioxide or the sesquichloride of iron by excess of ammonia, and washing, drying, and igniting the yellowish-brown hydrate thus produced: fixed alkali must not be used in this operation, as a portion is retained by the oxide. In fine powder, this oxide has a full red colour, and is used as a pigment, being prepared for the purpose by calcination of the sulphate of the protoxide; the tint varies somewhat with the temper-

ature to which it has been exposed. This oxide is unaltered in the fire, although easily reduced at a high temperature by carbon or hydrogen. It dissolves in acids, with difficulty after strong ignition, forming a series of reddish salts, which have an acid reaction and an astringent taste. Sesquioxide of iron is not acted upon by the magnet.

BLACK OXIDE; MAGNETIC OXIDE; LOADSTONE, Fe_3O_4 , or probably $\text{FeO} + \text{Fe}_2\text{O}_3$.—A natural product, one of the most valuable of the iron ores, often found in regular octahedral crystals, which are magnetic. It may be prepared by mixing due proportions of salts of the protoxide and sesquioxide of iron, precipitating them by excess of alkali, and then boiling the mixed hydrates, when the latter unite to a black sandy substance, consisting of minute crystals of the magnetic oxide. This oxide is the chief product of the oxidation of iron at a high temperature in the air and in aqueous vapour. It is incapable of forming salts.

FERRIC ACID, FeO_3 .—A very remarkable compound of recent discovery. The simplest mode of preparing it is to heat to full redness, for an hour, in a covered crucible, a mixture of one part of pure sesquioxide of iron, and four parts of dry nitre. The brown, porous, deliquescent mass is treated when cold with ice-cold water, by which a deep amethystine red solution of ferrate of potassa is obtained. This gradually decomposes even in the cold, evolving oxygen gas, and depositing sesquioxide; by heat the decomposition is very rapid. The solution of ferrate of potassa gives no precipitate with salts of lime, magnesia, or strontia, but when mixed with one of baryta, a deep crimson, insoluble compound falls, which is a ferrate of that base, and is very permanent.

PROTOCHLORIDE OF IRON, FeCl .—Formed by transmitting dry hydrochloric acid gas over red-hot metallic iron, or by dissolving iron in hydrochloric acid. The latter solution yields, when duly concentrated, green crystals of the protochloride, containing 4 equivalents of water; they are very soluble and deliquescent, and rapidly oxidize in the air.

SESQUICHLORIDE OF IRON, Fe_2Cl_3 .—Usually prepared by dissolving sesquioxide in hydrochloric acid. The solution, evaporated to a syrupy consistence, deposits red, hydrated crystals, which are very soluble in water and alcohol. It forms double salts with chloride of potassium and sal-ammoniac. When evaporated to dryness and strongly heated, much of the chloride is decomposed, yielding sesquioxide and hydrochloric acid: the remainder sublimes, and afterwards condenses in the form of small brilliant red crystals, which deliquesce rapidly. The solution of sesquichloride of iron is capable of dissolving a large excess of recently-precipitated hydrate of the sesquioxide, by which it acquires a much darker colour. Anhydrous sesquichloride of iron is also produced by the action of chlorine upon the heated metal.

PROTIODIDE OF IRON, FeI .—This is an important medicinal preparation; it is easily made by digesting iodine with water and

metallic iron. The solution is pale green, and yields, on evaporation, crystals resembling those of the chloride, which rapidly oxidize on exposure to air. It is best preserved in solution in contact with excess of iron. A sesqui-iodide of iron exist, which is yellowish-red and soluble.

SULPHIDES OF IRON.—Several compounds of iron and sulphur are described: of these the two most important are the following. *Protosulphide*, FeS , is a blackish, brittle substance, attracted by the magnet, formed by heating together iron and sulphur. It is dissolved by dilute acids with evolution of sulphuretted hydrogen gas, and is constantly employed for that purpose in the laboratory, being made by projecting into a red-hot crucible a mixture of $2\frac{1}{2}$ parts of sulphur and 4 parts of iron filings or borings of cast-iron, and excluding the air as much as possible. The same substance is formed when a bar of white-hot iron is brought in contact with sulphur. The *bisulphide of iron*, FeS_2 , iron pyrites, is a natural product, occurring in rocks of all ages, and evidently formed in many cases by the gradual de-oxidation of sulphate of iron by organic matter. It has a brass-yellow colour, is very hard, not attracted by the magnet, and not acted upon by dilute acids. Exposed to heat, sulphur is expelled, and an intermediate sulphide, analogous probably to the black oxide, is produced. This substance also occurs native, under the name of *magnetic pyrites*. The bisulphide is sometimes used in the manufacture of sulphuric acid.

Compounds of iron with phosphorus, carbon, and silicium exist, but little is known respecting them in a definite state. The carbide is contained in cast-iron and in steel, to which it communicates ready fusibility; the silicium-compound is also found in cast-iron. Phosphorus is a very hurtful substance in bar-iron, as it renders it brittle or *cold-short*.

SULPHATE OF PROTOXIDE OF IRON; GREEN VITRIOL, $\text{FeO}, \text{SO}_3 + 7\text{HO}$.—This beautiful and important salt may be obtained by directly dissolving iron in dilute sulphuric acid; it is generally prepared, however, and that on a very large scale, by contact of air and moisture with common iron pyrites, which, by absorption of oxygen, readily furnishes the substance in question. Heaps of this material are exposed to the air until the decomposition is sufficiently advanced; the salt produced is then dissolved out by water, and the solution made to crystallize. It forms large green crystals, of the composition above stated, which slowly effloresce and oxidize in the air; it is soluble in about twice its weight of cold water. Crystals containing 4, and also 2 equivalents of water, have been obtained. Sulphate of protoxide of iron forms double salts with the sulphates of potassa and ammonia.

SULPHATE OF SESQUIOXIDE OF IRON, $\text{Fe}_2\text{O}_3, 3\text{SO}_3$.—Prepared by adding to a solution of the protosalt exactly one-half as much sulphuric acid as it already contains, raising the liquid to the boiling-point, and

then dropping in nitric acid until the solution ceases to blacken by such addition. The red liquid thus obtained furnishes, on evaporation to dryness, a buff-coloured amorphous mass, which, when put into water, very slowly dissolves. With the sulphates of potassa and ammonia, this salt yields compounds, having the form and constitution of the alums; the crystals are nearly destitute of colour. These latter are decomposed by water, and sometimes by long keeping when in a dry state. They are best prepared by exposing to spontaneous evaporation a solution of sulphate of sesquioxide of iron, to which sulphate of potassa or of ammonia has been added.

NITRATE OF THE PROTOXIDE OF IRON, FeO, NO_3 .—When dilute cold nitric acid is made to act to saturation upon protosulphide of iron, and the solution evaporated in vacuo, pale-green and very soluble crystals of protonitrate are obtained, which are very subject to alteration. The *nitrate* of the sesquioxide is readily formed by pouring nitric acid, slightly diluted, upon iron; it is a deep-red liquid, apt to deposit an insoluble basic salt, and is used in dyeing.

CARBONATE OF PROTOXIDE OF IRON, FeO, CO_2 .—The white precipitate obtained by mixing solutions of protosalt of iron and alkaline carbonate: it cannot be washed and dried without losing carbonic acid and absorbing oxygen. This substance occurs in nature as *spathose iron ore*, associated with variable quantities of carbonate of lime and of magnesia; and also in the common *clay iron-stone*, from which nearly all the British iron is made. It is often found in mineral waters, being soluble in excess of carbonic acid; such waters are known by the rusty matter they deposit by exposure to the air. No carbonate of the sesquioxide is known.

The phosphates of iron are all insoluble.

Salts of the protoxide of iron are thus distinguished:—

Caustic alkalis, and ammonia, give nearly white precipitates, insoluble in excess of the reagent, rapidly becoming green, and ultimately brown, by exposure to air.

Alkaline carbonates, and carbonate of ammonia, throw down the white carbonate, also very subject to change.

Sulphuretted hydrogen gives no precipitate, but sulphide of ammonium throws down black protosulphide of iron, soluble in dilute acids.

Ferrocyanide of potassium gives a nearly-white precipitate, becoming deep blue on exposure to air.

Salts of the sesquioxide are thus characterized:—

Caustic alkalis, and ammonia, give foxy-red precipitates of hydrated sesquioxide, insoluble in excess.

The carbonates behave in a similar manner, the carbonic acid escaping.

Sulphuretted hydrogen gives a nearly white-precipitate of sulphur, and reduces the sesquioxide to protoxide.


Sulphide of ammonium gives a black precipitate, slightly soluble in excess.

Ferrocyanide of potassium yields Prussian blue.

Tincture or infusion of gall-nuts strikes intense bluish-black with the most dilute solutions of salts of sesquioxide of iron.

Iron Manufacture.—This most important branch of industry consists, as now conducted, of two distinct parts; viz., the production from the ore of a fusible (carbide) of iron, and the subsequent decomposition of the carbide, and its conversion into pure or malleable iron.

Fig. 145.



The clay iron ore is found in association with coal, forming thin beds or nodules: it consists, as already mentioned, of carbonate of iron mixed with clay; sometimes lime and magnesia are also present. It is broken in pieces, and exposed to heat in a furnace resembling a lime kiln, by which the water and carbonic acid are expelled, and the ore rendered dark-coloured, denser, and also magnetic; it is then ready for reduction. The furnace in which this operation is performed is

usually of very large dimensions, fifty feet or more in height, and constructed of brickwork with great solidity, the interior being lined with excellent fire-bricks: the figure will be at once understood from the sectional drawing. The furnace is close at the bottom, the fire being maintained by a powerful artificial blast introduced by two or three *tuyere-pipes*, as shown in the section. The materials, consisting of due proportions of coke or carbonized coal, roasted ore, and limestone, are constantly supplied from the top, the operation proceeding continuously night and day, often for years, or until the furnace is judged to require repair. In the upper part of the furnace, where the temperature is still very high, and where combustible gases abound, the iron of the ore is probably reduced to the metallic state, being disseminated through the earthy matter of the ore. As the whole sinks down and attains a still higher degree of heat, the iron becomes converted into carbide by *cementation*, while the silica and alumina unite with the lime, purposely added, to a kind of glass or *slag*, nearly free from oxide of iron. The carbide and slag, both in a melted state, reach at last the bottom of the furnace, where they arrange themselves in the order of their densities: the slag flows out at certain apertures contrived for the purpose, and the iron is discharged from time to time, and suffered to run into rude moulds of sand by opening an orifice at the bottom of the recipient, previously stopped with clay. Such is the origin of crude or cast-iron, of which there are several varieties, distinguished by differences of colour, hardness, and composition, and known by the names of *grey*, *black*, and *white* iron. The first is for most purposes the best, as it admits of being filed and cut with perfect ease. The black and grey kinds probably contain a mechanical admixture of graphite, which separates during solidification.

A great improvement has been made in the above-described process, by substituting raw coal for coke, and blowing hot air, instead of cold, into the furnace. This is effected by causing the air, on leaving the blowing-machine, to circulate through a system of red-hot iron pipes, until its temperature becomes high enough to melt lead. This alteration has already effected a prodigious saving in fuel, without, it appears, any injury to the quality of the product.

The conversion of cast into bar iron is effected by an operation called *puddling*; previous to which, however, it commonly undergoes a process, the theory of which is not perfectly intelligible. It is remelted, and suddenly cooled, by which it becomes white, crystalline, and exceedingly hard; in this state it is called *fine metal*. The puddling process is conducted in an ordinary reverberatory furnace, into which the charge of fine-metal is introduced by a side aperture. This is speedily melted by the flame, and its surface covered with a crust of oxide. The workman then by the aid of an iron tool, diligently stirs the melted mass, so as intimately to mix the oxide with the metal; he now and then also throws in a little water, with the view of promoting more rapid oxidation. Small jets of blue flame

soon appear upon the surface of the iron, and the latter, after a time, begins to lose its fluidity, and acquires in succession, a pasty and a granular condition. At this point the fire is strongly urged, the sandy particles once more cohere, and the contents of the furnace now admit of being formed into several large balls or masses, which are then withdrawn, and placed under an immense hammer, moved by machinery, by which each becomes quickly fashioned into a rude bar. This is re-heated, and passed between grooved cast-iron rollers, and drawn out into a long bar or rod. To make the best iron, the bar is cut into a number of pieces, which are afterwards piled or bound together, again raised to a welding heat, and hammered or rolled into a single bar; and this process of *piling* or *fagoting* is sometimes twice or thrice repeated, the iron becoming greatly improved thereby.

The general nature of the change in the puddling furnace is not difficult to explain. Cast-iron consists essentially of iron in combination with carbon and silicium. When strongly heated with oxide of iron, those compounds undergo decomposition, the carbon and silicium becoming oxidized at the expense of the oxygen of the oxide. As this change takes place, the metal gradually loses its fusibility, but retains a certain degree of adhesiveness, so that when at last it comes under the tilt-hammer, or between the rollers, the particles of iron become agglutinated into a solid mass, while the readily-fusible silicate of the oxide is squeezed out and separated.

All these processes are, in Great Britain, performed with coal or coke, but the iron obtained is, in many respects, inferior to that made in Sweden and Russia from the magnetic oxide, by the use of wood charcoal, a fuel too dear to be extensively employed in England. Plate-iron is, however, sometimes made with charcoal.

Steel.—A very remarkable, and most useful substance, prepared by heating iron in contact with charcoal. Bars of Swedish iron are imbedded in charcoal powder, contained in a large rectangular crucible or chest of some substance capable of resisting the fire, and exposed for many hours to a full red-heat. The iron takes up, under these circumstances, from 1·3 to 1·7 per cent. of carbon, becoming harder, and at the same time fusible, with a certain diminution, however, of malleability. The active agent in this cementation process is probably carbonic oxide; the oxygen of the air in the crucible combines with the carbon, to form that substance, which is afterwards decomposed by the heated iron, one-half of its carbon being abstracted by the latter. The carbonic acid thus formed takes up an additional dose of carbon from the charcoal, and again becomes carbonic oxide, the oxygen, or rather the carbonic acid, acting as a carrier between the charcoal and the metal. The product of this operation is called *blistered steel*, from the blistered and rough appearance of the bars: the texture is afterwards improved and equalized by welding a number of these bars together, and drawing the whole out under a light tilt-hammer.

The most perfect kind of steel is that which has undergone fusion, having been cast into ingot-moulds, and afterwards hammered: of this all fine cutting instruments are made; it is difficult to forge, requiring great skill and care on the part of the operator.

Steel may also be made directly from some particular varieties of cast-iron, as that from spathose iron ore, containing a little manganese. The metal is retained, in a melted state, in the hearth of a furnace, while a stream of air plays upon it, and causes partial oxidation; the oxide produced reacts, as before stated, on the carbon of the iron, and withdraws a portion of that element. When a proper degree of stiffness or pastiness is observed in the residual metal, it is withdrawn, and hammered or rolled into bars. The *wootz*, or native steel of India, is probably made in this manner. Annealed cast-iron, sometimes called *run-steel*, is now much employed as a substitute for the more costly products of the forge: the articles, when cast, are imbedded in powdered iron ore, or some earthy material, and, after being exposed to a moderate red-heat for some time, are allowed slowly to cool, by which a very extraordinary degree of softness and malleability is attained. It is very possible that some little decarbonization may take place during this process.

The most remarkable property of steel is that of becoming exceedingly hard when quickly cooled. When heated to redness, and suddenly quenched in cold water, steel, in fact, becomes capable of scratching glass with facility: if re-heated to redness, and once more left to cool slowly, it again becomes nearly as soft as ordinary iron; and between these two conditions, any required degree of hardness may be attained. The articles, forged into shape, are first hardened in the manner described; they are then *tempered*, or *let down*, by exposure to a proper degree of annealing heat, which is often judged of by the colour of the thin film of oxide which appears on the polished surface. Thus, a temperature of about 430° (221°C), indicated by a faint straw-colour, gives the proper temper for razors; that for scissors, pen-knives, &c., will be comprised between 470° (243°C) and 490° (254°C), and be attended by a full-yellow or brown tint. Swords and watch-springs require to be softer and more elastic, and must be heated to 550° (288°C) or 560° (293°C), or until the surface becomes deep blue. Attention to these colours has now become of less importance, as metal baths are often substituted for the open fire in this operation.

CHROMIUM.

Chromium is found in the state of oxide, in combination with oxide of iron, in some abundance in the Shetland Islands, and elsewhere; as chromate of lead it constitutes a very beautiful mineral, from which it was first obtained. The metal itself is got in a half-fused condition by mixing the oxide with $\frac{1}{3}$ of its weight of charcoal-powder, enclosing the mixture in a crucible lined with charcoal, and then subjecting it to the very highest heat of a powerful furnace. It is hard, greyish-white, and brittle; of 5.9 specific gravity, and exceedingly difficult of fusion. Chromium is but little oxidable, being scarcely attacked by the most powerful acids: it forms at least four compounds with oxygen, corresponding to, and probably isomorphous with, those of iron.

The equivalent of chromium is 26.7; its symbol is Cr.

PROTOXIDE OF CHROMIUM, CrO .—When potassa is added to a solution of the protochloride of chromium, a brown precipitate falls, which speedily passes to deep foxy-red, with disengagement of hydrogen. The protoxide, in the state of the pale-greenish hydrate, is perhaps obtained when ammonia is substituted for potassa in the preceding experiment. This substance is a powerful base, forming pale-blue salts, which absorb oxygen with extreme avidity. The double sulphate of protoxide of chromium and potassa contains 6 eq. of water, like the other members of the same group.

PROTOSSESQUIOXIDE OF CHROMIUM, $\text{CrO} + \text{Cr}_2\text{O}_3$, is the above brownish-red precipitate produced by the action of water upon the protoxide. The decomposition is not complete without boiling. This oxide corresponds with the magnetic oxide of iron, and is not salifiable.

SESQUIOXIDE OF CHROMIUM, Cr_2O_3 .—When chromate of mercury, prepared by mixing solutions of the nitrate of suboxide of mercury and of chromate or bichromate of potassa, is exposed to a red-heat, it is decomposed, pure sesquioxide of chromium having a fine green colour remaining. In this state the oxide is, like alumina after ignition, insoluble in acids. From a solution of sesquioxide of chromium in potassa or soda, green gelatinous hydrated sesquioxide of chromium is separated on standing. When finely powdered and dried over sulphuric acid, its formula is $\text{Cr}_2\text{O}_3 + 6\text{HO}$. A hydrate may also be had by boiling a somewhat dilute solution of bichromate of potassa, strongly acidulated by hydrochloric acid, with small successive portions of sugar or alcohol. In the former case, carbonic acid escapes; in the latter a substance called aldehyde and also acetic acid are formed, substances with which we shall become acquainted in organic chemistry; and the chromic acid of the salt becomes converted into sesquichloride of chromium, the colour of the liquid changing from red to deep

green. A slight excess of ammonia precipitates the hydrate from this solution. It has a pale purplish-green colour, which becomes full green on ignition: an extraordinary shrinking of volume and sudden incandescence are observed when the hydrate is decomposed by heat. Anhydrous sesquioxide in a beautifully-crystalline condition may be prepared by heating to full redness in an earthen crucible bichromate of potassa. One-half of the acid suffers decomposition, oxygen being disengaged, and oxide of chromium left. The melted mass is then treated with water, which dissolves out neutral chromate of potassa, and the oxide is, lastly, washed and dried. Sesquioxide of chromium communicates a fine green tint to glass, and is used in enamel-painting.

The sesquioxide of chromium is a feeble base, resembling, and isomorphous with, sesquioxide of iron and alumina: the salts it forms have a green or purple colour, and are said to be poisonous.

The sulphate of sesquioxide of chromium is prepared by dissolving the hydrated oxide in dilute sulphuric acid. It unites with the sulphates of potassa and of ammonia, giving rise to magnificent salts which crystallize in regular octahedrons of a deep-claret colour, and possess a constitution resembling that of common alum, the alumina being replaced by sesquioxide of chromium. The finest crystals of chromium-alum are obtained by spontaneous evaporation, the solution being apt to be decomposed by heat.

PROTOCHLORIDE OF CHROMIUM, CrCl .—The violet-coloured sesquichloride of chromium, contained in a porcelain or glass tube, is heated to redness in a current of perfectly dry and pure hydrogen gas; hydrochloric acid is disengaged, and a white foliated mass is obtained, which dissolves in water with great elevation of temperature, yielding a blue solution, which, by exposure to the air, absorbs oxygen with extraordinary energy, acquiring a deep-green colour, and passing into the state of oxychloride of chromium, $2\text{Cr}_2\text{Cl}_3, \text{Cr}_2\text{O}_3$. The protochloride of chromium is one of the most powerful reducing or de-oxidizing agents known.

SESQUICHLORIDE OF CHROMIUM, Cr_2Cl_3 .—This substance is readily obtained in the anhydrous condition by heating to redness in a porcelain tube a mixture of sesquioxide of chromium and charcoal, and passing dry chlorine gas over it. The sesquichloride sublimes, and is deposited in the cool part of the tube, in the form of beautiful crystalline plates of a pale violet-colour. According to M. Peligot, it is totally insoluble in water under ordinary circumstances, even at a boiling heat. It dissolves, however, and assumes the deep-green hydrated state in water containing an exceedingly minute quantity of the protochloride in solution. The hydration is marked by the evolution of much heat. This remarkable effect must probably be referred to the class of actions known at present under the name of katalysis.*

* See page 211.

The salts of the sesquioxide of chromium are easily recognized.

Caustic alkalis precipitate the hydrated oxide, easily soluble in excess.

Ammonia, the same, but nearly insoluble.

Carbonate of potassa, soda, and ammonia, throw down a green precipitate of carbonate and hydrate, slightly soluble in a large excess.

Sulphuretted hydrogen causes no change.

Sulphide of ammonium precipitates the hydrate of the sesquioxide.

CHROMIC ACID, CrO_3 .—Whenever sesquioxide of chromium is strongly heated with an alkali, in contact with air, oxygen is absorbed and chromic acid generated. Chromic acid may be obtained *nearly* pure, and in a state of great beauty, by the following simple process:—100 measures of a cold saturated solution of bichromate of potassa are mixed with 150 measures of oil of vitriol, and the whole suffered to cool. The chromic acid crystallizes in brilliant crimson-red prisms: the mother-liquor is poured off, and the crystals placed upon a tile to drain, being closely covered by a glass or bell-jar.* Chromic acid is very deliquescent and soluble in water; the solution is instantly reduced by contact with organic matter.

Chromate of Potassa, KO, CrO_3 .—This is the source of all the preparations of chromium: it is made directly from the native *chrome-iron ore*, which is a compound of the sesquioxide of chromium and protoxide of iron, analogous to *magnetic-iron ore*, by calcination with nitre or with carbonate of potassa, the stone being reduced to powder, and heated for a long time with the alkali in a reverberatory furnace. The product, when treated with water, yields a yellow solution, which, by evaporation, deposits anhydrous crystals of the same colour, isomorphous with sulphate of potassa. Chromate of potassa has a cool, bitter, and disagreeable taste, and dissolves in 2 parts of water at 60° ($15^\circ\cdot5\text{C}$).

Bichromate of Potassa, $\text{KO}, 2\text{CrO}_3$.—When sulphuric acid is added to the preceding salt in moderate quantity, one-half of the base is removed, and the neutral chromate converted into bichromate. The new salt, of which immense quantities are manufactured for use in the arts, crystallizes by slow evaporation in beautiful red tabular crystals, derived from an oblique rhombic prism. It melts when heated, and is soluble in 10 parts of water, and the solution has an acid reaction.

Chromate of Lead, PbO, CrO_3 .—On mixing solution of chromate or bichromate of potassa with nitrate or acetate of lead, a brilliant yellow precipitate falls, which is the compound in question; it is the *chrome-yellow* of the painter. When this compound is boiled with lime-water, one-half of the acid is withdrawn, and a subchromate of an orange-red colour left. The subchromate is also formed by adding chromate of lead to fused nitre, and afterwards dissolving out the

* Mr. Warington; Proceedings of Chem. Soc. i. 18

soluble salts by water; the product is crystalline, and rivals vermilion in beauty of tint. The yellow and orange chrome-colours are fixed upon cloth by the alternate application of the two solutions, and in the latter case by passing the dyed stuff through a bath of boiling lime-water.

Chromate of Silver, AgO, CrO_3 .—This salt precipitates as a reddish-brown powder when solutions of chromate of potassa and nitrate of silver are mixed. It dissolves in hot dilute nitric acid, and separates, on cooling, in small ruby-red platy crystals. The chromates of baryta, zinc, and mercury are insoluble; the first two are yellow, the last is brick-red.

PERCHROMIC ACID is obtained, according to Barreswill, by mixing chromic acid with dilute binoxide of hydrogen or bichromate of potassa with a dilute but very acid solution of binoxide of barium in hydrochloric acid, when a liquid is formed of a blue colour, which is removed from the aqueous solution by ether. The composition of this very unstable compound is perhaps Cr_2O_7 .

A salt of chromic acid is at once recognized by its behaviour with solutions of baryta and lead; and also by its colour and capability of furnishing, by deoxidation, the green sesquioxide of chromium.

CHLOROCHROMIC ACID, $\text{CrO}_2 + \text{Cl}$. *—3 parts of bichromate of potassa and $3\frac{1}{2}$ parts of common salt are intimately mixed and introduced into a small glass retort; 9 parts of oil of vitriol are then added, and heat applied as long as dense red vapours arise. The product is a heavy deep-red liquid resembling bromine; it is decomposed by water, with production of chromic and hydrochloric acids.

NICKEL.

Nickel is found in tolerable abundance in some of the metal-bearing veins of the Hartz mountains, and in a few other localities, chiefly as arsenide, the *kupfernichel* of mineralogists, so called from its yellowish-red colour. The word *nickel* is a term of detraction, having been applied by the old German miners to what was looked upon as a kind of false copper ore.

The artificial, or perhaps rather merely fused, product, called *speiss*,

* If this formula be trebled, we obtain $\text{Cr}_3\text{O}_6\text{Cl}_3 = 2\text{CrO}_2, \text{CrCl}_3$, and the substance becomes a compound of 2 eq. of chromic acid and 1 eq. of terchloride of chromium. The terchloride of chromium is not known in the free state.

is nearly the same substance, and may be employed as a source of the nickel-salts. This metal is found in meteoric iron, as already mentioned.

Nickel is easily prepared by exposing the oxalate to a high white heat, in a crucible lined with charcoal. It is a white, malleable metal, having a density of 8.8, a high melting point, and a less degree of oxidability than iron, since it is but little attacked by dilute acids. Nickel is strongly magnetic, but loses this property when heated to 660° (349°C). This metal forms two oxides, only one of which is basic. The equivalent of nickel is 29.6; its symbol is Ni.

PROTOXIDE OF NICKEL, NiO .—This compound is prepared by heating to redness the nitrate, or by precipitating a soluble salt with caustic potassa, and washing, drying, and igniting the apple-green hydrated oxide thrown down. It is an ash-grey powder, freely soluble in acids, which it completely neutralizes, being isomorphous with magnesia, and the other members of the same group. The salts of this substance, when hydrated, have usually a beautiful green colour; in the anhydrous state they are yellow.

SESQUIOXIDE, OR PEROXIDE OF NICKEL, Ni_2O_3 .—This oxide is a black insoluble substance, prepared by passing chlorine through the hydrated oxide suspended in water; chloride of nickel is formed, and the oxygen of the oxide decomposed transferred to a second portion. It is also produced when a salt of nickel is mixed with a solution of bleaching-powder. The sesquioxide is decomposed by heat, and evolves chlorine when put into hot hydrochloric acid.

CHLORIDE OF NICKEL, NiCl .—This is easily prepared by dissolving oxide or carbonate of nickel in hydrochloric acid. A green solution is obtained which furnishes crystals of the same colour, containing water. When rendered anhydrous by heat, the chloride is yellow, unless it contain cobalt, in which case it has a tint of green.

SULPHATE OF NICKEL, $\text{NiO}, \text{SO}_3 + 7\text{HO}$.—This is the most important of the salts of nickel. It forms green prismatic crystals, containing 7 equivalents of water, which require 3 parts of cold water for solution. Crystals with 6 equivalents of water have also been obtained. It forms with the sulphates of potassa and ammonia beautiful double salts, $\text{NiO}, \text{SO}_3 + \text{KO}, \text{SO}_3 + 6\text{HO}$ and $\text{NiO}, \text{SO}_3 + \text{NH}_4\text{O}, \text{SO}_3 + 6\text{HO}$. When a strong solution of oxalic acid is mixed with sulphate of nickel, a pale bluish-green precipitate of oxalate falls after some time, very little nickel remaining in solution. The oxalate can thus be obtained for preparing the metal.

CARBONATE OF NICKEL.—When solutions of sulphate or chloride of nickel and of carbonate of soda are mixed, a pale-green precipitate falls, which is a combination of carbonate and hydrate of nickel. It is readily decomposed by heat.

Pure salts of nickel are conveniently prepared on the small scale from crude speiss or kupfernickel by the following process:—The mineral is broken into small fragments, mixed with from one-fourth

to half its weight of iron-filings, and the whole dissolved in aqua regia. The solution is gently evaporated to dryness, the residuc treated with boiling water, and the insoluble arsenate of iron removed by a filter. The liquid is then acidulated with hydrochloric acid, treated with sulphuretted hydrogen in excess, which precipitates the copper, and, after filtration, boiled with a little nitric acid to bring back the iron to the state of sesquioxide. To the cold and largely-diluted liquid solution of bicarbonate of soda is gradually added, by which the sesquioxide of iron may be completely separated without loss of nickel-salt. Lastly, the filtered solution, boiled with carbonate of soda in excess, yields an abundant pale-green precipitate of carbonate of nickel,* from which all the other compounds may be prepared.

The salts of nickel are well characterized by their behaviour with reagents.

Caustic alkalis give a pale apple-green precipitate of hydrate, insoluble in excess.

Ammonia affords a similar precipitate, which is soluble in excess, with deep purplish-blue colour.

Carbonate of potassa and soda give pale-green precipitates.

Carbonate of ammonia, a similar precipitate, soluble in excess, with blue colour.

Ferrocyanide of potassium gives a greenish-white precipitate.

Cyauide of potassium produces a green precipitate, which dissolves in an excess of the precipitant to an amber-coloured liquid which is re-precipitated by addition of hydrochloric acid.

Sulphuretted hydrogen occasions no change, if the nickel be in combination with a strong acid.

Sulphide of ammonium throws down black sulphide of nickel.

The chief use of nickel in the arts is in the preparation of a white alloy, sometimes called German silver, made by melting together 100 parts of copper, 60 of zinc, and 40 of nickel. This alloy is very malleable, and takes a high polish.

COBALT.

This substance bears, in many respects, an extraordinary resemblance to the metal last described; it is often associated with it in nature, and may be obtained from its compounds by similar means.

* This precipitate may still contain cobalt, which can only be separated from it by very complicated processes, for which the more advanced student is referred to "Liebig and Kopp's Annual Report," ii. 334.

Cobalt is a white, brittle metal, having a specific gravity of 8.5, and a very high melting-point. It is unchanged in the air, and but feebly attacked by dilute hydrochloric and sulphuric acids. It is strongly magnetic. There are two oxides of this metal, corresponding in properties and constitution with those of nickel.

The equivalent of cobalt is 29.55; its symbol is Co.

PROTOXIDE OF COBALT, CoO .—This is grey powder, very soluble in acids, and is a strong base, isomorphous with magnesia, affording salts of a fine red tint. It is prepared by precipitating sulphate or chloride of cobalt with carbonate of soda, and washing, drying, and igniting the precipitate. When the cobalt-solution is mixed with caustic potassa a beautiful blue precipitate falls, which, when heated, becomes violet, and at length dirty red, from absorption of oxygen and a change in the state of hydration.

SESQUIOXIDE OF COBALT, Co_2O_3 .—The sesquioxide is a black, insoluble, neutral powder, obtained by mixing solutions of cobalt and of chloride of lime.

CHLORIDE OF COBALT, CoCl .—The chloride is easily prepared by dissolving the oxide in hydrochloric acid; it gives a deep rose-red solution, which, when sufficiently strong, deposits hydrated crystals of the same colour. When the liquid is evaporated by heat to a very small bulk, it deposits anhydrous crystals which are blue; these latter by contact with water again dissolve to a red liquid. A dilute solution of chloride of cobalt constitutes the well-known *blue sympathetic ink*; characters written on paper with this liquid are invisible from their paleness of colour until the salt has been rendered anhydrous by exposure to heat, when the letters appear blue. When laid aside, moisture is absorbed, and the writing once more disappears. Green sympathetic ink is a mixture of the chlorides of cobalt and nickel.

Chloride of cobalt may be prepared directly from *cobalt-glance*, the native arsenide, by a process exactly similar to that described in the case of nickel.

SULPHATE OF COBALT, $\text{CoO}, \text{SO}_3 + 7\text{HO}$.—This salt forms deep-red crystals, requiring for solution 24 parts of cold water; they are identical in form with those of sulphate of magnesia. It combines with the sulphates of potassa and ammonia, forming double salts, which contain as usual six equivalents of water.

A solution of oxalic acid added to one of sulphate of cobalt occasions, after some time, the separation of nearly the whole of the base in the state of oxalate.

CARBONATE OF COBALT.—The alkaline carbonates produce in solutions of cobalt a pale peach-blossom coloured precipitate of combined carbonate and hydrate, containing $3(\text{CoO}, \text{HO}) + 2(\text{CoO}, \text{CO}_2)$.

The salts of cobalt have the following characters:—

Solution of potassa gives a blue precipitate, changing by heat to violet and red.

Ammonia gives a blue precipitate, soluble with difficulty in excess, with brownish-red colour.

Carbonate of soda affords a pink precipitate.

Carbonate of ammonia, a similar compound, soluble in excess.

Ferrocyanide of potassium gives a greyish-green precipitate.

Cyanide of potassium affords a yellowish-brown precipitate, which dissolves in an excess of the precipitant. The clear solutions, after boiling, may be mixed with hydrochloric acid without giving a precipitate.

Sulphuretted hydrogen produces no change, if the cobalt be in combination with a strong acid.

Sulphide of ammonium throws down black sulphide of cobalt.

Oxide of cobalt is remarkable for the magnificent blue colour it communicates to glass: indeed, this is a character by which its presence may be most easily detected, a very small portion of the substance to be examined being fused with borax on a loop of platinum wire before the blowpipe. The substance called *smalt*, used as a pigment, consists of glass coloured by oxide of cobalt; it is thus made:—The cobalt ore is roasted until nearly free from arsenic, and then fused with a mixture of carbonate of potassa and quartz-sand, free from oxide of iron. Any nickel that may happen to be contained in the ore then subsides to the bottom of the crucible as arsenide: this is the *speiss* of which mention has already been made. The glass, when complete, is removed and poured into cold water; it is afterwards ground to powder and elutriated. *Cobalt-ultramarine* is a fine blue colour prepared by mixing 16 parts of freshly-precipitated alumina with 2 parts of phosphate or arsenate of cobalt: this mixture is dried and slowly heated to redness. By daylight the colour is pure blue, but by artificial light it is violet. *Zaffer* is the roasted cobalt ore mixed with a quantity of siliceous sand, and reduced to fine powder; it is used in enamel-painting. A mixture in due proportions of the oxides of cobalt, manganese, and iron is used for giving a fine black colour to glass.

ZINC.

Zinc is a somewhat abundant metal; it is found in the state of carbonate and sulphide, associated with lead ores in many districts, both in Britain and on the Continent: large supplies are obtained from Silesia. The native carbonate, or *calamine*, is the most valuable of

the zinc ores, and is preferred for the extraction of the metal: it is first roasted to expel water and carbonic acid, mixed with fragments of coke or charcoal, and then distilled at a full red-heat in a large earthen retort; carbonic oxide escapes, while the reduced metal volatilizes and is condensed by suitable means, generally with minute quantities of arsenic.

Zinc is a bluish-white metal, which slowly tarnishes in the air; it has a lamellar, crystalline structure, a density varying from 6.8 to 7.2, and is, under ordinary circumstances, brittle. Between 250° (121°C) and 300° (149°C) it is, on the contrary, malleable, and may be rolled or hammered without danger of fracture, and, what is very remarkable, after such treatment, retains its malleability when cold: the sheet-zinc of commerce is thus made. At 400° ($204^{\circ}\cdot4\text{C}$) it is so brittle that it may be reduced to powder. At 773° ($411^{\circ}\cdot6\text{C}$) it melts: at a bright red-heat it boils and volatilizes, and, if air be admitted, burns with a splendid green light, generating the oxide. Dilute acids dissolve zinc very readily; it is constantly employed in this manner in preparing hydrogen gas.

The equivalent of zinc has been fixed at 32.6; its symbol is Zn.

PROTOXIDE OF ZINC, ZnO .—Only one oxide of this metal is known to exist; it is a strong base, isomorphous with magnesia; it is prepared either by burning zinc in atmospheric air, or by heating to redness the carbonate. Oxide of zinc is a white tasteless powder, insoluble in water, but freely dissolved by acids. When heated it is yellow, but turns white again on cooling.

SULPHATE OF ZINC; WHITE-VITRIOL; $\text{ZnO}, \text{SO}_3 + 7\text{HO}$. This salt is hardly to be distinguished by the eye from sulphate of magnesia; it is prepared either by dissolving the metal in dilute sulphuric acid, or, more economically, by roasting the native sulphide, or *blende*, which, by absorption of oxygen, becomes in great part converted into sulphate of the oxide. The altered mineral is thrown hot into water, and the salt obtained by evaporating the clear solution. Sulphate of zinc has an astringent metallic taste, and is used in medicine as an emetic. The crystals dissolve in $2\frac{1}{2}$ parts of cold, and in a much smaller quantity of hot water. Crystals containing 6 equivalents of water have been observed. Sulphate of zinc forms double salts with the sulphates of potassa and ammonia.

CARBONATE OF ZINC, ZnO, CO_2 .—The neutral carbonate is found native; the white precipitate obtained by mixing solutions of zinc and of alkaline carbonates is a combination of carbonate and hydrate. When heated to redness, it yields pure oxide of zinc.

CHLORIDE OF ZINC, ZnCl .—The chloride may be prepared by heating metallic zinc in chlorine; by distilling a mixture of zinc-filings and corrosive sublimate; or, more easily, by dissolving zinc in hydrochloric acid. It is a nearly white, translucent, fusible substance, very soluble in water and alcohol, and very deliquescent. A strong solution of chloride of zinc is sometimes used as a bath for obtaining a

graduated heat above 212° (100°C). Chloride of zinc unites with sal-ammoniac and chloride of potassium to double salts; the former of these, made by dissolving an equivalent of zinc in the requisite quantity of hydrochloric acid, and then adding an equivalent of sal-ammoniac, is very useful in tinning and soft-soldering copper and iron.

A salt of zinc is easily distinguished by appropriate reagents.

Caustic potassa and soda give a white precipitate of hydrate, freely soluble in excess of alkali.

Ammonia behaves in the same manner; an excess re-dissolves the precipitate instantly.

The carbonates of potassa and soda give white precipitates, insoluble in excess.

Carbonate of ammonia gives also a white precipitate, which is re-dissolved by an excess.

Ferrocyanide of potassium gives a white precipitate.

Sulphuretted hydrogen causes no change.*

Sulphide of ammonium throws down white sulphide of zinc.

The applications of metallic zinc to the purposes of roofing, the construction of water-channels, &c., are well known; it is sufficiently durable, but inferior in this respect to copper.

CADMIUM.

This metal was discovered in 1817 by Stromeyer; it accompanies the ores of zinc, and, being more volatile than that substance, rises first in vapour when the calamine is subjected to distillation with charcoal. Cadmium resembles tin in colour, but is somewhat harder; it is very malleable, has a density of 8.7, melts below 500° (260°C), and is nearly as volatile as mercury. It tarnishes but little in the air, but, when strongly heated, burns. Dilute sulphuric and hydrochloric acids act but little on this metal in the cold; nitric acid is its best solvent.

The equivalent of cadmium is 56; its symbol is Cd.

PROTOXIDE OF CADMIUM, CdO .—The oxide may be prepared by igniting either the carbonate or the nitrate: in the former case it has a pale-brown colour, and in the latter a much darker tint and a crystalline aspect. Oxide of cadmium is infusible; it dissolves in acids, producing a series of colourless salts.

* With neutral solutions, or zinc-salts of an organic acid, a white precipitate ensues.

SULPHATE OF CADMIUM, $\text{CdO}, \text{SO}_3 + 4\text{HO}$.—This is easily obtained by dissolving the oxide or carbonate in dilute sulphuric acid; it is very soluble in water, and forms double salts with the sulphates of potassa and of ammonia, which contain respectively $\text{CdO}, \text{SO}_3 + \text{KO}, \text{SO}_3 + 6\text{HO}$ and $\text{CdO}, \text{SO}_3 + \text{NH}_4\text{O}, \text{SO}_3 + 6\text{HO}$.

CHLORIDE OF CADMIUM, CdCl .—This is a very soluble salt, crystallizing in small four-sided prisms.

SULPHIDE OF CADMIUM is a very characteristic compound, of a bright-yellow colour, fusible at a high temperature. It is obtained by passing sulphuretted hydrogen gas through a solution of the sulphate, nitrate, or chloride.

The salts of cadmium are thus distinguished:—

Fixed caustic alkalis give a white precipitate of hydrated oxide, insoluble in excess.

Ammonia gives a similar white precipitate, readily soluble in excess.

The alkaline carbonates, and carbonate of ammonia, throw down white carbonate of cadmium, insoluble in excess of either precipitant.

Sulphuretted hydrogen and sulphide of ammonium precipitate the yellow sulphide of cadmium.

BISMUTH.

Bismuth is found chiefly in the metallic state, disseminated through an earthy matrix, from which it is separated by simple exposure to heat. The metal is highly crystalline and very brittle; it has a reddish-white colour, and a density of 9.9. Cubic crystals of great beauty may be obtained by slowly cooling a considerable mass of this substance until solidification has commenced, and then piercing the crust, and pouring out the fluid residue. Bismuth melts at about 500° (260°C), and volatilizes at a high temperature: it is little oxidized by the air, but burns when strongly heated with a bluish flame. Nitric acid, somewhat diluted, dissolves it freely.

The equivalent of bismuth is 213, its symbol is Bi.

TEROXIDE OF BISMUTH, BiO_3 .—This is the base of all the salts. It is a straw-yellow powder, obtained by gently igniting the neutral or basic nitrate. It is fusible at a high temperature, and in that state acts towards siliceous matter as a powerful flux.

BISMUTHIC ACID, BiO_5 .—If teroxide of bismuth be suspended in a strong solution of potassa, and chlorine be passed through this liquid, decomposition of water ensues; hydrochloric acid being formed and the teroxide being converted into the pentoxide. To separate any teroxide which may have escaped oxidation, the powder is treated with dilute nitric acid, when the bismuthic acid is left as a

reddish powder, which is insoluble in water. This substance combines with bases, but the compounds are not very well known. When heated it loses oxygen, an intermediate oxide BiO_4 being formed, which may be considered as bismuthate of bismuth, $2\text{BiO}_4 = \text{BiO}_3, \text{BiO}_5$.

NITRATE OF BISMUTH, $\text{BiO}_3, 3\text{NO}_5 + 10\text{HO}$.—When bismuth is dissolved in moderately-strong nitric acid to saturation, and the whole left to cool, large, colourless, transparent crystals of the neutral nitrate are deposited. Water decomposes these crystals; an acid solution containing a little bismuth is obtained, and a brilliant white crystalline powder is left, which varies to a certain extent in composition according to the temperature and the quantity of water employed, but which frequently consists of a basic nitrate of the teroxide $\text{BiO}_3, \text{NO}_5 + 2\text{HO}$. A solution of nitrate of bismuth, free from any great excess of acid, poured into a large quantity of cold water, yields an insoluble basic nitrate, very similar in appearance to the above, but containing rather a larger proportion of teroxide of bismuth. This remarkable decomposition illustrates at once the basic property of water, and the feeble affinity of teroxide of bismuth for acids, the nitric acid dividing itself between the two bases. The decomposition of a neutral salt by water is by no means an uncommon occurrence in the history of the metals: a solution of terchloride of antimony exhibits the same phenomenon; certain salts of mercury are affected in a similar manner, and other cases might perhaps be cited, less conspicuous, where the same change takes place to a smaller extent.

The basic nitrate of teroxide of bismuth was once extensively employed as a cosmetic, but is said to injure the skin, rendering it yellow and leather-like. It has been used in medicine.

The other salts of bismuth possess few points of interest.

Bismuth is sufficiently characterized by the decomposition of the nitrate by water, and by the blackening the nitrate undergoes when exposed to the action of sulphuretted hydrogen gas.

A mixture of 8 parts of bismuth, 5 parts of lead, and 3 of tin, is known under the name of *fusible metal*, and is employed in taking impressions from dies and for other purposes; it melts below 212° (100°C). The discrepancies so frequently observed between the properties of alloys and those of their constituent metals, plainly show that such substances must be looked upon as true chemical compounds, and not as mere mixtures: in the present case the proof is complete, for the fusible metal has lately been obtained in crystals.

URANIUM.

This metal is found in a few minerals, as *pitchblende* and *uranite*, of which the former is the more abundant. It appears from the recent interesting researches of M. Péligot, that the substance hitherto taken for metallic uranium, obtained by the action of hydrogen gas upon the black oxide, is not in reality the metal, but a protoxide, capable of uniting directly with acids, and, like the protoxide of manganese, not decomposable by hydrogen at a red-heat. The metal itself can be obtained only by the intervention of potassium, applied in the same manner as in the preparation of magnesium. It is described as a black coherent powder, or a white malleable metal, according to the state of aggregation, not oxidized by air or water, but eminently combustible when exposed to heat. It unites also with great violence with chlorine and with sulphur. M. Péligot admits three distinct oxides of uranium, besides two other compounds of the metal and oxygen, which he designates as suboxides.

The equivalent of uranium is 60. Its symbol is U.

PROTOXIDE OF URANIUM, UO .—This is the body formerly considered as the metal; it is prepared by several processes, one of which has been already mentioned. It is a brown powder, sometimes highly crystalline. When in minute division it is pyrophoric, taking fire in the air, and burning to black oxide. It forms with acids a series of green salts. A corresponding chloride exists, which forms dark-green octahedral crystals, highly deliquescent and soluble in water. M. Péligot attributes a very extraordinary double function to this substance, namely, that of acting as a protoxide and forming salts with acids, and that of combining with chlorine or oxygen after the fashion of an elementary body.

PROTO-SESQUIOXIDE OF URANIUM; BLACK OXIDE; U_4O_5 , or $2\text{UO} + \text{U}_2\text{O}_3$.—The black oxide, formerly considered as protoxide, is produced when either protoxide or sesquioxide is strongly heated in the air, the former gaining, and the latter losing, a certain quantity of oxygen. It forms no salts, but is resolved by solution in acids into protoxide and sesquioxide.

SESQUIOXIDE OF URANIUM, U_2O_3 .—The sesquioxide is the best known and most important of the three; it forms a number of extremely beautiful yellow salts. When caustic alkali is added to a solution of nitrate of sesquioxide of uranium, a yellow precipitate of hydrated oxide falls, which retains, however, a portion of the precipitant. The hydrate cannot be exposed to a heat sufficient to expel the water without a commencement of decomposition. A better method of obtaining the sesquioxide is to heat by means of an oil-bath the powdered and dried crystals of the nitrate to 480° (249°C), until no more nitrous fumes are disengaged. Its colour in this state is chamois-yellow.

NITRATE OF SESQUIOXIDE OF URANIUM, $U_2O_3, NO_5 + 6HO$; or $(U_2O_2) O, NO_5 + 6HO$; U_2O_2 being the supposed *quasi-metal*.—This nitrate is the starting point in the preparation of all the compounds of uranium: it may be prepared from pitchblende by dissolving the pulverized mineral in nitric acid, evaporating to dryness, adding water and filtering; the liquid furnishes by due evaporation crystals of nitrate of uranium, which are purified by a repetition of the process, and, lastly, dissolved in ether. This latter solution yields the pure nitrate.

The green salts of uranium are peroxidized by boiling with nitric acid.

A yellow precipitate with caustic alkalis, convertible by heat into black oxide; a brown precipitate with sulphide of ammonium; and none at all with sulphuretted hydrogen gas, sufficiently characterize the salts of sesquioxide of uranium. A solution suspected to contain protoxide may be boiled with a little nitric acid, and then examined.

The only application of uranium is that to enamel-painting and the staining of glass; the protoxide giving a fine black colour, and the sesquioxide a delicate yellow.

COPPER.

Copper is a metal of great value in the arts of life; it sometimes occurs in the metallic state, crystallized in octahedrons, but is more abundant in the condition of red oxide, and in that of sulphide combined with sulphide of iron, or *yellow copper ore*. Large quantities of the latter substance are annually obtained from the Cornish mines and taken to South Wales for reduction, which is effected by a somewhat complex process. The principle of this may, however, be easily made intelligible. The ore is roasted in a reverberatory furnace, by which much of the sulphide of iron is converted into oxide, while the sulphide of copper remains unaltered. The product of this operation is then strongly heated with siliceous sand; the latter combines with the oxide of iron to a fusible *slag*, and separates from the heavier copper-compound. When the iron has, by a repetition of these processes been got rid of, the sulphide of copper begins to decompose in the flame-furnace, losing its sulphur and absorbing oxygen; the temperature is then raised sufficiently to reduce the oxide thus produced, by the aid of carbonaceous matter. The last part of the operation consists in thrusting into the melted metal a pole of birch-wood, the object of which is probably to reduce a little remaining oxide by the

combustible gases thus generated. Large quantities of extremely valuable ore, chiefly carbonate and red oxide, have lately been obtained from South Australia.

Copper has a well-known yellowish-red colour, a specific gravity of 8·96, and is very malleable and ductile; it is an excellent conductor of heat and electricity; it melts at a bright red-heat, and seems to be a little volatile at a very high temperature. Copper undergoes no change in dry air: exposed to a moist atmosphere, it becomes covered with a strongly adherent green crust, consisting in a great measure of carbonate. Heated to redness in the air, it is quickly oxidized, becoming covered with a black scale. Dilute sulphuric and hydrochloric acids scarcely act upon copper; boiling oil of vitriol attacks it with evolution of sulphurous acid; nitric acid, even dilute, dissolves it readily with evolution of binoxide of nitrogen. Two oxides are known which form salts; a third, or peroxide, is said to exist.

The equivalent of copper is 31·7; its symbol Cu.

PROTOXIDE OF COPPER; BLACK OXIDE; CuO .—This is the base of the ordinary blue and green salts. It is prepared by calcining metallic copper at a red-heat, with full exposure to air, or, more conveniently, by heating to redness the nitrate, which suffers complete decomposition. When a salt of this oxide is mixed with caustic alkali in excess, a bulky pale-blue precipitate of hydrated oxide falls, which, when the whole is raised to the boiling-point, becomes converted into a heavy dark-brown powder: this also is anhydrous oxide of copper, the hydrate suffering decomposition, even in contact with water. The oxide prepared at a high temperature is perfectly black and very dense. Protoxide of copper is soluble in acids, and forms a series of very important salts, being isomorphous with magnesia.

SUBOXIDE OF COPPER; RED OXIDE; Cu_2O .—The suboxide may be obtained by heating in a covered crucible a mixture of 5 parts of black oxide and 4 parts of fine copper-filings; or by adding grape-sugar to a solution of sulphate of copper, and then putting in an excess of caustic potassa, the blue solution, heated to ebullition, is reduced by the sugar, and deposits suboxide. It often occurs in beautifully transparent ruby-red crystals, associated with other ores of copper, and can be obtained in this state by artificial means. This substance forms colourless salts with acids, which are exceedingly unstable, and tend to absorb oxygen. The suboxide communicates to glass a magnificent red tint, while that given by the protoxide is green.

SULPHATE OF COPPER; BLUE VITRIOL; $\text{CuO}, \text{SO}_3 + 5\text{HO}$.—This beautiful salt is prepared by dissolving oxide of copper in sulphuric acid, or, at less expense, by oxidizing the sulphide. It forms large blue crystals, soluble in 4 parts of cold and 2 of boiling water; by heat it is rendered anhydrous and nearly white, and by a very high temperature decomposed. Sulphate of copper combines with the sulphates of potassa and of ammonia, forming pale-blue salts which con-

tain 6 equivalents of water, and also with *ammonia*, generating a remarkable compound of deep-blue colour, capable of crystallizing.

NITRATE OF COPPER, $\text{CuO}, \text{NO}_3 + 3\text{HO}$.—The nitrate is easily made by dissolving the metal in nitric acid; it forms deep-blue crystals, very soluble and deliquescent. It is highly corrosive. An insoluble subnitrate is known; it is green. Nitrate of copper also combines with ammonia.

CARBONATES OF COPPER.—When carbonate of soda is added in excess to a solution of sulphate of copper, the precipitate is at first pale blue and flocculent, but by warming it becomes sandy, and assumes a green tint; in this state it contains $\text{CuO}, \text{CO}_2 + \text{CuO}, \text{HO} + \text{HO}$. This substance is prepared as a pigment. The beautiful mineral *malachite* has a similar composition, but contains one equivalent of water less. Another natural compound, not yet artificially imitated, occurs in large transparent crystals of the most intense blue; it contains $2(\text{CuO}, \text{CO}_2) + \text{CuO}, \text{HO}$. *Verditer*, made by decomposing nitrate of copper by chalk, is said, however, to have a somewhat similar composition.

CHLORIDE OF COPPER, $\text{CuCl} + 2\text{HO}$.—The chloride is most easily prepared by dissolving the black oxide in hydrochloric acid, and concentrating the green solution thence resulting. It forms green crystals, very soluble in water and in alcohol; it colours the flame of the latter green. When gently heated, it parts with its water of crystallization and becomes yellowish-brown; at a high temperature it loses half its chlorine and becomes converted into the subchloride. The latter is a white fusible substance, but little soluble in water, and prone to oxidation; it is formed when copper-filings or copper-leaf are put into chlorine gas.

ARSENITE OF COPPER; SCHEEL'S GREEN.—This is prepared by mixing solutions of sulphate of copper and arsenite of potassa; it falls as a bright-green insoluble powder.

The characters of the protosalts of copper are well marked.

Caustic potassa gives a pale blue precipitate of hydrate, becoming blackish-brown anhydrous protoxide on boiling.

Ammonia also throws down the hydrate; but, when in excess, redissolves it, yielding an intense purplish-blue solution.

Carbonates of potassa and soda give pale-blue precipitates, insoluble in excess.

Carbonate of ammonia, the same, but soluble with deep-blue colour.

Ferrocyanide of potassium gives a fine red-brown precipitate of ferrocyanide of copper.

Sulphuretted hydrogen and sulphide of ammonium afford black sulphide of copper.

The alloys of copper are of great importance. *Brass* consists of copper alloyed with from 28 to 34 per cent. of zinc; the latter may be added directly to the melted copper, or granulated copper may be heated with calamine and charcoal-powder, as in the old process. *Gun-metal*, a most trustworthy and valuable alloy, consists of 90 parts copper and 10 tin. *Bell* and *speculum metal* contain a still larger proportion of tin; these are brittle, especially the last-named. A good bronze for statues is made of 91 parts copper, 2 parts tin, 6 parts zinc, and 1 part lead. The *brass* of the ancients is an alloy of copper with tin.


LEAD.

This abundant and useful metal is altogether obtained from the native sulphide, or *galena*, no other lead-ore being found in quantity. The reduction is effected in a reverberatory furnace, into which the crushed lead ore is introduced and roasted for some time at a dull red-heat, by which much of the sulphide becomes changed by oxidation to sulphate. The contents of the furnace are then thoroughly mixed, and the temperature raised, when the sulphate and sulphide react upon each other, producing sulphurous acid and metallic lead.*

Lead is a soft bluish metal, possessing very little elasticity; its specific gravity is 11.45. It may be easily rolled out into plates, or drawn into coarse wire, but has a very trifling degree of strength. Lead melts at 600° (315°·5C) or a little above, and at a white-heat boils and volatilizes. By slow cooling it may be obtained in octahedral crystals. In moist air this metal becomes coated with a film of grey matter, thought to be suboxide, and when exposed to the atmosphere in a melted state it rapidly absorbs oxygen. Dilute acids, with the exception of nitric, act but slowly upon lead. Chemists are familiar with four oxides of lead, only one of which possesses basic properties.

The equivalent of lead is 103.7; its symbol is Pb.

PROTOXIDE; LITHARGE; MASSICOT; PbO.—This is the product of the direct oxidation of the metal. It is most conveniently prepared by heating the carbonate to dull redness; common *litharge* is impure protoxide which has undergone fusion. Protoxide of lead has a delicate straw-yellow colour, is very heavy and slightly soluble in water, giving an alkaline liquid. At a red-heat it melts, and tends to crystallize on cooling. In a melted state it attacks and dissolves



siliceous matter with astonishing facility, often penetrating an earthen crucible in a few minutes. It is easily reduced when heated with organic substances of any kind containing carbon or hydrogen. Protoxide of lead forms a large class of salts, which are colourless if the acid itself be not coloured.

RED OXIDE; RED-LEAD; Pb_3O_4 , or $2\text{PbO} + \text{PbO}_2$.—The composition of this substance is not very constant; it is prepared by exposing for a long time to the air, at a very faint red-heat, protoxide of lead which has not been fused; it is a brilliant red and extremely heavy powder, decomposed with evolution of oxygen by a strong heat, and converted into a mixture of protoxide and binoxide by acids. It is used as a cheap substitute for vermilion.

BINOXIDE OF LEAD; PUCE OR BROWN OXIDE; PbO_2 .—This compound is obtained without difficulty by digesting red-lead in dilute nitric acid, when nitrate of protoxide is dissolved out, and insoluble binoxide left behind in the form of a deep brown powder. The binoxide is decomposed by a red-heat, yielding up one-half of its oxygen. Hydrochloric acid converts it into chloride of lead with disengagement of chlorine; hot oil of vitriol forms with it sulphate of lead, and liberates oxygen. The binoxide is very useful in separating sulphurous acid from certain gaseous mixtures, sulphate of lead being then produced.

SUBOXIDE OF LEAD, Pb_2O .—When oxalate of lead is heated to dull redness in a retort, a grey pulverulent substance is left, which is resolved by acids into protoxide of lead and metal. It absorbs oxygen with great rapidity when heated, and even when simply moistened with water and exposed to the air.

NITRATE OF LEAD, PbO, NO_3 .—The nitrate may be obtained by dissolving carbonate of lead in nitric acid, or by acting directly upon the metal by the same agent with the aid of heat; it is, as already noticed, a by-product in the preparation of the binoxide. It crystallizes in anhydrous octahedrons, which are usually milk-white and opaque; it dissolves in $7\frac{1}{2}$ parts of cold water, and is decomposed by heat, yielding nitrous acid, oxygen, and protoxide of lead, which obstinately retains traces of nitrogen. When a solution of this salt is boiled with an additional quantity of oxide of lead, a portion of the latter is dissolved, and a basic nitrate generated, which may be had in crystals. Carbonic acid separates this excess of oxide in the form of a white compound of carbonate and hydrate of lead.

Neutral and basic compounds of oxide of lead with nitrous, and the *elements* of hyponitric acid, have been described. These last are probably formed by the combination of a nitrite with a nitrate.

CARBONATE OF LEAD; WHITE-LEAD; PbO, CO_2 .—Carbonate of lead is sometimes found beautifully crystallized in long white needles, accompanying other metallic ores. It may be prepared artificially by precipitating in the cold a solution of the nitrate or acetate by an alkaline carbonate: when the lead solution is boiling, the precipitate

is a basic salt containing $2(\text{PbO}, \text{CO}_2) + \text{HO}, \text{PbO}$; it is also manufactured to an immense extent by other means for the use of the painter. Pure carbonate of lead is a soft, white powder, of great specific gravity, insoluble in water, but easily dissolved by dilute nitric or acetic acid.

Of the many methods put in practice, or proposed, for making white-lead, the two following are the most important and interesting : —One of these consists in forming a basic nitrate or acetate of lead by boiling finely-powdered litharge with the neutral salt. This solution is then brought into contact with carbonic acid gas : all the excess of oxide previously taken up by the neutral salt is at once precipitated as white-lead. The solution strained or pressed from the latter is again boiled with litharge, and treated with carbonic acid ; these processes being susceptible of indefinite repetition, when the little loss of neutral salt left in the precipitates is compensated. The second, and by far the more ancient method, is rather more complex, and at first sight not very intelligible. A great number of earthen jars are prepared, into each of which is poured a few ounces of crude vinegar ; a roll of sheet-lead is then introduced in such a manner that it shall neither touch the vinegar nor project above the top of the jar. The vessels are next arranged in a large building, side by side, upon a layer of stable manure, or, still better, spent-tan, and closely covered with boards. A second layer of tan is spread upon the top of the latter, and then a second series of pots ; these are in turn covered with boards and decomposing bark, and in this manner a pile of many alternations is constructed. After the lapse of a considerable time the pile is taken down and the sheets of lead removed and carefully unrolled ; they are then found to be in great part converted into carbonate, which merely requires washing and grinding to be fit for use. The nature of this curious process is generally explained by supposing the vapour of vinegar raised by the high temperature of the fermenting matter merely to act as a carrier between the carbonic acid evolved from the tan, and the oxide of lead formed under the influence of the acid vapour ; a neutral acetate, a basic acetate, and a carbonate being produced in succession, the action gradually travelling from the surface inwards. The quantity of acetic acid used is, in relation to the lead, quite trifling, and cannot directly contribute to the production of the carbonate. A preference is still given to the product of this old mode of manufacture on account of its superiority of opacity, or *body*, over that obtained by precipitation. Commercial white-lead, however prepared, always contains a certain proportion of hydrate.

When clean metallic lead is put into pure water and exposed to the atmosphere, a white crystalline, scaly powder begins to show itself in a few hours, and very rapidly increases in quantity. This substance may consist of hydrated protoxide of lead, formed by the action of the oxygen dissolved in the water upon the lead. It is

slightly soluble, and may be readily detected in the water. In most cases, however, the formation of this deposit is due to the action of the carbonic acid dissolved in the water; it consists of carbonate in combination with hydrate, and is very insoluble in water. When common river or spring water is substituted for the pure liquid, this effect is less observable, the little sulphate, almost invariably present, causing the deposition of a very thin but closely adherent film of sulphate of lead upon the surface of the metal, which protects it from farther action. It is on this account that leaden cisterns are used with impunity, at least in most cases, for holding water; if the latter were quite pure, it would be speedily contaminated with lead, and the cistern be soon destroyed. Natural water highly charged with carbonic acid cannot, under any circumstances, be kept in lead or passed through leaden pipes with safety, the carbonate, though very insoluble in pure water, being slightly soluble in water containing carbonic acid.

CHLORIDE OF LEAD, $PbCl$.—This salt is prepared by mixing strong solutions of acetate of lead and chloride of sodium; or by dissolving litharge in boiling dilute hydrochloric acid, and setting aside the filtered solution to cool. Chloride of lead crystallizes in brilliant, colourless needles, which require 135 parts of cold water for solution. It is anhydrous; it melts when heated, and solidifies on cooling to a horn-like substance.

IODIDE OF LEAD, PbI .—The iodide of lead separates as a brilliant yellow precipitate when a soluble salt of lead is mixed with iodide of potassium. This compound dissolves in boiling water, yielding a colourless solution, which deposits the iodide on cooling in splendid golden-yellow scales.

The soluble salts of lead thus behave with reagents:—

Caustic potassa and soda precipitate a white hydrate freely soluble in excess.

Ammonia gives a similar white precipitate, not soluble in excess.*

The carbonates of potassa, soda, and ammonia, precipitate carbonate of lead, insoluble in excess.

Sulphuric acid or a sulphate causes a white precipitate of sulphate of lead, insoluble in nitric acid.

Sulphuretted hydrogen and sulphide of ammonium throw down black sulphide of lead.

An alloy of 2 parts of lead and 1 of tin constitutes *plumber's solder*; these proportions reversed give a more fusible compound called *fine solder*. The lead employed in the manufacture of shot is combined with a little arsenic.

* Ammonia gives no immediate precipitate with the acetate.

SECTION V.

OXIDABLE METALS PROPER, WHOSE OXIDES FORM WEAK BASES OR ACIDS.

TIN.

THIS valuable metal occurs in the state of oxide, and more rarely as sulphide; the principal tin mines are those of the Erzgebirge in Saxony and Bohemia, Malacca, and more especially Cornwall. In Cornwall the tin-stone is found as a constituent of metal bearing veins, associated with copper ore, in granite and slate-rocks; and as an alluvial deposit, mixed with rounded pebbles, in the beds of several small rivers. The first variety is called *mine-* and the second *stream-tin*. Oxide of tin is also found disseminated through the rock itself in small crystals.

To prepare the ore for reduction, it is stamped to powder, washed, to separate as much as possible of the earthy matter, and roasted to expel sulphur and arsenic; it is then strongly heated with coal, and the metal thus obtained cast into large blocks, which, after being assayed, receive the stamp of the Duchy. Two varieties of commercial tin are known, called *grain-* and *bar-tin*; the first is the best; it is prepared from the stream ore.

Pure tin has a white colour, approaching to that of silver; it is soft and malleable, and when bent or twisted emits a peculiar crackling sound; it has a density of 7.3 and melts at 442° ($227^{\circ}77\text{C}$). Tin is but little acted upon by air and water, even conjointly: when heated above its melting-point it oxidizes rapidly, becoming converted into a whitish powder, used in the arts for polishing, under the name of *putty-powder*. The metal is easily attacked and dissolved by hydrochloric acid, with evolution of hydrogen: nitric acid acts with great energy, converting it into a white hydrate of the binoxide. There are two well-marked oxides of tin, which act as feeble bases or acids, according to circumstances, and a third, which has been less studied.

The equivalent of tin is 58; its symbol is Sn.

PROTOXIDE OF TIN, SnO .—When solution of protochloride of tin is mixed with carbonate of potassa, a white hydrate of the protoxide falls, the carbonic acid being at the same time expelled. When this is carefully washed, dried, and heated in an atmosphere of car-

bonic acid, it loses water, and changes to a dense black powder, which is permanent in the air, but takes fire on the approach of a red-hot body, and burns like tinder, producing binoxide. The hydrate is freely soluble in caustic potassa; the solution decomposes by keeping into metallic tin and binoxide.

SESQUIOXIDE OF TIN, Sn_2O_3 .—The sesquioxide is produced by the action of hydrated sesquioxide of iron upon protochloride of tin; it is a greyish, slimy substance, soluble in hydrochloric acid, and in ammonia. This oxide has been but little examined.

BINOXIDE OF TIN, SnO_2 .—This substance is obtained in two different states, having properties altogether dissimilar. When bichloride of tin is precipitated by an alkali, a white bulky hydrate appears, which is freely soluble in acids. If, on the other hand, the bichloride be boiled with excess of nitric acid, or if that acid be made to act directly on metallic tin, a white substance is produced, which refuses altogether to dissolve in acids, and possesses properties differing in other respects from those of the first modification. Both these varieties of binoxide of tin have the same composition, and when ignited, leave the pure binoxide of a pale lemon-yellow tint. Both dissolve in caustic alkali, and are precipitated with unchanged properties by an acid. The two hydrates redden litmus-paper.*

PROTOCHLORIDE OF TIN, SnCl .—The protochloride is easily made by dissolving metallic tin in hot hydrochloric acid. It crystallizes in needles containing 2 equivalents of water, which are freely soluble in a small quantity of water, but are apt to be decomposed in part when put into a large mass, unless hydrochloric acid in excess be present. The anhydrous chloride may be obtained by distilling a mixture of calomel and powdered tin, prepared by agitating the melted metal in a wooden box until it solidifies. The chloride is a grey, resinous-looking substance, fusible below redness, and volatile at a high temperature. Solution of protochloride of tin is employed as a deoxidizing agent; it reduces the salts of mercury and other metals of the same class.

BICHLORIDE, OR PERCHLORIDE OF TIN, SnCl_2 .—This is an old and very curious compound, formerly called *fuming liquor of Libavius*. It is made by exposing metallic tin to the action of chlorine, or, more conveniently, by distilling a mixture of 1 part of powdered tin, and 5 parts of corrosive sublimate. The bichloride is a thin, colourless, mobile liquid; it boils at 248° (120°C), and yields a colourless invisible vapour. It fumes in the air, and when mixed with a third part of water, solidifies to a crystalline mass. The solution of bichloride is much employed by the dyer as a *mordant*; it is commonly prepared by dissolving metallic tin in a mixture of hydrochloric and

* Frémy has called the first of these oxides stannic acid SnO_2 . The second he has named metastannic acid Sn_5O_{10} . See also H. Rose, Pogg. Ann. lxxv. 1, who thinks that there are other modifications of this oxide of tin.

nitric acids, care being taken to avoid too great elevation of temperature.

SULPHIDES OF TIN.—*Protosulphide*, SnS , is prepared by fusing tin with excess of sulphur, and strongly heating the product. It is a lead-grey, brittle substance, fusible at a red-heat, and soluble with evolution of sulphuretted hydrogen in hot hydrochloric acid. A *sesquisulphide* may be formed by gently heating the above compound with a third of its weight of sulphur; it is yellowish-grey, and easily decomposed by heat. *Bisulphide*, SnS_2 , or *Mosaic gold*, is prepared by exposing to a low red-heat, in a glass flask, a mixture of 12 parts of tin, 6 of mercury, 6 of sal-ammoniac, and 7 of flowers of sulphur. Sal-ammoniac, cinnabar, and protochloride of tin sublime, while the bisulphide remains at the bottom of the vessel in the form of brilliant gold-coloured scales; it is used as a substitute for gold-powder.

Salts of tin are thus distinguished:—

Protoxide.

Caustic alkalis; white hydrate soluble in excess.

Ammonia; carbonates of potassa, soda, and am- monia	} White hydrate, nearly insoluble in excess.
---	---

Sulphuretted hydrogen Sulphide of ammonium	} Black precipitate of protosulphide.
---	---------------------------------------

Binoxide.

Caustic alkalis; white hydrate soluble in excess.

Ammonia; white hydrate, slightly soluble in excess.

Alkaline carbonates; white hydrates, slightly soluble in excess.

Carbonate of ammonia; white hydrate, insoluble.

Sulphuretted hydrogen; yellow precipitate of sulphide.

Sulphide of ammonium; the same, soluble in excess.

Terchloride of gold, added to a dilute solution of protochloride of tin, gives rise to a brownish-purple precipitate, called *purple of Cassius*, very characteristic, the nature of which is not thoroughly understood; it is supposed to be a combination of oxide of gold and sesquioxide of tin, in which the latter acts as an acid. Heat resolves it into a mixture of metallic gold and binoxide of tin. Purple of Cassius is employed in enamel-painting.

The useful applications of tin are very numerous. *Tinned-plate* consists of iron superficially alloyed with this metal; *pewter*, of the best kind, is chiefly tin, hardened by the admixture of a little antimony, &c. Cooking-vessels of copper are usually tinned in the interior.

TUNGSTEN (WOLFRAMIUM).

Tungsten is found, as tungstate of protoxide of iron, in the mineral *wolfram*, tolerably abundant in Cornwall; a native tungstate of lime is also occasionally met with. Metallic tungsten is obtained in the state of a dark-grey powder, by strongly heating tungstic acid in a stream of hydrogen, but requires for fusion an exceedingly-high temperature. It is a white metal, very hard and brittle; it has a density of 17.4. Heated to redness in the air, it takes fire, and reproduces tungstic acid.

The equivalent of tungsten is 92, its symbol is W (wolframinm).

BINOXIDE OF TUNGSTEN, WO_2 .—This is most easily prepared by exposing tungstic acid to hydrogen, at a temperature which does not exceed dull redness. It is a brown powder, sometimes assuming a crystalline appearance and an imperfect metallic lustre. It takes fire when heated in the air, and burns, like the metal itself, to tungstic acid. The binoxide forms no salts with acids.

TUNGSTIC ACID, WO_3 .—When tungstate of lime can be obtained, simple digestion in hot nitric acid is sufficient to remove the base, and liberate the tungstic acid in a state of tolerable purity; its extraction from wolfram, which contains tungstic acid or oxide of tungsten in association with the oxides of iron and manganese, is more difficult. Tungstic acid is a yellow powder, insoluble in water, and freely dissolved by caustic alkalis. When strongly ignited in the open air, it assumes a greenish tint.

INTERMEDIATE OR BLUE OXIDE OF TUNGSTEN, $\text{W}_2\text{O}_5 = \text{WO}_2\text{WO}_3$.—This substance is obtained by heating tungstate of ammonia, or by exposing the brown binoxide to the action of hydrogen at a very low temperature. The same compound appears to be produced if tungstic acid be separated from one of its salts, by hydrochloric acid, and the liquid be digested with metallic zinc, when the solution or the precipitate assumes a beautiful blue colour, which is very characteristic of this metal.

Two chlorides and two sulphides of tungsten are known to exist.

MOLYBDENUM.

Metallic molybdenum is obtained by exposing molybdic acid in a charcoal-lined crucible to the most intense heat that can be obtained. It is a white, brittle, and exceedingly-infusible metal, having a density of 8.6, and oxidizing, when heated in the air, to molybdic acid.

The equivalent of molybdenum is 46; its symbol is Mo.

PROTOXIDE OF MOLYBDENUM, MoO .—Molybdate of potassa is

mixed with excess of hydrochloric acid, by which the molybdic acid first precipitated is redissolved; into this acid solution zinc is put: a mixture of chloride of zinc and protochloride of molybdenum results. A large quantity of caustic potassa is then added, which precipitates a black hydrate of the protoxide of molybdenum, and retains in solution the oxide of zinc. The freshly-precipitated protoxide is soluble in acids and in carbonate of ammonia; when heated in the air, it burns to binoxide.

BINOXIDE OF MOLYBDENUM, MoO_2 .—This is obtained in the anhydrous condition by heating molybdate of soda with sal-ammoniae, the molybdic acid being reduced to binoxide by the hydrogen of the ammoniacal salt; or, in a hydrated condition, by digesting metallic copper in a solution of molybdic acid in hydrochloric acid, until the liquid assumes a red colour, and then adding a large excess of ammonia. The anhydrous binoxide is deep brown, and insoluble in acids; the hydrate resembles hydrate of sesquioxide of iron, and dissolves in acids, yielding red solutions. It is converted into molybdic acid by strong nitric acid.

MOLYBDIC ACID, MoO_3 .—The native bisulphide of molybdenum is roasted, at a red-heat, in an open vessel, and the impure molybdic acid thence resulting dissolved in ammonia. The filtered solution is evaporated to dryness, the salt taken up by water, and purified by crystallization. It is, lastly, decomposed by heat, and the ammonia expelled. Molybdic acid is a white crystalline powder, fusible at a red-heat, and slightly soluble in water. It is dissolved with ease by the alkalis. It forms two series of salts, namely, neutral molybdates MO, MoO_3 , and acid molybdates $\text{MO}, 2\text{MoO}_3$. Three chlorides, and as many sulphides of molybdenum, are described.

VANADIUM.

Vanadium is found, in small quantity, in one of the Swedish iron ores, and also as *vanadate of lead*. It has also been discovered in the iron slag of Staffordshire. The most successful process for obtaining the metal is said to be the following:—The liquid chloride of vanadium is introduced into a bulb, blown in a glass tube, and dry ammoniacal gas passed over it; the latter is absorbed, and a white saline mass produced. When this is heated by the flame of a spirit-lamp, chloride of ammonium is volatilized, and metallic vanadium left behind. It is a white brittle substance, of perfect metallic lustre, and a very high degree of infusibility; it is neither oxidized by air nor water, nor attacked by sulphuric, hydrochloric, or even hydrofluoric acid; aqua regia dissolves it, yielding a deep-blue solution.

The equivalent of vanadium is 68.6; its symbol is V.

PROTOXIDE OF VANADIUM, VO.—This is prepared by heating

vanadic acid in contact with charcoal or hydrogen; it has a black colour and imperfect metallic lustre, conducts electricity, and is very infusible. Heated in the air, it burns to binoxide. Nitric acid produces the same effect, a blue nitrate of the binoxide being generated. It does not form salts.

BINOXIDE OF VANADIUM, VO_2 .—The binoxide is obtained by heating a mixture of 10 parts protoxide of vanadium, and 12 of vanadic acid in a vessel filled with carbonic acid gas; or by adding a slight excess of carbonate of soda to a salt of the binoxide; in the latter case it falls as a greyish-white hydrate, readily becoming brown by absorption of oxygen. The anhydrous oxide is a black insoluble powder, convertible by heat and air into vanadic acid. It forms a series of blue salts, which have a tendency to become green and ultimately red, by the production of vanadic acid. Binoxide of vanadium also unites with alkalis.

VANADIC ACID, VO_3 .—The native vanadate of lead is dissolved in nitric acid, and the lead and arsenic precipitated by sulphuretted hydrogen, which at the same time reduces the vanadic acid to binoxide of vanadium. The blue filtered solution is then evaporated to dryness, and the residue digested in ammonia, which dissolves out the vanadic acid reproduced during evaporation. Into this solution a lump of sal-ammoniac is put; as that salt dissolves, vanadate of ammonia subsides as a white powder, being scarcely soluble in a saturated solution of chloride of ammonium. By exposure to a temperature below redness in an open crucible, the ammonia is expelled, and vanadic acid left. It has a dark-red colour, and melts even below a red heat; water dissolves it sparingly, and acids with greater ease; the solutions easily suffer deoxidation. It unites with bases, forming a series of red or yellow salts, of which those of the alkalis are soluble in water.

CHLORIDES OF VANADIUM.—The *bichloride* is prepared by digesting vanadic acid in hydrochloric acid, passing a stream of sulphuretted hydrogen, and evaporating the whole to dryness. A brown residue is left, which yields a blue solution with water and an insoluble oxichloride. The *terchloride* is a yellow liquid obtained by passing chlorine over a mixture of protoxide of vanadium and charcoal. It is converted by water into hydrochloric and vanadic acids.

Two sulphides, corresponding to the chlorides, exist.

TANTALUM (COLUMBIUM).

This is an exceedingly rare substance; it is found in the minerals *tantalite* and *yttrio-tantalite*, and may be obtained pure by heating with potassium the double fluoride of tantalum and potassium. It is a grey metal, but little acted on by the ordinary acids, and burning

to tantalic acid when heated in the air, or when fused with hydrate of potassa.

The equivalent of tantalum is 184; its symbol is T.

BINOXIDE OF TANTALUM, TO_2 .—When tantalic acid is heated to whiteness in a crucible lined with charcoal, the greater part is converted into this substance. It is a dark-brown powder, insoluble in acids, and easily changed by oxidation to tantalic acid.

TANTALIC ACID, TO_3 .—The powdered ore is fused with three or four times its weight of carbonate of potassa, and the product digested with water; from this solution acids precipitate a white hydrate of the body in question. It is soluble in acids, but forms with them no definite compounds; with alkalis it yields, on the contrary, crystallizable salts. The specific gravity of the acid varies from 7.03 to 8.26.

NIOBIUM AND PELOPIUM.

The oxides of these two metals exist in the *tantalite* of Bodenmais, in Bavaria. When the supposed tantalic acid from this source is mixed with dry powdered charcoal, and heated to redness in a current of chlorine gas, a sublimate is obtained of a yellow, readily fusible, and very volatile substance, the chloride of *pelopium*, and a white, infusible, less volatile body, the chloride of *niobium*. The true chloride of tantalum, from the Finland tantalite, much resembles chloride of pelopium. The American tantalite contains niobic, pelopic, and tungstic acids, the former in greatest quantity.

All these chlorides are decomposed by water, with production of hydrochloric acid and the insoluble acids of the metals in the hydrated state. In properties these bodies greatly resemble each other. When heated to redness, they exhibit strongly the phenomenon of incandescence. While hot, tantalic acid remains white, pelopic acid is rendered slightly yellowish, and has a specific gravity varying from 5.79 to 6.37, and niobic acid becomes dark yellow, with a specific gravity between 4.56 and 5.26.

Tantalum, niobium, and pelopium may be obtained in a finely-divided metallic state by the action of ammonia on their respective chlorides at a high temperature. So prepared, they are black, pulverulent, not acted on by water, but burning, when heated in the air, to acids.

TITANIUM.

Crystallized oxide of titanium is found in nature in the forms of *titumite* and *anatase*. Occasionally in the slag adherent to the bottom of blast-furnaces in which iron ore is reduced small brilliant copper-coloured cubes, hard enough to scratch glass, and in the highest degree infusible, are found. This substance, of which a single smelt-

ing furnace in the Hartz produced as much as 80 pounds, was formerly believed to be metallic titanium. Recent researches of Wöhler, however, have shown it to be a combination of cyanide of titanium with nitride of titanium. When these crystals are powdered, mixed with hydrate of potassa and fused, ammonia is evolved, and titanate of potassa is formed. Metallic titanium in a finely-divided state may be obtained by heating fluoride of titanium and potassium with potassium. There are two compounds of this substance with oxygen; viz., an oxide and an acid: very little is known respecting the former.

The equivalent of titanium is 25; its symbol is Ti.

TITANIC ACID, TiO_2 .—Titanite, or titaniferous iron ore, is reduced to fine powder, and fused with twice its weight of carbonate of potassa, powdered, and dissolved in dilute hydrofluoric acid, when titanofluoride of titanium and potassium soon begins to separate. From its hot aqueous solution snow-like titanate of ammonia is precipitated by ammonia, which is easily soluble in hydrochloric acid, and when ignited gives pure titanitic acid. When pure the acid is quite white: it is, when recently precipitated from solutions, soluble in acids, but the solutions are decomposed by mere boiling. After ignition it is no longer soluble, passing over into metatitanic acid. Titanitic acid, on the whole, very much resembles silica, and is probably often overlooked and confounded with that substance in analytical researches.

BICHLORIDE OF TITANIUM.—This is a colourless, volatile liquid, resembling bichloride of tin; it is obtained by passing chlorine over a mixture of titanitic acid and charcoal at a high temperature. It unites very violently with water. On passing the vapour with hydrogen through a red-hot tube, hydrochloric acid and a new compound Ti_2Cl_3 are formed.

ANTIMONY.

This important metal is found chiefly in the state of sulphide. The ore is freed by fusion from earthy impurities, and is afterwards decomposed by heating with metallic iron or carbonate of potassa, which retains the sulphur. Antimony has a bluish-white colour and strong lustre; it is extremely brittle, being reduced to powder with the utmost ease. Its specific gravity is 6.8; it melts at a temperature just short of redness, and boils and volatilizes at a white-heat. This metal has always a distinctly crystalline, platy structure, but by particular management it may be obtained in crystals, which are rhombohedral. Antimony is not oxidized by the air at common temperatures; strongly heated, it burns with a white flame, producing teroxide, which is often deposited in beautiful crystals. It is dissolved by hot hydrochloric acid with evolution of hydrogen and production of terchloride. Nitric acid oxidizes it to antimonic acid, which is insoluble in that menstruum. There are three compounds of antimony

and oxygen; the first has doubtful basic properties, the second is indifferent, and the third is an acid.

The equivalent of antimony is 129. Its symbol is Sb (stibium).

TEROXIDE OF ANTIMONY, SbO_3 .—This compound may be prepared by several methods: as by burning metallic antimony at the bottom of a large red-hot crucible, in which case it is obtained in brilliant crystals; or by pouring solution of terchloride of antimony into water, and digesting the resulting precipitate with a solution of carbonate of soda. The teroxide thus produced is anhydrous; it is a pale buff-coloured powder, fusible at a red-heat, and volatile in a close vessel, but in contact with air, it, at a high temperature, absorbs oxygen, and becomes changed to the intermediate oxide. There exist a sulphate, nitrate, and oxalate of teroxide of antimony. When boiled with cream of tartar (bitartrate of potassa), it is dissolved, and the solution yields on evaporation crystals of *tartar-emetic*, which is almost the only compound of teroxide of antimony with an acid which bears admixture with water without decomposition. An impure oxide for this purpose is sometimes prepared by carefully roasting the powdered sulphide in a reverberatory furnace, and raising the heat at the end of the process, so as to fuse the product; it has long been known under the name of *glass of antimony*.

INTERMEDIATE OXIDE, $\text{SbO}_4 = \text{SbO}_3, \text{SbO}_5$.—This is the ultimate product of the oxidation of the metal by heat and air; it is a greyish-white powder, infusible, and destitute of volatility; it is insoluble in water and in acids, except when recently precipitated. When treated with tartaric acid or bitartrate of potassa, teroxide of antimony is dissolved, antimonious acid remaining behind; alkalis, on the other hand, remove antimonious acid, teroxide of antimony being left.

ANTIMONIOUS ACID, SbO_5 .—When strong nitric acid is made to act upon metallic antimony, the metal is oxidized to its highest point, and antimonious acid produced, which is insoluble. By exposure to a heat short of redness, it is rendered anhydrous, and then presents the appearance of a pale straw-coloured powder, insoluble in water and acids. It is decomposed by a red-heat, yielding the intermediate oxide, with loss of oxygen.

Antimonious acid is likewise obtained by decomposing pentachloride of antimony and an excess of water, when, together with the metallic acid, hydrochloric acid is produced. The hydrated antimonious acid produced by the two processes mentioned, differs in many of its properties, and especially in its deportment with bases. The substance produced by nitric acid is monobasic, producing salts of the formula MO, SbO_5 , the other is bibasic, and forms two series of salts of the composition $2\text{MO}, \text{SbO}_5$ and $\text{MO}, \text{HO}, \text{SbO}_5$. In order to distinguish the two modifications, M. Fremy, who first pointed out the bibasic nature of the acid obtained from the pentachloride, has proposed to distinguish it as metantimonious acid. Among the salts of the latter, an acid metantimonate of potassa

$\text{KO}, \text{HO}, \text{SbO}_3 + 6\text{HO}$, is to be noticed, which yields a precipitate with soda-salts. It is the only reagent which precipitates soda, but must be employed with great care and circumspection. It is obtained by fusing antimonie acid with an excess of potassa in a silver crucible, dissolving the fused mass in a small quantity of cold water, and allowing it to crystallize *in vacuo*. The crystals which form are metantimonate of potassa $2\text{KO}, \text{SbO}_3$, which, when dissolved in pure water, are decomposed into free potassa and acid metantimonate.



TERCHLORIDE OF ANTIMONY; BUTTER OF ANTIMONY; SbCl_3 .—This substance is produced when sulphuretted hydrogen is prepared by the action of strong hydrochloric acid on tersulphide of antimony. The impure and highly-acid solution thus obtained is put into a retort and distilled until each drop of the condensed product, on falling into the aqueous liquid of the receiver, produces a copious white precipitate. The receiver is then changed, and the distillation continued. Pure terchloride of antimony passes over, and solidifies on cooling to a white and highly-crystalline mass, from which the air requires to be carefully excluded. The same compound is formed by distilling metallic antimony in powder with $2\frac{1}{2}$ times its weight of corrosive sublimate. Terchloride of antimony is very deliquescent; it dissolves in strong hydrochloric acid without decomposition, and the solution poured into water gives rise to a white bulky precipitate, which, after a short time, becomes highly crystalline, and assumes a pale fawn colour. This is the old *powder of Algaroth*; it is a compound of terchloride and teroxide of antimony. Alkaline solutions extract the chloride and leave teroxide of antimony. Finely-powdered antimony thrown into chlorine gas inflames.

PENTACHLORIDE OF ANTIMONY, corresponding to antimonie acid, is formed by passing a stream of chlorine gas over gently-heated metallic antimony: a mixture of the two chlorides results, which may be separated by distillation. The *pentachloride* is a colourless volatile liquid, which forms a crystalline compound with a small portion of water, but is decomposed by a larger quantity into antimonie and hydrochloric acids.

TERSULPHIDE OF ANTIMONY; CRUDE ANTIMONY; SbS_3 .—The native sulphide is a lead-grey, brittle substance, having a radiated crystalline texture, and is easily fusible. It may be prepared artificially by melting together antimony and sulphur. When a solution of tartar-emetic is precipitated by sulphuretted hydrogen, a brick-red precipitate falls, which is the same substance combined with a little water. If the precipitate be dried and gently heated, the water may be expelled without other change of colour than a little darkening, but at a higher temperature it assumes the colour and aspect of the native sulphide. This remarkable change probably indicates a passage from the amorphous to the crystalline condition.

When powdered tersulphide of antimony is boiled in a solution of caustic potassa, it is dissolved, teroxide of antimony and sulphide of

potassium being produced. The latter unites with an additional quantity of tersulphide of antimony to a soluble sulphur-salt, in which the sulphide of potassium is the sulphur-base, and the tersulphide of antimony is the sulphur-acid.



The teroxide of antimony separates in small crystals from the boiling solution when the latter is concentrated, and the sulphur-salt dissolves an extra proportion of tersulphide of antimony, which it again deposits on cooling as a red amorphous powder, containing a small admixture of teroxide of antimony and sulphide of potassium. This is the *kermes mineral* of the old chemists. The filtered solution mixed with an acid gives a salt of potassa, sulphuretted hydrogen, and precipitated tersulphide of antimony. Kermes may also be made by fusing a mixture of 5 parts tersulphide of antimony and 3 of dry carbonate of soda, boiling the mass in 80 parts of water, and filtering while hot; the compound separates on cooling.

PENTASULPHIDE OF ANTIMONY, SbS_5 , formerly called *sulphur auratum*, also exists; it is a sulphur-acid. 18 parts finely-powdered tersulphide of antimony, 17 parts dry carbonate of soda, 13 parts lime in the state of hydrate, and $3\frac{1}{4}$ parts sulphur, are boiled for some hours in a quantity of water; carbonate of lime, antimonate of soda, pentasulphide of antimony, and sulphide of sodium are produced. The first is insoluble, and the second partially so; the two last-named bodies, on the contrary, unite to a soluble sulphur-salt, which may by evaporation be obtained in beautiful crystals. A solution of this substance, mixed with dilute sulphuric acid, furnishes sulphate of soda, sulphuretted hydrogen, and pentasulphide of antimony, which falls as a golden-yellow flocculent precipitate.

ANTIMONETTED HYDROGEN.—A compound of antimony and hydrogen exists, but has not been isolated: when zinc is put into a solution of teroxide of antimony, and sulphuric acid added, part of the hydrogen combines with the antimony. This gas burns with a greenish flame, giving rise to white fumes of teroxide of antimony. When the gas is conducted through a red-hot glass tube of narrow dimensions, or burned with a limited supply of air, such as is the case when a cold porcelain surface is pressed into the flame, metallic antimony is deposited.

The few salts of antimony soluble in water are amply characterized by the orange or brick-red precipitate with sulphuretted hydrogen, which is soluble in solution of sulphide of ammonium, and again precipitated by an acid.

Besides its application to medicine, antimony is of great importance in the arts of life, inasmuch as it forms with lead *type-metal*. This alloy expands at the moment of solidifying, and takes an exceedingly sharp impression of the mould. It is remarkable that both its constituents shrink under similar circumstances, and make very bad castings. Tersulphide of antimony enters into the composition of the blue signal-light, used at sea.*

TELLURIUM.

This metal, or semi-metal, is of very rare occurrence; it is found in a few scarce minerals in association with silver, lead, and bismuth, apparently replacing sulphur, and is most easily extracted from the sulpho-telluride of bismuth of Chemnitz, in Hungary. The finely-powdered ore is mixed with an equal weight of dry carbonate of soda, the mixture made into a paste with oil, and heated to whiteness in a closely-covered crucible. Telluride and sulphide of sodium are produced, and metallic bismuth set free. The fused mass is dissolved in water and the solution freely exposed to the air, when the sodium and sulphur oxidize to caustic soda and hyposulphite of soda, while the tellurium separates in the metallic state. Tellurium has the colour and lustre of silver; by fusion and slow cooling it may be made to exhibit the form of rhombohedral crystals similar to those of antimony and arsenic. It is brittle, and a comparatively bad conductor of heat and electricity; it has a density of 6.26, melts at a little below a red-heat, and volatilizes at a higher temperature. Tellurium burns when heated in the air, and is oxidized by nitric acid. Two compounds of this substance with oxygen are known, having acid properties; they much resemble the acids of arsenic.

The equivalent of tellurium is 64.2; its symbol is Te.

TELLUROUS ACID, TeO_2 .—This is obtained by burning tellurium in the air, or by heating it in fine powder with nitric acid of 1.25 specific gravity; a solution is rapidly formed, from which white anhydrous octahedral crystals of tellurous acid are deposited on standing. The acid is fusible at a red-heat, and slightly volatile at a higher temperature; it is but feebly soluble in water or acids, easily dissolved by alkalis, and reduced when heated with carbon or hydrogen. A hydrate of tellurous acid is thrown down when tellurite of potassa is mixed with a slight excess of nitric acid; it is a white powder, soluble to a certain extent in water, and reddens litmus.

TELLURIC ACID, TeO_3 .—Equal parts of tellurous acid and car-

* Blue or Bengal light:

Dry nitrate of potassa	6 parts.
Sulphur	2 "
Tersulphide of antimony	1 part.

All in fine powder, and intimately mixed.

bonate of soda are fused, and the product dissolved in water; a little hydrate of soda is added, and a stream of chlorine passed through the solution. The liquid is next saturated with ammonia, and mixed with solution of chloride of barium, by which a white insoluble precipitate of tellurate of baryta is thrown down. This is washed and digested with a quarter of its weight of sulphuric acid, diluted with water. The filtered solution gives, on evaporation in the air, large crystals of telluric acid.

Telluric acid is freely, although slowly, soluble in water; it has a metallic taste, and reddens litmus-paper. When the crystals are strongly heated, they lose water, and yield the anhydrous acid, which is then insoluble in water, and even in a boiling alkaline liquid. At the temperature of ignition, telluric acid loses oxygen, and passes into tellurous acid. The salts of the alkalis are soluble, but do not crystallize; those of the earths are nearly, or quite, insoluble.

There are two chlorides of tellurium, and also a hydrate, which closely resembles sulphuretted hydrogen.

ARSENIC.

Arsenic is sometimes found native: it occurs in considerable quantity as a constituent of many minerals, combined with metals, sulphur and oxygen. In the oxidized state it has been found in very minute quantity in a great many mineral waters. The largest proportion is derived from the roasting of natural arsenides of iron, nickel, and cobalt: the operation is conducted in a reverberatory furnace, and the volatile products condensed in a long and nearly horizontal chimney, or in a kind of tower of brickwork, divided into numerous chambers. The crude arsenious acid thus produced is purified by sublimation, and then heated with charcoal in a retort; the metal is reduced, and readily sublimes.

Arsenic has a steel-grey colour, and high metallic lustre; it is crystalline and very brittle; it tarnishes in the air, but may be preserved unchanged in pure water. Its density is 5.7 to 5.9. When heated, it volatilizes without fusion, and, if air be present, oxidizes to arsenious acid. The vapour has the odour of garlic. This substance combines with metals in the same manner as sulphur and phosphorus, which it resembles, especially the latter, in many respects. With oxygen it unites in two proportions, giving rise to arsenious and arsenic acids. There is no basic oxide of arsenic.

The equivalent of arsenic is 75; its symbol is As.

ARSENIOUS ACID; WHITE OXIDE OF ARSENIC; AsO_3 .—The origin of this substance is mentioned above. It is commonly met with in the form of a heavy, white, glassy-looking substance, with smooth conchoidal fracture, which has evidently undergone fusion. When freshly prepared, it is often transparent, but by keeping becomes

opaque, at the same time slightly diminishing in density, and acquiring a greater degree of solubility in water. 100 parts of that liquid dissolve, at 212° (100°C), about 11.5 parts of the opaque variety; the largest portion separates, however, on cooling, leaving about 3 parts dissolved: the solution feebly reddens litmus. Cold water, agitated with powdered arsenious acid, takes up a still smaller quantity. Alkalis dissolve this substance freely, forming arsenites; also compounds with ammonia, baryta, strontia, lime, magnesia, and oxide of manganese, have been formed; it is also easily soluble in hot hydrochloric acid. The vapour of arsenious acid is colourless and inodorous; it crystallizes on solidifying in brilliant transparent octahedrons. The acid itself has a feeble sweetish and astringent taste, and is a most fearful poison.

ARSENIC ACID, AsO_5 .—Powdered arsenious acid is dissolved in hot hydrochloric acid, and oxidized by the addition of nitric acid, the latter being added as long as red vapours are produced; the whole is then cautiously evaporated to complete dryness. The acid thus produced is white and anhydrous. Put into water, it slowly but completely dissolves, giving a highly-acid solution, which, on being evaporated to a syrupy consistence, deposits, after a time, hydrated crystals of arsenic acid. When strongly heated, it is decomposed into arsenious acid and oxygen gas.

This substance is a very powerful acid, comparable with phosphoric, which it resembles in the closest manner, forming salts strictly isomorphous with the corresponding phosphates; it is also tribasic. An arsenate of soda, $2\text{NaO}, \text{HO}, \text{AsO}_5 + 24\text{HO}$, indistinguishable in appearance from common phosphate of soda, may be prepared by adding the carbonate to a solution of arsenic acid, until an alkaline reaction is apparent, and then evaporating. This salt also crystallizes with 14 equivalents of water. Another arsenate, $3\text{NaO}, \text{AsO}_5 + 24\text{HO}$, is produced when carbonate of soda in excess is fused with arsenic acid, or when the preceding salt is mixed with caustic soda. A third, $\text{NaO}, 2\text{HO}, \text{AsO}_5 + 2\text{HO}$, is made by substituting an excess of arsenic acid for the solution of alkali. The alkaline arsenates which contain basic water lose the latter at a red-heat, but unlike the phosphates, recover it when again dissolved.* The salts of the alkalis are soluble in water; those of the earths and other metallic oxides are insoluble, but are dissolved by acids. The precipitate with nitrate of silver is highly characteristic of arsenic acid; it is reddish-brown.

Three SULPHIDES OF ARSENIC are known. *Realgar*, AsS_2 , occurs native; it is formed artificially, by heating arsenic acid with the proper proportion of sulphur. It is an orange-red, fusible, and volatile substance, employed in painting and by the pyrotechnist in making *white-fire*. *Orpiment*, AsS_3 , which is also a natural product of the mineral kingdom, is made by fusing arsenic acid with excess of

* Graham, Elements, p. 630, first edition.

sulphur, or by precipitating a solution of the acid by sulphuretted hydrogen. It is a golden-yellow crystalline substance, fusible and volatile by heat. A higher sulphide, AsS_5 , corresponding to arsenic acid, is produced when sulphuretted hydrogen is transmitted through a solution of arsenic acid. The solution of arsenic acid is not immediately precipitated, the pentasulphide being deposited only after some hours' standing. Its precipitation is considerably accelerated by ebullition. It is a yellow fusible substance, capable of sublimation. Realgar, orpiment, and pentasulphide of arsenic are sulphur-acids.

Arsenic unites with chlorine, iodine, &c. The *terchloride*, AsCl_3 , is formed by distilling a mixture of 1 part of arsenic, and 6 parts of corrosive sublimate; it is a colourless, volatile liquid, decomposed by water into arsenious and hydrochloric acids. The same substance is produced, with disengagement of heat and light, when powdered arsenic is thrown into chlorine gas. The *iodide*, AsI_3 , is formed by heating metallic arsenic with iodine; it is a deep-red crystalline substance, capable of sublimation. The *bromide* and *fluoride* are both liquid.

Arsenic also combines with hydrogen, forming a gaseous compound, AsH_3 , analogous to phosphoretted hydrogen. It is obtained pure by the action of strong hydrochloric acid on an alloy of equal parts of zinc and arsenic, and is produced in greater or less proportion whenever hydrogen is set free in contact with arsenious acid. Arsenetted hydrogen is a colourless gas, of 2.695 specific gravity, slightly soluble in water, and having the smell of garlic. It burns when kindled with a blue flame, generating arsenious acid. It is also decomposed by transmission through a red-hot tube. Many metallic solutions are precipitated by this substance. It is, when inhaled, exceedingly poisonous, even in very minute quantity.

Arsenious acid is distinguished by characters which cannot be misunderstood.

Nitrate of silver, mixed with a solution of arsenious acid in water, occasions no precipitate, or merely a faint cloud; but if a little alkali, as a drop of ammonia, be added, a yellow precipitate of arsenite of silver immediately falls. The precipitate is exceedingly soluble in excess of ammonia; that substance must, therefore, be added with great caution; it is likewise very soluble in nitric acid.

Sulphate of copper gives no precipitate with solution of arsenious acid, until the addition has been made of a little alkali, when a brilliant yellow-green precipitate (Scheele's green) falls, which also is very soluble in excess of ammonia.

Sulphuretted hydrogen passed into a solution of arsenious acid, to which a few drops of hydrochloric or sulphuric acid have been added, occasions the production of a copious bright-yellow precipitate

of orpiment, which is dissolved with facility by ammonia, and reprecipitated by acids.

Solid arsenious acid, heated by the blowpipe in a narrow glass tube with small fragments of dry charcoal, affords a sublimate of metallic arsenic in the shape of a brilliant steel-grey metallic ring. A portion of this, detached by the point of a knife and heated in a second glass tube, with access of air, yields, in its turn, a sublimate of colourless, transparent, octahedral crystals of arsenious acid.

All these experiments, which *jointly* give demonstrative proof of the presence of the substance in question, may be performed, with perfect precision and certainty, upon exceedingly small quantities of material.

The detection of arsenious acid in complex mixtures containing organic matter and common salt, as beer, gruel, soup, &c., or the fluid contents of the stomach in cases of poisoning, is a very far more difficult problem, but one which is, unfortunately, often required to be solved. These organic matters interfere completely with the liquid tests, and render their indications worthless. Sometimes the difficulty may be eluded by a diligent search in the suspected liquid, and in the vessel containing it, for fragments or powder of solid arsenious acid, which, from its small degree of solubility, often escape solution, and from the high density of the substance may be found at the bottom of the vessels in which the fluids are contained. If anything of the kind be found, it may be washed by decantation with a little cold water, dried, and then reduced with charcoal. For the latter purpose, a small glass tube is taken, having the figure represented in the margin; white German glass, free from lead, is to be preferred. The arsenious acid, or what is suspected to be such, is dropped to the bottom, and covered with splinters or little fragments of charcoal, the tube being filled to the shoulder. The whole is gently heated, to expel any moisture that may be present in the charcoal, and the deposited water wiped from the interior of the tube with bibulous paper. The narrow part of the tube containing the charcoal, from *a* to *b*, is now heated by the blowpipe flame; when red-hot the tube is inclined, so that the bottom also may become heated. The arsenious acid, if present, is vaporized, and reduced by the charcoal, and a ring of metallic arsenic deposited on the cool part of the tube. To complete the experiment, the tube may be melted at *a* by the point of the flame, drawn off, and closed, and the arsenic oxidized to arsenious acid, by chasing it up and down by the heat of a small spirit-lamp. A little water may afterwards be introduced, and boiled in the tube, by which the arsenious acid will be dissolved, and to this solution the tests of nitrate of silver and ammonia,

Fig. 146.



sulphate of copper and ammonia, and sulphuretted hydrogen, may be applied.

When the search for solid arsenious acid fails, the liquid itself must be examined; a tolerably-limpid solution must be obtained, from which the arsenic may be precipitated by sulphuretted hydrogen, and the orpiment collected, and reduced to the metallic state. It is in the first part of this operation that the chief difficulty is found; such organic mixtures refuse to filter, or filter so slowly, as to render some method of acceleration indispensable. Boiling with a little caustic potassa or acetic acid will sometimes effect this object. The following is an outline of a plan, which has been found successful in a variety of cases, in which a very small quantity of arsenious acid had been purposely added to an organic mixture. Oil of vitriol, itself perfectly free from arsenic, is mixed with the suspected liquid, in the proportion of about a measured ounce to a pint, having been previously diluted with a little water, and the whole is boiled in a flask for half an hour, or until a complete separation of solid and liquid matter becomes manifest. The acid converts any starch that may be present into dextrin and sugar; it coagulates completely albuminous substances, and casein, in the case of milk, and brings the whole in a very short time into a state in which filtration is both easy and rapid. Through the filtered solution, when cold, a current of sulphuretted hydrogen is transmitted, and the liquid is warmed, to facilitate the deposition of the tersulphide, which falls in combination with a large quantity of organic matter, which often communicates to it a dirty colour. This is collected upon a small filter, and washed. It is next transferred to a capsule, and heated with a mixture of nitric and hydrochloric acids, by which the organic impurities are in a great measure destroyed, and the arsenic oxidized to arsenic acid. The solution is evaporated to dryness, the soluble part taken up by dilute hydrochloric acid, and then the solution saturated with sulphurous acid, whereby the arsenic acid is reduced to the state of arsenious acid, the sulphurous being oxidized to sulphuric acid. The solution of arsenious acid may be precipitated by sulphuretted hydrogen without any difficulty. The liquid is warmed, and the precipitate washed by decantation, and dried. It is then mixed with *black-flux*, and heated in a small glass tube, similar to that already described, with similar precautions; a ring of reduced arsenic is obtained, which may be oxidized to arsenious acid, and farther examined. The *black-flux* is a mixture of carbonate of potassa and charcoal, obtained by calcining cream of tartar in a close crucible; the alkali transforms the sulphide into arsenious acid, the charcoal subsequently effecting the deoxidation. A mixture of anhydrous carbonate of soda and charcoal may be substituted with advantage for the common *black-flux*, as it is less hygroscopic.

Other methods of proceeding, different in principle from the foregoing, have been proposed, as that of the late Mr. Marsh, which is

exceedingly delicate. The suspected liquid is acidulated with sulphuric acid and placed in contact with metallic zinc; the hydrogen reduces the arsenious acid and combines with the arsenic, if any be present. The gas is burned at a jet, and a piece of glass or porcelain held in the flame, when any admixture of arsenetted hydrogen is at once known by the production of a brilliant black metallic spot of reduced arsenic on the porcelain.

It has been observed (page 344) that antimonetted hydrogen gives a similar result. In order to distinguish the two substances, the gas may be passed into a solution of nitrate of silver. Both gases give rise to a black precipitate, which, in the case of antimonetted hydrogen, consists of antimonide of silver, Ag_3S_6 , whilst it is pure silver in the case of arsenetted hydrogen, the arsenic being then converted into arsenious acid, which combines with a portion of oxide of silver. The arsenite of silver remains dissolved in the nitric acid which is liberated by the precipitation of the silver, and may be thrown down with its characteristic yellow colour by adding ammonia to the liquid filtered off from the black precipitate.

A convenient form of Marsh's instrument is that shown in the drawing; it consists of a bent tube, having two bulbs blown upon it, fitted with a stop-cock and narrow jet. Slips of zinc are put into the lower bulb, which is afterwards filled with the liquid to be examined. On replacing the stop-cock, closed, the gas collects and forces the fluid into the upper bulb, which then acts by its hydrostatic pressure, and expels the gas through the jet so soon as the stop-cock is opened. It must be borne in mind that both common zinc and sulphuric acid often contain traces of arsenic.

A slip of copper-foil boiled in the poisoned liquid, previously acidulated with hydrochloric acid, withdraws the arsenic and becomes covered with a white alloy. By heating the metal in a glass tube, the arsenic is expelled, and oxidized to arsenious acid.

Fig. 147.



SECTION VI.

METALS WHOSE OXIDES ARE REDUCED BY HEAT.

SILVER.

SILVER is found in the metallic state, in union with sulphur, and also as chloride and bromide. Among the principal silver mines may be mentioned those of the Hartz mountains in Germany, of Kongsberg in Norway, and, more particularly, of the Andes in both North and South America.

The greater part of the silver of commerce is extracted from ores so poor as to render any process of *smelting* or fusion inapplicable, even where fuel could be obtained, and this is often difficult to be procured. Recourse, therefore, is had to another method, that of *amalgamation*, founded on the easy solubility of silver and many other metals in metallic mercury.

The amalgamation-process, as conducted in Germany, differs somewhat from that in use in America. The ore is crushed to powder, mixed with a quantity of common salt, and roasted at a low red-heat in a suitable furnace, by which treatment any sulphide of silver it may contain is converted into chloride. The mixture of earthy matter, oxides of iron, copper, soluble salts, chloride of silver, and metallic silver, is sifted and put into large barrels, made to revolve on axes, with a quantity of water and scraps of iron, and the whole agitated together for some time, during which the iron reduces the chloride of silver to the state of metal. A certain proportion of mercury is then introduced, and the agitation repeated; the mercury dissolves out the silver, together with gold, if there be any, metallic copper, and other substances, forming a fluid amalgam easily separable from the thin mud of earthy matter by subsidence and washing. This amalgam is strained through strong linen cloth, and the solid portion exposed to heat in a kind of retort, by which the remaining mercury is distilled off and the silver left behind in an impure condition.

A considerable quantity of silver is obtained from argentiferous galena; in fact, almost every specimen of native sulphide of lead will be found to contain traces of this metal. When the proportion rises to a certain amount it becomes worth extracting. The ore is reduced in the usual manner, the whole of the silver remaining with the lead; the latter is then re-melted in a large vessel, and allowed slowly to

cool until solidification commences. The portion which first crystallizes is nearly pure lead, the alloy with silver being *more fusible than lead itself*; by particular management this is drained away, and is found to contain nearly the whole of the silver. This rich mass is next exposed to a red-heat on the shallow hearth of a furnace, while a stream of air is allowed to impinge upon its surface: oxidation takes place with great rapidity, the fused oxide or litharge being constantly swept from the metal by the blast. When the greater part of the lead has been thus removed, the residue is transferred to a *cupel* or shallow dish made of bone-ashes, and again heated; the last of the lead is now oxidized, and the oxide sinks in a melted state into the porous vessel, while the silver, almost chemically pure, and exhibiting a brilliant surface, remains behind.

Pure silver may be easily obtained. The metal is dissolved in nitric acid; if it contain copper, the solution will have a blue tint; gold will remain undissolved as a black powder. The solution is mixed with hydrochloric acid or with common salt, and the white, insoluble curdy precipitate of chloride of silver washed and dried. This is then mixed with about twice its weight of anhydrous carbonate of soda, and the mixture, placed in an earthen crucible, gradually raised to a temperature approaching whiteness, during which the carbonate of soda and the chloride react upon each other, carbonic acid and oxygen escape, while metallic silver and chloride of sodium result; the former fuses into a button at the bottom of the crucible, and is easily detached.

Pure silver has a most perfect white colour and a high degree of lustre; it is exceedingly malleable and ductile, and is probably the best conductor both of heat and electricity known. Its specific gravity is 10.5. In hardness it lies between gold and copper. It melts at a bright red-heat, about 1873° (1023°C), according to the observations of Mr. Daniell. Silver is unalterable by air and moisture; it refuses to oxidize at any temperature, but possesses the extraordinary faculty, already noticed in an earlier part of the work, of absorbing many times its volume of oxygen when strongly heated in an atmosphere of that gas, or in common air. This oxygen is again disengaged at the moment of solidification, and gives rise to the peculiar arborescent appearance often remarked on the surface of masses or buttons of pure silver. The addition of 2 per cent. of copper is sufficient to prevent this absorption of oxygen. Silver oxidizes when heated with fusible siliceous matter, as glass, which it stains yellow or orange, from the formation of a silicate. It is little attacked by hydrochloric acid; boiling oil of vitriol converts it into sulphate with evolution of sulphurous acid; nitric acid, even dilute and in the cold, dissolves it readily. The tarnishing of surfaces of silver exposed to the air is due to sulphuretted hydrogen, the metal having a strong attraction for sulphur. There are three oxides of silver, one of which is a powerful base isomorphous with potassa, soda, and oxide of ammonium.

The equivalent of silver is 108 ; its symbol is Ag (argentum).

SUBOXIDE OF SILVER, Ag_2O .—When dry citrate of silver is heated to 212° (100°C) in a stream of hydrogen gas, it loses oxygen and becomes dark brown. The product, dissolved in water, gives a dark-coloured solution containing free citric acid and citrate of the suboxide of silver. The suboxide is then precipitated by potassa. It is a black powder, very easily decomposed, and soluble in ammonia. The solution of citrate is rendered colourless by heat, being resolved into a salt of the protoxide and metallic silver.

PROTOXIDE OF SILVER, AgO .—Caustic potassa added to a solution of nitrate of silver throws down a pale-brown precipitate, which consists of protoxide of silver. It is very soluble in ammonia, and is dissolved also to a small extent by pure water ; the solution is alkaline. Recently-precipitated chloride of silver, boiled in a solution of caustic potassa of specific gravity 1.25, according to the observation of Dr. Gregory, is converted, although with difficulty, into oxide of silver, which in this case is black and very dense. The protoxide of silver neutralizes acids completely, and forms, for the most part, colourless salts. It is decomposed by a red-heat, with evolution of oxygen, spongy metallic silver being left ; the sun's rays also effect its decomposition to a small extent.

PEROXIDE OF SILVER.—This is a black crystalline substance which forms upon the positive electrode of a voltaic arrangement employed to decompose a solution of nitrate of silver. It is reduced by heat, evolves chlorine when acted upon by hydrochloric acid, explodes when mixed with phosphorus and struck, and decomposes solution of ammonia with great energy and rapid disengagement of nitrogen gas.

NITRATE OF SILVER, AgO, NO_5 .—The nitrate is prepared by directly dissolving silver in nitric acid and evaporating the solution to dryness, or until it is strong enough to crystallize on cooling. The crystals are colourless, transparent, anhydrous tables, soluble in an equal weight of cold, and in half that quantity of boiling water ; they also dissolve in alcohol. They fuse when heated like those of nitre, and at a higher temperature suffer decomposition ; the *lunar caustic* of the surgeon is nitrate of silver which has been melted and poured into a cylindrical mould. The salt blackens when exposed to light, more particularly if organic matters of any kind be present, and is frequently employed to communicate a dark stain to the hair ; it enters into the composition of the “indelible” ink used for marking linen. The black stain has been thought to be metallic silver ; it may possibly be suboxide. Pure nitrate of silver may be prepared from the metal alloyed with copper : the alloy is dissolved in nitric acid, the solution evaporated to dryness, and the mixed nitrates cautiously heated to fusion. A small portion of the melted mass is removed from time to time for examination ; it is dissolved in water, filtered, and ammonia added to it in excess. While any copper salt remains

undecomposed, the liquid will be blue, but when that no longer happens, the nitrate may be suffered to cool, dissolved in water, and filtered from the insoluble black oxide of copper.

SULPHATE OF SILVER, AgO, SO_3 .—The sulphate may be prepared by boiling together oil of vitriol and metallic silver, or by precipitating a concentrated solution of nitrate of silver by an alkaline sulphate. It dissolves in 88 parts of boiling water, and separates in great measure in a crystalline form on cooling, having but a feeble degree of solubility at a low temperature. It forms a crystallizable compound with ammonia, freely soluble in water, containing $\text{AgO}, \text{SO}_3 + 2\text{NH}_3$.

Hyposulphate of Silver, $\text{AgO}, \text{S}_2\text{O}_5 + \text{HO}$, is a soluble crystallizable salt, permanent in the air. The *hyposulphite* is insoluble, white, and very prone to decomposition; it combines with the alkaline hypsulphites, forming soluble compounds distinguished by an intensely sweet taste. The alkaline hypsulphites dissolve both oxide and chloride of silver, and give rise to similar salts, an oxide or chloride of the alkaline metal being at the same time formed. *Carbonate of silver* is a white insoluble substance obtained by mixing solutions of nitrate of silver and of carbonate of soda. It is blackened and decomposed by boiling.

CHLORIDE OF SILVER, AgCl .—This substance is almost invariably produced when a soluble salt of silver and a soluble chloride are mixed. It falls as a white curdy precipitate, quite insoluble in water and nitric acid; but one part of chloride of silver is soluble in 200 parts of hydrochloric acid when concentrated, and in about 600 parts when diluted with double its weight of water. When heated it melts, and on cooling becomes a greyish crystalline mass, which cuts like horn; it is found native in this condition, constituting the *horn-silver* of the mineralogist. Chloride of silver is decomposed by light both in a dry and wet state, *very* slowly if pure, and quickly if organic matter be present: it is reduced also when put into water with metallic zinc or iron. It is soluble with great ease in ammonia and in a solution of cyanide of potassium. In practical analysis the proportion of chlorine or hydrochloric acid in a compound is always estimated by precipitation by solution of silver. The liquid is acidulated with nitric acid, and an excess of nitrate of silver added; the chloride is collected on a filter, or better by subsidence, washed, dried, and fused; 100 parts correspond to 24.7 of chlorine, or 25.43 of hydrochloric acid.

IODIDE OF SILVER, AgI .—The iodide is a pale-yellow insoluble precipitate, produced by adding nitrate of silver to iodide of potassium; it is insoluble or nearly so in ammonia, and forms an exception to the silver-salts in general in this respect. The *bromide* of silver very closely resembles the chloride.

SULPHIDE OF SILVER, AgS .—This is a soft, grey and somewhat malleable substance, found native in a crystallized state, and easily

produced by melting together its constituents, or by precipitating a solution of silver by sulphuretted hydrogen. It is a strong sulphur-base, and combines with the sulphides of antimony and arsenic; examples of such compounds are found in the beautiful minerals *dark* and *light red silver ore*.

AMMONIA-COMPOUND OF SILVER; BERTHOLLET'S FULMINATING SILVER.—When precipitated oxide of silver is digested in ammonia, a black substance is produced, possessing exceedingly dangerous explosive properties. It explodes while moist, when rubbed with a hard body, but when dry the touch of a feather is sufficient. The ammonia retains some of this substance in solution, and deposits it in small crystals by spontaneous evaporation. A similar compound containing oxide of gold exists. It is easy to understand the reason why these bodies are subject to such violent and sudden decomposition by the slightest cause, on the supposition that they contain an oxide of an easily-reducible metal and ammonia: the attraction between the two constituents of the substance is very feeble, while that between the oxygen of the one and the hydrogen of the other is very powerful. The explosion is caused by the sudden evolution of nitrogen gas and vapour of water, the metal being set free.

A soluble salt of silver is perfectly characterized by the white curdy precipitate of chloride of silver, darkening by exposure to light, and insoluble in hot nitric acid, which is produced by the addition of any soluble chloride. Lead is the only metal which can be confounded with it in this respect; but chloride of lead is soluble to a great extent in boiling water, and is deposited in brilliant acicular crystals when the solution cools. Solutions of silver are reduced to the metallic state by iron, copper, mercury, and other metals.

The economical uses of silver are many: it is admirable for culinary and other similar purposes, not being attacked in the slightest degree by any of the substances used for food. It is necessary, however, in these cases to diminish the softness of the metal by a small addition of copper. The standard silver of England contains 222 parts of silver and 18 parts of copper.

GOLD.

Gold, in small quantities, is a very widely-diffused metal; traces are constantly found in the iron pyrites of the more ancient rocks. It is always met with in the metallic state, sometimes beautifully crystallized in the cubic form, associated with quartz, oxide of iron, and other substances, in regular mineral veins. The sands of various

rivers have long furnished gold derived from this source, and separable by a simple process of washing; such is the *gold-dust* of commerce. When a vein-stone is wrought for gold, it is stamped to powder, and shaken in a suitable apparatus with water and mercury; an amalgam is formed, which is afterwards separated from the mixture and decomposed by distillation.

The pure metal is obtained by solution in nitro-hydrochloric acid and precipitation by a salt of protoxide of iron, which, by undergoing peroxidation, reduces the gold. The latter falls as a brown powder, which acquires the metallic lustre by friction.

Gold is a soft metal, having a beautiful yellow colour. It surpasses all other metals in malleability, the thinnest gold-leaf not exceeding, it is said, $\frac{1}{200000}$ of an inch in thickness, while the gilding on the silver wire used in the manufacture of *gold lace* is still thinner. It may also be drawn into very fine wire. Gold has a density of 19.5; it melts at a temperature a little above the fusing-point of silver. Neither air nor water affect it in the least at any temperature; the ordinary acids fail to attack it singly. A mixture of nitric and hydrochloric acids dissolves gold, however, with ease, the active agent being the liberated chlorine. Gold forms two compounds with oxygen, and two corresponding compounds with chlorine, iodine, sulphur, &c. Both oxides refuse to unite with acids.

The equivalent of gold is 197. Its symbol is Au (aurum).

PROTOXIDE OF GOLD, AuO.—The protoxide is produced when caustic potassa in solution is poured upon the protochloride. It is a green powder, partly soluble in the alkaline liquid; the solution rapidly decomposes into metallic gold, which subsides, and into teroxide, which remains dissolved.

TEROXIDE OF GOLD; AURIC ACID; AuO₃.—When magnesia is added to the terchloride of gold, and the sparingly soluble aurate of that base well washed and digested with nitric acid, the teroxide is left as an insoluble reddish-yellow powder, which, when dry, becomes chestnut-brown. It is easily reduced by heat, and also by mere exposure to light; it is insoluble in oxygen acids with the exception of strong nitric acid, insoluble in hydrofluoric acid, easily dissolved by hydrochloric and hydrobromic acids. Alkalis dissolve it freely; indeed, the acid properties of this substance are very strongly marked; it partially decomposes a solution of chloride of potassium when boiled with that liquid, potassa being produced. When digested with ammonia, it furnishes fulminating gold.

PROTOCHLORIDE OF GOLD, AuCl.—This substance is produced when the terchloride is evaporated to dryness and exposed to a heat of 440° (226°·6C) until chlorine ceases to be exhaled. It forms a yellowish-white mass, insoluble in water. In contact with that liquid it is decomposed slowly in the cold, and rapidly by the aid of heat, into metallic gold and terchloride.

TERCHLORIDE OF GOLD, AuCl₃.—This is the most important com-

pound of the metal; it is always produced when gold is dissolved in nitro-hydrochloric acid. The deep-yellow solution thus obtained yields, by evaporation, yellow crystals of the double chloride of gold and hydrogen; when this is cautiously heated, hydrochloric acid is expelled, and the residuc, on cooling, solidifies to a red crystalline mass of terchloride of gold, very deliquescent, and soluble in water, alcohol, and ether. The terchloride of gold combines with a number of metallic chlorides, forming a series of double salts, of which the general formula in the anhydrous state is $MCl + AuCl_3$, M representing an equivalent of the second metal. These compounds are mostly yellow when in crystals, and red when deprived of water.

A mixture of terchloride of gold with excess of bicarbonate of potassa or soda is used for gilding small ornamental articles of copper; these are cleaned by dilute nitric acid, and then boiled in the mixture for some time, by which means they acquire a thin but perfect coating of reduced gold.

The other compounds of gold are of very little importance.

The presence of this metal in solution may be known by the brown precipitate with sulphate of protoxide of iron, fusible before the blow-pipe into a bead of gold; and by the purple compound formed when the terchloride of gold is added to a solution of protochloride of tin.

Gold intended for coin, and most other purposes, is always alloyed with a certain proportion of silver or copper, to increase its hardness and durability; the first-named metal confers a pale-greenish colour. English standard gold contains $\frac{1}{12}$ of alloy, now always copper. *Gold-leaf* is made by rolling out plates of pure gold as thin as possible, and then beating them between folds of membrane by a heavy hammer, until the requisite degree of tenuity has been reached. The leaf is made to adhere to wood, &c., by size or varnish.

Gilding on copper has very generally been performed by dipping the articles into a solution of nitrate of mercury, and then shaking them with a small lump of a soft amalgam of gold with that metal, which thus becomes spread over their surfaces: the articles are subsequently heated to expel the mercury and then burnished. Gilding on steel is done either by applying a solution of terchloride of gold, in ether, or by roughening the surface of the metal, heating it, and applying gold-leaf, with a burnisher. Gilding by electrolysis—an elegant and simple method, now rapidly superseding many of the others—has already been noticed. The solution usually employed is obtained by dissolving oxide or cyanide of gold in a solution of cyanide of potassium.*

* Messrs. Elkington, Application of Electro-Metallurgy to the Arts.

MERCURY, OR QUICKSILVER.

This very remarkable metal has been known from an early period, and perhaps more than all others has excited the attention and curiosity of experimenters, by reason of its peculiar physical properties. Mercury is of great importance in several of the arts, and enters into the composition of many valuable medicaments.

Metallic mercury is occasionally met with in globules disseminated through the native sulphide, which is the ordinary ore. This latter substance, sometimes called *cinnabar*, is found in considerable quantity in several localities, of which the most celebrated are Almaden in New Castile, and Idria in Carniola. Only recently it has been discovered in great abundance, and of remarkable purity, in California. The metal is obtained by heating the sulphide in an iron retort with lime or scraps of iron, or by roasting it in a furnace, and conducting the vapours into a large chamber, where the mercury is condensed, while the sulphurous acid is allowed to escape. Mercury is imported into this country in bottles of hammered iron, containing seventy-five pounds each, and in a state of considerable purity. When purchased in smaller quantities, it is sometimes found adulterated with tin and lead, which metals it dissolves to some extent without much loss of fluidity. Such admixture may be known by the foul surface the mercury exhibits when shaken in a bottle containing air, and by the globules, when made to roll upon the table, having a train or tail.

Mercury has a nearly silver-white colour, and a very high degree of lustre; it is liquid at all ordinary temperatures, and only solidifies when cooled to -40° (-40°C). In this state it is soft and malleable. At 662° (350°C) it boils, and yields a transparent, colourless vapour, of great density. The metal volatilizes, however, to a sensible extent at all temperatures above 68° (20°C) or 70° (21°C); below this point its volatility is imperceptible. The volatility of mercury at the boiling-heat is singularly retarded by the presence of minute quantities of lead or zinc. The specific gravity of mercury at 60° ($15^{\circ}\cdot 5\text{C}$) is 13.59; that of frozen mercury about 14, great contraction taking place in the act of solidification.

Pure quicksilver is quite unalterable in the air at common temperatures, but when heated to near its boiling-point it slowly absorbs oxygen, and becomes converted into a crystalline dark-red powder, which is the highest oxide. At a dull red-heat this oxide is again decomposed into its constituents. Hydrochloric acid has little or no action on mercury, and the same may be said of sulphuric acid in a diluted state; when the latter is concentrated and boiling hot, it oxidizes the metal, converting it into sulphate of the red oxide, with evolution of sulphurous acid. Nitric acid, even dilute and in the cold, dissolves mercury freely, with an evolution of binoxide of nitrogen.

Mercury combines with oxygen in two proportions, forming a grey and a red oxide, both of which are salifiable. As the salts of the red oxide are the most stable and permanent, that substance may be regarded as the true protoxide, instead of the grey oxide, to which the term has formerly been applied. Until, however, isomorphous relations connecting mercury with the other metals shall be established, the constitution of the two oxides and that of the corresponding chlorides, iodides, &c., must remain somewhat unsettled.

The equivalent of mercury, on the above supposition, will be 100; its symbol is Hg (hydrargyrum).

SUBOXIDE OF MERCURY; GREY OXIDE; Hg_2O .—The suboxide is easily prepared by adding caustic potassa to the nitrate of this substance, or by digesting calomel in solution of caustic alkali. It is a dark grey, nearly black, heavy powder, insoluble in water. It is slowly decomposed by the action of light into metallic mercury and red oxide. The preparations known in pharmacy by the names *blue pill*, *grey ointment*, *mercury with chalk*, &c., often supposed to owe their efficacy to this substance, merely contain the finely-divided metal.

PROTOXIDE OF MERCURY; RED OXIDE; HgO .—There are numerous methods by which this compound may be obtained; the following may be cited as the most important:—(1) By exposing mercury in a glass flask, with a long narrow neck, for several weeks to a temperature approaching 600° ($315^\circ\cdot5\text{C}$); the product has a dark-red colour and is highly crystalline: it is the *red precipitate* of the old writers. (2) By cautiously heating any of the nitrates of either oxide to complete decomposition, when the acid is decomposed and expelled, oxidizing the metal to a maximum, if it happen to be in the condition of suboxide. The product is in this case also crystalline and very dense, but has a much paler colour than the preceding; while hot it is nearly black. It is by this method that the oxide is generally prepared; it is apt to contain undecomposed nitrate, which may be discovered by strongly heating a portion in a test-tube: if red fumes are produced or the odour of nitrous acid exhaled, the oxide has been insufficiently heated in the process of manufacture. (3) By adding caustic potassa in excess to a solution of corrosive sublimate, by which a bright-yellow precipitate of oxide is thrown down, which only differs from the foregoing preparations in being destitute of crystalline texture and much more minutely divided. It must be well washed and dried.

Red oxide of mercury is slightly soluble in water, communicating to the latter an alkaline reaction and metallic taste; it is highly poisonous. When strongly heated, it is decomposed, as before observed, into metallic mercury and oxygen gas.

NITRATES OF THE OXIDES OF MERCURY.—Nitric acid varies in its action upon mercury, according to the temperature. When cold and somewhat diluted, only salts of the grey oxide are formed, and

these are neutral or basic (*i. e.* with excess of oxide), as the acid or the metal happens to be in excess. When, on the contrary, the nitric acid is concentrated and hot, the mercury is raised to its highest state of oxidation, and a salt of the red oxide produced. Both classes of salts are apt to be decomposed by a large quantity of water, giving rise to insoluble, or sparingly soluble, compounds containing an excess of base.

Neutral nitrate of the suboxide, $\text{Hg}_2\text{O}, \text{NO}_5 + 2\text{HO}$, forms large colourless crystals, soluble in a small quantity of water without decomposition; it is made by dissolving mercury in an excess of cold dilute nitric acid.



When excess of mercury has been employed, a finely-crystallized basic salt is, after some time, deposited, containing $3\text{Hg}_2\text{O}, 2\text{NO}_5 + 3\text{HO}$; this is also decomposed by water. The two salts are easily distinguished when rubbed in a mortar, with a little chloride of sodium; the neutral compound gives nitrate of soda and calomel; the basic salt, nitrate of soda and a black compound of calomel with oxide of mercury. A black substance, called *Hahnemann's soluble mercury*, is produced when ammonia in small quantity is dropped into a solution of the nitrate of the suboxide; it contains $3\text{Hg}_2\text{O}, \text{NO}_5 + \text{NH}_3$, or, according to Sir R. Kane, $2\text{HgO}, \text{NO}_5 + \text{NH}_3$; the composition of this preparation evidently varies according to the temperature and the concentration of the solutions.

Nitrates of the Protoxide (Red Oxide) of Mercury.—By dissolving red oxide of mercury in excess of nitric acid, and evaporating gently, a syrupy liquid is obtained, which, enclosed in a bell-jar over lime or sulphuric acid, deposits voluminous crystals and crystalline crusts. The crystals and crusts have the same composition, $2(\text{HgO}, \text{NO}_5) + \text{HO}$. The same substance is deposited from the syrupy liquid as a crystalline powder by dropping it into concentrated nitric acid. The syrupy liquid itself appears to be a definite compound containing $\text{HgO}, \text{NO}_5 + 2\text{HO}$. By saturating hot dilute nitric acid with the red oxide, a salt is obtained on cooling which crystallizes in needles, permanent in the air, containing $2\text{HgO}, \text{NO}_5 + \text{HO}$. The preceding crystallized salts are decomposed by water, with production of compounds more and more basic as the washing is prolonged or the temperature of the water raised. The nitrates of the protoxide of mercury combine with ammonia.

Sulphate of the Suboxide of Mercury, $\text{Hg}_2\text{O}, \text{SO}_3$, falls as a white crystalline powder when sulphuric acid is added to a solution of the nitrate of the suboxide; it is but slightly soluble in water. *Sulphate of the protoxide*, HgO, SO_3 , is readily prepared by boiling together oil of vitriol and metallic mercury until the latter is wholly converted into a heavy white crystalline powder, which is the salt in question; the excess of acid is then removed by evaporation, carried to perfect dryness. Equal weights of acid and metal may be conveniently employed. Water decomposes the sulphate, dissolving out an acid salt and leaving


an insoluble, yellow, basic compound, formerly called *turpeth* or *turbith mineral*, containing, according to Kane's analysis, $3\text{HgO}, \text{SO}_3$. Long-continued washing with hot water entirely removes the remaining acid, and leaves pure protoxide of mercury.

SUBCHLORIDE OF MERCURY; CALOMEL; Hg_2Cl_2 .—This very important substance may be easily and well prepared by pouring a solution of the nitrate of the suboxide into a large excess of dilute solution of common salt. It falls as a dense white precipitate, quite insoluble in water; it must be thoroughly washed with boiling distilled water, and dried. Calomel is generally procured by another and more complex process. Dry sulphate of the red oxide is rubbed in a mortar with as much metallic mercury as it already contains, and a quantity of common salt, until the globules disappear, and an uniform mixture has been produced. This is subjected to sublimation, the vapour of the calomel being carried into an atmosphere of steam, or into a chamber containing air; it is thus condensed in a minutely-divided state, and the laborious process of pulverization of the sublimed mass avoided. The reaction is thus explained: *—





Pure calomel is a heavy, white, insoluble, tasteless powder; it rises in vapour at a temperature below redness, and is obtained by ordinary sublimation as a yellowish-white crystalline mass. It is as insoluble in cold diluted nitric acid as the chloride of silver; boiling-hot strong nitric acid oxidizes and dissolves it. Calomel is instantly decomposed by an alkali, or by lime-water, with production of suboxide. It is sometimes apt to contain a little chloride, which would be a very dangerous contamination in calomel employed for medical purposes. This

* If the grey oxide be considered as protoxide, the sulphate will be sulphate of the binoxide, $\text{HgO}_2, 2\text{SO}_3$, and the decomposition will stand thus:—



is easily discovered by boiling with water, filtering the liquid and adding caustic potassa. Any corrosive sublimate is indicated by a yellow precipitate.



PROTOCHLORIDE OF MERCURY; CORROSIVE SUBLIMATE; HgCl .—The chloride may be obtained by several different processes. (1) When metallic mercury is heated in chlorine gas, it takes fire and burns, producing this substance. (2) It may be made by dissolving the red oxide in hot hydrochloric acid, when crystals of corrosive sublimate separate on cooling. (3) Or, more economically, by subliming a mixture of equal parts of sulphate of the red oxide of mercury and dry common salt; and this is the plan generally followed. The decomposition is thus easily explained: *—



The sublimed protochloride forms a white transparent crystalline mass, of great density; it melts at 509° (265°C), and boils and volatilizes at a somewhat higher temperature. It is soluble in 16 parts of cold and 3 of boiling water, and crystallizes from a hot solution in long white prisms. Alcohol and ether also dissolve it with facility; the latter even withdraws it from a watery solution. Chloride of mercury combines with a great number of other metallic chlorides, forming a series of beautiful double salts, of which the ancient *sal alembroth* may be taken as a good example: it contains $\text{HgCl} + \text{NH}_4\text{Cl} + \text{HO}$. Corrosive sublimate absorbs ammoniacal gas with great avidity, generating a compound supposed to contain $2\text{HgCl} + \text{NH}_3$.

When excess of ammonia is added to a solution of corrosive sublimate, a white insoluble substance is thrown down, long known under the name of *white precipitate*. Sir Robert Kane, who has devoted much attention to the salts of mercury, represents this white precipitate as a double amide and chloride of mercury, or $\text{HgCl} + \text{HgNH}_2$, 2 equivalents of chloride of mercury and 1 of ammonia, yielding 1 equivalent of the new body and 1 of hydrochloric acid. A corresponding

* Or on the other supposition:—



black compound, $\text{Hg}_2\text{Cl} + \text{HgNH}_2$, is produced when ammonia is digested with calomel, which must be carefully distinguished from the suboxide.

Several compounds of protochloride of mercury with protoxide of mercury also exist. These are produced by several processes, as when an alkaline carbonate or bicarbonate is added in varying proportions to a solution of corrosive sublimate. They differ greatly in colour and physical character, and are mostly decomposed by water.

Corrosive sublimate forms insoluble compounds with many of the azotized organic principles, as albumin, &c. It is perhaps to this property that its great antiseptic virtues are due. Animal and vegetable substances are preserved by it from decay, as in Mr. Kyan's method of preserving timber and cordage. Albumin is on this account an excellent antidote to corrosive sublimate in cases of poisoning.

SUBIODIDE OF MERCURY, Hg_2I .—The subiodide is formed when a solution of iodide of potassium is added to nitrate of the suboxide of mercury; it separates as a dirty yellow, insoluble precipitate, with a cast of green. It may be prepared by rubbing together in a mortar mercury and iodine in the proportion of 2 equivalents of the former to 1 of the latter, the mixture being moistened from time to time with a little alcohol.

PROTIODIDE OF MERCURY, HgI .—When solution of iodide of potassium is mixed with protochloride of mercury, a precipitate falls, which is at first yellow, but in a few moments changes to a most brilliant scarlet, which colour is retained on drying. This is the neutral iodide; it may be made, although of rather duller tint, by triturating single equivalents of iodine and mercury with a little alcohol. When prepared by precipitation, it is better to weigh out the proper proportions of the two salts, as the iodide is soluble in an excess of either, more especially in excess of iodide of potassium. The iodide of mercury exhibits a very remarkable case of dimorphism, attended with difference of colour, the latter being red or yellow, according to the figure assumed. Thus, when the iodide is suddenly exposed to a high temperature, it becomes bright yellow throughout, and yields a copious sublimate of minute but brilliant yellow crystals. If in this state it be touched by a hard body, it instantly becomes red, and the same change happens spontaneously after a certain lapse of time. On the other hand, by a very slow and careful heating, a sublimate of red crystals, having a totally different form, may be obtained, which are permanent. The same kind of change happens with the freshly-precipitated iodide, as Mr. Warington has shown, the yellow crystals first formed breaking up in the course of a few seconds from the passage of the salt to the red modification.*

SUBSULPHIDE OF MERCURY, Hg_2S .—The black precipitate thrown down from a solution of the nitrate of suboxide of mercury by sul-

* Memoirs of Chemical Society of London, i. 85.

phuretted hydrogen, is a subsulphide; it is decomposed by heat into metallic mercury and neutral sulphide.

SULPHIDE OF MERCURY; ARTIFICIAL CINNABAR; VERMILION; HgS .—Sulphuretted hydrogen gas causes a precipitate of a white colour when passed in small quantity into a solution of corrosive sublimate or nitrate of the red oxide: this is a combination of sulphide with the salt itself. An excess of the gas converts the whole into sulphide, the colour at the same time changing to black. When this black sulphide is sublimed, it becomes dark red and crystalline, but undergoes no change of composition; it is then cinnabar. The sulphide is most easily prepared by subliming an intimate mixture of 6 parts of mercury and 1 of sulphur, and reducing to very fine powder the resulting cinnabar, the beauty of the tint depending much upon the extent to which division is carried. The red or crystalline sulphide may also be formed directly, without sublimation, by heating the black precipitated substance in a solution of pentasulphide of potassium; the sulphide of mercury is in fact soluble, to a certain extent, in the alkaline sulphides, and forms with them crystallizable compounds.

When vermilion is heated in the air, it yields metallic mercury and sulphurous acid; it resists the action both of caustic alkali in solution, and of strong mineral acids, even nitric, and is only attacked by *aqua regia*.

When protoxide of mercury is put into a large excess of pure caustic ammonia, a compound is obtained, the colour of which varies with the state of the oxide. If the latter be amorphous, it is pale yellow; if crystalline, then the action of the ammonia is much less energetic, and the product darker in colour. This substance possesses very extraordinary properties, those namely of a most powerful base, and probably belongs to the same class as the compound bases containing platinum, described under that metal. The body in question bears a temperature of 260° ($126^{\circ}\cdot 5\text{C}$), without decomposition, becoming brown and anhydrous by the loss of 3 equivalents of water. In this state it contains $\text{NH}_2\text{Hg}_4\text{O}_3 = \text{NH}_2\text{Hg}_2\text{O} + 2\text{HgO}$, or $\text{NHg}_4\text{O} + 2\text{HO}$. It is insoluble in water, alcohol, and ammonia; cold solution of potassa has no action on the hydrate, but at a boiling heat some ammonia is disengaged. The anhydrous base is only acted on by hydrate of potassa in fusion. It combines directly and energetically with acids, forming well-defined compounds; it absorbs carbonic acid with avidity from the air, like baryta or lime. It even decomposes ammoniacal salts by boiling, expelling the ammonia and combining with the acid.*

* Ann. Chim. et Phys. 3rd series, xviii. 333.

The salts of mercury are all volatilized or decomposed by a temperature of ignition; those which fail to yield the metal by simple heating may in all cases be made to do so by heating in a test-tube with a little dry carbonate of soda. The metal is precipitated from its soluble combinations by a plate of copper, and also by a solution of protochloride of tin, used in excess. The behaviour of the protochloride and soluble salts of the red oxide with caustic potassa and ammonia is also highly characteristic.

Alloys of mercury with other metals are termed *amalgams*; mercury dissolves in this manner many of the metals, as gold, silver, tin, lead, &c. These combinations sometimes take place with considerable violence, as in the case of potassium, where light and heat are produced; besides this, many of the amalgams crystallize after a while, becoming solid. The amalgam of tin used in silvering looking-glasses, and that of silver sometimes employed for stopping hollow teeth, are examples.

PLATINUM.

Platinum, palladium, rhodium, iridium, ruthenium, and osmium, form a small group of metals, allied in some cases by properties in common, and still more closely by their natural association. *Crude platinum*, a native alloy of platinum, palladium, rhodium, iridium, and a little iron, occurs in grains and rolled masses, sometimes of tolerably large dimensions, mixed with gravel and transported materials, on the slope of the Ural Mountains in Russia, in Ceylon, and in a few other places. It has never been seen in the rock, which, however, is judged, from the accompanying minerals, to have been serpentine. It is stated to be always present in small quantities with native silver.

From this substance platinum is prepared by the following process:—The crude metal is acted upon as far as possible by nitro-hydrochloric acid, containing an excess of hydrochloric acid, and slightly diluted with water, in order to dissolve as small a quantity of iridium as possible; to the deep yellowish-red and highly-acid solution thus produced sal-ammoniae is added, by which nearly the whole of the platinum is thrown down in the state of ammonio-chloride. This substance is washed with a little cold water, dried and heated to redness; metallic platinum in the spongy state is left. Although this metal cannot be fused into a compact mass by any furnace-heat, yet the same object may be accomplished by taking advantage of its property of welding, like iron, at a very high temperature. The spongy platinum is made into a thin uniform paste with water, introduced into a slightly-conical mould of brass, and subjected to a graduated pressure, by which the water is squeezed out, and the mass rendered at

length sufficiently solid to bear handling. It is then dried, very carefully heated to whiteness, and hammered, or subjected to powerful pressure by suitable means. If this operation be properly conducted, the platinum will then be in a state to bear forging into a bar, which can afterwards be rolled into plates, or drawn into wire, at pleasure.

Platinum is in point of colour a little whiter than iron; it is exceedingly malleable and ductile, both hot and cold, and is very infusible, melting only before the oxyhydrogen blowpipe. It is the heaviest substance known, its specific gravity being 21.5. Neither air, moisture, nor the ordinary acids attack platinum in the slightest degree at any temperature; hence its great value in the construction of chemical vessels. It is dissolved by *aqua regia*, and superficially oxidized by fused hydrate of potassa, which enters into combination with the oxide.

The remarkable property of the spongy metal to determine the union of oxygen and hydrogen has been already noticed. There is a still more curious state in which platinum can be obtained, that of *platinum-black*, where the division is pushed much farther. It is easily prepared by boiling a solution of bichloride of platinum to which an excess of carbonate of soda, and a quantity of sugar have been added, until the precipitate formed after a little time becomes perfectly black, and the supernatant liquid colourless. The black powder is collected on a filter, washed and dried by gentle heat. This substance appears to possess the property of condensing gases, more especially oxygen, into its pores to a very great extent: when placed in contact with a solution of formic acid, it converts the latter, with copious effervescence, into carbonic acid; alcohol, dropped upon the platinum-black, becomes changed by oxidation to acetic acid, the rise of temperature being often sufficiently great to cause inflammation. When exposed to a red-heat, the black substance shrinks in volume, assumes the appearance of common spongy platinum, and loses these peculiarities, which are no doubt the result of its excessively-comminuted state. Platinum forms two compounds with oxygen, chlorine, &c. The equivalent of platinum is 98.7. Its symbol is Pt.

PROTOXIDE OF PLATINUM, PtO .—When protochloride of platinum is digested with caustic potassa, a black powder, soluble in excess of alkali, is produced: this is the protoxide. It is soluble in acids with brown colour, and the solutions are not precipitated by sal-ammoniac. When binoxide of platinum is heated with solution of oxalic acid, it is reduced to protoxide, which remains dissolved. The liquid has a dark-blue colour, and deposits fine copper-red needles of oxalate of the protoxide of platinum.

BINOXIDE OF PLATINUM, PtO_2 .—This is best prepared by adding nitrate of baryta to sulphate of the binoxide of platinum; sulphate of baryta and nitrate of the binoxide are produced. From the latter, caustic soda precipitates one-half of the binoxide of platinum. The sulphate is itself obtained by acting with strong nitric acid upon the

bisulphide of platinum, which falls as a black powder when a solution of bichloride is dropped into sulphide of potassium. The hydrate of the binoxide is a bulky brown powder, which, when gently heated, becomes black and anhydrous. It may also be formed by boiling bichloride of platinum with a great excess of caustic soda, and then adding acetic acid. It dissolves in acids, and also combines with bases; the salts have a yellow or red tint, and a great disposition to unite with salts of the alkalis and alkaline earths, giving rise to a series of double compounds, which are not precipitated by excess of alkali. A combination of binoxide of platinum with ammonia exists, which is explosive. Both oxides of platinum are reduced to the metallic state by ignition.

PROTOCHLORIDE OF PLATINUM, PtCl .—The protochloride is produced when bichloride of platinum, dried and powdered, is exposed for some time to a heat of 400° ($204^{\circ}\cdot5\text{C}$), by which half of the chlorine is expelled; also, when sulphurous acid is passed into a solution of the bichloride until the latter ceases to give a precipitate with sal-ammoniac. It is a greenish-grey powder, insoluble in water, but dissolved by hydrochloric acid. The latter solution, mixed with sal-ammoniac or chloride of potassium, deposits a double salt in fine red prismatic crystals, containing, in the last case, $\text{PtCl} + \text{KCl}$. The corresponding sodium-compound is very soluble and difficult to crystallize. The protochloride is decomposed by heat into chlorine and metallic platinum.

BICHLORIDE OR PERCHLORIDE OF PLATINUM, PtCl_2 .—This substance is always formed when platinum is dissolved in nitro-hydrochloric acid. The acid solution yields on evaporation to dryness a red or brown residue, deliquescent, and very soluble both in water and alcohol; the aqueous solution has a pure orange-yellow tint. Bichloride of platinum combines to double salts with a great variety of metallic chlorides; the most important of these compounds are those containing the metals of the alkalis and ammonium. *Bichloride of platinum and chloride of potassium*, PtCl_2 , KCl , forms a bright yellow crystalline precipitate, being produced whenever solutions of the chlorides of platinum and of potassium are mixed, or a salt of potassa, mixed with a little hydrochloric acid, added to bichloride of platinum. It is feebly soluble in water, still less soluble in dilute alcohol, and is decomposed with some difficulty by heat. It is readily reduced by hydrogen at a high temperature, furnishing a mixture of chloride of potassium and platinum-black; the latter substance may thus, indeed, be very easily prepared. The *sodium-salt*, PtCl_2 , $\text{NaCl} + 6\text{HO}$, is very soluble, crystallizing in large, transparent, yellow-red prisms of great beauty. The *ammonio-chloride of platinum*, PtCl_2 , NH_4Cl , is indistinguishable, in physical characters, from the potassium-salt; it is thrown down as a precipitate of small, transparent, yellow, octahedral crystals when sal-ammoniac is mixed with chloride of platinum; it is but feebly soluble in water, still less so in dilute

alcohol, and is decomposed by heat, yielding spongy platinum, while sal-ammoniac, hydrochloric acid, and nitrogen are driven off. Compounds of platinum with iodine, bromine, sulphur, and phosphorus, have been formed, but are comparatively unimportant.

Some very extraordinary compounds have been derived from the protoxide of platinum.

When ammonia in excess is added to a hot solution of the protochloride of platinum and ammonium, a green crystalline salt separates after a time, which is quite insoluble in water, and is not affected by hydrochloric or sulphuric acids, ammonia, or even a boiling-hot solution of potassa. This substance is known as the *green salt of Magnus*, and contains the elements of protochloride of platinum and ammonia, or $\text{PtCl} + \text{NH}_3$.

When the above compound is heated with concentrated nitric acid, it becomes converted into a white, granular, crystalline powder, which on addition of water, dissolves, leaving a residue of metallic platinum. The solution yields on standing small, brilliant, colourless, prisms of a substance very soluble in water, containing the elements of protochloride of platinum, ammonia, nitric acid, and an additional equivalent of oxygen:—



The platinum and chlorine in this curious body are insensible to ordinary reagents, and ammonia is evolved from it only on boiling with caustic alkali; the presence of nitric acid can be detected immediately by gently heating a small portion with copper-filings and oil of vitriol. From this substance a series of salt-like bodies can be obtained, some of which have been carefully studied by M. Gros. Thus, when treated with hydrochloric acid, the nitric acid is wholly displaced, and a compound formed which crystallizes in small, transparent, yellowish octahedrons, sparingly soluble in boiling water, containing $\text{PtCl}, \text{N}_2\text{H}_6\text{Cl}$. With sulphuric acid it gives a substance which crystallizes in small, sparingly soluble, colourless needles, containing $\text{PtCl}, \text{N}_2\text{H}_6\text{O} + \text{SO}_3$. The oxalic acid compound is white and insoluble; it contains $\text{PtCl}, \text{N}_2\text{H}_6\text{O} + \text{C}_2\text{O}_3$. Crystallizable compounds containing phosphoric, tartaric, citric, malic, formic, and even carbonic acids, were obtained by similar means. The substances have very much the characters of salts of a compound base or *quasi-metal* containing $\text{PtCl}, \text{N}_2\text{H}_6$, and which yet remains unknown in a separate state. M. Raewsky has repeated and extended the observations of M. Gros.

MM. Reiset and Pcyronc have also described two other basic bodies containing platinum in the same remarkable condition: these differ from the preceding in being free from chlorine.

Protochloride of platinum put into ammonia becomes rapidly converted into a green powder, which, by boiling, slowly dissolves; the solution, on evaporation and cooling, furnishes beautiful yellowish crystals of the chlorine-compound of one of these bases, compounded

of platinum and the elements of ammonia. The crystals contained $\text{PtN}_2\text{H}_6\text{Cl} + \text{HO}$. The equivalent of water is easily expelled by heat, and regained by absorption from the air. The green salt of Magnus, boiled with ammonia, yields the same product.

A solution of this substance, mixed with nitrate of silver, gives ehloride of silver and the nitrate of the new base, which crystallizes on evaporation in fine, white, transparent needles, containing $\text{PtN}_2\text{H}_6\text{O} + \text{NO}_3$. The sulphide, iodide, and bromide are also crystallizable. Two carbonates exist. By adding baryta-water to a solution of the sulphate, or by treating the ehloride with protoxide of silver, and evaporating the filtered liquid *in vacuo*, a white, crystalline, deliquescent mass is obtained, which is the hydrate of the base, $\text{PtN}_2\text{H}_6\text{O} + \text{HO}$. It is almost comparable in point of alkalinity with potassa itself, absorbing carbonic acid with energy, and decomposing ammoniacal salts. When this hydrate is heated to 230° (110°C), it abandons water and ammonia, and leaves a greyish, porous, insoluble mass containing PtNH_3O . This is probably an isomeric modification of the second base, whose salts are mentioned below.

When a solution of the iodide, $\text{PtN}_2\text{H}_6\text{I}$, is long boiled, it deposits a sparingly-soluble yellow powder, the composition of which is expressed by the formula PtNH_3I : this is the iodine-compound of a second basic substance, PtNH_3 ; and from it by double decomposition a series of analogous salts can be obtained. When the iodine-compound is treated with protoxide of silver, the base itself is obtained in the form of a powerfully-alkaline solution. The green salt of Magnus has the same composition as the ehloride of this new base, which is yellow and soluble in boiling water, and may be converted into it. The salts of the first base are generally convertible into those of the second by heat, and the converse change may also be often effected by ebullition with ammonia.

The subject of the platinum-bases appears to be by no means exhausted. Only quite recently another remarkable basic compound containing ammonia and platinum has been discovered by M. Gerhard. The ehloride of Reiset's second base, the compound PtNH_3Cl , when treated with ehlorine, absorbs this element, and becomes converted into a lemon-yellow powder, consisting of small octahedrons, and having the composition PtNH_3Cl_2 . Boiled with nitrate of silver, this substance yields ehloride of silver and, according to the quantity of nitric acid present, a salt, $\text{PtNH}_3\text{O}_2, 2\text{NO}_3$, or $\text{PtNH}_3\text{O}_2, \text{NO}_3 + 3\text{HO}$. On adding ammonia to the latter nitrate, a crystalline precipitate takes place, which consists of $\text{PtNH}_3\text{O}_2 + 2\text{HO}$. This substance, which is slightly soluble in water, may be viewed as the hydrated base existing in the bichloride and in the nitrates previously described.

The bichloride, or a solution of binoxide of platinum, can be at once recognised by the yellow precipitate with sal-ammoniac, decomposable by heat, with production of spongy metal.

Bichloride of platinum and the sodio-chloride of platinum are employed in analytical investigations to detect the presence of potassa, and separate it from soda. For the latter purpose, the alkaline salts are converted into chlorides, and in this condition mixed with four times their weight of sodio-chloride of platinum in crystals, the whole being dissolved in a little water. When the formation of the yellow salt appears complete, alcohol is added, and the precipitate collected on a weighed filter, washed with weak spirit, carefully dried and weighed. The chloride of potassium is then easily reckoned from the weight of the double salt, and this, subtracted from the weight of the mixed chlorides employed, gives that of the chloride of sodium by difference; 100 parts of potassio-chloride of platinum correspond to 35.06 parts of chloride of potassium.

Capsules and crucibles of platinum are of great value to the chemist; the latter are constantly used in mineral analysis for fusing siliceous matter with alkaline carbonates. They suffer no injury in this operation, although the caustic alkali roughens and corrodes the metal. The experimenter must be particularly careful to avoid introducing any oxide of an easily-fusible metal, as that of lead or tin, into a platinum crucible. If reduction should by any means occur, these metals will at once alloy themselves with the platinum, and the vessel will be destroyed. A platinum crucible must never be put naked into the fire, but be always placed within a covered earthen crucible.

PALLADIUM.

The solution of crude platinum, from which the greater part of that metal has been precipitated by sal-ammoniac, is neutralized by carbonate of soda, and mixed with a solution of cyanide of mercury; cyanide of palladium separates as a whitish insoluble substance, which, on being washed, dried, and heated to redness, yields metallic palladium in a spongy state. The palladium is then welded into a mass, in the same manner as platinum.

Palladium closely corresponds with platinum in colour, appearance, and difficult fusibility; it is also very malleable and ductile. In density it differs very much from that metal, being only 11.8. Palladium is more oxidable than platinum. When heated to redness in the air, especially in the state of sponge, it acquires a blue or purple superficial film of oxide, which is again reduced at a white

heat. This metal is slowly attacked by nitric acid; its best solvent is *aqua regia*. There are two compounds of palladium and oxygen.

The equivalent of palladium is 53.3; its symbol is Pd.

PROTOXIDE OF PALLADIUM, PdO .—This is obtained by evaporating to dryness, and cautiously heating, the solution of palladium in nitric acid. It is black, and but little soluble in acids. The hydrate falls as a dark-brown precipitate when carbonate of soda is added to the above solution. It is decomposed by a strong heat.

BINOXIDE OF PALLADIUM, PdO_2 .—The pure binoxide is very difficult to obtain. When solution of caustic potassa is poured, little by little, with constant stirring, upon the double chloride of palladium and potassium in a dry state, the latter is converted into a yellowish-brown substance, which is the binoxide, in combination with water and a little alkali. It is but feebly soluble in acids.

PROTOCHLORIDE OF PALLADIUM, PdCl .—The solution of the metal in *aqua regia* yields this substance when evaporated to dryness. It is a dark-brown mass, soluble in water when the heat has not been too great, and forms double salts with many metallic chlorides. The potassio- and ammonio-chlorides of palladium are much more soluble than those of platinum; they have a brownish-yellow tint.

BICHLORIDE OF PALLADIUM only exists in solution, and in combination with the alkaline chlorides. It is formed when the protochloride of palladium is digested in *aqua regia*. The solution has an intensely brown colour, and is decomposed by evaporation. Mixed with ehloride of potassium or sal-ammoniae, it gives rise to a red crystalline precipitate, which is but little soluble in water.

A sulphide of palladium, PdS , is formed by fusing the metal with sulphur, or by precipitating a solution of protochloride by sulphuretted hydrogen.

A palladium-salt is well marked by the pale yellowish-white precipitate with solution of cyanide of mercury, convertible by heat into the spongy metal. This precipitate is a double salt, having the formula $\text{PdCy}, \text{HgCy}, \text{HO}$.

Palladium is readily alloyed with other metals, as copper: one of these compounds, namely, the alloy with silver, has been applied to useful purposes. A native alloy of gold with palladium is found in the Brazils, and imported into England.

RHODIUM.

The solution from which platinum and palladium have been separated in the manner described is mixed with hydrochloric acid, and

evaporated to dryness. The residue is treated with alcohol of specific gravity 0·837, which dissolves everything except the double ehloride of rhodium and sodium. This is well washed with spirit, dried, heated to whiteness, and then boiled with water; ehloride of sodium is dissolved out, and metallie rhodium remains. Thus obtained, rhodium is a white, coherent, spongy mass, which is more infusible and less capable of being welded than platinum. Its specific gravity varies from 10·6 to 11.

Rhodium is very brittle: reduced to powder and heated in the air, it becomes oxidized, and the same alteration happens to a greater extent when it is fused with nitrate or bisulphate of potassa. None of the acids, singly or conjoined, dissolve this metal, unless it be in the state of alloy, as with platinum, in which it is attacked by *aqua regia*.

The equivalent of rhodium is 52·2; its symbol is R.

PROTOXIDE OF RHODIUM, RO, is obtained by roasting finely-divided metallie rhodium. It is but little known.

SESQUIOXIDE OF RHODIUM, R₂O₃.—Finely-powdered metallic rhodium is heated in a silver crueible with a mixture of hydrate of potassa and nitre; the fused mass boiled with water leaves a dark-brown insoluble substance, consisting of sesquioxide of rhodium in union with potassa. This is digested with hydrochloric acid, which removes the potassa and leaves a greenish-grey hydrate of the sesquioxide of rhodium, insoluble in acids. A soluble modification of the same substance, retaining, however, a portion of alkali, may be had by adding an excess of carbonate of potassa to the double ehloride of rhodium and potassium, and evaporating.

SESQUICHLORIDE OF RHODIUM, R₂Cl₃.—The pure sesquiehloride is prepared by adding hydrofluosilicic acid to the double ehloride of rhodium and potassium, evaporating the filtered solution to dryness, and dissolving the residue in water. It forms a brownish-red deliquescent mass, soluble in water, with a fine red colour. It is decomposed by heat into chlorine and metallie rhodium. The *chloride of rhodium and potassium*, R₂Cl₃+2KCl+2HO, is prepared by heating in a stream of chlorine a mixture of equal parts of finely-powdered rhodium and chloride of potassium. This salt has a fine red colour, is soluble in water, and crystallizes in 4-sided prisms. *Chloride of rhodium and sodium* is also a very beautiful red salt, obtained by a similar process; it contains R₂Cl₃+3NaCl+18HO. The *chloride of rhodium and ammonium* resembles the potassium-compound.

SULPHATE OF RHODIUM, R₂O₃.3SO₃.—The sulphide of rhodium, obtained by precipitating one of the salts by a soluble sulphide, is oxidized by strong nitric acid. The product is a brown powder, nearly insoluble in nitric acid, but dissolved by water; it cannot be made to crystallize. *Sulphate of rhodium and potassium* is produced when metallic rhodium is strongly heated with bisulphate of potassa. It is a yellow salt, slowly soluble in cold water.

An alloy of steel with a small quantity of rhodium is said to possess extremely valuable properties.

IRIDIUM.

When crude platinum is dissolved in *aqua regia*, a small quantity of a grey scaly metallic substance usually remains behind, having altogether resisted the action of the acid: this is a native alloy of *iridium* and *osmium*. It is reduced to powder, mixed with an equal weight of dry chloride of sodium, and heated to redness in a glass tube, through which a stream of moist chlorine gas is transmitted. The farther extremity of the tube is connected with a receiver containing solution of ammonia. The gas, under these circumstances, is rapidly absorbed, chloride of iridium and chloride of osmium being produced: the former remains in combination with the chloride of sodium; the latter, being a volatile substance, is carried forward into the receiver, where it is decomposed by the water into osmic and hydrochloric acids, which combine with the alkali. The contents of the tube when cold are treated with water, by which the double chloride of iridium and sodium is dissolved out: this is mixed with an excess of carbonate of soda, and evaporated to dryness. The residue is ignited in a crucible, boiled with water, and dried; it then consists of a mixture of sesquioxide of iron, and a combination of oxide of iridium with soda; it is reduced by hydrogen at a high temperature, and treated successively with water and strong hydrochloric acid, by which the alkali and the iron are removed, while metallic iridium is left in a divided state. By strong pressure and exposure to a white heat, a certain degree of compactness may be communicated to the metal.

Iridium is a white brittle metal, fusible with great difficulty before the oxyhydrogen blowpipe. It is not attacked by any acid, but is oxidized by fusion with nitre, and by ignition to redness in the air.

The equivalent of iridium is 99. Its symbol is Ir.

OXIDES OF IRIDIUM.—Four of these compounds are described. *Protoxide of iridium*, IrO , is prepared by adding caustic alkali to the protochloride, and digesting the precipitate in an acid. It is a heavy black powder, insoluble in acids. It may be had in the state of hydrate by precipitating the protochloride of iridium and sodium by caustic potassa. The hydrate is soluble in acids with dirty green colour. *Sesquioxide of iridium*, Ir_2O_3 , is produced when iridium is heated in the air, or with nitre; it is best prepared by fusing in a silver crucible a mixture of carbonate of potassa and the terechloride of iridium and potassium, and boiling the product with water. This oxide is bluish-black, and is quite insoluble in acids. It is reduced by combustible substances with explosion. *Bin oxide of iridium*, IrO_2 , is unknown in a separate state; it is supposed to exist in the sulphate, produced when the sulphide is oxidized by nitric acid. A solution of sulphate

heated with excess of alkali evolves oxygen gas, and deposits sesquioxide of iridium. *Teroxide of iridium*, IrO_3 , is produced when carbonate of potassa is gently heated with the terchloride of iridium; it forms a greyish-yellow hydrate, which contains alkali.

CHLORIDES OF IRIDIUM.—*Protochloride*, IrCl , is formed when the metal is brought in contact with chlorine at a dull red-heat, it is a dark olive-green insoluble powder. It is dissolved by hydrochloric acid, and forms double salts with the alkaline chlorides, which have a green colour. The *sesquichloride*, Ir_2Cl_3 , is prepared by strongly heating iridium with nitre, adding water and enough nitric acid to saturate the alkali, warming the mixture, and then dissolving the precipitated hydrate of the sesquioxide in hydrochloric acid it forms a dark yellowish-brown solution. This substance combines with metallic chlorides. *Bichloride of iridium* is obtained in solution by adding hydrofluosilicic acid to the bichloride of iridium and potassium, formed when chlorine is passed over a heated mixture of iridium and chloride of potassium. It forms with metallic chlorides a number of double salts, which resemble the platinum-compounds of the same order. *Terchloride of iridium*, IrCl_3 , is unknown in a separate state. *Terchloride of iridium and potassium* is obtained by heating iridium with nitre, and then dissolving the whole in *aqua regia*, and evaporating to dryness. The excess of chloride of potassium may be extracted by a small quantity of water. The crystallized salt has a beautiful red colour. The variety of tints exhibited by the different soluble compounds of iridium is very remarkable, and suggested the name of the metal, from the word *iris*.

Platinum, palladium, and iridium combine with carbon when heated in the flame of a spirit-lamp; they acquire a covering of soot, which, when burned, leaves a kind of skeleton of spongy metal.

RUTHENIUM.

M. Claus has described under this name a new metal contained in the residue from crude platinum, insoluble in *aqua regia*. It closely resembles iridium in its general characters, but yet possesses distinctive features of its own. It was obtained in the form of small angular masses, with perfect metallic lustre, very brittle and infusible. Its specific gravity is 8.6. It resists the action of acids, but oxidizes readily when heated in the air.

The equivalent of ruthenium is 52.2, and its symbol Ru.

OXIDES OF RUTHENIUM.—*Protoxide of ruthenium*, RuO , is a greyish-black metallic-looking powder, obtained by heating bichloride of ruthenium with excess of carbonate of soda in a stream of carbonic acid gas, and then washing away the soluble saline matter. It is insoluble in acids. The *sesquioxide*, Ru_2O_3 , in the anhydrous condi-

tion, is a bluish-black powder formed by heating the metal in the air. It is also precipitated by alkalis from the sesquichloride as a blackish-brown hydrate, soluble in acids with orange-yellow colour. The *bin-oxide*, RuO_2 , is a deep-blue powder, procured by roasting the bisulphide. A hydrate of this oxide is known in an impure condition. An *acid* of ruthenium is also supposed to exist.

Sesquichloride of ruthenium, Ru_2Cl_3 , is an orange-yellow soluble salt of astringent taste; when the solution is heated it becomes green and finally blue, by reduction, in all probability, to protochloride. Sesquichloride of ruthenium forms double salts with the chlorides of potassium and ammonium.

OSMIUM.

The solution of osmic acid in ammonia, already mentioned, is gently heated for some time in a loosely-stopped vessel; its original yellow colour becomes darker, and at length a brown precipitate falls, which is a combination of sesquioxide of osmium with ammonia: it results from the reduction of the osmic acid by the hydrogen of the volatile alkali. A little of the precipitate is held in solution by the sal-ammoniac, but may be recovered by heating the clear liquid with caustic potassa. The brown substance is dissolved in hydrochloric acid, a little chloride of ammonium is added, and the whole evaporated to dryness. The residue is strongly heated in a small porcelain retort; the oxygen of the oxide combines with hydrogen from the ammonia, vapour of water, hydrochloric acid, and sal-ammoniac are expelled, and osmium left behind, as a greyish porous mass, having the metallic lustre.

In the most compact state in which this metal can be obtained, it has a bluish-white colour, and although somewhat flexible in thin plates, is yet easily reduced to powder. Its specific gravity is 10; it is neither fusible nor volatile. It burns when heated to redness, yielding osmic acid, which volatilizes. Osmate of potassa is produced when the metal is fused with nitre. When in a finely divided state, it is oxidized by strong nitric acid.

The equivalent of osmium is 99.6; its symbol is Os.

OXIDES OF OSMIUM.—Five compounds of osmium with oxygen are known. *Protoxide*, OsO , is obtained, in combination with a little alkali, when caustic potassa is added to a solution of protochloride of osmium and potassium. It is a dark-green powder, slowly soluble in acids. *Sesquioxide*, Os_2O_3 , has already been noticed; it is generated by the deoxidation of osmate of ammonia; it is black, and but little soluble in acids. It always contains ammonia, and explodes feebly when heated. *Binoxide of osmium*, OsO_2 , is prepared by strongly heating in a retort a mixture of carbonate of soda and the bichloride of osmium and potassium, and treating the residue with

water, and afterwards with hydrochloric acid. The binoxide is a black powder, insoluble in acids, and burning to osmic acid when heated in the air. *Osmious acid*, OsO_3 , is known only in combination. On adding alcohol to a solution of osmate of potassa, the alcohol is oxidized at the expense of the osmic acid, and a rose-red crystalline powder of osmite of potassa is produced. On attempting to separate the acid, it is decomposed into the binoxide and osmic acid. *Osmic acid*, OsO_4 , is by far the most important and interesting of the oxides of this metal. It is prepared by heating osmium in a current of pure oxygen gas; it condenses in the cool part of the tube in which the experiment is made in colourless transparent crystals. Osmic acid melts and even boils below 212° (100°C); its vapour has a peculiarly offensive odour, and is exceedingly irritating and dangerous. Water slowly dissolves this substance. It has acid properties, and combines with bases. Nearly all the metals precipitate osmium from a solution of osmic acid. By the action of ammonia on osmic acid, a new acid has been formed, containing osmium, nitrogen, and oxygen, it has been called osman-osmic acid or osmanic acid. Some doubts are hanging over the formula of this substance. It produces salts with many bases.

CHLORIDES OF OSMIUM.—*Protochloride*, OsCl , is a dark-green crystalline substance, formed by gently heating osmium in chlorine gas. It is soluble in a small quantity of water, with green colour, but decomposed by a large quantity into osmic and hydrochloric acids and metallic osmium. It forms double salts with the metallic chlorides. The *sesquichloride*, Os_2Cl_3 , has not been isolated; it exists in the solution obtained by dissolving the sesquioxide in hydrochloric acid. *Bichloride*, OsCl_2 , in combination with chloride of potassium, is produced when a mixture of equal parts metallic osmium and the last-named salt is strongly heated in chlorine gas. It forms fine red octahedral crystals, containing $\text{OsCl}_2 + \text{KCl}$.

Osmium combines also with sulphur and with phosphorus.

PART III.

ORGANIC CHEMISTRY.

INTRODUCTION.

ORGANIC substances, whether directly derived from the vegetable or animal kingdom, or produced by the subsequent modification of bodies which thus originate, are remarkable as a class for a degree of complexity of constitution far exceeding that observed in any of the compounds yet described. And yet the number of elements which enter into the composition of these substances is extremely limited; very few, comparatively speaking, contain more than four, viz., carbon, hydrogen, oxygen, and nitrogen; sulphur and phosphorus are occasionally associated with these in certain natural products; and compounds containing chlorine, bromine, iodine, arsenic, antimony, zinc, &c., have been formed by artificial means. This paucity of elementary bodies is compensated by the very peculiar and extraordinary properties of the four first-mentioned, which possess capabilities of combination to which the remaining elements are strangers. There appears to be absolutely no limit to the number of definite, and often crystallizable, substances which can be thus generated, each marked by a perfect individuality of its own.

The mode of association of the elements of organic substances is in general altogether different from that so obvious in the other division of the science. The latter is invariably characterized by what may be termed a *binary* plan of combination, union taking place between *pairs* of elements, and the compounds so produced again uniting themselves to other compound bodies in the same manner. Thus, copper and oxygen combine to oxide of copper, potassium and oxygen to potassa, sulphur and oxygen to sulphuric acid; sulphuric acid, in its turn, combines both with oxide of copper and oxide of potassium, generating a pair of salts, which are again capable of uniting to form the double compound, $\text{CuO}, \text{SO}_3 + \text{KO}, \text{SO}_3$.

The most complicated products of inorganic chemistry may be thus shown to be built up by this repeated pairing on the part of their con-

stituents. With organic bodies, however, the case is strikingly different; no such arrangement can here be traced. In sugar, $C_{12}H_{22}O_{11}$, or morphine, $C_{34}H_{49}NO_6$, or the radical of bitter-almond oil, $C_{14}H_5O_2$, and a multitude of similar cases, the elements concerned are, as it were, bound up together into a single whole, which can enter into combination with other substances, and be thence disengaged with properties unaltered.

A curious consequence of this peculiarity is to be found in the comparatively *instable* character of organic compounds, and their general proneness to decomposition and change, when the balance of opposing forces, to which they owe their existence, becomes deranged by some external cause.

If a complex inorganic substance be attentively considered, it will usually be found that the elements are combined in such a manner as to satisfy the most powerful affinities, and to give rise to a state of very considerable permanence and durability. But in the case of an organic substance containing three or four elements associated in the way described, this is very far from being true: the carbon and oxygen strongly tend to unite to form carbonic acid; the hydrogen and oxygen attract each other in a powerful manner; and the nitrogen, if that body be present, also contributes its share to these internal sources of weakness by its disposition to generate ammonia. While the opposing forces remain exactly balanced, the integrity of the compound is preserved; but the moment one of them, from some accidental cause, acquires preponderance over the rest, equilibrium is destroyed, and the organic principle breaks up into two or more new bodies of simpler and more permanent constitution. The agency of heat produces this effect by exalting the attraction of oxygen for hydrogen and carbon; hence the almost universal destructibility of organic substances by a high temperature. Mere molecular disturbance of any kind may cause destruction when the instability is very great.

As a general rule, it may be assumed that those bodies which are most complex from the number of elements, and the want of simplicity in their equivalent relations, are by constitution weakest, and least capable of resisting the action of disturbing forces; and that this susceptibility of change diminishes with increased simplicity of structure, until it reaches its minimum in those bodies which, like the carbides of hydrogen, like cyanogen, and oxalic acid, connect, by imperceptible gradations, the organic and the mineral departments of chemical science.

The definite organic principles of the vegetable and animal kingdoms form but a very small proportion of the immense mass of compounds included within the domain of organic chemistry; by far the greater number of these are produced by modifying by suitable means the bodies furnished by the plant or the animal, and which have themselves been formed from the elements of the air by processes for

the most part unknown, carried on under the control of vitality. Unlike these latter, the artificial modifications referred to, by oxidation, by the action of other powerful reagents, by the influence of heat, and by numerous other sources of disturbance, are, for the most part, changes of descent in order of complexity, new products being thus generated more simple in constitution and more stable in character than the bodies from which they were derived. These, in turn, by a repetition of such treatment under perhaps varied circumstances, may be broken up into other and still simpler organic combinations; until at length the binary compounds of inorganic chemistry, or bodies so allied to them that they may be placed indifferently in either group, are by such means reached.

Organic substitution-products: Law of Substitution.—The study of the action of chlorine, bromine, iodine, and nitric acid, upon various organic substances, has led to the discovery of a very remarkable law regulating the formation of chlorinetted and other analogous compounds, which, without being of necessity absolute in every case, is yet of sufficient generality and importance to require careful consideration. This peculiar mode of action consists in the replacement of the hydrogen of the organic substance by chlorine, bromine, iodine, the elements of hyponitric acid, and more rarely other substances of the same class, equivalent for equivalent, without the destruction of the primitive type or constitution of the compound so modified. The hydrogen thus removed takes of course the form of hydrochloric or hydrobromic acid, &c., or that of water, by combination with another portion of the active body. Strange as it may appear, and utterly opposed to the ordinary views of the functions of powerful salt-radicals, this loss of hydrogen and assumption of the new element do actually occur with a great variety of substances belonging to different groups with comparatively trifling disturbance of physical and chemical properties; the power of saturation, the density of the vapour, and other peculiarities of the original substance remain the same, saving the modification they may suffer from the difference of the equivalent weights of hydrogen and the body by which it is replaced.

This change may take place by several successive steps, giving rise to a series of substitution-compounds, which depart more and more in properties from the original substance with each successive increase in the proportion of the replacing body. The substitution may even be total, the whole of the hydrogen being lost, and its place supplied by a similar number of equivalents of the new element. And even in these extreme cases, of very common occurrence, however, with one class of substances, the resulting compound retains generally the stamp of its origin.

Although numerous examples of these changes will be found described in detail in the following pages, it will be well perhaps to mention here two or three cases by way of illustration.

Dutch-liquid, the compound formed by the union of equal measures


of olefant gas and chlorine, containing $C_4H_4Cl_2$, is affected by chlorine in obedience to the law of substitution; one, two, three, four equivalents of hydrogen being successively removed by the prolonged action of the gas aided by sunshine, and one, two, three, or four equivalents of chlorine introduced in place of the hydrogen withdrawn as hydrochloric acid. In the last product, the sesquichloride of carbon, C_4Cl_6 , the replacement is total; the intermediate products are volatile liquids not differing very much in general characters from Dutch-liquid itself. A great number of compound ethers of the ethyl- and methyl-series are attacked by chlorine and bromine in a similar manner; indeed, the majority of the examples of the law in question are to be found in the history of this class of bodies.

Concentrated acetic acid, placed in a vessel of dry chlorine and exposed to the sun, gives rise to *chloracetic acid*, containing $C_4Cl_3O_3$, HO, and in which consequently the whole hydrogen of the real acid is replaced by chlorine. Chloracetic acid is a stable substance, of strong acid characters, and forms a series of salts, some of which bear no slight resemblance to the normal acetates.


Basic substitution-products have been likewise obtained: *chloraniline*, *bromaniline*, and *iodaniline* are the most striking examples. These will be found fully described in the section on organic bases.

The action of fuming nitric acid upon organic substances very commonly indeed gives rise to substitution-products containing the elements of hyponitric acid, NO_4 , in place of hydrogen. The benzoyl-compounds, and several of the essential oils natural and derived from resins, will be found to furnish illustrations.

In formulæ representing substitution-compounds retaining some hydrogen, the practice is often adopted of placing the substituting body beneath or beside this residual hydrogen, and uniting them by a bracket on each side. Thus, the formulæ of the first two products of the action of chlorine on Dutch-liquid are thus written:—



And pyroxylin, or gun-cotton, which is supposed to be a substitution-product from lignin, $C_{24}H_{20}O_{20}$, having 5 equivalents of hydrogen replaced by the elements of hyponitric acid, will stand:—



Isomeric bodies, or substances different in properties, yet identical in composition, are of constant occurrence in organic chemistry, and stand, indeed, among its most striking and peculiar features. Every year brings to light fresh examples of compounds so related. In most cases, discordance in properties is fairly and properly ascribed to difference of constitution, the elements being differently arranged. For in-

stance, formic ether and acetate of methyl are isomeric, both containing $C_6H_6O_4$; but then the first is supposed to consist of formic acid, C_2HO_3 , combined with ether, C_4H_5O ; while the second is imagined, in accordance with the same views, to be made up of acetic acid, $C_4H_3O_3$, and the ether of wood-spirit, C_2H_3O . And this method of explanation is generally sufficient and satisfactory: when it can be shown that a difference of constitution, or even a difference in the equivalent numbers, exists between two or more bodies identical in ultimate composition, the reason of their discordant characters becomes to a certain extent intelligible.

Organic bodies may be thus classified:—

1. *Quasi-elementary Substances*, and their compounds. These affect the disposition and characters of the true elements, and like the latter evince a tendency to unite on the one hand with hydrogen and the metals, and on the other with chlorine, iodine, and oxygen. The former are designated *organic salt-radicals*, and the latter *organic salt-basyles*. Few of either kind have yet been isolated, and it is very possible that very many of them are unable to exist in a separate state. Some of these quasi-elements are among the most important and interesting substances in organic chemistry.

2. *Organic Salt-bases*, not being the oxides of known radicals.—The principal members of this class are the vegeto-alkalis; they form crystallizable compounds with acids, organic and inorganic, and even possess in some cases a distinct alkaline reaction to test-paper.

3. *Organic acids*, not being compounds of known radicals.—These bodies are very numerous and important. Many of them have an intensely sour taste, redden vegetable blues, and are almost comparable in chemical energy with the acids of mineral origin.

4. *Neutral non-azotized substances*, containing oxygen and hydrogen in the proportions to form water.—The term *neutral*, as applied to these compounds, is not strictly correct, as they usually manifest feeble acid properties by combining with metallic oxides. This group comprehends the sugars, the different modifications of starch, gum, &c.

5. *Neutral azotized substances*; the albuminous principles and their allies, the great components of the animal frame.—These are in the highest degree complex in constitution, and are destitute of the faculty of crystallization.

6. *Carbides of Hydrogen*, their oxides and derivatives.

7. *Fatty bodies*.

8. *Compound acids*, containing the elements of an organic substance in combination with those of a mineral or other acid.—These bodies form a large and very interesting class, of which sulphovinic acid may be taken as the type or representative.

9. *Colouring principles*, and other substances not referable to either of the preceding classes.

The action of heat on organic substances presents many important and interesting points, of which a few of the more prominent may be

noticed. Bodies of simple constitution and of some permanence, which do not sublime unchanged, as many of the organic acids, yield, when exposed to a high, but regulated temperature, in a retort, new compounds, perfectly definite and often crystallizable, which partake, to a certain extent, of the properties of the original substance: the numerous *pyro-acids*, of which many examples will occur in the succeeding pages, are thus produced. Carbonic acid and water are often eliminated under these circumstances. If the heat be suddenly raised to redness, then the regularity of the decomposition vanishes, while the products become more uncertain and more numerous; carbonic acid and watery vapour are succeeded by inflammable gases, as carbonic oxide and carbonetted hydrogen; oily matter and tar distil over, and increase in quantity until the close of the operation, when the retort is found to contain, in most cases, a residue of charcoal. Such is destructive distillation.

If the organic substance contain nitrogen, and be not of a kind capable of taking a new and permanent form at a moderate degree of heat, then that nitrogen is in most instances partly disengaged in the shape of ammonia, or substances analogous to it, partly left in combination with the carbonaceous matter in the distillatory vessel. The products of dry distillation thus become still more complicated.

A much greater degree of regularity is observed in the effects of heat on fixed organic matters, when these are previously mixed with an excess of strong alkaline base, as potassa or lime. In such cases an acid, the nature of which is chiefly dependent upon the temperature applied, is produced, and remains in union with the base, the residual element or elements escaping in some volatile form. Thus, benzoic acid distilled with hydrate of lime, at a dull red-heat, yields carbonate of lime and a bicarbide of hydrogen, benzole; woody fibre and caustic potassa, heated to a very moderate temperature, yield ulmic acid and free hydrogen; with a higher degree of heat, oxalic acid appears in the place of the ulmic; and, at the temperature of ignition, carbonic acid, hydrogen being the other product.

The spontaneous changes denominated *decay* and *putrefaction*, to which many of the more complicated organic, and, more particularly, azotized principles are subject, have lately attracted much attention. By the expression *decay*,* Liebig and his school understood a decomposition of moist organic matter, freely exposed to the air, by the oxygen of which it is gradually burned and destroyed, without sensible elevation of temperature; the term *putrefaction*, on the other hand, is limited to changes occurring in and beneath the surface of water, the effect being a mere transposition of elements, or metamorphosis of the organic body. The conversion of sugar into alcohol and carbonic acid furnishes, perhaps, the simplest case of the kind. It is proper to remark, however, that contact of oxygen is indispensable, in the first instance, to the change, which, when once begun, pro-

* Or *eramaucasis*, that is, slow burning.

ceeds, without the aid of any other substance external to the decomposing body, unless it be water or its elements. Every case of putrefaction thus begins with decay; and if the decay or its cause, namely, the absorption of oxygen, be prevented, no putrefaction occurs. The most putrescible substances, as animal flesh intended for food, milk, and highly-azotized vegetables, are preserved indefinitely, by enclosure in metallic cases, from which the air has been *completely* removed and excluded.

Some of the curious phenomena of communicated chemical activity, where a decomposing substance seems to involve others in destructive change, which, without such influence, would have remained in a permanent and quiescent state, will be found noticed in their proper places, as under the head of Vinous Fermentation. These actions are yet very obscure, and require to be discussed with great caution.

THE ULTIMATE ANALYSIS OF ORGANIC BODIES.

As organic substances cannot be produced at will from their elements, the *analytical* method of research is alone applicable to the investigation of their exact chemical composition; hence the ultimate analysis of these substances becomes a matter of great practical importance. The operation is always executed by causing complete combustion of a known weight of the body to be examined, in such a manner that the carbonic acid and water produced shall be collected, and their quantity determined; the carbon and hydrogen they respectively contain may from these data be easily calculated. When nitrogen, sulphur, phosphorus, chlorine, &c., are present, special and separate means are resorted to for their estimation.

The method to be described for the determination of the carbon and hydrogen owes its convenience and efficiency to the improvements of Professor Liebig; it has superseded all other processes, and is now invariably employed in inquiries of the kind. With proper care, the results obtained are wonderfully correct; and equal, if not surpass in precision, those of the best mineral analyses. The principle upon which the whole depends is the following:—When an organic substance is heated with the oxides of copper, lead, and several other metals, it undergoes complete combustion at the expense of the oxygen of the oxide, the metal being at the same time reduced, either completely, or to a lower state of oxidation. This effect takes place with greatest ease and certainty with the black oxide of copper, which, although unchanged by heat alone, gives up oxygen to combustible matter with extreme facility. When nothing but carbon and hydrogen, or those bodies together with oxygen, are present, one experiment suffices; the carbon and hydrogen are determined directly, and the oxygen by difference.

It is of course indispensable that the substance to be analyzed should possess the physical characters of purity, otherwise the inquiry cannot lead to any good result; if in the solid state, it must also be freed with the most scrupulous care from the moisture which many substances retain with great obstinacy. If it will bear the application of a moderate heat, this desiccation is very easily accomplished by a water or steam bath; in other cases, exposure at common temperatures to the absorbent powers of a large surface of oil of vitriol in the vacuum of an air-pump must be substituted.

The operation of weighing the dried powder is conducted in a narrow open tube, about $2\frac{1}{2}$ or 3 inches long: the tube and substance are weighed together, and, when the latter has been removed, the tube with any little adherent matter is reweighed. This weight, subtracted from the former, gives the weight of the substance employed in the experiment. As only 5 or 6 grains are used, the weighings should not involve a greater error than $\frac{1}{200}$ part of a grain.

Fig. 148.



The protoxide of copper is best made from the nitrate by complete ignition in an earthen crucible: it is reduced to powder, and reheated just before use, to expel hygroscopic moisture, which it absorbs, even while warm, with avidity. The combustion is performed in a tube of hard white Bohemian glass, having a diameter of 0.4 or 0.5 inch, and in length varying from 14 to 18 inches: this kind of glass bears a moderate red-heat without becoming soft enough to lose its shape. One end of the tube is drawn out to a point, as shown in fig. 149, and closed; the other is simply heated to fuse and soften the sharp edges of the glass. The tube is now two-thirds filled with the yet warm protoxide of copper, nearly the whole of which is transferred to a small porcelain or Wedgwood mortar, and very intimately mixed with the organic substance. The mixture is next transferred to the tube, and the mortar rinsed with a little fresh and hot oxide,

Fig. 149.



which is added to the rest; the tube is, lastly, filled to within an inch of the open end with oxide from the crucible. A few gentle taps on the table suffice to shake together the contents, so as to leave

a free passage for the evolved gases from end to end. The arrangement of the mixture and oxide in the tube is represented in the sketch.

The tube is then ready to be placed in the furnace or chauffer: this is constructed of thin sheet-iron, and is furnished with a series of supports of equal height, which serve to prevent flexure in the combustion-tube when softened by heat. The chauffer is placed upon

Fig. 150.




flat bricks or a piece of stone, so that but little air can enter the grating, unless the whole be purposely raised. A slight inclination is also given towards the extremity occupied by the mouth of the combustion-tube, which passes through a hole provided for the purpose.

To collect the water produced in the experiment, a small light tube of the form represented in fig. 151, filled with fragments of spongy chloride of calcium, is attached by a perforated cork, thoroughly dried,

Fig. 152.

Fig. 151.




to the open extremity of the combustion-tube. The carbonic acid is condensed into a solution of caustic potassa, of specific gravity 1.27, which is contained in a small glass apparatus on the principle of a Woulfe's bottle, shown in fig. 152. The connection between the latter and the chloride-of-calcium-tube is completed by a little tube of caoutchouc, secured with silk cord. The whole is shown in fig. 153, as arranged for use. Both the chloride-of-calcium-tube and the potass-apparatus are weighed with the utmost care before the experiment.

The tightness of the junctions may be ascertained by slightly rarefying the included air by sucking a few bubbles from the interior

through the liquid, using the dry lips, or better a little bent tube with a perforated cork: if the difference of level of the liquid in the two limbs of the potass-apparatus be preserved for several minutes, the joints are perfect. Red-hot charcoal* is now placed around the anterior portion of the combustion-tube, containing the pure oxide of copper; and when this is red-hot, the fire is slowly extended towards the farther extremity by shifting the movable screen represented in the drawing.

Fig. 153.



Drawing of the whole arrangement.

The experiment must be so conducted, that an uniform stream of carbonic acid shall enter the potass-apparatus by bubbles which may be easily counted; when no nitrogen is present, these bubbles are towards the termination of the experiment almost completely absorbed by the alkaline liquid, the little residue of air alone escaping. In the case of an azotized body, on the contrary, bubbles of nitrogen gas pass through the potassa-solution during the whole process.

When the tube has become completely heated from end to end, and no more gas is disengaged, but, on the other hand, absorption begins to be evident, the coals are removed from the farther extremity of the combustion-tube, and the point of the latter broken off. A little air is drawn through the whole apparatus, by which the remaining carbonic acid and watery vapour are secured. The parts are, lastly, detached, and the chloride-of-calcium-tube and potass-apparatus reweighed. The following account of a real experiment will serve as an illustration; the substance examined was crystallized sugar.

Quantity of sugar employed . . .	4.750 grains.
Potass-apparatus weighed after experiment	781.13
" " before experiment	773.82
Carbonic acid . . .	7.31
Chloride-of-calcium-tube after experiment	226.05
" " before experiment	223.30
Water . . .	2.75


* Instead of charcoal gas may be used as fuel: but then the whole disposition of the apparatus has to be changed. See Liebig's Handbook of Organic Analysis, p. 127.

7.31 gr. carbonic acid = 1.994 gr. carbon : and 2.75 gr. water = 0.3056 gr. hydrogen ; or in 100 parts of sugar,*

Carbon	41.98
Hydrogen	6.43
Oxygen, by difference	51.59
					<hr/>
					100.00

When the organic substance cannot be mixed with the protoxide of copper in the manner described, the process must be slightly modified to meet the particular case. If, for example, a volatile liquid is to be

Fig. 154.



examined, it is enclosed in a little glass bulb with a narrow stem, which is weighed before and after the introduction of the liquid, the point being hermetically sealed. The combustion-tube must have, in this case, a much greater length ; and, as the protoxide of copper cannot be introduced hot, it must be ignited and cooled out of contact with the atmosphere, to prevent absorption of watery vapour. This is most conveniently effected by transferring it, in a heated state, to a large platinum crucible, to which a closely fitting cover can be adapted. When quite cold, the cover is

removed and instantly replaced by a dry glass funnel, by the assistance of which the oxide may be directly poured into the combustion-tube, with merely momentary exposure to the air. A little oxide is put in, then the bulb, with its stem broken at *a*, a file-scratch having been previously made ; and, lastly, the tube is filled with the cold and dry protoxide of copper. It is arranged in the chauffer, the chloride-of-calcium-tube and potass-apparatus adjusted, and then, some six or eight inches of oxide having been heated to redness, the liquid in the bulb is, by the approximation of a hot coal, expelled, and slowly converted into vapour, which, in passing over the hot oxide, is completely burned. The experiment is then terminated in the usual manner. Fusible fatty substances, and volatile concrete bodies, as camphor, require rather different management, which need not be here described.

Protoxide of copper, which has been used, may be easily restored by


* The theoretical composition of sugar $C_{12}H_{11}O_{11}$, reckoned to 100 parts, gives—

Carbon	42.11
Hydrogen	6.43
Oxygen	51.46
					<hr/>
					100.00

moistening with nitric acid, and igniting to redness; it becomes, in fact, rather improved than otherwise, as after frequent employment its density is increased, and its troublesome hygroscopic powers diminished. For substances which are very difficult of combustion, from the large proportion of carbon they contain, and for compounds into which chlorine enters as a constituent, fused and powdered chromate of lead is very advantageously substituted for the protoxide of copper. Chromate of lead freely gives up oxygen to combustible matters, and even evolves, when strongly heated, a little of that gas, which thus insures the perfect combustion of the organic body.

Analysis of Azotized Substances.—The presence of nitrogen in an organic compound is easily ascertained by heating a small portion with solid hydrate of potassa in a test-tube: the nitrogen, if present, is converted into ammonia, which may be recognized by its odour and alkaline reaction. There are several methods of determining the proportion of nitrogen in azotized organic substances, the experimenter being guided in his choice of means by the nature of the substance and its comparative richness in that element. The carbon and hydrogen are first determined in the usual manner, a longer tube than usual is employed, and four or five inches of its anterior portion filled with spongy metallic copper, made by reducing the protoxide by hydrogen: this serves to decompose any nitrous acid or binoxide of nitrogen, which may be formed in the act of combustion. During the experiment some idea of the abundance or paucity of the nitrogen may be formed from the number of bubbles of incondensable gas which traverse the solution of potassa.

Fig. 155.



In the case of compounds abounding in nitrogen, and readily burned by protoxide of copper, a method may be employed, which is very easy of execution: this consists in determining the ratio borne by the liberated nitrogen to the carbonic acid produced in the combustion. A tube of hard glass, of the usual diameter, and about 15 inches long,

is sealed at one end; a little of the organic substance, mixed with protoxide of copper, is introduced, and allowed to occupy about two inches of the tube; about as much pure oxide is placed over it, and then another portion of a similar mixture; after which the tube is filled up with a second and larger portion of pure oxide, and a quantity of spongy metallic copper. A short bent tube, made moveable by a caoutchouc joint, is fitted by a perforated cork, and made to dip into a mercurial trough, while the combustion-tube itself rests in the chauffer. (Fig. 155.)

Fire is first applied to the anterior part of the tube containing the metal and unmixed oxide, and, when this is red-hot, to the extreme end. Combustion of the first portion of the mixture takes place, the gaseous products sweeping before them nearly the whole of the air of the apparatus. When no more gas issues, the tube is slowly heated by half an inch at a time, in the usual manner, and all the gas very carefully collected in a graduated jar, until the operation is at an end.

The volume is then read off, and some strong solution of caustic potassa thrown up into the jar by a *pipette* with a curved extremity. When the absorption is complete, the residual volume of nitrogen is observed, and compared with that of the mixed gases, proper correction being made for differences of level in the mercury, and from these data the exact proportion borne by the nitrogen to the carbon can be at once determined.*



If the proportion of nitrogen be but small, the error from the nitrogen of the residual atmospheric air becomes so great as to destroy all confidence in the result of the experiment; and the same thing happens when the substance is incompletely burned by protoxide of copper: other means must then be employed. The *absolute* method of determination, also known by the name of Dumas' method, may be had recourse to when the foregoing, or *comparative* method, fails from the first cause mentioned; it gives excellent results, and is applicable

to all azotized substances.

A tube of good Bohemian glass, 28 inches long, is securely sealed at one end; into this enough dry bicarbonate of soda is put to occupy 6 inches. A little pure protoxide of copper is next introduced, and afterwards the mixture of oxide and organic substance, the weight of the latter, between 4.5 and 9 grains, in a dry state, having been


* *Volumes* of the two gases represent *equivalents*; for

100	cubic inches	carbonic acid	weigh	47.26	grains.
100	"	nitrogen	"	30.14	
47.26	:	30.14	=	22	: 14

The last two terms are the equivalent numbers: one equivalent of carbonic acid contains one equivalent of carbon.

correctly determined. The remainder of the tube, amounting to nearly one-half of its length, is then filled up with pure protoxide of copper and spongy metal, and a round cork, perforated by a piece of narrow tube, is securely adapted to its mouth. This tube is connected by means of a caoutchouc joint with a bent delivery-tube, *a*, and the combustion-tube, arranged in the furnace. A few coals are now applied to the farther end of the tube, so as to decompose a portion of the bicarbonate of soda, the remainder of the carbonate as well as of the other part of the tube being protected from the heat by a screen *n*. The current of carbonic acid thus produced is intended to expel all the air from the apparatus. In order to ascertain that this object, on which the success of the whole operation depends, is accomplished, the delivery-tube is depressed under the level of a mercurial trough, and the gas, which is evolved, collected in a test-tube filled with concentrated potassa-solution. If the gas be perfectly absorbed, or, after the introduction of a considerable quantity, only a minute bubble be left, the air may be considered as expelled. The next step is to fill a graduated glass jar two-thirds with mercury and one-third with a strong solution of potassa, and to invert it over the delivery-tube, as represented in fig. 157.

Fig. 157.




This done, fire is applied to the tube, commencing at the front end, and gradually proceeding to the closed extremity, which still contains some undecomposed bicarbonate of soda. This, when the fire at length reaches it, yields up carbonic acid, which chases forward the nitrogen lingering in the tube. The carbonic acid generated during the combustion is wholly absorbed by the potassa in the jar, and nothing is left but the nitrogen. When the operation is at an end, the jar, with its contents, is transferred to a vessel of water, and the volume of the nitrogen read off. This is properly corrected for temperature, pressure, and aqueous vapour, and its weight determined by calculation. When the operation has been very successful, and all precautions minutely ob-

served, the result still leaves an error in excess, amounting to 0·3 or 0·5 per cent., due to the residual air of the apparatus, or that condensed in the pores of the protoxide of copper.

A most elegant process for estimating nitrogen in all organic compounds, except those containing the nitrogen in the form of nitrous, hyponitric, and nitric acids, has been put in practice by MM. Will and Varrentrapp. When a non-azotized organic substance is heated to redness with a large excess of hydrate of potassa or soda, it suffers complete and speedy combustion at the expense of the water of the hydrate, the oxygen combining with the carbon of the organic matter to carbonic acid, which is retained by the alkali, while its hydrogen, together with that of the substance, is disengaged, sometimes in union with a little carbon. The same change happens when nitrogen is present, but with this addition: the whole of the nitrogen thus abandoned combines with a portion of the liberated hydrogen to form ammonia. It is evident, therefore, that if this experiment be made on a weighed quantity of matter, and circumstances allow the collection of the whole of the ammonia thus produced, the proportion of nitrogen can be easily calculated.

An intimate mixture is made of 1 part caustic soda, and 2 or 3 parts quick-lime, by slaking lime of good quality with the proper proportion of strong caustic soda, drying the mixture in an iron vessel, and then heating it to redness in an earthen crucible. The ignited mass is rubbed to powder in a warm mortar, and carefully preserved from the air. The lime is useful in many ways: it diminishes the tendency of the alkali to deliquesce, facilitates mixture with the organic substance, and prevents fusion and liquefaction. A proper quantity of the substance to be analyzed, namely, from 5 to 10 grains, is dried and accurately weighed out: this is mixed in a warm

Fig. 158.



porcelain mortar with enough of the soda-lime to fill two-thirds of an ordinary combustion-tube, the mortar being rinsed with a little more of the alkaline mixture, and, lastly, with a small quantity of powdered glass, which completely removes everything adherent to its surface; the tube is then filled to within an inch of the open end with the lime-mixture, and arranged in the chauffer in the usual manner. The ammonia is collected in a little apparatus of three bulbs, containing moderately strong hydrochloric acid, attached by a cork to the com-

bustion-tube. Matters being thus adjusted, fire is applied to the tube commencing with the anterior extremity. When ignited throughout its whole length, and when no more gas issues from the apparatus, the point of the tube is broken, and a little air drawn through the whole. The acid liquid is then emptied into a capsule, the bulbs rinsed into the same, first with a little alcohol, and then repeatedly with distilled water; an excess of pure bichloride of platinum is added, and the whole evaporated to dryness in a water-bath. The dry mass, when cold, is treated with a mixture of alcohol and ether, which dissolves out the superfluous bichloride of platinum, but leaves untouched the yellow crystalline double chloride of platinum and ammonium. The latter is collected upon a small weighed filter, washed with the same mixture of alcohol and ether, dried at 212° (100°C), and weighed; 100 parts correspond to 6.272 parts of nitrogen; or, the salt with its filter may be very carefully ignited, and the filter burned in a platinum crucible, and the nitrogen reckoned from the weight of the spongy metal, 100 parts of that substance corresponding to 14.18 parts of nitrogen. The former plan is to be preferred in most cases.

Bodies very rich in nitrogen, as urea, must be mixed with about an equal quantity of pure sugar, to furnish incondensable gas, and thus diminish the violence of the absorption which otherwise occurs; and the same precaution must be taken, for a different reason, with those which contain little or no hydrogen.

A modification of this process has been lately suggested by M. Peligot, which is very convenient if a large number of nitrogen-determinations is to be made. By this plan the ammonia, instead of being received in hydrochloric acid, is conducted into a known volume (from $\frac{1}{2}$ to 1 cubic inch) of a standard solution of sulphuric acid, contained in the ordinary nitrogen-bulbs. After the combustion is finished, the acid containing the ammonia is poured out into a beaker, coloured with a drop of tincture of litmus, and then neutralized with a standard solution of soda in water or of lime in sugar-water, the point of neutralization becoming perceptible by the sudden appearance of a blue tint. The lime-solution is conveniently poured out from the graduated glass-tube, described under the head of alkalimetry. The volume of lime-solution necessary to neutralize the same amount of acid, which is used for condensing the ammonia, having been ascertained by a preliminary experiment, it is evident that the difference of the quantities used in the two experiments gives the ammonia collected during the combustion in the acid. The amount of nitrogen may thus be calculated. If, for instance, an acid be prepared, containing 20 grains of pure hydrated sulphuric acid (SO_3, HO) in 1,000 grain-measures—200 grain-measures of this acid—the quantity introduced into the bulbs—correspond to 1.38 grains of ammonia, or 1.14 grains of nitrogen. The alkaline solution is so graduated that 1,000 grain measures will exactly neutralize the

200 grain-measures of the standard acid. If we now find that the acid, partly saturated with the ammonia disengaged during the combustion of a nitrogenous substance, requires only 700 grain-measures of the alkaline solution, it is evident that

$$\frac{200 \times 300}{1000} = 60 \text{ grain-measures}$$

were saturated by the ammonia, and the quantity of nitrogen is obtained by the proportion

$$200 : 1.14 = 60 : x, \text{ wherefrom } x = \frac{1.14 \times 60}{200} = 0.342 \text{ grains of nitrogen.}$$

Estimation of Sulphur in Organic Compounds.—When bodies of this class containing sulphur are burned with protoxide of copper, a small tube containing binoxide of lead must be interposed between the chloride-of-calcium-tube and the potass-apparatus to retain any sulphurous acid which may be formed. It is better, however, to use chromate of lead in such cases. The proportion of sulphur is determined by oxidizing a known weight of the substance by strong nitric acid, or by fusion in a silver vessel with ten or twelve times its weight of pure hydrate of potassa and half as much nitre. The sulphur is thus converted into sulphuric acid, the quantity of which can be determined by dissolving the fused mass in water, acidulating with nitric acid, and adding a salt of baryta. Phosphorus is, in like manner, oxidized to phosphoric acid, the quantity of which is determined by precipitation in combination with sesquioxide of iron, or otherwise.

Estimation of Chlorine.—The case of a volatile liquid containing chlorine is of very frequent occurrence, and may be taken as an illustration of the general plan of proceeding. The combustion with protoxide of copper must be very carefully conducted, and two or three inches of the anterior portion of the tube kept cool enough to prevent volatilization of the chloride of copper into the chloride-of-calcium-tube. Chromate of lead is much better for the purpose. The chlorine is correctly determined by placing a small weighed bulb of liquid in a combustion-tube, which is afterwards filled with fragments of pure quick-lime. The lime is brought to a red-heat, and the vapour of the liquid driven over it, when the chlorine displaces oxygen from the lime, and gives rise to chloride of calcium. When cold, the contents of the tube are dissolved in the dilute nitric acid, filtered, and the chlorine precipitated by nitrate of silver.

EMPIRICAL AND RATIONAL FORMULÆ.

A chemical formula is termed *empirical* when it merely gives the simplest possible expression of the composition of the substance to which it refers. A *rational* formula, on the contrary, aims at de-

scribing the exact composition of one *equivalent*, or *combining proportion* of the substance, by stating the absolute number of equivalents of each of its elements essential to that object, as well as the mere relations existing between them. The empirical formula is at once deduced from the analysis of the substance, reckoned to 100 parts; the rational formula requires in addition a knowledge of its combining quantity, which can only be obtained by direct experiment, by synthesis, or by the careful examination of one or more of its most definite compounds. Farther, the rational may either coincide with the empirical formula, or it may be a multiple of the latter.

Thus, the composition of acetic acid is expressed by the formula $C_4H_3O_3$, which exhibits the simplest relations of the three elements, and at the same time expresses the quantities of these, in equivalents, required to make up an *equivalent* of acetic acid; hence, it is both empirical and rational. On the other hand, the empirical formula of crystallized lactic acid is $C_7H_6O_6$, while its rational formula, determined by its capacity of saturation, is double, or $C_{14}H_{12}O_{12}$, otherwise written $C_{14}H_{11}O_{11}, HO$. In like manner, the empirical formula of the artificial alkaloids *furfurine* and *amarine* are respectively $C_{15}H_6NO_3$ and $C_{21}H_9N$. The equivalents of these substances, that is to say, the quantities required to form neutral salts with one equivalent of any well-defined monobasic acid will, however, be expressed by the formulæ $C_{30}H_{12}N_2O_6$ and $C_{42}H_{18}N_2$; hence these latter deserve the name of rational formulæ.

The deduction of an empirical formula from the ultimate analysis is very easy; the case of sugar, already cited, may be taken as an example. This contains, according to the analysis, in 100 parts—

Carbon	.	.	.	41.98
Hydrogen	.	.	.	6.43
Oxygen	.	.	.	51.59
				<hr/>
				100.00

If each of these quantities be divided by the equivalent of the element, the quotients will express in *equivalents* the relations existing between them; these are afterwards reduced to their simplest expression. This is the only part of the calculation attended with any difficulty: if the numbers were rigidly correct, it would only be necessary to divide each by the greatest divisor common to the whole; as they are, however, only approximative, something is of necessity left to the judgment of the experimenter, who is obliged to use more indirect means.

$$\frac{41.98}{6} = 6.99; \quad 6.43; \quad \frac{51.59}{8} = 6.44,$$

or 699 eq. carbon, 643 eq. hydrogen, and 644 eq. oxygen.

It will be evident, in the first place, that the hydrogen and oxygen are present in the proportions to form water, or as many equivalents of one as of the other. Again, the equivalents of carbon and hydrogen are nearly in the proportion of 12 : 11, so that the formula $C_{12}H_{11}O_{11}$ appears likely to be correct. It is now easy to see how far this is admissible, by reckoning it back to 100 parts, comparing the result with the numbers given by the actual analysis, and observing whether the difference falls fairly in direction and amount within the limits of error of what may be termed a good experiment, viz., two or three tenths per cent. *deficiency* in the carbon, and not more than one-tenth per cent. *excess* in the hydrogen.

Carbon	$6 \times 12 = 72$
Hydrogen	$11 \text{ eq.} = 11$
Oxygen	$8 \times 11 = 88$

171

$$171 : 72 = 100 : 42.11$$

$$171 : 11 = 100 : 6.43$$

$$171 : 88 = 100 : 5.146$$

Organic acids and salt-radicals have their proper equivalents most frequently determined by an analysis of their lead- and silver-salts, by burning these latter with suitable precautions in a thin porcelain capsule, and noting the weight of the protoxide of lead or metallic silver left behind. If the protoxide of lead be mixed with globules of reduced metal, the quantity of the latter must be ascertained by dissolving away the oxide by acetic acid. Or the lead-salt may be converted into sulphate, and the silver-compound into chloride, and both metals thus estimated. An organic base, on the contrary, or a basyle, has its equivalent fixed by the observation of the quantity of a mineral acid, or an inorganic salt-radical, required to form with it a combination having the characters of neutrality.

DETERMINATION OF THE DENSITY OF VAPOURS.

The determination of the specific gravity of the vapour of a volatile substance is frequently a point of great importance, inasmuch as it gives the means, in conjunction with the analysis, of representing the constitution of the substance by measure in a gaseous state. The following is a sketch of the plan of operation usually followed:—A light glass globe, about three inches in diameter, is taken, and its neck softened and drawn out in the blowpipe-flame, as represented in the figure: this is accurately weighed. About one hundred grains of the volatile liquid are then introduced, by gently warming the globe

and dipping the point into the liquid, which is then forced upwards by the pressure of the air as the vessel cools. The globe is next firmly attached by wire to a handle, in such a manner that it may be plunged into a bath of boiling water or heated oil, and steadily held with the point projecting upwards. The bath must have a temperature considerably above that of the boiling-point of the liquid. The latter becomes rapidly converted into vapour, which escapes by the narrow orifice, chasing before it the air of the globe. When the issue of vapour has wholly ceased, and the temperature of the bath, carefully observed, appears pretty uniform, the open extremity of the point is hermetically sealed by a small blowpipe-flame. The globe is removed from the bath, suffered to cool, cleansed if necessary, and weighed, after which the neck is broken off beneath the surface of water which has been boiled and cooled out of contact of air, or better mercury. The liquid enters the globe, and, if the expulsion of the air by the vapour has been complete, fills it; if otherwise, an air-bubble is left, whose volume can be easily ascertained by pouring the liquid from the globe into a jar graduated to cubic inches, and then refilling the globe, and repeating the same observation. The capacity of the vessel is thus at the same time known; and these are all the data required. An example will render the whole intelligible.

Fig. 159.



Determination of the density of the vapour of Acetone.

Capacity of globe	31.61 cubic inches.
Weight of globe filled with dry air at 52° (11°·11C) and 30·24 inches barometer	2070·88 grains.
Weight of globe filled with vapour at 212° (100°C) temp. of the bath at the moment of sealing the point, and 30·24 inches barometer	2076·81 grains.
Residual air, at 45° (7°·22C), and 30·24 inches barometer	0·60 cubic inch.

31.61 cub. inches of air at 52° and 30·24 in bar. = 32·36 cub. inches
at 60° (15°·5C) and 30 inch. bar., weighing . . . 10·035 grains.
Hence, weight of empty globe, 2070·88 — 10·035 = 2060·845 grains.

398 DETERMINATION OF THE DENSITY OF VAPOURS.

0·6 c. inch of air at 45° = 0·8 c. inch at 212° ; weight of do. by calculation = 0·191 grain.

31·61—0·8 = 30·81 cubic inches of vapour at 212° and 30·24 in bar., which, *on the supposition that it could bear cooling to 60° without liquefaction*, would, at that temperature, and under a pressure of 30 inch. bar., become reduced to 24·18 cubic inches.

Hence,

Weight of globe and vapour	2076·810 grains.
„ residual air	0·191

2076·619

Weight of globe	2060·845
---------------------------	----------

Weight of the 24·18 cubic inches of vapour	15·774
--	--------

Consequently, 100 cubic inches of such vapour must

weigh	65·23 grains.
-----------------	---------------

100 cubic inches of air, under similar circumstances,

weigh	31·01
-----------------	-------

65·23

— = 2·103, the specific gravity of the vapour in question,

31·01

air being unity.

In the foregoing statement a correction has been, for the sake of simplicity, omitted, which, in very exact experiments, must not be lost sight of, viz., the expansion and change of capacity of the glass globe by the elevated temperature of the bath. The density so obtained will be always on this account a little too high.

The error to which the mercurial thermometer is, at high temperatures, liable, tends in the opposite direction.

It is easy to compare the actual specific gravity of the vapour found in the manner above described with the theoretical specific gravity deduced from the formula of the substance:—

The formula of acetone is C_3H_3O . In combining volumes this is represented by 3 vols. of the hypothetical vapour of carbon, 3 vols. of hydrogen, and half a volume of oxygen. Or the weight of the unit of volume of acetone-vapour will be equal to three times the specific gravity of carbon-vapour, three times that of hydrogen, and one-half that of oxygen added together, one volume of the compound vapour containing $6\frac{1}{2}$ volumes of its components:—

3 vols. hypothetical vapour of carbon	$0·4183 \times 3 = 1·2549$
3 vols. hydrogen	$0·0693 \times 3 = 0·2079$
$\frac{1}{2}$ vol. oxygen	$= 0·5528$

Theoretical specific gravity	2·0156
--	--------

SECTION I.

NON-AZOTIZED BODIES OF THE SACCHARINE AND
AMYLACEOUS GROUP.

SUGAR, STARCH, GUM, LIGNIN, AND ALLIED SUBSTANCES.

THE members of this remarkable and very natural group present several interesting cases of isomerism. They are characterized by their feeble aptitude to enter into combination, and also by containing, with one or two exceptions, oxygen and hydrogen in the proportions to form water.

Table of Saccharine and Amylaceous Substances.

Cane-sugar, crystallized	$C_{24}H_{22}O_{22}$
Cane-sugar, in combination	$C_{24}H_{18}O_{18}$
Grape-sugar, crystallized	$C_{24}H_{28}O_{28}$
Grape-sugar, in combination	$C_{24}H_{21}O_{21}$
Milk-sugar, crystallized	$C_{21}H_{24}O_{24}$
Milk-sugar, in combination	$C_{24}H_{19}O_{19}$
Sugar from <i>Secale cornutum</i>	$C_{24}H_{26}O_{26}$
Mannite	$C_6H_7O_6$
Dulcose	$C_6H_7O_6$
Sorbin	$C_6H_6O_6$
Starch, unaltered, dried at 212° ($100^{\circ}C$)	$C_{24}H_{20}O_{20}$
Amadin, or gelatinous starch	$C_{24}H_{20}O_{20}$
Dextrin, or gummy starch	$C_{24}H_{20}O_{20}$
Starch from <i>Cetraria Islandica</i>	$C_{24}H_{20}O_{20}$
Inulin	$C_{24}H_{21}O_{21}$
Gum-Arabic	$C_{24}H_{22}O_{22}$
Gum-tragacanth	$C_{24}H_{20}O_{20}$
Lignin, or cellulose	$C_{24}H_{20}O_{20}$

CANE-SUGAR; ORDINARY SUGAR, $C_{24}H_{22}O_{22}$.—This most useful substance is found in the juice of many of the grasses, in the sap of several forest-trees, in the root of the beet and the mallow, and in several other plants. It is extracted most easily and in greatest abundance from the sugar-cane, cultivated for the purpose in many tropical countries. The canes are crushed between rollers, and the expressed juice suffered to flow into a large vessel where it is slowly heated nearly to its boiling-point. A small quantity of hydrate of lime mixed with water is then added, which occasions the separation of a coagulum consisting chiefly of earthy phosphates, waxy matter, a peculiar albuminous principle, and mechanical impurities. The clear liquid separated from the coagulum thus produced is rapidly

evaporated in open pans heated by a strong fire made with the crushed canes of the preceding year, dried in the sun and preserved for the purpose. When sufficiently concentrated, the syrup is transferred to a shallow vessel, and left to crystallize, during which time it is frequently agitated in order to hasten the change and hinder the formation of large crystals. It is, lastly, drained from the dark uncrystallizable syrup, or *molasses*, and sent into commerce, under the name of *raw* or *Muscovado* sugar. The refining of this crude product is effected by redissolving it in water, adding a quantity of albumen in the shape of serum of blood or white of egg, and sometimes a little lime-water, and heating the whole to the boiling-point; the albumen coagulates, and forms a kind of network of fibres, which enclose and separate from the liquid all mechanically-suspended impurities. The solution is decolorized by filtration through animal charcoal, evaporated to the crystallizing-point, and put into conical earthen moulds, where it solidifies, after some time, to a confusedly crystalline mass, which is drained, washed with a little clear syrup, and dried in a stove: the product is ordinary *loaf-sugar*. When the crystallization is allowed to take place quietly and slowly, *sugar-candy* results, the crystals under these circumstances acquiring large volume and regular form. The evaporation of the decolorized syrup is best conducted in strong close boilers exhausted of air; the boiling-point of the syrup is reduced in consequence from 230° (110°C) to 150° ($65^{\circ}\cdot5\text{C}$) or below, and the injurious action of the heat upon the sugar in great measure prevented. Indeed the production of molasses in the rude colonial manufacture is chiefly the result of the high and long-continued heat applied to the cane-juice, and might be almost entirely prevented by the use of vacuum-pans, the product of sugar being thereby greatly increased in quantity, and so far improved in quality as to become almost equal to the refined article.

In many parts of the continent of Europe sugar is manufactured on a large scale from beet-root, which contains about 8 per cent. of that substance. The process is far more complicated and troublesome than that just described, and the product much inferior. When refined, however, it is scarcely to be distinguished from the preceding. The inhabitants of the Western States of America prepare sugar in considerable quantity from the sap of the sugar maple, *Acer saccharinum*, which is common in those parts. The tree is tapped in the spring by boring a hole a little way into the wood, and inserting a small spout to convey the liquid into a vessel placed for its reception. This is boiled down in an iron pot, and furnishes a coarse sugar, which is almost wholly employed for domestic purposes, but little finding its way into commerce.

Pure sugar slowly separates from a strong solution in large, transparent, colourless crystals, having the figure of a modified oblique rhombic prism. It has a pure, sweet taste, is very soluble in water, requiring for solution only one-third of its weight in the cold, and is also dissolved by alcohol, but with more difficulty. When mode-

rately heated it melts, and solidifies on cooling to a glassy amorphous mass, familiar under the name of *barley-sugar*: at a higher temperature it blackens and suffers decomposition; and the same effect is produced, as already remarked, by long-continued boiling of the aqueous solution, which loses its faculty of crystallizing and becomes coloured. The crystals have a specific gravity of 1.6, and are unchangeable in the air.

The deep-brown soluble substance called *caramel*, used for colouring spirits, and other purposes, is a product of the action of heat upon cane-sugar. It contains $C_{24}H_{18}O_{18}$, and is isomeric with cane-sugar in combination.

The following is the composition assigned to the principal compounds of cane-sugar by M. Péligot, who has devoted much attention to the subject.*

Crystallized cane-sugar	$C_{24}H_{18}O_{18} + 4HO$
Compound of sugar with common salt		$C_{24}H_{18}O_{18} + NaCl + 3HO$
Compound of sugar with baryta	$C_{24}H_{18}O_{18} + 2BaO + 4HO$
Compound of sugar with lime	$C_{24}H_{18}O_{18} + 2CaO + 4HO$
Compound of sugar with protoxide of lead		$C_{24}H_{18}O_{18} + 4PbO$

The compounds with baryta and lime are prepared by digesting sugar at a gentle heat with the hydrates of the earths. The lime-compound has a bitter taste, and is more soluble in cold water than in hot. Both are readily decomposed by carbonic acid, crystals of carbonate of lime being occasionally produced. The combination with protoxide of lead is prepared by mixing sugar with a solution of acetate of lead, adding excess of ammonia, and drying the white insoluble product out of contact with air. The compound with common salt is crystallizable, soluble, and deliquescent.

GRAPE-SUGAR; GLUCOSE; SUGAR OF FRUITS, $C_{24}H_{26}O_{28}$.—This variety of sugar is very abundantly diffused through the vegetable kingdom; it may be extracted in large quantity from the juice of sweet grapes, and also from honey, of which it forms the solid crystalline portion, by washing with cold alcohol, which dissolves the fluid syrup. It may also be prepared by artificially modifying cane-sugar, starch, and woody fibre, by processes presently to be described. The appearance of this substance, to an enormous extent, in the urine, is the most characteristic feature of the disease called *diabetes*.

Grape-sugar is easily distinguished by several important peculiarities from cane-sugar: it is much less sweet, and less soluble in water, requiring $1\frac{1}{2}$ parts of the cold liquid for solution. Its mode of crystallization is also completely different: instead of forming, like cane-sugar, bold, distinct crystals, it separates from its solutions in water and alcohol in granular warty masses, which but seldom present crystalline faces. When pure it is nearly white. When heated, it melts,

* Ann. Chim. et Phys. lxxvii. 113.

and loses 4 eq. of water, and at a higher temperature blackens and suffers decomposition. Grape-sugar combines with difficulty with lime, baryta, and oxide of lead, and is converted into a brown or black substance when boiled with solution of caustic alkali, by which cane-sugar is but little affected. It dissolves, on the contrary, in strong oil of vitriol without blackening, and gives rise to a peculiar compound acid, whose baryta-salt is soluble. Cane-sugar is, under these circumstances, instantly changed to a black mass resembling charcoal.

When solutions of cane and grape sugar are mixed with two separate portions of solution of sulphate of copper, and caustic potassa added in excess to each, deep-blue liquids are obtained, which, on being heated, exhibit different characters; the one containing cane-sugar is at first but little altered; a small quantity of red powder falls after a time, but the liquid long retains its blue tint: with the grape-sugar, on the other hand, the first application of heat throws down a copious greenish precipitate, which rapidly changes to scarlet, and eventually to dark red, leaving a nearly colourless solution. This is an excellent test for distinguishing the two varieties of sugar, or discovering an admixture of grape with cane sugar.

Grape-sugar unites with common salt, forming a soluble compound of sweetish saline taste, which crystallizes in a regular and beautiful manner.

Compounds of Grape-sugar, according to Pélégot.

Crystalline grape-sugar, dried in the air	$C_{24}H_{21}O_{21} + 7HO$
The same, dried at 266° ($130^{\circ}C$)	$C_{24}H_{21}O_{21} + 3HO$
Compound of grape-sugar with common salt	$C_{24}H_{21}O_{21} + NaCl + 5HO$
The same, dried at 266° ($130^{\circ}C$)	$C_{24}H_{21}O_{21} + NaCl + 2HO$
Compound of grape-sugar with baryta	$C_{24}H_{21}O_{21} + 3BaO + 7HO$
Compound of grape-sugar with lime	$C_{24}H_{21}O_{21} + 3CaO + 7HO$
Compound of grape-sugar with protoxide of lead	$C_{24}H_{21}O_{21} + 6PbO$

Sulphosaccharic Acid, $C_{24}H_{20}O_{20},SO_3$.—Melted grape-sugar is cautiously mixed with concentrated sulphuric acid, the product dissolved in water, and neutralized with carbonate of baryta; sulphate of baryta is formed together with a soluble sulphosaccharate of that earth, from which the acid itself may be afterwards eliminated. It is a sweetish liquid, forming a variety of soluble salts, and very prone to decompose into sugar and sulphuric acid.

Action of dilute Acids upon Sugar.—Cane-sugar dissolved in dilute sulphuric acid is gradually but completely converted, at the common temperature of the air, into grape-sugar. The same solution, when long boiled, yields a brownish-black and nearly insoluble substance, which is a mixture of two distinct bodies, one having the appearance

of small shining scales, and the other that of a dull-brown powder. The first, called by Boullay and Malaguti *ulmin*, and by Liebig *sacchulmin*, is insoluble in ammonia and alkalis; the second, *ulmic acid*, the *sacchulmic acid* of Liebig, dissolves freely, yielding dark-brown solutions precipitable by acids. By long-continued boiling with water, sacchulmic acid is converted into sacchulmin. Both these substances have the same composition, expressed by the empirical formula C_2HO . Hydrochloric acid, in a dilute state, produces the same effects.*

Action of Alkalis upon Sugar.—When lime or baryta is dissolved in a solution of grape-sugar, and the whole left to itself several weeks in a close vessel, the alkaline reaction will be found to have disappeared from the formation of an acid substance. By mixing this solution with basic acetate of lead, a voluminous white precipitate is obtained, which, when decomposed by sulphuretted hydrogen, yields sulphide of lead, and the new acid, to which the term *kalisaccharic* or *glucic* is applied. Glucic acid is very soluble and deliquescent, has a sour taste and acid reaction: its salts, with the exception of that containing protoxide of lead, are very soluble. It contains $C_8H_5O_5$. When grape-sugar is heated in a strong solution of potassa, soda, or baryta, the liquid darkens, and at length assumes a nearly black colour. The addition of an acid then gives rise to a black flocculent precipitate of a substance called *melasinic acid*, containing $C_{24}H_{12}O_{10}$. Cane-sugar long boiled with alkalis undergoes the same changes, being probably first converted into grape-sugar.

SUGAR FROM ERGOT OF RYE.—This variety of sugar, extracted by alcohol from the ergot, crystallizes in transparent colourless prisms, which have a sweet taste, and are very soluble in water. It differs from cane-sugar in not reducing the acetate of copper when boiled with a solution of that substance. It contains $C_{24}H_{26}O_{26}$.

SUGAR OF DIABETES INSIPIDUS.—A substance having the general properties of a sugar, but destitute of sweet taste, has been described by M. Thénard as having been obtained from the above-mentioned source. It was capable of furnishing alcohol by fermentation, and of suffering conversion into grape-sugar by dilute sulphuric acid. Its composition is unknown.

LIQUORICE-SUGAR; GLYCYRRHIZIN.—The root of the common liquorice yields a large quantity of a peculiar sweet substance, which is soluble in water, but refuses to crystallize; it is remarkable for

* Under the names *ulmin* and *ulmic acid* have been confounded a number of brown or black uncrystallizable substances, produced by the action of powerful chemical agents upon sugar, lignin, &c., or generated by the putrefactive decay of vegetable fibre. Common garden mould, for example, treated with dilute, boiling solution of caustic potassa, yields a deep-brown solution, from which acids precipitate a flocculent, brown substance, having but a slight degree of solubility in water. This is generally called *ulmic* or *humic acid*, and its origin ascribed to the reaction of the alkali on the *ulmin* or *humus* of the soil. It is known that these bodies differ exceedingly in composition: they are too indefinite to admit of ready investigation.

forming with acids compounds which have but sparing solubility. Glycyrrhizin cannot be made to ferment. The formula of this substance is not definitely settled.

SUGAR OF MILK; LACTIN, $C_{24}H_{24}O_{24}$.—This curious substance is an important constituent of milk; it is obtained in large quantities by evaporating *whoy* to a syrupy state, and purifying the lactic, which slowly crystallizes out, by animal charcoal. It forms white, translucent, four-sided prisms, of great hardness. It is slow and difficult of solution in cold water, requiring for that purpose 5 or 6 times its weight; it has a feeble, sweet taste, and in the solid state feels gritty between the teeth. When heated, it loses water, and at a high temperature blackens and decomposes. Milk-sugar forms several compounds with protoxide of lead, and is converted into grape-manna by boiling with dilute mineral acids. It is not directly fermentable, but can be made under particular circumstances to furnish alcohol.

MANNA-SUGAR; MANNITE, $C_6H_7O_6$ or $C_{12}H_{14}O_{12}$.—This is the chief component of *manna*, an exudation from a species of ash; it is also found in the juice of certain other plants, and in several seaweeds, and may be formed artificially from ordinary sugar by a peculiar kind of fermentation. It is best prepared by treating manna with boiling alcohol, and filtering the solution whilst hot; the mannite crystallizes on cooling in tufts of slender colourless needles. It is fusible by heat without loss of weight, is freely soluble in water, possesses a powerfully sweet taste, and has no purgative properties. Mannite refuses to ferment. This substance combines with sulphuric acid, giving rise to a new acid, the composition of which is not yet definitely established. It is likewise acted on by concentrated nitric acid. The product of this action will be noticed farther on. The substance formerly described as *mushroom-sugar* is merely mannite.

DULCOSE, $C_6H_7O_6$ or $C_{12}H_{14}O_{12}$.—Closely allied to, and identical in composition with mannite, is a substance, imported into Europe from Madagascar, the origin of which is uncertain, but which has been lately examined by Messrs. Soubeiran, Laurent, and Jaquelain. It forms large crystals, which fuse at 374° ($190^\circ C$). Dulcose is insoluble in boiling alcohol, and not precipitated by basic acetate of lead. It is not capable of undergoing fermentation.

SORBIN, $C_6H_6O_6$ or $C_{12}H_{12}O_{12}$.—Mr. Pelouze has quite recently observed that the juice of the berries of the mountain ash, when allowed to stand for some time in open vessels, deposits a brown crystalline matter, which, on recrystallization, may be obtained in transparent colourless crystals. This substance is almost insoluble in alcohol, but easily soluble in water, which assumes an exceedingly sweet taste. Sorbin is, however, no sugar; it is not capable of fermenting, nor can it by the action of acids, be converted into grape-sugar. A solution of sorbin, when mixed with ammonia and a solution of acetate of lead, furnishes a white flocculent precipitate, which contains $2P_2O_5$, $C_6H_4O_4$.

STARCH; FECULA.—This is one of the most important and widely

diffused of the vegetable proximate principles, being found to a greater or less extent in every plant. It is most abundant in certain roots and tubers, and in soft stems: seeds often contain it in large quantity. From these sources the fecula can be obtained by rasping or grinding to pulp the vegetable structure, and washing the mass upon a sieve, by which the torn cellular tissue is retained, while the starch passes through with the liquid, and eventually settles down from the latter as a soft, white, insoluble powder, which may be washed with cold water, and dried with very gentle heat. Potatoes treated in this manner yield a large proportion of starch. Starch from grain may be prepared in the same manner, by mixing the meal with water to a paste, and washing the mass upon a sieve: a nearly white, insoluble substance called *gluten* or *glutin* remains behind, which contains a large proportion of nitrogen. The gluten of wheat flour is extremely tenacious and elastic. The value of meal as an article of food greatly depends upon this substance. Starch from grain is commonly manufactured on the large scale by steeping the material in water for a considerable period, when the lactic acid, always developed under such circumstances from the sugar of the seed, disintegrates, and in part dissolves the azotized matter, and greatly facilitates the mechanical separation of that which remains. A still more easy and successful process has lately been introduced, in which a very dilute solution of caustic soda, containing about 200 grains of alkali to a gallon of liquid, is employed with the same view. Excellent starch is thus prepared from rice. Starch is insoluble in cold water, as indeed its mode of preparation sufficiently shows; it is equally insoluble in alcohol and other liquids which do not effect its decomposition. To the naked eye it presents the appearance of a soft, white, and often glistening powder; under the microscope it is seen to be altogether destitute of crystalline structure, but to possess, on the contrary, a kind of organization, being made up of multitudes of little rounded transparent bodies, upon each of which a series of depressed parallel rings, surrounding a central spot or hilum, may often be traced. The starch-granules from different plants vary both in magnitude and form; those from the *Canna coccinea*, or *tous les mois*, and potato being largest; and those from wheat, and the cereals in general very much smaller. The figure in the margin will serve to convey an idea of the appearance of the granules of potato-starch, highly magnified.

Fig. 160.



When a mixture of starch and water is heated to near the boiling-point of the latter, the granules burst and disappear, producing, if the proportion of starch be considerable, a thick gelatinous mass, very slightly opalescent from the shreds of fine membrane, the envelope of each separate granule. By the addition of a large quantity of water, this gelatinous starch, or *amidin*, may be so far diluted as to pass in great measure through filter-paper. It is very doubtful, however, how far the substance itself is really soluble in water, at least when cold; it is more likely to be merely suspended in the liquid in the form of a swollen, transparent, insoluble jelly, of extreme tenuity. Gelatinous starch, exposed in a thin layer to a dry atmosphere, becomes converted into a yellowish, horny substance, like gum, which, when put into water, again softens and swells.

Thin gelatinous starch is precipitated by many of the metallic oxides, as lime, baryta, and protoxide of lead, and also by a large addition of alcohol. Infusion of galls throws down a copious yellowish precipitate containing tannic acid, which redissolves when the solution is heated. By far the most characteristic reaction, however, is that with free iodine, which forms with starch a deep indigo-blue compound, which appears to dissolve in pure water, although it is insoluble in solutions containing free acid or saline matter. The blue liquid has its colour destroyed by heat, temporarily if the heat be quickly withdrawn, and permanently if the boiling be long continued, in which case the compound is decomposed and the iodine volatilized. Starch in the dry state, put into iodine-water, acquires a purplish-black colour.

The unaltered and the gelatinous starch, in a dried state, have the same composition, namely, $C_{24}H_{20}O_{20}$; a compound of starch and protoxide of lead was found to contain, when dried at 212° ($100^{\circ}C$), $C_{24}H_{20}O_{20} + 4PbO$.

DEXTRIN.—When gelatinous starch is boiled with a small quantity of dilute sulphuric, hydrochloric, or indeed, almost any acid, it speedily loses its consistency, and becomes thin and limpid, from having suffered conversion into a soluble substance resembling gum, called dextrin.* The experiment is most conveniently made with sulphuric acid, which may be afterwards withdrawn by saturation with chalk. The liquid filtered from the nearly insoluble gypsum may then be evaporated in a water-bath to dryness. The result is a gum-like mass, destitute of crystalline structure, soluble in cold water, and precipitable from its solution by alcohol, and capable of combining with protoxide of lead.

When the ebullition with the dilute acid is continued for a considerable period, the dextrin first formed undergoes a farther change, and becomes converted into grape-sugar, which can be thus artificially produced with the greatest facility. The length of time required for this remarkable change depends upon the quantity of acid present;

* From its action on polarized light, twisting the plane of polarization towards the right hand,

if the latter be very small, it is necessary to continue the boiling many successive hours, replacing the water which evaporates. With a larger proportion of acid, the conversion is much more speedy. A mixture of 15 parts potato-starch, 60 parts water, and 6 parts sulphuric acid, may be kept boiling for about four hours; the liquid neutralized with chalk, filtered, and rapidly evaporated to a small bulk. By digestion with animal charcoal and a second filtration much of the colour will be removed, after which the solution may be boiled down to a thin syrup and left to crystallize; in the course of a few days it solidifies to a mass of grape-sugar. There is another method of preparing this substance from starch which deserves particular notice. Germinating seeds, and buds in the act of development, are found to contain a small quantity of a peculiar azotized substance, formed at this particular period from the gluten or vegetable albuminous matter, to which the name *diastase* is given. This substance possesses the same curious property of effecting the conversion of starch into dextrin, and ultimately into grape-sugar, and at a much lower temperature than that of ebullition. A little infusion of malt, or germinated barley, in tepid water, mixed with a large quantity of thick gelatinous starch, and the whole maintained at 160° (71°C), or thereabouts, occasions complete liquefaction in the space of a few minutes from the production of dextrin, which in its turn becomes in three or four hours converted into sugar. If a greater degree of heat be employed, the diastase is coagulated and rendered insoluble and inactive. Very little is known respecting diastase itself; it seems very much to resemble vegetable albumen, but has never been got in a state of purity.

The change of starch or dextrin into sugar, whether produced by the action of dilute acid or by diastase, takes place quite independently of the oxygen of the air, and is unaccompanied by any secondary product. The acid takes no direct part in the reaction; it may, if not volatile, be all withdrawn without loss after the experiment. The whole reaction lies between the starch and the elements of water; a fixation of the latter occurring in the new product, as will be seen at once on comparing their composition. The sugar, in fact, so produced, very sensibly exceeds in weight the starch employed. Dextrin itself has exactly the same composition as the original starch.

Dextrin is used in the arts as a substitute for gum: it is sometimes made in the manner above described, but more frequently by heating dry potato-starch to 400° ($204^{\circ}\cdot 5\text{C}$), by which it acquires a yellowish tint and becomes soluble in cold water. It is sold in this state under the appellation of *British Gum*.

Starch is an important article of food, especially when associated as in ordinary meal with albuminous substances. Arrow-root, and the fecula of the *Canna coccinea*, are very pure varieties, employed as articles of diet; arrow-root is obtained from the *Maranta arundinacea*, cultivated in the West Indies; it is with difficulty distinguished from potato-starch. *Tapioca* is prepared from the root of the *Iatropa*

manihot, being thoroughly purified from its poisonous juice. *Cassava* is the same substance modified whilst moist by heat. *Sago* is made from the soft central portion of the stem of a palm-tree.

STARCH FROM ICELAND MOSS.—The lichen called *Cetraria Islandica*, purified by a little cold solution of potassa from a bitter principle, yields when boiled in water a slimy and nearly colourless liquid, which gelatinizes on cooling, and dries up to a yellowish amorphous mass, which does not dissolve in cold water, but merely softens and swells. A solution of this substance in warm water is not affected by iodine, although the jelly, on the contrary, is rendered blue. It is precipitated by alcohol, acetate of lead, and infusion of galls, and is converted by boiling with dilute sulphuric acid into grape-sugar. According to Mulder, lichen-starch likewise contains $C_{24}H_{20}O_{20}$. The jelly from certain *algæ*, as that of Ceylon, and the so-called *Carraheen moss*, closely resembles the above.

INULIN.—This substance, which differs from common starch in some important particulars, is found in the root of the *Inula helenium*, the *Helianthus tuberosus*, the *dahlia*, and several other plants; it may be easily obtained by washing the rasped root on a sieve, and allowing the inulin to settle down from the liquid; or by cutting the root into thin slices, boiling these in water, and filtering while hot; the inulin separates as the solution cools. It is a white, amorphous, tasteless substance, nearly insoluble in cold water, but freely dissolved by the aid of heat; the solution is precipitated by alcohol, but not by acetate of lead or infusion of galls. Iodine communicates a brown colour. Inulin has been analyzed by Mr. Parnell, who finds it to contain, when dried at 212° ($100^{\circ}C$), $C_{24}H_{21}O_{21}$.

GUM.—*Gum Arabic*, which is the produce of an acacia, may be taken as the most perfect type of this class of bodies. In its purest and finest condition, it forms white or slightly-yellowish irregular masses, which are destitute of crystalline structure, and break with a smooth conchoidal fracture. It is soluble in cold water, forming a viscid, adhesive, tasteless solution, from which the pure soluble gummy principle, or *arabin*, is precipitated by alcohol and by basic acetate of lead, but not by the neutral acetate. Arabin is composed of $C_{24}H_{22}O_{22}$, and is consequently isomeric with crystallized cane-sugar.

Mucilage, so abundant in linseed, in the roots of the mallow, in *saleb*, the fleshy root of *Orchis mascula*, and in other plants, differs in some respects from the foregoing, although it agrees in the property of dissolving in cold water. The solution is less transparent than that of gum, and is precipitated by neutral acetate of lead. *Gum tragacanth* is chiefly composed of a kind of mucilage to which the name *bassorin* has been given, and which refuses to dissolve in water, merely softening and assuming a gelatinous aspect. It is dissolved by caustic alkali. *Cerasin* is the term given to the insoluble portion of the gum of the cherry-tree; it resembles bassorin. The composition of these various substances has been carefully examined by M. Schmidt, who finds that it closely agrees with that of

starch. Mucilage invariably contains hydrogen and oxygen in the proportion in which they form water, and when treated with acid, yields grape-sugar.

Pectin, or the jelly of fruits, is, in its physical properties, closely allied to the foregoing bodies. It may be extracted from various vegetable juices by precipitation by alcohol. It forms when moist a transparent jelly, soluble in water, and tasteless, which dries up to a translucent mass. It is to this substance that the firm consistence of currant and other fruit jellies is ascribed. According to M. Frémy, the composition of pectin is $C_{64}H_{48}O_{64}$. By ebullition with water and with dilute acids it is changed into two isomeric modifications, to which the names *parapectin* and *metapectin* have been given. In contact with bases, these three substances become converted into *pectic acid*, which, except that it possesses feeble acid properties, and is insoluble in water, resembles in the closest manner pectin itself. By long boiling with solution of caustic alkali, a farther change is produced, and a new acid, the *metapectic*, developed, which does not gelatinize. The salts of these two acids are incapable of crystallizing. Their composition is represented by the following formulæ:—



Much doubt still exists respecting the composition of the various bodies of the pectin-series: they do not appear, from the analyses yet made, to contain oxygen and hydrogen in equal equivalents, and consequently scarcely belong to the starch-group.

LIGNIN; CELLULOSE.—This substance constitutes the fundamental material of the structure of plants; it is employed in the organization of cells, and vessels of all kinds, and forms a large proportion of the solid parts of every vegetable. It must not be confounded with *lignaceous* or *woody tissue*, which is in reality cellulose, with other substances superadded, which cement the walls of the original membranous cells, and confer stiffness and inflexibility. Thus woody tissue, even when freed as much as possible from colouring matter and resin by repeated boiling with water and alcohol, yields on analysis a result indicating an excess of hydrogen above that required to form water with the oxygen, besides traces of nitrogen. Pure cellulose, on the other hand, is a ternary compound of carbon and the elements of water, closely allied in composition to starch, if not actually isomeric with that substance.*

The properties of lignin may be conveniently studied in fine linen and cotton, which are almost entirely composed of the body in question, the associated vegetable principles having been removed or destroyed

* Dumas, *Chimie appliquée aux Arts*, vi. 5.

by the variety of treatment to which the fibre has been subjected. Pure lignin is tasteless, insoluble in water and alcohol, and absolutely innutritious; it is not sensibly affected by boiling water, unless it happen to have been derived from a soft or imperfectly-developed portion of the plant, in which case it is disintegrated and rendered pulpy. Dilute acids and alkalis exert but little action on lignin, even at a boiling temperature; strong oil of vitriol converts it, in the cold, into a nearly colourless, adhesive substance, which dissolves in water, and presents the characters of dextrin. This curious and interesting experiment may be conveniently made by very slowly adding concentrated sulphuric acid to half its weight of lint, or linen cut into small shreds, taking care to avoid any rise of temperature, which would be attended with charring or blackening. The mixing is completed by trituration in a mortar, and the whole left to stand a few hours; after which it is rubbed up with water, and warmed, and filtered from a little insoluble matter. The solution may then be neutralized with chalk, and again filtered. The gummy liquid retains lime, partly in the state of sulphate, and partly in combination with a peculiar acid, composed of the elements of sulphuric or hyposulphuric acid, in union with those of the lignin, to which the name sulpholignic acid is given. If the liquid, previous to neutralization, be boiled during three or four hours, and the water replaced as it evaporates, the dextrin becomes entirely changed to grape-sugar. Linen rags may, by these means, be made to furnish more than their own weight of that substance.

Lignin is not coloured by iodine.

PRODUCTS ARISING FROM THE ALTERATION OF THE PRECEDING
SUBSTANCES BY CHEMICAL AGENTS.


ACTION OF NITRIC ACID.

OXALIC ACID, $C_2O_3.HO + 2HO$.—This important compound occurs ready formed in several plants, in combination with potassa as an acid salt, or with lime. It is now manufactured in large quantities as an article of commerce, by the action of nitric acid on sugar, starch, and dextrin. With the exception of gum and sugar of milk, which yield another product, all the substances comprehended in the saccharine and starch group furnish oxalic acid, as the chief and characteristic result of the long-continued action of moderately-strong nitric acid at an elevated temperature.

One part of sugar is gently heated in a retort with 5 parts of nitric acid of sp. gr. 1.42, diluted with twice its weight of water; copious red fumes are disengaged, and the oxidation of the sugar proceeds with violence and rapidity. When the action slackens, heat may be again applied to the vessel, and the liquid concentrated, by distilling off the superfluous nitric acid, until it deposits crystals on cooling. These are drained, redissolved in a small quantity of hot water, and the solution set aside to cool. The acid separates from a hot solution in colourless, transparent crystals derived from an oblique rhombic prism, which contain three equivalents of water, one of these being basic and inseparable, except by substitution; the other two may be expelled by a very gentle heat, the crystals crumbling down to a soft white powder, which may be sublimed in great measure without decomposition. The crystallized acid, on the contrary, is decomposed by a high temperature into carbonic and formic acids and carbonic oxide, without solid residue.

The crystals of oxalic acid dissolve in 8 parts of water at 60° (15°·5C), and in their own weight, or less, of hot water; they are also soluble in spirit. The aqueous solution has an intensely sour taste and most powerfully acid reaction, and is highly poisonous. The proper antidote is chalk or magnesia. Oxalic acid is decomposed by hot oil of vitriol into a mixture of carbonic oxide and carbonic acid; it is slowly converted into carbonic acid by nitric acid, whence arises a considerable loss in the process of manufacture. The bin-oxides of lead and manganese effect the same change, becoming reduced to protoxides, which combine with the unaltered acid.

Oxalic acid is formed from sugar by the replacement of the whole of its hydrogen by an equivalent quantity of oxygen.



The most important salts of oxalic acid are the following:—

NEUTRAL OXALATE OF POTASSA, $\text{KO}, \text{C}_2\text{O}_3 + \text{HO}$.—This is prepared by neutralizing oxalic acid by carbonate of potassa. It crystallizes in transparent rhombic prisms, which become opaque and anhydrous by heat, and dissolve in 3 parts of water. Oxalate of potassa is often produced when a variety of organic substances are cautiously heated with excess of caustic alkali.

BINOXALATE OF POTASSA, $\text{KO}, 2\text{C}_2\text{O}_3 + 3\text{HO}$.—Sometimes called *salt of sorrel*, from its occurrence in that plant. This, or the substance next to be mentioned, is found also in the *rumex* and *oxalis acetosella*, and in the garden rhubarb, associated with malic acid. It is easily prepared by dividing a solution of oxalic acid, in hot water, into two

equal portions, neutralizing one with carbonate of potassa, and adding the other; the salt crystallizes on cooling, in colourless rhombic prisms. The crystals have a sour taste, and require 40 parts of cold, and 6 of boiling water for solution.

QUADROXALATE OF POTASSA, $\text{KO}, 4\text{C}_2\text{O}_3 + 7\text{HO}$.—Prepared by a process similar in principle to that last described. The crystals are modified octahedra, and are less soluble than those of the binoxalate, which the salt in other respects resembles.

Oxalate of soda, $\text{NaO}, \text{C}_2\text{O}_3$, has but little solubility; a binoxalate exists.

OXALATE OF AMMONIA, $\text{NH}_4\text{O}, \text{C}_2\text{O}_3 + \text{HO}$.—This beautiful salt is prepared by neutralizing by carbonate of ammonia a hot solution of oxalic acid. It crystallizes in long, colourless, rhombic prisms, which effloresce in dry air from loss of water of crystallization. They are not very soluble in cold water, but freely dissolve by the aid of heat. Oxalate of ammonia is of great value in analytical chemistry, being employed to precipitate lime from its solutions. When oxalate of ammonia is heated in a retort, it is completely decomposed, yielding water, ammonia and carbonate of ammonia, cyanogen and carbonic acid gases, and a small quantity of a peculiar greyish-white sublimate. The latter bears the name of *oxamide*; it is a very remarkable body, and forms the type of a large class of substances containing the elements of an ammoniacal salt, *minus* those of water. Oxamide is composed of $\text{C}_2\text{H}_2\text{NO}_2$, i. e., $\text{NH}_4\text{O}, \text{C}_2\text{O}_3 - 2\text{HO}$, or the elements of 1 eq. amidogen, and 2 eq. carbonic oxide. It is insoluble in water and alcohol: when boiled with an alkali it furnishes an oxalate of the base, and ammonia, which is expelled; and when heated with an acid, it produces an ammoniacal salt. When treated with nitrous acid it likewise reproduces oxalic acid, pure nitrogen being evolved $\text{C}_2\text{H}_2\text{NO}_2 + \text{NO}_3 = \text{C}_2\text{O}_3, \text{HO} + \text{HO} + 2\text{N}$. Oxamide is the representative of a tolerably large class of bodies having very analogous chemical relations, and apparently a common constitution. Oxamide is obtained purer and more abundantly from oxalic ether; its preparation will be found described under the head of that substance. Oxalate of ammonia, when distilled with anhydrous phosphoric acid, loses four equivalents of water and yields a considerable quantity of cyanogen, $\text{NH}_4\text{O}, \text{C}_2\text{O}_3 - 4\text{HO} = \text{C}_2\text{N}$. There are, however, other compounds simultaneously produced.

The *binoxalate* of ammonia is still less soluble than the oxalate. When this salt is heated in an oil-bath to 450° (232°C), among other products an acid called the *oxamic* is generated, containing $\text{C}_4\text{H}_2\text{NO}_5, \text{HO}$, i. e., $\text{NH}_4\text{O}, \text{C}_2\text{O}_3$; $\text{HO}, \text{C}_2\text{O}_3 - 2\text{HO}$, and may be viewed as a compound of oxalic acid with oxamide. It forms soluble compounds with lime and baryta. When heated with alkalis it yields ammonia and an oxalate; hot oil of vitriol resolves it into carbonic oxide and carbonic acid; and water converts it, at a boiling temperature, into binoxalate of ammonia. Oxamic acid, too, is inte-

resting as the type of a very large class of similarly-constructed compounds.

OXALATE OF LIME, $\text{CaO}, \text{C}_2\text{O}_3 + 2\text{HO}$.—This compound is formed whenever oxalic acid or an oxalate is added to a soluble salt of lime; it falls as a white powder, which acquires density by boiling, and is but little soluble in dilute hydrochloric, and entirely insoluble in acetic acid. Nitric acid dissolves it easily. When dried at 212° (100°C) it retains an equivalent of water, which may be driven off by a rather higher temperature. Exposed to a red-heat in a close vessel, it is converted into carbonate of lime, with escape of carbonic oxide.

The oxalates of *baryta*, *zinc*, *manganese*, *protoxide of iron*, *copper*, *nickel*, and *cobalt*, are nearly insoluble in water; that of *magnesia* is sparingly soluble, and that of the *sesquioxide of iron* freely soluble. The double *oxalate of chromium and potassa*, made by dissolving in hot water 1 part bichromate of potassa, 2 parts binoxalate of potassa, and 2 parts crystallized oxalic acid, is one of the most beautiful salts known. The crystals appear black by reflected light from the intensity of their colour, which is pure deep blue; they are very soluble. The salt contains $3(\text{KO}, \text{C}_2\text{O}_3) + \text{Cr}_2\text{O}_3, 3\text{C}_2\text{O}_3 + 6\text{HO}$. A corresponding compound containing sesquioxide of iron has been formed; it crystallizes freely, and has a beautiful green colour.

SACCHARIC ACID, $\text{C}_6\text{H}_4\text{O}_7, \text{HO}$.—This substance was once thought to be identical with malic acid, which is not the case; it is formed by the action of dilute nitric acid on sugar, and is often produced in the preparation of oxalic acid, being, from its superior solubility, found in the mother-liquor from which the oxalic acid has crystallized. It may be made by heating together 1 part sugar, 2 parts nitric acid, and 10 parts water. When the reaction seems terminated, the acid liquid is diluted, neutralized with chalk, and the filtered liquid mixed with acetate of lead. The insoluble saccharate of lead is washed, and decomposed by sulphuretted hydrogen. The acid slowly crystallizes from a solution of syrupy consistence in long colourless needles; it has a sour taste, and forms soluble salts with lime and baryta. When mixed with nitrate of silver, it gives no precipitate, but, on the addition of ammonia, a white insoluble substance separates, which is reduced, by gently warming the whole, to metallic silver, the vessel being lined with a smooth and brilliant coating of the metal. Nitric acid converts the saccharic into oxalic acid.

XYLOIDIN and PYROXYLIN.—When starch is mixed with nitric acid of specific gravity 1.5, it is converted without disengagement of gas into a transparent, colourless jelly, which, when put into water, yields a white, curdy, insoluble substance: this is the new body *xyloidin*. When dry, it is white and tasteless, insoluble even in boiling water, but freely dissolved by dilute nitric acid, and the solution yields oxalic acid when boiled. Other substances belonging to the same class also yield xyloidin; paper dipped into the strongest nitric acid, quickly plunged into water, and afterwards dried, becomes

in great part so changed; it assumes the appearance of parchment, and acquires an extraordinary degree of combustibility.

If pure finely-divided ligneous matter, as cotton-wool, be steeped for a few minutes in a mixture of nitric acid of sp. gr. 1.5 and concentrated sulphuric acid, squeezed, thoroughly washed and dried by very gentle heat, it will be found to have increased in weight about 70 per cent., and to have become in the highest degree explosive, taking fire at a temperature not much above 300° ($148^{\circ}8\text{C}$), and burning without smoke or residue. This is *pyroxylin*, the *gun-cotton* of Professor Schoenbein. It differs from xyloidin in composition, in its mode of combustion, and in resisting the action of certain liquids, as ether containing a little alcohol, which dissolve xyloidin with facility. To a solution of this description the name *collodion* has been given; it is used in surgery.

Both xyloidin and pyroxylin appear to be substitution-compounds, in which the elements of hyponitric acid replace respectively 3 and 5 equivalents of hydrogen in starch and lignin. The analytical results are not very uniform, but the formulæ which best agree with them are, xyloidin $\text{C}_{24}\text{H}_{17}\text{N}_3\text{O}_{32}$, and pyroxylin $\text{C}_{24}\text{H}_{15}\text{N}_5\text{O}_{40}$.

An analogous compound is produced by the action of nitric acid upon mannite (vide p. 404). This substance may be crystallized from spirit, and contains $\text{C}_6\text{H}_4\text{N}_3\text{O}_{18}$; it may be viewed as mannite, in which three equivalents of hydrogen are replaced by hyponitric acid.

MUCIC ACID, $\text{C}_{12}\text{H}_8\text{O}_{14}, 2\text{HO}$.—Sugar of milk and gum, heated with nitric acid somewhat diluted, furnish, in addition to a small quantity of oxalic acid, a white and nearly insoluble substance called *mucic acid*. It may be easily prepared by heating together in a flask or retort 1 part of milk-sugar, or gum, 4 parts of nitric acid, and 1 of water; the mucic acid is afterwards collected upon a filter, washed and dried. It has a slightly-sour taste, reddens vegetable colours, and forms salts with bases. It requires for solution 66 parts of boiling water. Oil of vitriol dissolves it with production of a red colour. Mucic acid is decomposed by heat, yielding, among other products, a volatile acid, the *pyromucic*, which is soluble in water, and crystallizes in a form resembling that of benzoic acid. Pyromucic acid is monobasic; it contains $\text{C}_{10}\text{H}_3\text{O}_5, \text{HO}$.

SUBERIC ACID, $\text{C}_{16}\text{H}_{12}\text{O}_6, 2\text{HO}$, is formed by the action of nitric acid on the peculiar ligneous matter of cork, and also on certain fatty bodies; it much resembles mucic acid, but is more soluble in water. It is a dibasic acid. See farther on, Section VII., Oils and Fats.

The following bodies are closely allied in composition to oxalic acid:—

MELLITIC ACID, $\text{C}_4\text{O}_3, \text{HO}$.—This substance occurs, in combination with alumina, in a very rare mineral called *mellite* or *honey-stone*, found in deposits of imperfect coal, or *lignite*. It is soluble in water and alcohol, and is crystallizable, forming colourless needles. It combines with bases: the mellitates of the alkalis are soluble

and crystallizable; those of the earths and metals proper are mostly insoluble.

Mellitate of ammonia yields by distillation two curious compounds, *paramide* and *euchronic acid*. The former is a white, amorphous, insoluble substance, containing C_8HNO_4 , (i. e., bimellitate of ammonia—4 eq. of water), and convertible by boiling with water into bimellitate of ammonia. The latter forms colourless, sparingly soluble crystals, containing in the anhydrous state $C_{12}NO_6, 2HO$. In contact with metallic zinc and deoxidizing agents in general, euchronic acid yields a deep-blue insoluble substance called *euchrone*.

RHODIZONIC and CROCONIC ACIDS.—When potassium is heated in a stream of dry carbonic oxide gas, the latter is absorbed in large quantity, and a black porous substance generated, which, when put into water, evolves inflammable gas, and produces a deep-red solution containing the potassa-salt of a peculiar acid, the *rhodizonic*: by adding alcohol to the liquid, the rhodizonate of potassa is precipitated. This and the lead-salt are the only two compounds which have been fully examined; the acid itself cannot be isolated. Rhodizonate of potassa is composed of $C_7O_7, 3KO$; hence the acid would appear to be tribasic.

When solution of rhodizonate of potassa is boiled, it becomes orange yellow from decomposition of the acid, and is then found to contain oxalate of potassa, free potassa, and a salt of an acid to which the term *croconic* is applied. This acid can be isolated; it is yellow, easily crystallizable, and soluble both in water and alcohol. Crystallized croconic acid contains C_5O_4, HO .

THE FERMENTATION OF SUGAR AND ITS PRODUCTS.

The term fermentation is applied in chemistry to a peculiar metamorphosis of a complex organic substance, by a transposition of its elements under the agency of an external disturbing force, different from ordinary chemical attraction, and more resembling those obscure phenomena of contact already noticed, to which the expression *katalysis* is sometimes applied. The explanation which Liebig has suggested of the cause and nature of the fermentative change is a very happy one, although of necessity only hypothetical. It has long been known that one of the most indispensable conditions of that process is the presence in the fermenting liquid of certain azotized substances, called *ferments*, whose decomposition proceeds simultaneously with that of the body undergoing metamorphosis. They all belong to the class of albuminous principles, bodies which in a moist condition putrefy and decompose spontaneously. It is imagined that when these substances, in the act of undergoing change, are brought into

contact with neutral ternary compounds of slight stability, as sugar, the molecular disturbance of the body, already in a state of decomposition, may be, as it were, propagated to the other, and bring about destruction of the equilibrium of forces to which it owes its being. The complex body, under these circumstances, breaks up into simpler products, which possess greater permanence. Whatever may be the ultimate fate of this ingenious hypothesis, it is certain that decomposing azotized bodies not only do possess very energetic and extraordinary powers of exciting fermentation, but that the *kind* of fermentation set up is, in a great degree, dependent on the phase or stage of decomposition of the ferment.

ALCOHOL; VINOUS FERMENTATION.—A solution of pure sugar, in an open or close vessel, may be preserved unaltered for any length of time; but, if putrescible azotized matters be present, in the proper state of decay, the sugar is converted into alcohol, with escape of carbonic acid. Putrid blood, white of egg, or flour-paste, will effect this. By far the most potent alcoholic ferment is, however, to be found in the insoluble, yellowish, viscid matter deposited from beer in the act of fermentation, called *yeast*. If the sugar be dissolved in a large quantity of water, a due proportion of active yeast added, and the whole maintained at a temperature of 70° ($21^{\circ}\cdot1\text{C}$) or 80° ($26^{\circ}\cdot6\text{C}$), the change will go on with great rapidity. The gas disengaged will be found to be nearly pure carbonic acid; it is easily collected and examined, as the fermentation, once commenced, proceeds perfectly well in a close vessel, as a large bottle or flask, fitted with a cork and conducting-tube. When the effervescence is at an end, and the liquid has become clear, it will yield alcohol by distillation. Such is the origin of this important compound; it is a product of the metamorphosis of sugar, under the influence of a ferment.

The composition of alcohol is expressed by the formula $\text{C}_4\text{H}_6\text{O}_2$; it is produced by the breaking up of an equivalent of grape-sugar, $\text{C}_{24}\text{H}_{28}\text{O}_{28}$, into 4 eq. of alcohol, 8 of carbonic acid, and 4 of water. It is grape-sugar alone which yields alcohol, the ferment in the experiment above related first converting the cane-sugar into that substance. Milk-sugar may sometimes apparently be made to ferment, but a change into grape-sugar always really precedes the production of alcohol.

The spirit first obtained by distilling a fermented saccharine liquid is very weak, being diluted with a large quantity of water. By a second distillation, in which the first portions of the distilled liquid are collected apart, it may be greatly strengthened: the whole of the water cannot, however, be thus removed. The strongest rectified spirit of wine of commerce has a density of about $0\cdot835$, and yet contains 13 or 14 per cent. of water. Pure or *absolute* alcohol may be obtained from this by redistilling it with half its weight of fresh quick-lime. The lime is reduced to coarse powder, and put into a retort; the alcohol is added, and the whole mixed by agitation. The

neck of the retort is securely stopped with a cork, and the mixture left for several days. The alcohol is distilled off by the heat of a water-bath.

Pure alcohol is a colourless, limpid liquid, of pungent and agreeable taste and odour; its specific gravity at 60° ($15^{\circ}\cdot5\text{C}$) is $0\cdot7938$, and that of its vapour $1\cdot613$. It is very inflammable, burning with a pale-bluish flame, free from smoke: it has never been frozen. Alcohol boils at 173° ($78^{\circ}\cdot4\text{C}$) when in the anhydrous condition; in a diluted state, the boiling-point is higher, being progressively raised by each addition of water. In the act of dilution a contraction of volume occurs, and the temperature of the mixture rises many degrees; this takes place not only with pure alcohol, but with rectified spirit. It is miscible with water in all proportions, and, indeed, has a great attraction for the latter, absorbing its vapour from the air, and abstracting the moisture from membranes and other similar substances immersed in it. The solvent powers of alcohol are very extensive; it dissolves a great number of saline compounds, and likewise a considerable proportion of potassa. With many of these substances it forms definite compounds. The substance which is produced by potassa contains $\text{C}_4\text{H}_5\text{O}, \text{KO}$; it may be likewise formed by acting with potassium upon anhydrous alcohol, when hydrogen is evolved. Alcohol dissolves, moreover, many organic substances, as the vegeto-alkalis, resins, essential oils, and various other bodies; hence its great use in chemical investigations and in several of the arts.

The strength of commercial spirit is inferred from its density, when free from sugar and other substances added subsequent to distillation; a table exhibiting the proportions of real alcohol and water in spirits of different densities will be found at the end of the volume. The excise *proof spirit* has a sp. gr. of $0\cdot9198$ at 60° ($15^{\circ}\cdot5\text{C}$), and contains $49\frac{1}{4}$ per cent. by weight of real alcohol.

Wine, beer, &c., owe their intoxicating properties to the alcohol they contain, the quantity of which varies very much. Port and sherry, and some other strong wines, contain, according to Mr. Brande, from 19 to 25 per cent. of alcohol, while in the lighter wines of France and Germany it sometimes falls as low as 12 per cent. Strong ale contains about 10 per cent.; ordinary spirits, as brandy, gin, whisky, 40 to 50 per cent., or occasionally more. These latter owe their characteristic flavours to certain essential oils, present in very small quantity, either generated in the act of fermentation or purposely added.

In making wine, the expressed juice of the grape is simply set aside in large vats, where it undergoes spontaneously the necessary change. The vegetable albumin of the juice absorbs oxygen from the air, runs into decomposition, and in that state becomes a ferment to the sugar, which is gradually converted into alcohol. If the sugar be in excess, and the azotized matter deficient, the resulting wine remains sweet; but if, on the other hand, the proportion of sugar be

small, and that of albumin large, a *dry* wine is produced. When the fermentation stops, and the liquor becomes clear, it is drawn off from the lees, and transferred to casks, to ripen and improve.

The colour of red wine is derived from the skins of the grapes, which in such cases are left in the fermenting liquid. Effervescent wines, as champagne, are bottled before the fermentation is complete; the carbonic acid is disengaged under pressure, and retained in solution in the liquid. The process requires much delicate management.

During the fermentation of the grape-juice, or *must*, a crystalline, stony matter, called *argol*, is deposited. This consists chiefly of acid tartrate of potassa, with a little tartrate of lime and colouring matter, and is the source of all the tartaric acid met with in commerce. The salt in question exists in the juice in considerable quantity; it is but sparingly soluble in water, but still less so in dilute alcohol; hence, as the fermentation proceeds, and the quantity of spirit increases, it is slowly deposited. The acid of the juice is thus removed as the sugar disappears. It is this circumstance which renders grape-juice alone fit for making good wine: when that of gooseberries or currants is employed as a substitute, the malic and citric acids which these fruits contain cannot be thus withdrawn. There is, then, no other resource but to add sugar in sufficient quantity to mask and conceal the natural acidity of the liquor. Such wines are necessarily acescent, prone to a second fermentation, and, to many persons at least, very unwholesome.

Beer is a well-known liquor, of great antiquity, prepared from germinated grain, generally barley, and is used in countries where the vine does not flourish. The operation of *malting* is performed by steeping the barley in water until the grains become swollen and soft, then piling it in a heap or *couch*, to favour the elevation of temperature caused by the absorption of oxygen from the air, and afterwards spreading it upon a floor, and turning it over from time to time, to prevent unequal heating. When germination has proceeded far enough, the vitality of the seed is destroyed by kiln-drying. During this process, the curious substance already referred to, diastase, is produced, and a portion of the starch of the grain converted into sugar, and rendered soluble.

In brewing, the crushed malt is infused in water at about 170° (76° 6C), and the mixture left to stand during the space of two hours or more. The easily soluble diastase has thus an opportunity of acting upon the unaltered starch of the grain, and changing it into dextrin and sugar. The clear liquor, or *wort*, strained from the exhausted malt, is next pumped up into a copper boiler, and boiled with the requisite quantity of hops, for communicating a pleasant bitter flavour, and conferring on the beer the property of keeping without injury. The flowers of the hop contain a bitter, resinous principle, called *lupulin*, and an essential oil, both of which are useful.

When the wort has been sufficiently boiled, it is drawn from the copper, and cooled, as rapidly as possible, to near the ordinary temperature of the air, in order to avoid an irregular acid fermentation, to which it would otherwise be liable. It is then transferred to the fermenting vessels, which in large breweries are of great capacity, and mixed with a quantity of yeast, the product of a preceding operation, by which the change is speedily induced. This is the most critical part of the whole operation, and one in which the skill and judgment of the brewer are most called into play. The process is in some measure under control by attention to the temperature of the liquid, and the extent to which the change has been carried is easily known by the diminished density, or *attenuation*, of the wort. The fermentation is never suffered to run its full course, but is always stopped at a particular point, by separating the yeast, and drawing off the beer into casks. A slow and almost insensible fermentation succeeds, which in time renders the beer stronger and less sweet than when new, and charges it with carbonic acid.

Highly-coloured beer is made by adding to the malt a small quantity of strongly-dried or charred malt, the sugar of which has been changed to caramel: porter and stout are so prepared.

The yeast of beer is a very remarkable substance, and has excited much attention. To the naked eye it is a greyish-yellow soft solid, nearly insoluble in water, and dries up to a pale-brownish mass, which readily putrefies when moistened, and becomes offensive. Under the microscope it exhibits a kind of organized appearance, being made up of little transparent globules, which sometimes cohere in clusters or strings, like some of the lowest members of the vegetable kingdom. Whatever may be the real nature of the substance, no doubt can exist that it is formed from the soluble azotized portion of the grain during the fermentive process. No yeast is ever produced in liquids free from azotized matter; that added for the purpose of exciting fermentation in pure sugar is destroyed, and rendered inert thereby. When yeast is deprived, by straining and strong pressure, of as much water as possible, it may be kept in a cool place, with unaltered properties, for a long time; otherwise it speedily spoils.

The distiller, who prepares spirits from grain, makes his wort, or *wash*, much in the same manner as the brewer; he uses, however, with the malt a large quantity of raw grain, the starch of which suffers conversion into sugar by the diastase of the malt, which is sufficient for his purpose. He does not boil his infusion with hops, but proceeds at once to the fermentation, which he pushes as far as possible by large and repeated doses of yeast. Alcohol is manufactured in many cases from potatoes; the potatoes are ground to pulp, mixed with hot water and a little malt, to furnish diastase, made to ferment, and then the fluid portion distilled. The potato-spirit is contaminated by a very offensive volatile oil, again to be mentioned: the crude product from corn contains a substance of a similar kind.

The business of the rectifier consists in removing or modifying these volatile oils, and in replacing them by others of a more agreeable character.

In making bread, the vinous fermentation plays an important part; the yeast added to the dough converts the small portion of sugar the meal naturally contains into alcohol and carbonic acid. The gas thus disengaged forces the tough and adhesive materials into bubbles, which are still farther expanded by the heat of the oven, which at the same time dissipates the alcohol; hence the light and spongy texture of all good bread. Sometimes carbonate of ammonia is employed with the same view, being completely volatilized by the high temperature of the oven. Bread is now sometimes made by mixing a little hydrochloric acid and carbonate of soda in the dough; if proper proportions be taken, and the whole thoroughly mixed, the operation appears to be very successful. The use of *leaven* is one of great antiquity: this is merely dough in a state of incipient putrefaction. When mixed with a large quantity of fresh dough, it excites in the latter the alcoholic fermentation, in the same manner as yeast, but less perfectly; it is apt to communicate a disagreeable sour taste and odour.

LACTIC ACID; LACTIC ACID FERMENTATION; BUTYRIC ACID FERMENTATION.—Azotized albuminous substances, which in an advanced state of putrefactive change act as alcohol-ferments, often possess, at certain periods of decay, the property of inducing an acid fermentation in sugar, the consequence of which is the conversion of that substance into *lactic acid*. Thus, the azotized matter of malt, when suffered to putrefy in water for a few days, acquires the power of acidifying the sugar which accompanies it, while in a more advanced state of decomposition it converts, under similar circumstances, the sugar into alcohol. The gluten of grain behaves in the same manner: wheat flour, made into a paste with water, and left four or five days in a warm situation, becomes a true lactic acid ferment; if left a day or two longer, it changes its character, and then acts like common yeast. Moist animal membranes, in a slightly-decaying condition, often act energetically in developing lactic acid.

Cane-sugar, probably by previously becoming grape-sugar, and the sugar of milk, both yield lactic acid, the latter, however, most readily, the grape-sugar having a strong tendency towards the alcoholic change. A good method of preparing lactic acid is the following. An additional quantity of milk-sugar is dissolved in ordinary milk, which is then set aside in a warm place, until it becomes sour and coagulated. The casein of the milk absorbs oxygen from the air, runs into putrefaction, and acidifies a portion of the sugar. The lactic acid formed, after a time coagulates and renders insoluble the casein, and the production of that acid ceases. By carefully neutralizing, however, the free acid by carbonate of soda, the casein becomes soluble, and resuming its activity, changes a fresh quantity of sugar into lactic acid,

which may be also neutralized, and by a sufficient number of repetitions of this process all the sugar of milk present may, in time, be acidified. When this has taken place, the liquid is boiled, filtered, and evaporated to dryness in a water-bath. The residue is treated with hot alcohol, which dissolves out the lactate of soda. The alcoholic solution may then be decomposed by the cautious addition of sulphuric acid, which precipitates sulphate of soda, insoluble in spirit. The free acid may, if needful, be neutralized with lime, and the resulting salt purified by re-crystallization and the use of animal charcoal, after which it may be decomposed by oxalic acid.

The following process will be found more economical on a large scale:—A mixture is made of two gallons of milk, which may be stale or skimmed milk, six pounds of raw sugar, twelve pints of water, eight ounces of putrid cheese, and four pounds of chalk, which should be mixed up to a creamy consistence with some of the liquid. This mixture is exposed in a loosely-covered jar to a temperature of about 86° (30°C), with occasional stirring. At the end of two or three weeks it will be found converted into a semi-solid mass of lactate of lime, which may be drained, pressed, and purified by re-crystallization from water.

The lactate of lime may be decomposed by the necessary quantity of pure oxalic acid, the filtered liquor neutralized with carbonate of zinc, and, after a second filtration, evaporated until the zinc-salt crystallizes out on cooling. The latter may, lastly, be re-dissolved in water, and decomposed by sulphuretted hydrogen, in order to obtain the free acid.

If in the first part of the process the solid lactate of lime be not removed at the proper period from the fermenting liquid, it will gradually re-dissolve and disappear. On examination the liquid will then be found to consist chiefly of a solution of *butyrate of lime*.

This second stage of the process, to which the name of *butyric acid fermentation* has been given, is attended with an evolution of hydrogen and carbonic acid. It will be mentioned more in detail in the Section on Oils and Fats.

Lactic acid may be extracted from a great variety of liquids containing decomposing organic matter, as *sauerkraut*, a preparation of white cabbage; the sour liquor of the starch-maker, &c. It has been supposed to exist in the blood, urine, and other animal fluids. Recent researches have, however, failed to detect it in either blood or urine, although it has been shown by Liebig to exist in considerable quantity in the juice of flesh or muscle.

Lactic acid has been lately produced artificially in a most remarkable manner by the action of nitrous acid upon *alanine*. (See the Section on Organic Bases.)

Solution of lactic acid may be concentrated in the vacuum of the air-pump, over a surface of oil of vitriol, until it acquires the aspect of a colourless, syrupy liquid, of sp. gr. 1.215. It has an intensely

sour taste and acid reaction; it is hygroscopic, and very soluble in water, alcohol, and ether. It forms soluble salts with all the metallic oxides. The syrupy acid contains $C_6H_5O_5 + HO$, or $C_{12}H_{10}O_{10} + 2HO$, the water being basic, and susceptible of replacement by a metallic oxide.

When syrupy lactic acid is heated in a retort to 266° ($130^\circ C$), water containing a little lactic acid distils over, and the residue on cooling forms a yellowish solid fusible mass, very bitter, and nearly insoluble in water. This is anhydrous lactic acid, $C_6H_5O_5$. Long-continued boiling with water converts it into ordinary lactic acid. When this substance is farther heated it decomposes, yielding numerous products. One of these is *lactide*, formerly erroneously called anhydrous lactic acid, a volatile substance, crystallizing in brilliant colourless rhombic plates, which, when put into water, slowly dissolve, with production of common lactic acid. Lactide contains $C_6H_4O_4$; it combines with ammonia, forming *lactamide*, $C_6H_7NO_4$, a colourless, crystallizable, soluble substance, resembling in its chemical relations oxamide. Another product of the action of heat on lactic acid is *lactone*, a colourless volatile liquid, boiling at 198° ($92^\circ \cdot 2 C$). Acetone is also formed, and carbonic oxide and carbonic acid are disengaged.

A salt of lactic acid, gently heated with five or six parts of oil of vitriol, yields an enormous quantity of perfectly pure carbonic oxide gas.

The most important and characteristic of the lactates are those of lime and the oxide of zinc.

LACTATE OF LIME, $CaO, C_6H_5O_5 + 5HO$, exists ready-formed, to a small extent, in *Nux vomica*. When pure, it crystallizes in tufts of minute white needles grouped in concentric layers. It dissolves in 10 parts of cold, and indefinitely in boiling water, melting in its water of crystallization at that temperature.

LACTATE OF ZINC, $ZnO, C_6H_5O_5 + 3HO$, is deposited from a hot solution in small brilliant 4-sided prismatic crystals, which require for solution 58 parts of cold and 6 of boiling water.

LACTATE OF PROTOXIDE OF IRON, $FeO, C_6H_5O_5 + 3HO$, is now used in medicine. It is prepared by adding alcohol to a mixture of lactate of ammonia and protochloride of iron, when the salt is precipitated in the form of small yellowish needles.

When the expressed juice of the beet is exposed to a temperature of 90° ($32^\circ \cdot 9 C$) or 100° ($37^\circ \cdot 7 C$) for a considerable time, the sugar it contains suffers a peculiar kind of fermentation, to which the term *viscous* has been applied. Gases are evolved which contain hydrogen, and when the change appears complete, and the products come to be examined, the sugar is found to have disappeared. Mere traces of

alcohol are produced, but, in place of that substance, a quantity of lactic acid, mannite, and a mucilaginous substance resembling gum-Arabic, and said to be identical with gum in composition.

Pure sugar can be converted into this substance; by boiling yeast or the gluten of wheat in water, dissolving sugar in the filtered solution, and exposing it to a tolerably high temperature, the viscous fermentation is set up, and a large quantity of the gummy principle generated. A little gas is at the same time disengaged, which is a mixture of carbonic acid and hydrogen.

PRODUCTS OF THE ACTION OF ACIDS ON ALCOHOL.

ETHER; OXIDE OF ETHYL.—When equal weights of rectified spirit and oil of vitriol are mixed in a retort, the latter connected with a good condensing arrangement, and the liquid heated to ebullition, a colourless and highly-volatile liquid, long known under the name of *ether*, or *sulphuric ether*, distils over. The process must be stopped as soon as the contents of the retort blacken and froth, otherwise the product will be contaminated with other substances, which then make their appearance. The ether obtained may be mixed with a little caustic potassa, and re-distilled by a very gentle heat.

Pure ether is a colourless, transparent, fragrant liquid, very thin and mobile. Its sp. gr. at 60° ($15^{\circ}\cdot5\text{C}$) is about 0.720; it boils at 96° ($35^{\circ}\cdot5\text{C}$) under the pressure of the atmosphere, and bears without freezing the severest cold. When dropped on the hand it occasions a sharp sensation of cold, from its rapid volatilization. Ether is very combustible; it burns with a white flame, generating water and carbonic acid. Although the substance itself is one of the lightest of liquids, its vapour is very heavy, having a density of 2.586. Mixed with oxygen gas, and fired by the electric spark, or otherwise, it explodes with the utmost violence. Preserved in an imperfectly-stopped vessel, ether absorbs oxygen, and becomes acid from the production of acetic acid: this attraction for oxygen is increased by elevation of temperature. It is decomposed by transmission through a red-hot tube into olefiant gas, light carbonetted hydrogen, and a substance yet to be described, *aldehyde*.

Ether is miscible with alcohol in all proportions, but not with water; it dissolves to a small extent in that liquid, 10 parts of water taking up 1 part, or thereabouts, of ether. It may be separated from alcohol, provided the quantity of the latter be not excessive, by an addition of water, and in this manner samples of commercial ether may be conveniently examined. Ether is a solvent for oily and fatty

substances generally, and phosphorus to a small extent, a few saline compounds and some organic principles, but its powers in this respect are much more limited than those of alcohol or water.

Ether was the first of a great number of analogous substances in which the property of producing temporary insensibility to pain was recognized. In surgical operations, the use of ether is now superseded by that of chloroform.

Ether is found by analysis to contain C_4H_5O ; it, therefore, differs from alcohol, $C_4H_6O_2$, by the elements of water. Alcohol is often regarded as the hydrate of ether; but as ether cannot be made to combine with water directly, and as alcohol cannot be converted into ether by the abstraction of water by the aid of substances known to possess a strong affinity for that body, such a view was always looked upon as hypothetical. Recent experiments have, in fact, shown that a very different relation exists between alcohol and ether. We shall return to these researches, when we consider the theory of the production of ether, which will be discussed partly in connection with the history of sulphovinic acid, and partly with that of the methyl-compounds.

COMPOUND ETHERS; ETHYL-THEORY; ETHYL.—The so-called compound ethers constitute a very large and important class of substances derived from alcohol, and containing either the elements of ether, in combination with those of an oxygen-acid, inorganic or organic, or the elements of olefiant gas in union with those of a hydrogen-acid. The relations of these compounds to alcohol and the acids are most simply and clearly illustrated by comparing them with ordinary salts, in which the metal is replaced by a salt-base termed *ethyl*, containing C_4H_5 . This substance forms haloid-salts by combining with chlorine, iodine, bromine, &c., and its oxide, identical or isomeric with common ether, with oxygen-acids, like basic metallic oxides in general. A body containing carbon and hydrogen in the proportions indicated by the formula C_4H_5 , has been lately obtained by Dr. Fraukland, from one of the members of this group of compounds, and described under the name of *ethyl*. It is formed by exposing iodide of ethyl, in sealed tubes, to the action of metallic zinc, at a temperature of 320° ($160^\circ C$).^{*} In this reaction, the iodine of the iodide of ethyl, C_4H_5I combines with the zinc, and ethyl is set free. On opening the sealed tubes, and allowing the gas, which is ethyl mixed with several secondary products (especially olefiant gas), to pass into a freezing mixture, the temperature of which is kept below -9° ($-23^\circ C$), the ethyl condenses to a colourless mobile liquid. It is not attacked by concentrated sulphuric and nitric acids. Chlorine acts upon it under the influence of light, but not in the dark. Hitherto no compound ether has been reproduced from ethyl. The ethyl-theory, proposed by Liebig long before the separation of ethyl itself, will be found very useful as an aid to the memory; it must not, how-

^{*} See also, zinc-ethyl, page 445.

ever, be forgotten that the compound ethers are distinguished by important characters from real and undoubted salts.

Table of Ethyl-Compounds.

Ethyl, symbol Ae	C_4H_5
Oxide of ethyl; ether	C_4H_5O
Hydrate of the oxide; alcohol	C_4H_5O, HO
Chloride of ethyl	C_4H_5Cl
Bromide of ethyl	C_4H_5Br
Iodide of ethyl	C_4H_5I
Cyanide of ethyl	C_4H_5Cy
Nitrate of oxide of ethyl	C_4H_5O, NO_3
Nitrite of oxide of ethyl	C_4H_5O, NO_2
Oxalate of oxide of ethyl	C_4H_5O, C_2O_3
Hydride of ethyl	C_4H_5H
Zinc-ethyl	C_4H_5Zn
&c. &c.	

The ethers of many of the acids may be formed by the direct action of the latter upon alcohol at a high temperature, the elements of water being displaced by those of the acid: this is chiefly conspicuous with the volatile acids. A more ready general method of forming them, however, is to distil a mixture of alcohol, sulphuric acid, and a salt of the acid the ether of which is required. The fatty acids, which in general cannot be distilled without more or less decomposition, yield their ethers with great facility by the action of hydrochloric acid gas upon an alcoholic solution of the acid.

The compound ethers are mostly volatile aromatic liquids, in a few cases crystallizable solids, without action on vegetable colours, sparingly soluble in water, but dissolved in all proportions by alcohol and ether. They are not acted upon in the cold by alkaline carbonates, but suffer decomposition with more or less difficulty when heated with aqueous solutions of caustic alkali, a salt of the acid of the ether being usually generated, and alcohol formed and set free. An alcoholic solution of hydrate of potassa or soda is more active in this respect. The same kind of decomposition is often brought about by the prolonged contact of boiling water.

CHLORIDE OF ETHYL; LIGHT HYDROCHLORIC ETHER; $AeCl$.—Rectified spirit of wine is saturated with dry hydrochloric acid gas, and the product distilled with very gentle heat; or a mixture of 3 parts oil of vitriol and 2 of alcohol is poured upon 4 parts of dry common salt in a retort, and heat applied; in either case the vapour of the hydrochloric ether should be conducted through a little tepid water in a wash-bottle, and then conveyed into a small receiver surrounded by ice and salt. It is purified from adhering water by contact with a few fragments of fused chloride of calcium. Hydro-


chloric ether is a thin, colourless, and excessively volatile liquid, of a penetrating, aromatic, and somewhat alliaceous odour. At the freezing point of water, its sp. gr. is 0·921, and it boils at 50° ($12^{\circ}\cdot5\text{C}$); it is soluble in 10 parts of water, is not decomposed by solution of nitrate of silver, but is quickly resolved into chloride of potassium and alcohol by a hot solution of caustic potassa.

BROMIDE OF ETHYL; HYDROBROMIC ETHER; AeBr.—This is prepared by distilling a mixture of 8 parts bromine, 1 part phosphorus, and 32 parts alcohol. The phosphorus is converted into phosphorous acid by the oxygen of the alcohol, when the ethyl combines with the bromine; 3 equivalents of alcohol, 3 equivalents of bromine, and 1 equivalent of phosphorus, yield 3 equivalents of bromide of ethyl, 3 equivalents of water, and 1 equivalent of phosphorous acid. It is a very volatile liquid, boiling at 106° (41°C), of penetrating taste and smell, and superior in density to water.

IODIDE OF ETHYL; HYDRIODIC ETHER; AeI.—Obtained by gradually mixing, with precaution, 1 part of phosphorus, 5 parts of alcohol, and 10 parts of iodine (1 eq. of phosphorus, 3 eq. of alcohol, and 3 eq. of iodine), and distilling. The reaction is analogous to that described in the case of the bromide. Iodide of ethyl is a colourless liquid, of penetrating ethereal odour, having a density of 1·92, and boiling at 158° (70°C). It becomes red by contact with air from a commencement of decomposition. This substance has become highly important as a source of ethyl, and from its remarkable deportment with ammonia, which will be discussed in the Section on Organic Bases.

SULPHIDE OF ETHYL; AeS.—Formed by the action of chloride of ethyl upon a solution of the protosulphide of potassium. It is colourless, has a disagreeable garlic odour, and boils at 180° (82°C).

CYANIDE OF ETHYL, AcCy.—This is produced when a mixture of sulphovinate of potassa and cyanide of potassium, both in a dry state, is slowly heated. It is colourless; when perfectly pure it has a powerful, not disagreeable odour, and a sp. gr. of 0·788. It boils at $190^{\circ}\cdot4$ (88°C). This substance has lately been studied by Drs. Kolbe and Frankland. They have found that cyanide of ethyl differs from the ordinary ethers in its deportment with the alkalis. Instead of yielding cyanide of potassium and alcohol, it is converted into ammonia and propionic acid, $\text{C}_6\text{H}_5\text{O}_3\cdot\text{HO}$, a peculiar acid closely allied to acetic acid, and which will be noticed more in detail under the head of acetone. Cyanide of ethyl, in this reaction, absorbs 4 equivalents of water:—



(See also cyanide of methyl.)—When acted upon by potassium, cyanide

of ethyl furnishes a gas, the nature of which is not definitely settled; the residue contains cyanide of potassium and an organic alkali *cyanethine*, which contains $C_{18}H_{15}N_3$, and is formed by the coalescence of three equivalents of the cyanide.

SULPHITE OF OXIDE OF ETHYL; SULPHUROUS ETHER; AeO,SO_2 .—This substance was obtained by adding absolute alcohol in excess to subchloride of sulphur. Hydrochloric acid is evolved, and sulphur deposited, while the sulphite of ethyl distils as a limpid strongly smelling liquid, of sp. gr. 1.085, boiling at 338° ($170^\circ C$); it is slowly decomposed by water.

SULPHATE OF OXIDE OF ETHYL; SULPHURIC ETHER; AeO,SO_3 .—This substance has been only recently obtained. It is formed by passing the vapour of anhydrous sulphuric acid into perfectly anhydrous ether. A syrupy liquid is produced, which is shaken with 4 vols. of water, and 1 vol. of ether, when two layers are formed; the lower contains sulphovinic acid (see this substance, page 432) and various other compounds, while the upper layer consists of an ethereal solution of sulphate of ethyl. At a gentle heat the ether is volatilized, and the sulphate of ethyl remains as a colourless liquid. It cannot be distilled without decomposition.

PHOSPHATE OF OXIDE OF ETHYL; PHOSPHORIC ETHER.—See phosphovinic acid.

NITRATE OF OXIDE OF ETHYL; NITRIC ETHER; AeO,NO_3 .—The nitrate likewise has only recently been obtained; it is prepared by cautiously distilling a mixture of equal weights of alcohol and moderately strong nitric acid, to which a small quantity of nitrate of urea has been added. The action of nitric acid upon alcohol is peculiar: the facility with which that acid is deoxidized by combustible bodies, leads, under ordinary circumstances, to the production of nitrous acid on the one hand, and an oxidized product of alcohol on the other, a *nitrite* of the oxide of ethyl being generated instead of a nitrate. M. Millon has shown that the addition of urea, from reasons to be explained when this compound will be described, entirely prevents the formation of that substance, and at the same time preserves the alcohol from oxidation by undergoing that change in its place, the sole liquid product being the new ether. The experiment is most safely conducted on a small scale, and the distillation must be stopped when seven-eighths of the whole have passed over: a little water added to the distilled product separates the nitric ether. Nitric ether has a density of 1.112; it is insoluble in water, has an agreeable sweet taste and odour, and is not decomposed by an aqueous solution of caustic potassa, although that substance dissolved in alcohol attacks it even in the cold, with production of nitrate of potassa. Its vapour is apt to explode when strongly heated.

NITRITE OF OXIDE OF ETHYL; NITROUS ETHER; AeO,NO_2 .—Pure nitrous ether can only be obtained by the direct action of the acid itself upon alcohol. 1 part of potato-starch, and 10 parts of

nitric acid, are gently heated in a capacious retort or flask, and the vapour of nitrous acid thereby evolved conducted into alcohol mixed with half its weight of water, contained in a two-necked bottle, which is to be plunged into cold water, and connected with a good condensing arrangement. All elevation of temperature must be carefully avoided. The product of this operation is a pale-yellow volatile liquid, possessing an exceedingly agreeable odour of apples; it boils at 62° (16°C), and has a density of 0.947. It is decomposed by potassa, without darkening, into the nitrite of the base, and alcohol.

Nitrous ether, but contaminated with aldehyde, may be prepared by the following simple method:—Into a tall cylindrical bottle or jar are to be introduced successively 9 parts of alcohol of sp. gr. 0.830, 4 parts of water, and 8 parts of strong fuming nitric acid; the two latter are added by means of a long funnel with very narrow orifice, reaching to the bottom of the bottle, so that the contents may form three distinct strata, which slowly mix from the solution of the liquids in each other. The bottle is then loosely stopped, and left two or three days in a cool place, after which it is found to contain two layers of liquids, of which the uppermost is the ether. It is purified by rectification. A somewhat similar product may be obtained by carefully distilling a mixture of 3 parts rectified spirit and 2 of nitric acid of 1.28 sp. gr.: the fire must be withdrawn as soon as the liquid boils.

The *sweet spirits of nitre* of pharmacy, prepared by distilling three pounds of alcohol with four ounces of nitric acid, is a solution of nitrous ether, aldehyde, and perhaps other substances, in spirit of wine.

CARBONATE OF OXIDE OF ETHYL; CARBONIC ETHER; AeO, CO_2 .—Fragments of potassium or sodium are dropped into oxalic ether as long as gas is disengaged; the brown pasty product is then mixed with water and distilled. The carbonic ether is found floating upon the surface of the water of the receiver as a colourless, limpid liquid of aromatic odour and burning taste. It boils at 259° (126°C), and is decomposed by an alcoholic solution of potassa into carbonate of that base and alcohol. The reaction which gives rise to this substance is unexplained.

SILICIC AND BORACIC ETHERS.—A number of these compounds appears to exist, containing different proportions of the acids. *Silicic ether*, containing $3\text{AeO}, \text{SiO}_3$, was obtained by M. Ebelmen by the action of anhydrous alcohol upon chloride of silicium. It is a colourless, limpid, aromatic liquid, of sp. gr. 0.933, boiling at 329° (165°C), and decomposed by water with production of silicic acid and alcohol. In contact with moist air it is gradually resolved into translucent hydrate of silica, which becomes in the end hard enough to scratch glass. By substituting ordinary spirit for absolute alcohol, other compounds containing a larger portion of silicic acid are obtained.

Boracic ether was procured by a similar process, substituting the chloride of boron for chloride of silicium. It formed a thin, limpid

liquid of agreeable odour, having the sp. gr. of 0.885, and boiling at 246° (118°C). It is decomposed by water. Its alcoholic solution burns with a fine green flame, throwing off a thick smoke of boracic acid. It contains $3\text{AeO}, \text{BoO}_3$. A second boracic ether in the form of a solid glassy fusible substance, containing $\text{AeO}, 2\text{BoO}_3$, was formed by the action of fused boracic acid upon absolute alcohol. It is volatile in the vapour of alcohol only, and is decomposed by water.

Of the ethers of the organic acids, the following are the most important:—

OXALATE OF THE OXIDE OF ETHYL; OXALIC ETHER; $\text{AeO}, \text{C}_2\text{O}_3$.
—This compound is most easily obtained by distilling together 4 parts binoxalate of potassa, 5 parts oil of vitriol, and four parts strong alcohol. The distillation may be pushed nearly to dryness, and the receiver kept *warm* to dissipate any ordinary ether that may be formed. The product is mixed with water, by which the oxalic ether is separated from the undecomposed spirit; it is repeatedly washed to remove adhering acid, and re-distilled in a small retort, the first portions being received apart and rejected. Another very simple process consists in digesting equal parts of alcohol and dehydrated oxalic acid, in a flask furnished with a long glass tube, in which the volatilized spirit may condense. After 6 or 8 hours' digestion, the mixture generally contains only traces of oxalic acid which is not etherified.

Pure oxalic ether is a colourless, oily liquid, of pleasant aromatic odour, and 1.09 sp. gr. It boils at 363° ($183^{\circ}\cdot 8\text{C}$), is but little soluble in water, and is readily decomposed by caustic alkalis into an oxalate and alcohol. With solution of ammonia in excess, it yields *oxamide* and alcohol. $\text{C}_4\text{H}_5\text{O}, \text{C}_2\text{O}_3 + \text{NH}_3 = \text{C}_2\text{O}_2, \text{NH}_2 + \text{C}_4\text{H}_5\text{O}, \text{HO}$. This is the best process for preparing oxamide, which is obtained perfectly white and pure. (See page 412). When dry gaseous ammonia is conducted into a vessel containing oxalic ether, the gas is rapidly absorbed, and a white solid substance produced, which is soluble in hot alcohol, and separates, on cooling, in colourless, transparent, scaly crystals. They dissolve in water, and are both fusible and volatile. The name *oxamethane* is given to this body; it consists of $\text{C}_6\text{H}_7\text{NO}_6 = \text{C}_4\text{H}_5\text{O}, \text{C}_4\text{H}_2\text{NO}_5$, i. e., the ether of oxamic acid (see page 412). The same substance is formed when ammonia in small quantity is added to a solution of oxalic ether in alcohol.

When oxalic ether is treated with dry chlorine in excess in the sunshine, a white, colourless, crystalline, fusible body is produced, insoluble in water, and instantly decomposed by alcohol. It contains $\text{C}_6\text{Cl}_5\text{O}_4$, or oxalic ether in which the whole of the hydrogen is replaced by chlorine.

ACETATE OF OXIDE OF ETHYL; ACETIC ETHER; $\text{AeO}, \text{C}_4\text{H}_3\text{O}_3$.—Acetic ether is conveniently made by heating together in a retort 3 parts of acetate of potassa, 3 parts of strong alcohol, and 2 of oil of vitriol. The distilled product is mixed with water, to separate the alcohol, digested first with a little chalk, and afterwards with fused

chloride of calcium, and, lastly, rectified. The pure ether is an exceedingly fragrant limpid liquid; it has a density of 0.890, and boils at 165° (73°C). Alkalis decompose it in the usual manner. When treated with ammonia, it yields *acetamide*, a crystalline substance soluble in water and alcohol, which contains $\text{C}_4\text{H}_5\text{NO}_2 = \text{C}_4\text{H}_3\text{O}_2\text{NH}_2$, i. e., acetate of ammonia—2 equivalents of water. Its formation is analogous to that of oxamide. Alkalis and acids reconvert it into ammonia and acetic acid. When treated with nitrous acid, it yields acetic acid, water and nitrogen gas, $\text{C}_4\text{H}_5\text{NO}_2 + \text{NO}_3 = \text{C}_4\text{H}_3\text{O}_3\text{HO} + \text{HO} + 2\text{N}$.

FORMATE OF THE OXIDE OF ETHYL; FORMIC ETHER; $\text{AeO}, \text{C}_2\text{HO}_3$.—A mixture of 7 parts of dry formate of soda, 10 of oil of vitriol, and 6 of strong alcohol, is to be subjected to distillation. The formic ether, separated by the addition of water to the distilled product, is agitated with a little magnesia, and left several days in contact with chloride of calcium. Formic ether is colourless, has an aromatic smell, and density of 0.915, and boils at 133° (56°C). Water dissolves this substance to a small extent.

The ethers of many of the vegetable acids have been obtained and described.

The ethers of cyanic and cyanuric acids have been formed and studied. The description of these remarkable substances and of their important products of decomposition is postponed until the history of the acids themselves has been given.

ETHERS OF THE FATTY ACIDS.—Normal *stearic ether* has not yet been obtained. By passing hydrochloric acid gas into an alcoholic solution of stearic acid, Redtenbacher succeeded in obtaining the compound $\text{AeO}, \text{HO}, \text{C}_{68}\text{H}_{66}\text{O}_5$. It resembled white wax, was inodorous and tasteless, melted at 86° (30°C), and could not be distilled without decomposition. It was readily decomposed by boiling with caustic alkalis. *Margaric ether* is prepared by a similar mode of proceeding. When purified from excess of acid by agitation with successive small quantities of weak spirit, and afterwards made to crystallize slowly from the same menstruum, it forms regular, brilliant, colourless crystals, fusible at 70° (21°C), and distilling without decomposition; when less pure it is in great part destroyed by this latter process. Margaric ether contains $\text{AeO}, \text{C}_{34}\text{H}_{33}\text{O}_3$. An *oleic ether*, and corresponding compounds of several other less important fatty acids, have been formed and described. They greatly resemble each other in characters.

BUTYRIC AND VALERIC ETHERS, $\text{AeO}, \text{C}_8\text{H}_7\text{O}_3$, and $\text{AeO}, \text{C}_{10}\text{H}_9\text{O}_3$.—The ether-compounds of these acids are easily obtained by the preceding process. They are fragrant volatile liquids, having an odour resembling that of the rind of the pine-apple. They are used for flavouring brandy. They are lighter than water, boil at a high temperature, and possess the constitution and general character of the class of bodies to which they belong.

ÆNANTHIC ETHER.—The aroma possessed by certain wines appears due to the presence of the ether of a peculiar acid called *ænanthie*, and which is probably generated during fermentation. When such wines are distilled on the large scale, an oily liquid passes over towards the close of the operation, which consists, in great measure, of the crude ether; it may be purified by agitation with solution of carbonate of potassa, freed from water by a few fragments of chloride of calcium, and re-distilled. Ænanthic ether is a thin, colourless liquid, having a powerful and almost intoxicating vinous odour; it has a density of 0.862, boils at 482° (250°C), and is but sparingly soluble in water, although, like the compound ethers in general, it dissolves with facility in alcohol. It contains $\text{C}_{22}\text{H}_{12}\text{O}_4$, or $\text{AeO}, \text{C}_{18}\text{H}_{17}\text{O}_3$.

A hot solution of caustic potassa instantly decomposes ænanthic ether; alcohol distils over, and ænanthate of potassa remains in the retort; the latter is readily decomposed by warm dilute sulphuric acid, with liberation of ænanthic acid. Purified by repeated washing with hot water, ænanthic acid presents the appearance of a colourless inodorous oil, which at 77° (25°C) becomes a soft solid, like butter. It reddens litmus-paper, and dissolves easily in solutions of the alkaline carbonates and in spirit, and very much resembles the fatty acids, to be hereafter described. The acid thus obtained is a hydrate, composed of $\text{C}_{18}\text{H}_{17}\text{O}_3 + \text{HO}$. An acid of exactly the same composition has been obtained from *Pelargonium roseum*, and described by the name of pelargonic acid. It is likewise produced, together with a host of similar acids, by the action of nitric acid upon oleic acid. Ænanthic ether may be reproduced by distilling a mixture of 5 parts sulphovinate of potassa, and 1 part hydrated ænanthic acid, or perhaps better, by the ordinary process for the ethers of the fatty acids.

CHLOROCARBONIC ETHER.—Although the constitution of this substance is doubtful, it may be here described. Absolute alcohol is introduced into a glass globe containing chlorocarbonic acid (phosgene gas, see p. 138); the gas is absorbed in large quantity, and a yellowish liquid produced, from which water separates the chlorocarbonic ether. When freed from water by chloride of calcium, and from adhering acid by rectification from litharge, it forms a thin, colourless, neutral liquid, which burns with a green flame. Its density is 1.133; it boils at 202° ($94^{\circ}.5\text{C}$). The vapour, mixed with a large quantity of air, has an agreeable odour, but when nearly pure is extremely suffocating. It contains $\text{C}_6\text{H}_5\text{ClO}_4 = \text{C}_4\text{H}_5\text{O}, \text{C}_2\text{ClO}_3$. The density of the vapour is 3.82.

The action of ammonia, gaseous or liquid, upon this substance, gives rise to a very curious product, called by M. Dumas *urethane*; sal-ammoniac is at the same time formed. Urethane is a white, solid, crystallizable body, fusible below 212° (100°C), and distilling unchanged, when in a dry state, at about 356° (180°C); if moisture

be present, it is decomposed, with evolution of ammonia. Water dissolves this substance very easily; the solution is not affected by nitrate of silver, and yields, by spontaneous evaporation, large and distinct crystals. It contains $C_6H_7NO_4$, or the elements of carbonic ether and *urea*,—whence the name.

COMPOUND ACIDS CONTAINING THE ELEMENTS OF ETHER.

SULPHOVINIC ACID, $C_4H_5O, 2SO_3, HO$.—Strong rectified spirit of wine is mixed with twice its weight of concentrated sulphuric acid: the mixture is heated to its boiling-point, and then left to cool. When cold, it is diluted with a large quantity of water, and neutralized with chalk: much sulphate of lime is produced. The mass is placed upon a cloth filter, drained, and pressed; the clear solution is evaporated to a small bulk by the heat of a water-bath, filtered from a little sulphate, and left to crystallize: the product is *sulphovinate of lime*, in beautiful colourless, transparent crystals, containing $CaO, C_4H_5O, 2SO_3 + 2HO$. They dissolve in an equal weight of cold water, and effloresce in a dry atmosphere.

A similar salt, containing baryta, $BaO, C_4H_5O, 2SO_3 + 2HO$, equally soluble, and still more beautiful, may be produced by substituting, in the above process, carbonate of baryta for chalk; from this substance the hydrated acid may be procured by exactly precipitating the base by dilute sulphuric acid, and evaporating the filtered solution, *in vacuo*, at the temperature of the air. It forms a sour syrupy liquid, in which sulphuric acid cannot be recognised, and is very easily decomposed by heat, and even by long exposure in the vacuum of the air-pump. All the sulphovinates are soluble; the solutions are decomposed by ebullition. The lead-salt resembles the baryta-compound. That of potassa, easily made by decomposing sulphovinate of lime by carbonate of potassa, is anhydrous; it is permanent in the air, very soluble, and crystallizes well.

Sulphovinate of potassa, distilled with concentrated sulphuric acid, gives ether; with dilute sulphuric acid, alcohol; and with strong acetic acid, acetic ether. Heated with hydrate of lime or baryta, the sulphovinates yield a sulphate of the base and alcohol.

PHOSPHOVINIC ACID, $C_4H_5O, PO_3, 2HO$.—This acid is bibasic. The baryta-salt is prepared by heating to 180° ($82^\circ.2C$) a mixture of equal weights of strong alcohol and syrupy phosphoric acid, diluting this mixture, after the lapse of 24 hours, with water, and neutralizing by carbonate of baryta. The solution of phosphovinate, separated by

filtration from the insoluble phosphate, is evaporated at a moderate temperature. The salt crystallizes in brilliant hexagonal plates, which have a pearly lustre, and are more soluble in cold than in hot water; it dissolves in 15 parts of water at 68° (20°C). The crystals contain $2\text{BaO}, \text{C}_4\text{H}_5\text{O}, \text{PO}_5 + 12\text{HO}$. From this substance the hydrated acid may be obtained by precipitating the baryta by dilute sulphuric acid, and evaporating the filtered liquid in the vacuum of the air-pump; it forms a colourless, syrupy liquid, of intensely sour taste, which sometimes exhibits appearances of crystallization. It is very soluble in water, alcohol, and ether, and easily decomposed by heat when in a concentrated state. The phosphovimates of lime, silver, and lead possess but little solubility; those of the alkalis, magnesia, and strontia are freely soluble.

Voegeli has lately observed that, by the action of syrupy phosphoric acid upon alcohol, together with phosphovinic acid, another acid is formed, to which he gives the name phosphobiethylic acid, phosphovinic acid being designated as phosphethylic acid. The baryta- silver- and lead-salts of this acid are more soluble than the corresponding phosphovimates. The lead-salt and lime-salt are anhydrous, and contain respectively $\text{PbO}, 2\text{C}_4\text{H}_5\text{O}, \text{PO}_5$ and $\text{CaO}, 2\text{C}_4\text{H}_5\text{O}, \text{PO}_5$.

The former of these salts when heated to a temperature of between 356° and 374° (180° and 190°C), yields an aromatic, limpid liquid, which is tribasic phosphoric ether, $3\text{C}_4\text{H}_5\text{O}, \text{PO}_5$. It boils at $288^{\circ} \cdot 5$ ($142^{\circ} \cdot 5\text{C}$). Its formation is represented by the equation: $2(\text{PbO}, 2\text{C}_4\text{H}_5\text{O}, \text{PO}_5) = 3\text{C}_4\text{H}_5\text{O}, \text{PO}_5 + 2\text{PbO}, \text{C}_4\text{H}_5\text{O}, \text{PO}_5$.

OXALOVINIC ACID, $\text{C}_4\text{H}_5\text{O}, 2\text{C}_2\text{O}_3, \text{HO}$.—Oxalic ether is dissolved in anhydrous alcohol, and enough alcoholic solution of caustic potassa added to neutralize one-half of the oxalic acid present, whereupon the potassa-salt of the new acid precipitates in the form of crystalline scales, insoluble in alcohol, but easily dissolved by water. The free acid is obtained as a sour and exceedingly instable liquid by the addition of hydrofluosilicic acid to a solution of the preceding salt in dilute alcohol. It forms with baryta a very soluble salt.

A *tartrovinic acid* has been described, and many other compounds of the same type exist.

Another and a different view is very frequently taken of the substances just described, and of many analogous compounds. The sulphovimates, phosphovimates, &c., are supposed to possess a constitution resembling that of ordinary double salts, one of the bases being a metallic oxide, and the second ether. Thus, anhydrous sulphovinate of baryta is written $\text{BaO}, \text{SO}_3 + \text{C}_4\text{H}_5\text{O}, \text{SO}_3$, or double sulphate of baryta and ether; hydrated sulphovinic acid is $\text{HO}, \text{SO}_3 + \text{C}_4\text{H}_5\text{O}, \text{SO}_3$, or bisulphate of ether. There are, however, grave objections against this mode of viewing the subject: in every true double salt the characters both of acid and bases remain unchanged; alum gives

the reactions of sulphuric acid, of alumina, and of potassa; while in sulphovinic acid or sulphovinate not a trace of sulphuric acid can be detected by any method short of actual decomposition, by heat or otherwise. If sulphovinate of baryta contain sulphate of baryta ready formed, it is very difficult to understand how that salt can be decomposed by an addition of sulphuric acid. The student must, however, bear in mind that *all* views of the constitution of complex organic compounds must, of necessity, be to a great extent hypothetical, and liable to constant alteration with the progress of science.


Products of the Decomposition of Sulphovinic Acid by Heat.

A solution of sulphovinic acid, or, what is equivalent to it, a mixture, in due proportions, of oil of vitriol and strong alcohol, undergoes decomposition when heated, yielding products which differ with the temperature to which the liquid is subjected. The cause of the decomposition is to be traced to the instability of the compound itself, to the basic power of water, and the attraction of sulphuric acid for the latter, in virtue of which it determines the production of that substance, and liberates the elements of ether.

When the sulphovinic acid is so far diluted as to boil at 260° ($126^{\circ}\cdot6\text{C}$) or below, or when a temperature not exceeding this is applied to a stronger solution by the aid of a liquid bath, the compound acid is resolved into sulphuric acid, which remains behind in the retort or distillatory vessel, while alcohol, and mere traces of ether, are volatilized.

An acid whose boiling-point lies between 260° and 310° ($126^{\circ}\cdot6$ and $154^{\circ}\cdot5\text{C}$) is decomposed by ebullition into hydrated sulphuric acid and ether, which is accompanied by small quantities of alcohol.


Lastly, when, by the addition of a large quantity of oil of vitriol, the boiling-point of the mixture is made to rise to 320° (160°C) and above, the production of ether diminishes, and other substances begin to make their appearance, of which the most remarkable is olefiant gas. The mixture in the retort blackens, sulphurous acid and carbonic acid are disengaged, a yellow, oily aromatic liquid passes over, and a coaly residue is left, which contains sulphur. The chief and characteristic product is olefiant gas; the others may be considered the result of secondary actions. The three modes of decomposition may be thus contrasted:—



The ether-producing temperature is thus seen to be circumscribed within narrow limits. In the old process, however, in which a mixture of equal weights of alcohol and sulphuric acid is subjected to distillation, these conditions can be but partially complied with. At first the temperature of the mixture is too low to yield ether in any quantity, and towards the end of the process, long before all the sulphovinic acid has been decomposed, it becomes too high, so that olefiant gas and its accompanying products appear instead. The remedy to this inconvenience consists in restraining the temperature of ebullition of the mixture within its proper bounds by the introduction of a constant supply of alcohol, to combine with the liberated sulphuric acid, and reproduce the sulphovinic acid as fast as it becomes destroyed. The improved, or *continuous* ether process, in which the same acid is made to etherify an almost indefinite quantity of spirit, may be thus elegantly conducted upon a small scale.

A wide-necked flask is fitted with a sound cork, perforated by three apertures, one of which is destined to receive a thermometer, with the graduation on the stem; a second, the vertical portion of a long narrow tube, terminating in an orifice of about $\frac{1}{20}$ of an inch in diameter; and the third, a wide bent tube, connected with the condenser, to carry off the volatilized products. A mixture is made of 8 parts by weight of concentrated sulphuric acid, and 5 parts of rectified spirit of wine, of about 0.834 sp. gr. This is introduced into the flask, and heated by a lamp. The liquid soon boils, and the thermometer very shortly indicates a temperature of 300° (149°C). When this happens alcohol of the above density is suffered slowly to enter by the narrow tube, which is put into communication with a reservoir of that liquid, consisting of a large bottle perforated by a hole near the bottom, and furnished with a small brass stopcock, fitted by a cork: the stopcock is secured to the end of the long tube by a caoutchouc connector, tied, as usual, with silk cord. As the tube passes nearly to the bottom of the flask, the alcohol gets thoroughly mixed with the acid liquid, the hydrostatic pressure of the fluid column being sufficient to insure the regularity of the flow: the quantity is easily adjusted by the aid of the stopcock. For condensation, a Liebig's condenser may be used, supplied with ice-water. The arrangement is figured on the following page.

The intensity of the heat, and the supply of alcohol, must be so adjusted that the thermometer may remain at 300° (149°C), or as near that temperature as possible, while the contents of the flask are maintained in a state of *rapid and violent ebullition*—a point of essential importance. Ether and water distil over together, and collect in the receiver, forming two distinct strata; the mixture slowly blackens, from some slight secondary action of the acid upon the spirit, or upon the impurities in the latter, but retains, after many hours' ebullition, its etherifying powers unimpaired. The acid, however, slowly volatilizes, partly in the state of *oil of wine*, and the

*Fig. 161.**

quantity of liquid in the flask is found, after the lapse of a considerable interval, sensibly diminished. This loss of acid constitutes the only limit to the duration of the process, which might otherwise be continued indefinitely.

On the large scale, the flask may be replaced by a vessel of lead, the tubes being also of the same metal; the stem of the thermometer

* Fig. 161. Apparatus for the preparation of ether. *a.* Flask containing the mixture of oil of vitriol and alcohol. *b.* Reservoir with stopcock, for supplying a constant stream of alcohol. *c.* Wide bent tube connected with the condenser for conveying away the vapours. *d.* The thermometer for regulating the temperature of the boiling liquid.

may be made to pass air-tight through the cover, and heat may, perhaps, be advantageously applied by high-pressure steam, or hot oil, circulating in a spiral of metal tube, immersed in the mixture of acid and spirit.

The crude ether is to be separated from the water on which it floats, agitated with a little solution of caustic potassa, and re-distilled by the heat of warm water. The aqueous portion, treated with an alkaline solution, and distilled, yields alcohol, containing a little ether. Sometimes the spontaneous separation before mentioned does not occur, from the accidental presence of a larger quantity than usual of undecomposed alcohol; the addition of a little water, however, always suffices to determine it.

We shall once more return to the formation of ether, when we discuss the methyl-compounds.


HEAVY OIL OF WINE.—When a mixture of $2\frac{1}{2}$ parts of concentrated sulphuric acid, and 1 part of rectified spirit of wine, of 0.833 sp. gr., is subjected to distillation, a little ether comes over, but is quickly succeeded by a yellowish, oily liquid, which may be freed from sulphurous acid by agitation with water, and from ether and undecomposed alcohol by exposure in the vacuum of the air-pump, beside two open capsules, the one containing hydrate of potassa, and the other concentrated sulphuric acid. This substance may be prepared in larger quantity by the destructive distillation of dry sulphovinate of lime; alcohol, oil of wine, and a small quantity of an exceedingly volatile liquid, yet imperfectly examined, are produced. Pure oil of wine is colourless, or greenish, of oily consistence, and heavier than water; it has an aromatic taste, and an odour resembling that of peppermint. Its boiling-point is tolerably high. It is soluble in alcohol and ether, but scarcely so in water. By analysis it is found to contain $C_8H_9O, 2SO_3$, or perhaps $C_4H_4, SO_3 + C_4H_5O, SO_3$; that is, neutral sulphate of ether, in combination with the sulphate of a hydro-carbon, *etherole*.

In contact with boiling water, oil of wine is resolved into sulphovinic acid, and a volatile liquid, known by the name of *light*, or *sweet oil of wine*; with an alkaline solution this effect is produced with even greater facility. Light oil of wine, left in a cool place for several days, deposits crystals of a white solid matter, which is tasteless, and has but little odour; it is called *etherin*. The fluid residual portion is yellowish, oily, and lighter than water; it has a high boiling-point, solidifies at a very low temperature, and is freely soluble in alcohol and ether; it bears the name of *etherole*. Both etherole and etherin have the same composition, namely C_4H_4 , and are consequently isomeric with olefiant gas.

OLEFIANT GAS; ETHYLENE.—This substance may also be advantageously prepared on the principle described, by restraining the temperature within certain bounds, and preventing the charring and destruction of the alcohol, which always occurs in the old process,

and which, at the same time, leads to the production of sulphurous and carbonic acids, which contaminate the gas.

If the vapour of alcohol be passed into somewhat diluted sulphuric acid, maintained at a boiling-heat, it is absorbed with production of



sulphovinic acid, which is shortly afterwards decomposed into water and olefiant gas. The process is thus conducted:—A wide-necked flask, containing rectified spirit of wine, is fitted with a cork, through which pass an ordinary safety-tube, with a little water, and the bent glass tube, intended to convey the vapour of the spirit into the acid. The latter must be of such strength as to have a boiling-point between 320° and 330° (160° and $165^{\circ}.5\text{C}$); it is prepared by diluting strong oil of vitriol with rather less than half its weight of water. The acid is placed in a second and larger flask, also closed by a cork, into which are inserted two tubes and a thermometer. The first is a piece of straight tube, wide enough to allow the tube conveying the alcohol-vapour to pass freely down it, and dipping a little way into the acid; the second is a narrow bent tube, the extremity of which is immersed in the water of the pneumatic trough. Both flasks are heated; and as soon as it is seen that the acid is in a state of tranquil


ebullition, while the thermometer marks the temperature above mentioned, the spirit is made to boil, and its vapour carried into the acid, which very soon begins to evolve olefiant gas and vapour of water, accompanied by a little ether and oil of wine, but no sulphurous acid. The acid liquid does not blacken, and the experiment may be carried on as long as may be desired. This is a very elegant and instructive, although somewhat troublesome, method of preparing the gas. The essential parts of the apparatus are shown in fig. 162.

CHLORIDE OF OLEFIANT GAS; DUTCH-LIQUID.—It has long been known that when equal measures of olefiant gas and chlorine are mixed over water, absorption of the mixture takes place, and a yellowish oily liquid is produced, which collects upon the surface of the water, and ultimately sinks to the bottom in drops. It may be easily prepared, in quantity, by causing the two gases to combine in a glass globe, having a narrow neck at the lower part, dipping into a small bottle, destined to receive the product. The two gases are conveyed by separate tubes, and allowed to mix in the globe, the olefiant gas being kept a little in excess. The chlorine should be washed with water, and the olefiant gas passed through strong oil of vitriol, to remove vapour of ether: the presence of sulphurous and carbonic acids is not injurious. Combination takes place very rapidly, and the liquid product trickles down the sides of the globe into the receiver. When a considerable quantity has been collected, it is agitated first with water, and afterwards with concentrated sulphuric acid; it is, lastly, purified by re-distillation. If impure olefiant gas be employed, the crude product contains a large quantity of a substance called by M. Regnault *chloro-sulphuric acid*, SO_2Cl , which, on contact with water, is converted, by the decomposition of the latter, into sulphuric and hydrochloric acids.

Pure Dutch-liquid is a thin, colourless liquid, of agreeably fragrant odour and sweet taste; it is slightly soluble in water, and readily so in alcohol and ether. It is heavier than water, and boils when heated to 180° ($82^\circ\text{.}3\text{C}$); it is unaffected by oil of vitriol and solid hydrate of potassa. When inflamed, it burns with a greenish, smoky light. This substance yields, by analysis, $\text{C}_4\text{H}_4\text{Cl}_2$.

When Dutch-liquid is treated with an alcoholic solution of caustic potassa, it is slowly resolved into chloride of potassium, which sepa-

Fig. 163.



rates, and into a new and exceedingly volatile substance, containing C_4H_3Cl , whose vapour requires to be cooled down to 0° ($-17^\circ 7C$) before it condenses. At this temperature it forms a limpid, colourless liquid. Chlorine is absorbed by this substance, and a compound produced, which contains $C_4H_3Cl_3$; this is in turn decomposed by an alcoholic solution of hydrate of potassa into chloride of potassium and a new volatile liquid, $C_4H_2Cl_2$.

BROMIDE AND IODIDE OF OLEFIANT GAS, $C_4H_4Br_2$ and $C_4H_4I_2$.—These compounds correspond to Dutch-liquid; they are produced by bringing olefiant gas in contact with bromine and iodine. The bromide is a colourless liquid, of agreeable ethereal odour, and has a density of 2.16; it boils at 265° ($129^\circ 5C$), and solidifies, when cooled, to near 0° ($-17^\circ 7C$). The iodide is a colourless, crystalline, volatile substance, of penetrating odour; it melts at 174° ($78^\circ 8C$), resists the action of sulphuric acid, but is decomposed by caustic potassa.

PRODUCTS OF THE ACTION OF CHLORINE ON DUTCH-LIQUID; CHLORIDES OF CARBON.—Dutch-liquid readily absorbs chlorine gas, and yields several new compounds, produced by the abstraction of successive portions of hydrogen, and its replacement or substitution by equivalent quantities of chlorine. This regular *substitution* of chlorine, bromine, iodine, &c., in place of hydrogen, as before stated, is a phenomenon of constant occurrence in reactions between these bodies and very many organic compounds. In the present case four such steps may be traced, giving rise, in each instance, to hydrochloric acid and a new substance. Three out of the four new products are volatile liquids, containing respectively, $C_4H_3Cl_3$, $C_4H_2Cl_4$ and C_4HCl_5 ; the fourth C_4Cl_6 in which the substitution of chlorine for hydrogen is complete, is the *chloride of carbon*, long ago obtained by Mr. Faraday by putting Dutch-liquid into a vessel of chlorine gas, and exposing the whole to the influence of light.

Sesquichloride or *Perchloride of Carbon*, C_4Cl_6 , is a white, solid crystalline substance, of aromatic odour, insoluble in water, but easily dissolved by alcohol and ether; it melts at 320° ($160^\circ C$), and boils at a temperature a little above. It burns with difficulty, and is unaffected by both acids and alkalis. It is prepared as above stated.

Protochloride of Carbon, C_4Cl_4 .—When the vapour of the preceding substance is transmitted through a red-hot porcelain tube filled with fragments of glass or rock-crystal, it is decomposed into free chlorine, and a second chloride of carbon, which condenses in the form of a volatile, colourless liquid, which has a density of 1.55, and boils at 248° ($120^\circ C$). The density of its vapour is 5.82. It resembles in chemical relations the perchloride.

Subchloride of Carbon, C_4Cl_2 , is produced when the protochloride is passed many successive times through an ignited porcelain tube; it is a white, volatile, silky substance, soluble in ether.

Bichloride of Carbon, C_2Cl_4 .—A fourth chloride of carbon is known

and will be described here, although it is not derived from the alcohol group. It is formed by passing the vapour of bisulphide of carbon, together with chlorine, through a red-hot porcelain-tube. A mixture of chloride of sulphur and bichloride of carbon is formed, which is distilled with potassa, when the chloride of sulphur is decomposed, and pure bichloride passes over. It is a colourless liquid of 1.56 sp. gr., and boils at $170^{\circ}6$ (77°C). An alcoholic solution of potassa converts this compound into a mixture of chloride of potassium and carbonate of potassa. The same compound is formed by exhausting the action of chlorine upon marsh-gas and chloride of methyl in the sunshine.

COMBUSTIBLE PLATINUM-SALTS OF ZEISE.—A solution of bichloride of platinum in alcohol is mixed with a little chloride of potassium dissolved in hydrochloric acid, and the whole digested some hours at a high temperature. The alcohol is distilled off, the acid residue neutralized by carbonate of potassa, and left to crystallize. The distilled liquid contains hydrochloric ether and aldehyde. The platinum-salt forms yellow, transparent, prismatic crystals, which become opaque on heating from loss of water: when introduced into the flame of a spirit-lamp, the salt burns vividly, leaving metallic platinum. It is soluble in 5 parts of warm water. When dried at 212° (100°C), this substance contains $\text{Pt}_2\text{Cl}_2, \text{C}_4\text{H}_4 + \text{KCl}$. Corresponding compounds, containing $\text{Pt}_2\text{Cl}_2, \text{C}_4\text{H}_4 + \text{NaCl}$, and $\text{Pt}_2\text{Cl}_2, \text{C}_4\text{H}_4 + \text{NH}_4\text{Cl}$, are known to exist.

The chloride of potassium can be separated from the above compound by the cautious addition of bichloride of platinum: the filtered solution yields by evaporation *in vacuo* a yellow, gummy, acid mass. The solution is slowly decomposed in the cold, and rapidly at a boiling heat, with separation of a black precipitate. These compounds are of uncertain constitution.

PRODUCTS OF THE ACTION OF ANHYDROUS SULPHURIC ACID ON ALCOHOL AND OLEFIANT GAS.

When absolute alcohol is made to absorb the vapour of anhydrous sulphuric acid, a white, crystalline, solid substance is produced, fusible at a gentle heat, which, when purified from adhering acid, is found to consist of carbon, hydrogen, and the elements of sulphuric acid, in the relation of the equivalent numbers, or probably, $\text{C}_4\text{H}_4, 4\text{SO}_3$. To this substance Magnus applies the name *sulphate of carbyl*. A body very similar in appearance and properties, and probably identical with this, had previously been produced by M. Regnault, by passing pure and dry olefiant gas over anhydrous sulphuric acid contained in a bent tube.

When the crystals of sulphate of carbyl are dissolved in alcohol, water added, the whole neutralized by carbonate of baryta, and the filtered solution concentrated by very gentle heat to a small bulk, and then mixed with a quantity of alcohol, a precipitate falls, which consists of baryta, in combination with a peculiar acid closely resembling the sulphovinic, but yet differing in many important particulars. By the cautious addition of dilute sulphuric acid, the base may be withdrawn, and the hydrate of the new acid left in solution; it bears the name of *ethionic acid*, and contains $C_4H_5O_4SO_3 + 2HO$. The ethionates differ completely from the sulphovinates; all are soluble in water, and appear to be anhydrous. Those of lime, baryta, and oxide of lead refuse to crystallize; the ethionates of potassa, soda, and ammonia, on the contrary, may readily be obtained in good crystals.

When a solution of ethionic acid is boiled, it is decomposed into sulphuric acid, and a second new acid, the *isethionic*, isomeric with sulphovinic acid. The isethionic acid and its salts are very stable: their solutions may be boiled without decomposition. The isethionates of baryta, lead, copper, potassa, soda, and ammonia crystallize with facility, and cannot be confounded with the sulphovinates. The hydrated acid contains $C_4H_5O_4, 2SO_3 + HO$.

The action of anhydrous sulphuric acid on ether, as has been already mentioned, gives rise to the formation of neutral sulphate of ethyl (see page 427). Together with this substance sulphuric acid and several other acids *methionic* and *althionic* are obtained, which are not yet sufficiently studied.

PRODUCTS OF THE ACTION OF CHLORINE ON ALCOHOL, ETHER, AND ITS COMPOUNDS.

CHLORAL.—Perfectly dry chlorine is passed into anhydrous alcohol to saturation; the gas is absorbed in large quantity, and hydrochloric acid abundantly produced. Towards the end of the process the reaction must be aided by heat. When no more hydrochloric acid appears, the current of chlorine is interrupted, and the product agitated with three times its volume of concentrated sulphuric acid. On gently warming this mixture in a water-bath, the impure chloral separates as an oily liquid, which floats on the surface of the acid; it is purified by distillation from fresh oil of vitriol, and afterwards from a small quantity of quick-lime, which must be kept completely covered by the liquid, until the end of the operation. Chloral has been obtained from starch, by distillation with hydrochloric acid and binoxide of manganese.

Chloral is a thin, oily, colourless liquid, of peculiar and penetrating

odour, which excites tears; it has but little taste. When dropped upon paper it leaves a greasy stain, which is not, however, permanent. It has a density of 1.502, and boils at $201^{\circ}.2$ (94°C). Chloral is freely soluble in water, alcohol, and ether; it forms, with a small quantity of water, a solid, crystalline hydrate; the solution is not affected by nitrate of silver. Caustic baryta and lime decompose the vapour of chloral when heated in it with appearance of ignition; the oxide is converted into chloride, carbon is deposited, and carbonic oxide set free. Solutions of caustic alkalis also decompose it, with production of a formate of the base, and a new volatile liquid, *chloroform*. Chloral contains $\text{C}_4\text{HCl}_3\text{O}_2$.

When chloral is preserved for any length of time, even in a vessel hermetically sealed, it undergoes a very extraordinary change, it becomes converted into a solid, white, translucent substance, *insoluble chloral*, possessing exactly the same composition as the liquid itself. The new product is but very slightly soluble in water, alcohol, or ether; when exposed to heat, alone or in contact with oil of vitriol, it is reconverted into ordinary chloral. Solution of caustic potassa resolves it into formic acid and chloroform. Bromine acts upon alcohol in the same manner as chlorine, and gives rise to a product very similar in properties to the foregoing, called *bromal*, which contains $\text{C}_4\text{HBr}_3\text{O}_2$. It forms a crystallizable hydrate with water, and is decomposed by strong alkaline solutions into formic acid and *bromoform*. A corresponding iodine-compound probably exists.

Chlorine acts in a different manner upon alcohol which contains water: when very dilute, the principal products are hydrochloric acid and *aldehyde*, the change being one of oxidation at the expense of the water. With strong spirit the reaction is more complex, one of its products being a volatile, oily, colourless liquid, of uncertain composition, long known under the name of *heavy muriatic ether*.

The mode of action of dry chlorine on pure ether conforms strictly to the law of substitution before mentioned; the carbon remains intact, while a portion or the whole of the hydrogen is removed, and its place supplied by an equivalent quantity of chlorine. Ether exposed to a current of the dry gas for a considerable period, the temperature being at first artificially reduced, yields a heavy oily product, having the odour of fennel. This is found by analysis to contain $\text{C}_4\text{H}_3\text{Cl}_2\text{O}$, or ether, in which 2 eq. of chlorine have been substituted for 2 eq. of hydrogen. It may be termed bichlorinected ether. By the farther action of chlorine, aided by sunlight, the remaining hydrogen is removed, and a white crystalline solid substance, closely resembling sesquichloride of carbon produced. This is composed of $\text{C}_4\text{Cl}_5\text{O}$; it is called pentachlorinected ether. In a substance called *clorethetal*, $\text{C}_4\text{H}_4\text{ClO}$, accidentally formed by M. d'Arcet, in the preparation of Dutch-liquid, from the ether-vapour mixed with the olefant gas, we have evidently the first member of this series.

With the compound ethers, the same remarkable law is usually fol-

lowed. The change is, however, often complicated by the appearance of secondary products. Thus, *chlorinatted acetic ether*, a dense, oily liquid, very different from common acetic ether, was found to contain $C_8H_6Cl_2O_4$, being a substitution-product of $C_8H_8O_4 = C_4H_5O, C_4H_3O_3$; and *chlorinatted formic ether*, $C_6H_4Cl_2O_4$, is formed, in like manner, by the substitution of 2 eq. chlorine for 2 eq. hydrogen in ordinary formic ether, $C_6H_6O_4 = C_4H_5O, C_2HO_3$. A most remarkable and interesting set of compounds, due to substitution of this kind, are formed by the action of chlorine on chloride of ethyl, or light hydrochloric ether. When the vapour of this substance is brought into contact with chlorine gas, the two bodies combine to a colourless oily liquid, very like Dutch-liquid, but yet differing from it in several important points; it has, however, precisely the same composition, and its vapour has the same density. By the prolonged action of chlorine three other compounds are successively obtained, each poorer in hydrogen and richer in chlorine than the preceding, the ultimate product being the well-known sesquichloride of carbon of Mr. Faraday.

Hydrochloric ether	C_4H_5Cl
Monochlorinatted hydrochloric ether	$C_4H_4Cl_2$
Bichlorinatted	"	"	.	.	$C_4H_3Cl_3$
Trichlorinatted	"	"	.	.	$C_4H_2Cl_4$
Quadrichlorinatted	"	"	.	.	C_4HCl_5
Sesquichloride of carbon	C_4Cl_6

DERIVATIVES OF ALCOHOL CONTAINING SULPHUR.

MERCAPTAN.—A solution of caustic potassa, of 1.28 or 1.3 sp. gr., is saturated with sulphuretted hydrogen, and mixed in a retort with an equal volume of solution of sulphovinate of lime of the same density. The retort is connected with a good condenser, and heat is applied by means of a bath of salt and water. Mercaptan and water distil over together, and are easily separated by a funnel. The product thus obtained is a colourless, limpid liquid, of sp. gr. 0.842, but slightly soluble in water, easily miscible, on the contrary, with alcohol. It boils at 97° ($36^\circ C$). The vapour of mercaptan has a most intolerable odour of onions, which adheres to the clothes and person with great obstinacy; it is very inflammable, and burns with a blue flame. Mercaptan contains $C_4H_6S_2 = C_4H_5S, HS$; or alcohol, having sulphur in the place of oxygen.

When brought into contact with red oxide of mercury, even in the cold, violent reaction ensues,* water is formed, and a white substance is produced, soluble in alcohol, and separating from that liquid in distinct crystals, which contain C_4H_5S, HgS . This compound is

* Whence the name, *mercurium captans*.

decomposed by sulphuretted hydrogen, sulphide of mercury being thrown down, and mercaptan reproduced. By adding solutions of the oxides of lead, copper, silver, and gold, to an alcoholic solution of mercaptan, corresponding compounds containing those metals are formed. Caustic potassa produces no effect upon mercaptan, but potassium displaces hydrogen, and gives rise to a crystallizable compound soluble in water.

XANTHIC ACID.—The elements of ether and those of bisulphide of carbon combine in presence of an alkali to a very extraordinary substance, possessing the properties of an oxygen-acid, to which the name *xanthic* is applied, on account of the yellow colour of one of its most permanent and characteristic salts, that of oxide of copper.

Alcohol of 0·800 sp. gr. is saturated, whilst boiling, with potassa, and into this solution bisulphide of carbon is dropped until it ceases to be dissolved, or until the liquid loses its alkalinity. The whole is then cooled to 0° (—17°·8C), when the potassa-salt separates in the form of brilliant, slender, colourless prisms, which must be quickly pressed between folds of bibulous paper, and dried *in vacuo*. It is freely soluble in water and alcohol, but insoluble in ether, and is gradually destroyed by exposure to air by oxidation of a part of the sulphur. Hydrated xanthic acid may be prepared by decomposing the foregoing compound by dilute sulphuric or hydrochloric acid. It is a colourless, oily liquid, heavier than water, of powerful and peculiar odour, and very combustible; it reddens litmus-paper, and ultimately bleaches it. Exposed to gentle heat, it is decomposed into alcohol and bisulphide of carbon; this happens at a temperature of 75° (23°·8C). Exposed to the air, or kept beneath the surface of water open to the atmosphere, it becomes covered with a whitish crust, and is gradually destroyed. The xanthates of the alkalis and of baryta are colourless and crystallizable; the lime-salt dries up to a gummy mass; the xanthates of the oxides of zinc, lead, and mercury are white, and but feebly soluble, that of copper is a flocculent, insoluble substance, of beautiful yellow colour.

Hydrated xanthic acid contains $C_6H_5S_4O,HO$; or C_4H_5O,C_2S_4,HO . In the salts this water is replaced by one equivalent of a metallic oxide.

DERIVATIVES OF ALCOHOL CONTAINING METALS.

ZINC-ETHYL.—In heating iodide of ethyl with zinc in sealed glass-tubes (see compound ethers; ethyl-theory, p. 424), a white substance remains in the tube, which is a mixture of iodide of zinc and a peculiar volatile compound, to which Dr. Frankland has given the name *zinc-ethyl*. It may be separated from the residue by distilling it in a current of hydrogen, when it is obtained in the form of a liquid of a disagreeable odour, which contains C_4H_5Zn . In contact with atmo-

spheric air it is rapidly oxidized. When mixed with water, this compound is decomposed with evolution of a carbonated hydrogen, having the formula $C_4H_6 = C_4H_5, H$, which may be viewed as the hydride of ethyl.

STANNETHYL.—A series of substances have been lately described by Frankland and by Loewig, which contain the elements of ethyl, associated with the metal tin. Iodide of ethyl, when submitted in sealed tubes to the action of metallic tin at a temperature of $302^\circ - 320^\circ$ ($150^\circ - 160^\circ C$), iodide of stannethyl, C_4H_5SnI , is obtained in the form of yellow crystals, which fuse at 107.6° ($42^\circ C$) and sublime at 464° ($240^\circ C$). They are easily soluble in alcohol and ether, but difficultly soluble in water. The iodine of this compound may be readily separated by the action of metals, such as potassium and zinc, when a metallic iodide is formed, stannethyl C_4H_5Sn , being liberated in the form of a dense, oily liquid, having a sp. gr. of 1.55. Exposed to the action of the atmosphere, stannethyl absorbs oxygen, and is converted into oxide of stannethyl C_4H_5SnO , which is an inodorous and tasteless powder of a whitish colour. This substance combines with most acids, giving rise to a series of well-crystallizable salts, which are soluble in water and alcohol, but dissolve only with difficulty in ether. As yet the following terms of this series have been analysed:—

Stannethyl.	C_4H_5Sn
Oxide of stannethyl	C_4H_5SnO
Chloride of stannethyl	C_4H_5SnCl (Frankland)
Bromide of stannethyl	C_4H_5SnBr
Iodide of stannethyl	C_4H_5SnI
Nitrate of stannethyl	C_4H_5SnO, NO_5

Several other analogous substances have been discovered by Loewig: the action of an alloy of six parts of tin with one part of sodium on iodide of ethyl, at the common temperature, gives rise to the formation of a series of compounds, which may be extracted from the residue by means of ether, but which are difficult to separate. This mixture is left behind, on evaporating the ether, in the form of a thick, oily liquid, emitting dense fumes in contact with the air. It absorbs oxygen from the atmosphere, and becomes converted into a mixture of oxides, of which oxide of stannethyl constitutes the chief part. They are partly soluble in water and alcohol, and partly insoluble, and can, by means of these solvents, be separated to a certain extent. They form crystallizable salts with the acids. Loewig distinguishes the following series, some of which exhibit a rather unusual ratio of composition:—

C_4H_5SnO	} Insoluble in water.
$2(C_4H_5)Sn_2O$	
$4(C_4H_5)Sn_4O$	
$3(C_4H_5)Sn_2O$	} Soluble in water.
$5(C_4H_5)Sn_4O$	

BISM-ETHYL.—This substance is formed by the action of iodide of ethyl upon an alloy of bismuth and potassium; from the residue it is extracted with ether. It contains $\text{BiC}_{12}\text{H}_{15} = \text{Bi}3\text{C}_4\text{H}_5$, and forms a yellow liquid of 1.82 sp. gr., which possesses a most nauseous odour, and emits fumes which are inflamed when coming in contact with the air. It combines with oxygen, chlorine, bromine, iodine, and with nitric acid.

HYDRARGYRETHYL.—According to Frankland, iodide of ethyl is readily attacked by mercury. The mixture solidifies after some time into a white crystalline mass, which is iodide of hydrargyrethyl, $\text{C}_4\text{H}_5\text{Hg}_2\text{I}$. It is insoluble in water, soluble in alcohol and ether, readily fusible, and may be sublimed without decomposition. There is a corresponding nitrate and chloride known:—



They are both crystallizable compounds.

STIBETHYL.—Iodide of ethyl, when distilled with an alloy of antimony and potassium, yields a curious substance, which MM. Locwig and Schweizer have described under the name of stibethyl. It contains $\text{SbC}_{12}\text{H}_{15} = \text{Sb}3(\text{C}_4\text{H}_5)$. We shall return to this substance when speaking of the compound ammonias.

PRODUCTS OF THE OXIDATION OF ALCOHOL.

When alcohol and ether burn with flame in free air, the products of their combustion are, as with all bodies of like chemical nature, carbonic acid and water. Under peculiar circumstances, however, these substances undergo partial oxidation, in which the hydrogen alone is affected, the carbon remaining untouched. The result is the production of certain compounds, which form a small series, supposed by some chemists to contain a common radical, to which the name *acetyl* is applied. It is derived from ethyl by the oxidation and removal of 2 eq. of hydrogen.

Table of Acetyl-Compounds.

Acetyl (symbol Ac).	C_4H_3
Oxide of acetyl (unknown)	$\text{C}_4\text{H}_3\text{O}$
Hydrate of oxide of acetyl; aldehyde	$\text{C}_4\text{H}_3\text{O}, \text{HO}$
Acetyloous acid; aldehydic acid	$\text{C}_4\text{H}_3\text{O}_2, \text{HO}$
Anhydrous acetic acid	$\text{C}_4\text{H}_3\text{O}_3$
Acetylic acid; acetic acid	$\text{C}_4\text{H}_3\text{O}_3, \text{HO}$

Acetyl and its protoxide are alike hypothetical.

ALDEHYDE, $C_4H_4O_2$ or AcO,HO .—This substance is formed, as already noticed, among other products, when the vapour of ether or alcohol is transmitted through a red-hot tube; also, by the action of chlorine on weak alcohol. It is best prepared by the following process:—6 parts of oil of vitriol are mixed with 4 parts of rectified spirit of wine, and 4 parts of water; this mixture is poured upon 6 parts of powdered binocide of manganese, contained in a capacious retort, in connection with a condenser, cooled by ice-cold water. Gentle heat is applied; and when six parts of liquid have passed over the process is interrupted. The distilled product is put into a small retort, with its own weight of chloride of calcium, and re-distilled: this operation is repeated. The aldehyde, still retaining alcohol and other impurities, is mixed with twice its volume of ether, and saturated with dry ammoniacal gas; a crystalline compound of aldehyde and ammonia separates, which may be washed with a little ether, and dried in the air. From this substance the aldehyde may be separated by distillation in a water-bath, with sulphuric acid, diluted with an equal quantity of water: by careful rectification from chloride of calcium, at a temperature not exceeding 87° ($30^\circ \cdot 5C$), it is obtained pure and anhydrous.

Aldehyde* is a limpid, colourless liquid, of characteristic ethereal odour, which, when strong, is exceedingly suffocating. It has a density of 0.790, boils at 72° ($22^\circ \cdot 3C$), and mixes in all proportions with water, alcohol, and ether; it is neutral to test-paper, but acquires acidity on exposure to air, from the production of acetic acid: under the influence of platinum-black this change is very speedy. When a solution of this compound is heated with caustic potassa, a remarkable brown resin-like substance is produced, the so-called *aldehyde-resin*. Gently heated with protoxide of silver, it reduces the latter without evolution of gas, the metal being deposited on the inner surface of the vessel as a brilliant and uniform film; the liquid contains aldehyde of silver.

When treated with hydrocyanic acid, aldehyde yields a substance called *alanine*, which was already noticed, when treating of lactic acid, and which will be described more in detail in the section on vegetable-alkalis, under the head of bases from aldehyde.

The action of sulphuretted hydrogen upon the ammonia-compound gives rise to the formation of *thialdine*, noticed likewise under the head of bases from aldehyde.

The ammonia-compound above mentioned forms transparent, colourless crystals, of great beauty; it has a mixed odour of ammonia and turpentine; it dissolves very easily in water, with less facility in alcohol, and with difficulty in ether; it melts at about 170° ($76^\circ C$), and distils unchanged at 212° ($100^\circ C$). Acids decompose it, with production of an ammoniacal salt and separation of aldehyde.

* *Alcohol dehydrogenatus*.

The crystals, which are apt to become yellow, and lose their lustre in the air, contain $C_4H_4O_2 + NH_3$.

When pure aldehyde is long preserved in a closely-stopped vessel, it is sometimes found to undergo spontaneous change into one, and even two isomeric modifications, differing completely in properties from the original compound. In a specimen kept some weeks at 32° ($0^\circ C$), transparent acicular crystals were observed to form in considerable quantity, which, at a temperature little exceeding that of the freezing-point of water melted to a colourless liquid, miscible with water, alcohol, and ether; a few crystals remained, which sublimed without fusion, and were probably composed of the second substance. This new body received the name *elaldehyde*; it was found to be identical in composition with aldehyde, but to differ in properties and in the density of its vapour; the latter has a sp. gr. of 4.515, while that of aldehyde is only 1.532, or one-third of that number. It refuses to combine with ammonia, is not rendered brown by potassa, and is but little affected by solution of silver.

The second modification, or *metlaldehyde*, is sometimes produced in pure aldehyde, kept at the common temperature of the air, even in hermetically-sealed tubes: the conditions of its formation are unknown. It forms colourless, transparent, prismatic crystals, which sublime without fusion at a temperature above 212° ($100^\circ C$), and are soluble in alcohol and ether, but not in water. They also were found, by analysis, to have the same composition as aldehyde. The substance which we have described by the term of *chloral* may be viewed as bichlorinetted aldehyde.

ALDEHYDIC ACID, $C_4H_3O_2, HO$.—When solution of aldehydate of silver, obtained by digesting oxide of silver in excess with aldehyde, is precipitated by sulphuretted hydrogen, an acid liquid is obtained, which neutralizes alkalis, and combines with the oxides of the metals. It is very easily decomposed. Aldehydate of silver, mixed with baryta-water, gives rise to aldehydate of baryta and oxide of silver: if this precipitate be heated in the liquid, the metal is reduced, and neutral acetate of baryta formed; whence it is inferred that the new acid contains the elements of acetic acid, *minus* an equivalent of oxygen.


ACETAL.—This substance is one of the products of the slow oxidation of alcohol-vapour under the influence of platinum-black. Spirit of wine is poured into a large, tall, glass-jar, to the depth of about an inch, and a shallow capsule, containing slightly-moistened platinum-black, arranged above the surface of the liquid; the jar is loosely covered by a glass plate, and left during two or three weeks, in a warm situation. At the expiration of that period the liquid is found highly acid: it is to be neutralized with carbonate of potassa, as much chloride of calcium added as the liquid will dissolve, and the whole subjected to distillation, the first fourth only being collected. Fused chloride of calcium added to the distilled product now throws up a

light oily liquid, which is a mixture of acetal with alcohol, aldehyde, and acetic ether. By fresh treatment with chloride of calcium, and long exposure to gentle heat in a retort, the aldehyde is expelled. The acetic ether is destroyed by caustic potassa, and the alcohol removed by washing with water, after which the acetal is again digested with fused chloride of calcium, and re-distilled.

Pure acetal is a thin, colourless fluid, of agreeable ethereal odour, of sp. gr. 0.821 at 72° ($22^{\circ}\cdot 2\text{C}$), and boiling at 220° (104°C). It is soluble in 18 parts of water, and miscible in all proportions with alcohol and ether. It is unchanged in the air; but, under the influence of platinum-black, becomes converted into aldehyde, and eventually into acetic acid. Nitric and chromic acids produce a similar effect. Strong boiling solution of potassa has no action on this substance. Acetal contains $\text{C}_{12}\text{H}_{14}\text{O}_4$, or the elements of 2 eq. ether and 1 eq. aldehyde, $\text{C}_{12}\text{H}_{14}\text{O}_4 = 2\text{C}_4\text{H}_5\text{O} + \text{C}_4\text{H}_4\text{O}_2$.

When a coil of fine platinum wire is heated to redness, and plunged into a mixture of ether, or alcohol-vapour and atmospheric air, it determines upon its surface the partial combustion of the former, and gives rise to an excessively pungent acrid vapour, which may be condensed to a colourless liquid by suitable means. The heat evolved

Fig. 164.



in the act of oxidation is sufficient to maintain the wire in an incandescent state. The experiment may be made by putting a little ether into an ale-glass, and suspending over it the heated spiral from a card; or by slipping the coil over the wick of a spirit-lamp, so that the greater part may be raised above the cotton; the lamp is supplied with ether or spirit of wine, lighted for a moment, and then blown out. The coil continues to glow in the mixed atmosphere of air and combustible vapour, until the ether is exhausted. This is the *lamp without flame* of Sir H. Davy. A ball of spongy platinum may be substituted for the coil of wire. The condensed liquid contains acetic and formic acids with aldehyde

and aldehydic acid.

ACETIC ACID.—Pure alcohol, exposed to the air, or thrown into a vessel of oxygen gas, fails to suffer the slightest change by oxidation; when diluted with water, it remains also unaffected. If, on the other hand, spirit of wine be dropped upon dry platinum-black, the oxygen condensed into the pores of the latter reacts so powerfully upon the alcohol as to cause its instant inflammation. When the spirit is mixed with a little water, and slowly dropped upon the finely-divided metal, oxidation still takes place, but with less energy, and vapour of acetic acid is abundantly evolved. It is almost unnecessary to add, that the platinum itself undergoes no change in this experiment.

Dilute alcohol, mixed with a little yeast, or almost any azotized organic matter, susceptible of putrefaction, and exposed to the air, speedily becomes oxidized to acetic acid. Acetic acid is thus manufactured in Germany, by suffering such a mixture to flow over wood-shavings, steeped in a little vinegar, contained in a large cylindrical vessel, through which a current of air is made to pass. The greatly extended surface of the liquid expedites the change, which is completed in a few hours. No carbonic acid is produced in this reaction.

The best vinegar is made from wine by spontaneous acidification in a partially-filled cask to which the air has access. Vinegar is first introduced into the empty vessel, and a quantity of wine added; after some days a second portion of wine is poured in, and after similar intervals a third and a fourth. When the whole has become vinegar, a quantity is drawn off equal to that of the wine employed, and the process is recommenced. The temperature of the building is kept up to 86° (30°C). Such is the plan adopted at Orleans.* In England vinegar is prepared from a kind of beer made for the purpose. The liquor is exposed to the air in half-empty casks, loosely stopped, until acidification is complete. Frequently a little sulphuric acid is afterwards added, with a view of checking farther decomposition, or *mothering*, by which the product would be spoiled.

There is another source of acetic acid besides the oxidation of alcohol: when dry, hard wood, as oak and beech, is subjected to destructive distillation at a red-heat, acetic acid is found among the liquid condensable products of the operation. The distillation is conducted in an iron cylinder of large dimensions, to which a worm or condenser is attached; a sour watery liquid, a quantity of tar, and much inflammable gas pass over, while charcoal of excellent quality remains in the retort. The acid liquid is subjected to distillation, the first portion being collected apart for the sake of a peculiar volatile body, shortly to be described, which it contains. The remainder is saturated with lime, concentrated by evaporation, and mixed with solution of sulphate of soda; sulphate of lime precipitates, while the acetic acid is transferred to the soda. The filtered solution is evaporated to its crystallizing-point; the crystals are drained as much as possible from the dark, tarry mother-liquor, and deprived by heat of their combined water. The dry salt is then cautiously fused, by which the last portions of tar are decomposed or expelled; it is then re-dissolved in water, and re-crystallized. Pure acetate of soda, thus obtained, readily yields hydrated acetic acid by distillation with sulphuric acid.

The strongest acetic acid is prepared by distilling finely-powdered anhydrous acetate of soda with three times its weight of concentrated oil of vitriol. The liquid is purified by rectification from sulphate of soda, accidentally thrown up, and then exposed to a low temperature. Crystals of hydrate of acetic acid form in large quantity, which may

* Dumas, *Chimie appliquée aux Arts*, vi. 537.

be drained from the weaker fluid portion, and then suffered to melt. Below 60° ($15^{\circ}\cdot5\text{C}$) this substance forms large, colourless, transparent crystals, which above that temperature fuse to a thin, colourless liquid, of exceedingly pungent and well-known odour; it raises blisters on the skin. It is miscible in all proportions with water, alcohol, and ether, and dissolves camphor and several resins. When diluted it has a pleasant acid taste. The hydrate of acetic acid in the liquid condition has a density of 1.063, and boils at 240° (119°C); its vapour is inflammable. Acetic acid forms a great number of exceedingly important salts, all of which are soluble in water; the acetates of silver and mercury are the least soluble.


The hydrate of acetic acid contains $\text{C}_4\text{H}_3\text{O}_3\cdot\text{HO} = \text{AcO}_3\cdot\text{HO}$; it is formed from alcohol by the substitution of 2 eq. of oxygen for 2 eq. of hydrogen. The water is *basic*, and can be replaced by metallic oxides. Dr. Williamson assumes in acetic acid, a peculiar radical, which he terms othyl $\text{C}_4\text{H}_3\text{O}_2$, *i. e.*, ethyl in which 2 eq. of hydrogen are replaced by 2 eq. of oxygen. The constitution of acetic acid thus becomes analogous to that of benzoic acid in which Liebig and Wöhler assume a peculiar radical, benzoyl $\text{C}_{14}\text{H}_5\text{O}_2$. See the article on this substance.

Benzoic acid	$\text{HO}(\text{C}_{14}\text{H}_5\text{O}_2)\text{O}$	Hydrated oxide of benzoyl.
Acetic acid	$\text{HO}(\text{C}_4\text{H}_3\text{O}_2)\text{O}$	Hydrated oxide of othyl.

A different view regarding the constitution of this acid has been proposed by Prof. Kolbe; it is chiefly based upon the remarkable decomposition which acetic acid undergoes when submitted to the action of the galvanic current. We shall return to this subject when speaking of valeric acid.

Dilute acetic acid, or distilled vinegar, used in pharmacy, should always be carefully examined for copper and lead; these impurities are contracted from the metallic vessel or condenser sometimes employed in the process. The strength of any sample of acetic acid cannot be safely inferred from its density, but is easily determined by observing the quantity of dry carbonate of soda necessary to saturate a known weight of the liquid.

Mr. Gerhardt has lately made the remarkable discovery that *anhydrous acetic acid*, the substance $\text{C}_4\text{H}_3\text{O}_3$, may be obtained by a process which is of general applicability for the isolation of the anhydrous acid. In one of the subsequent chapters a substance will be described under the name of chloride of benzoyl, which may be viewed as the chloride of the radical of benzoic acid. If this body be heated with anhydrous acetate of soda, a lively reaction ensues, and anhydrous acetic acid distils over, while a mixture of chloride of sodium and acetate of soda remain in the retort.



Anhydrous acetic acid is a heavy oil which combines only slowly with water, giving rise to the formation of ordinary hydrated acetic acid.

ACETATE OF POTASSA, $\text{KO}, \text{C}_4\text{H}_3\text{O}_3$.—This salt crystallizes with great difficulty: it is generally met with as a foliated, white, crystalline mass, obtained by neutralizing carbonate of potassa by acetic acid, evaporating to dryness, and heating the salt to fusion. The acetate is extremely deliquescent, and soluble in water and alcohol; the solution is usually alkaline, from a little loss of acid by the heat to which it has been subjected. From the alcoholic solution, carbonate of potassa is thrown down by a stream of carbonic acid.

ACETATE OF SODA, $\text{NaO}, \text{C}_4\text{H}_3\text{O}_3 + 6\text{HO}$.—The mode of preparation of this salt on the large scale has been already described; it forms large, transparent, colourless crystals, derived from a rhombic prism, which are easily rendered anhydrous by heat, effloresce in dry air, and dissolve in 3 parts of cold, and in an equal weight of hot water,—it is also soluble in alcohol. The taste of this substance is cooling and saline. The dry salt undergoes the igneous fusion at 550° ($287^\circ\text{.}8\text{C}$), and begins to decompose at 600° ($315^\circ\text{.}5\text{C}$).

ACETATE OF AMMONIA; SPIRIT OF MINDERERUS; $\text{NH}_4\text{O}, \text{C}_4\text{H}_3\text{O}_3$.—The neutral solution obtained by saturating strong acetic acid by carbonate of ammonia cannot be evaporated without becoming acid from loss of base; the salt passes off in large quantity with the vapour of water. Solid acetate of ammonia is best prepared by distilling a mixture of equal parts acetate of lime and powdered sal-ammoniac; chloride of calcium remains in the retort. A saturated solution of the solid salt in hot water, suffered slowly to cool in a close vessel, deposits long slender crystals, which deliquesce in the air. Acetate of ammonia has a sharp and cooling, yet sweet, taste; its solution becomes alkaline on keeping, from decomposition of the acid.

ACETONITRILE.—Acetate of ammonia when distilled with anhydrous phosphoric acid, loses 4 eq. of water, being converted into a colourless liquid, immiscible with water, of an aromatic odour, and boiling at 170° (77°C), which has received the name of *acetonitrile*. When boiled with acids or alkalis it re-assimilates the 4 eq. of water, being converted again into acetic acid and ammonia. This substance is the type of a class; a great many ammonia-salts of acids, analogous to acetic acid, undergoing a similar change when treated with anhydrous phosphoric acid. It is likewise obtained by a perfectly-different process, which will be described when treating of the methyl-compounds. (See cyanide of methyl, page 465, and also acetic ether, page 429.)

The acetates of *lime*, *baryta*, and *strontia* are very soluble, and can be procured in crystals; acetate of *magnesia* crystallizes with difficulty.

ACETATE OF ALUMINA, $\text{Al}_2\text{O}_3, 3\text{C}_4\text{H}_3\text{O}_3$.—This salt is very soluble in water, and dries up in the vacuum of the air-pump to a gummy

mass, without trace of crystallization. If foreign salts be present, the solution of the acetate becomes turbid on heating, from the separation of a basic compound, which re-dissolves as the liquid cools. Acetate of alumina is much employed in calico-printing; it is prepared by mixing solutions of acetate of lead and alum, and filtering from the insoluble sulphate of lead. The liquid is thickened with gum or other suitable material, and with it the design is impressed upon the cloth by a wood-block, or by other means. Exposure to a moderate degree of heat drives off the acetic acid, and leaves the alumina in a state capable of entering into combination with the dye-stuff.

Acetate of manganese forms colourless, rhombic, prismatic crystals, permanent in the air. *Acetate of protoxide of iron* crystallizes in small greenish-white needles, very prone to oxidation; both salts dissolve freely in water. *Acetate of sesquioxide of iron* is a dark-brownish red, uncrystallizable liquid, of powerful astringent taste. *Acetate of cobalt* forms a violet-coloured, crystalline, deliquescent mass. The *nickel-salt* separates in green crystals, which dissolve in 6 parts of water.

ACETATE OF LEAD, $\text{PbO}, \text{C}_4\text{H}_3\text{O}_3 + 3\text{HO}$.—This important salt is prepared on a large scale by dissolving litharge in acetic acid; it may be obtained in colourless, transparent prismatic crystals, but is generally met with in commerce as a confusedly crystalline mass, somewhat resembling loaf-sugar. From this circumstance, and from its sweet taste, it is often called *sugar of lead*. The crystals are soluble in about $1\frac{1}{4}$ parts of cold water, effloresce in dry air, and melt when gently heated in their water of crystallization; the latter is easily driven off, and the anhydrous salt obtained, which suffers the igneous fusion, and afterwards decomposes, at a high temperature. Acetate of lead is soluble in alcohol. The watery solution has an intensely sweet, and at the same time astringent, taste, and is not precipitated by ammonia. It is an article of great value to the chemist.

BASIC ACETATES (SUB-ACETATES) OF LEAD.—*Sesqui-basic acetate* is produced when the neutral anhydrous salt is so far decomposed by heat as to become converted into a porous white mass, decomposable only at a much higher temperature. It is soluble in water, and separates from the solution evaporated to a syrupy consistence in the form of crystalline scales. It contains $3\text{PbO}, 2\text{C}_4\text{H}_3\text{O}_3$. A sub-acetate with 3 eq. of base is obtained by digesting at a moderate heat 7 parts of finely-powdered litharge, 6 parts of acetate of lead, and 30 parts of water. Or, by mixing a cold saturated solution of neutral acetate with a fifth of its volume of caustic ammonia, and leaving the whole some time in a covered vessel; the salt separates in minute needles, which contain $3\text{PbO}, \text{C}_4\text{H}_3\text{O}_3 + \text{HO}$. The solution of sub-acetate prepared by the first method is known in pharmacy under the name of *Goulard water*. A third sub-acetate exists, formed by adding a great excess of ammonia to a solution of acetate of lead, or by digesting acetate of lead with a large quantity of oxide. It is a white, slightly

crystalline substance, insoluble in cold, and but little soluble in boiling water. It contains $6\text{PbO}, \text{C}_4\text{H}_3\text{O}_3$. The solutions of the subacetates of lead have a strong alkaline reaction, and absorb carbonic acid with the greatest avidity, becoming turbid from the precipitation of basic carbonate.

ACETATE OF COPPER.—The neutral acetate, $\text{CuO}, \text{C}_4\text{H}_3\text{O}_3 + \text{HO}$, is prepared by dissolving *verdigris* in hot acetic acid, and leaving the filtered solution to cool. It forms beautiful dark-green crystals, which dissolve in 14 parts of cold and 5 parts of boiling water, and are also soluble in alcohol. A solution of this salt, mixed with sugar and heated, yields suboxide of copper in the form of minute red octahedral crystals; the residual copper solution is not precipitated by an alkali. Acetate of copper furnishes, by destructive distillation, strong acetic acid, containing acetone, and contaminated with copper. The salt is sometimes called *distilled verdigris*, and is used as a pigment.

BASIC ACETATES (SUB-ACETATES) OF COPPER.—Common *verdigris*, made by spreading the marc of grapes upon plates of copper exposed to the air during several weeks, or by substituting, with the same view, pieces of cloth dipped in crude acetic acid, is a mixture of several basic acetates of copper which have a green or blue colour. One of these, $3\text{CuO}, 2\text{C}_4\text{H}_3\text{O}_3 + 6\text{HO}$, is obtained by digesting the powdered *verdigris* in warm water, and leaving the soluble part to spontaneous evaporation. It forms a blue, crystalline mass, but little soluble in cold water. When boiled, it deposits a brown powder, which is a sub-salt with large excess of base. The green insoluble residue of the *verdigris* contains $3\text{CuO}, \text{C}_4\text{H}_3\text{O}_3 + 3\text{HO}$; it may be formed by digesting neutral acetate of copper with the hydrated oxide. By ebullition with water it is resolved into neutral acetate and the brown sub-salt.

ACETATE OF SILVER, $\text{AgO}, \text{C}_4\text{H}_3\text{O}_3$, is obtained by mixing acetate of potassa with nitrate of silver, and washing the precipitate with cold water to remove the nitrate of potassa. It crystallizes from a warm solution in small colourless needles, which have but little solubility in the cold.

Acetate of suboxide of mercury forms small scaly crystals, which are as feebly soluble as those of acetate of silver. The salt of the *red oxide of mercury* dissolves with facility.


CHLORACETIC ACID.—When a small quantity of crystallizable acetic acid is introduced into a bottle of dry chlorine gas, and the whole exposed to the direct solar rays for several hours, the interior of the vessel is found coated with a white crystalline substance, which is a mixture of the new product, chloracetic acid, with a small quantity of oxalic acid. The liquid at the bottom contains the same substances, together with the unaltered acetic acid. Hydrochloric and carbonic acid gases are at the same time produced, together with a suffocating vapour, resembling chloro-carbonic acid. The crystalline matter is dissolved out with a small quantity of water, added to the liquid con-

tained in the bottle, and the whole placed in the vacuum of the air-pump, with capsules containing fragments of caustic potassa, and concentrated sulphuric acid. The oxalic acid is first deposited, and afterwards the new substance in beautiful rhombic crystals. If the liquid refuse to crystallize, it may be distilled with a little anhydrous phosphoric acid, and then evaporated. The crystals are spread upon bibulous paper to drain, and dried *in vacuo*.

Chloracetic acid is a colourless and extremely deliquescent substance; it has a faint odour, and a sharp, caustic taste, bleaching the tongue and destroying the skin; the solution is powerfully acid. At 115° (46°C) it melts to a clear liquid, and at 390° ($218^{\circ}\cdot8\text{C}$) boils and distils unchanged. The density of the fused acid is 1.617; that of the vapour, which is very irritating, is probably 5.6. The substance contains, according to the analysis of M. Dumas, $\text{C}_4\text{Cl}_3\text{O}_3$, HO, or the elements of hydrated acetic acid from which 3 eq. of hydrogen have been withdrawn, and replaced by 3 eq. of chlorine.

Chloracetic acid forms a variety of salts, which have been examined and described; it combines also with ether, and with the ether of wood-spirit. These compounds correspond to the ethers of the other organic acids. *Chloracetate of potassa* crystallizes in fibrous, silky needles, which are permanent in the air, and contain $\text{KO}, \text{C}_4\text{Cl}_3\text{O}_3 + \text{HO}$. The *ammoniacal* salt is also crystallizable and neutral; it contains $\text{NH}_4\text{O}, \text{C}_4\text{Cl}_3\text{O}_3 + 5\text{HO}$. *Chloracetate of silver* is a soluble compound, crystallizing in small greyish scales, which are easily altered by light; it gives, on analysis, $\text{AgO}, \text{C}_4\text{Cl}_3\text{O}_3$, and is consequently anhydrous.

When chloracetic acid is boiled with an excess of ammonia, it is decomposed, with production of chloroform and carbonate of ammonia.



With caustic potassa, it yields a smaller quantity of chloroform, chloride of potassium, carbonate and formate of potassa. The chloride and the formate are secondary products of the reaction of the alkali upon the chloroform.

Normal acetic acid may be reproduced from this curious substitution-compound. When an amalgam of potassium and mercury is put into a strong aqueous solution of chloracetic acid, chemical action ensues, the temperature of the liquid rises, without disengagement of gas, and the solution is found to contain acetate of potassa, chloride of potassium, and some caustic potassa.

ACETONE; PYROACETIC SPIRIT.—When metallic acetates in an anhydrous state are subjected to destructive distillation, they yield, among other products, a peculiar inflammable, volatile liquid, designated by the above names. It is most easily prepared by distilling carefully dried acetate of lead in a large earthen or coated glass retort, by a heat gradually raised to redness; the retort must be connected with a condenser well supplied with cold water. Much gas is evolved, chiefly

carbonic acid, and the volatile product, but slightly contaminated with tar, collects in the receiver. The retort is found after the operation to contain minutely-divided metallic lead, which is sometimes pyrophoric. The crude acetone is saturated with carbonate of potassa, and afterwards rectified in a water-bath from chloride of calcium. This compound may also be prepared by passing the vapour of strong acetic acid through an iron tube heated to dull redness; the acid is resolved into acetone, carbonic acid, carbonic oxide, and carbonetted hydrogen.


Pure acetone is a colourless limpid liquid, of peculiar odour; it has a density of 0.792, and boils at 132° ($55^{\circ}\cdot5\text{C}$); the density of its vapour is 2.022. Acetone is very inflammable, and burns with a bright flame; it is miscible in all proportions with water, alcohol, and ether. The simplest formula of this substance, which is produced by the resolution of acetic acid into acetone and carbonic acid, is $\text{C}_3\text{H}_5\text{O}$; but it is probable that this formula should be doubled.

When acetone is distilled with half its volume of Nordhausen sulphuric acid, an oily liquid is obtained, which in a state of purity has a feeble garlic odour. It is lighter than water, and very inflammable. It contains $\text{C}_{18}\text{H}_{12}$, and is produced by the abstraction of the elements of water from acetone. It has received the name *mesitolole*. If pentachloride of phosphorus be dropped into carefully-cooled acetone, and the whole mixed with water, a heavy oily liquid separates, which is stated to contain $\text{C}_6\text{H}_5\text{Cl}$. When this is dissolved in alcohol, and mixed with caustic potassa, a second oily product results. This is lighter than water, has an aromatic odour, and contains $\text{C}_6\text{H}_5\text{O}$.

Sir Robert Kane has described a number of other compounds formed by the action of acids, and other chemical agents, on acetone, from which he has inferred the existence of an organic salt-basyle, containing C_6H_5 , and to which the name of *mesityl* has been given. Zeise, on the other hand, has shown that by the action of chloride of platinum upon acetone, a yellow crystallizable compound can be obtained, having a composition expressed by the formula $\text{C}_6\text{H}_5\text{O} + \text{PtCl}_2$.

Acetic acid is not the only source of acetone; it is produced in the destructive distillation of citric acid, and may be procured from sugar, starch, and gum, by distillation with 8 times their weight of powdered quicklime. The acetone is, in this case, accompanied by an oily, volatile liquid, separable by water, in which it is insoluble. This substance is called *metacetone* or *propione*; it contains $\text{C}_5\text{H}_5\text{O}$, its boiling-point is 212° (100°C).

When acetate of potassa is heated with a great excess of caustic alkali it is converted, as has been already remarked,* into carbonic acid and light carbonetted hydrogen, by the reaction of the oxygen of the water of the hydrate upon the carbon of the acid.



* See page 169.

PROPIONIC ACID.—Metacetone distilled with a mixture of bichromate of potassa and sulphuric acid yields, among other products, *metacetic* or *propionic acid*, $C_6H_5O_3.HO$, a volatile acid, very closely resembling acetic acid, and chiefly distinguished from that substance by the high degree of solubility of its soda-salt. Mr. Morley has lately shown that propionate of baryta, when submitted to destructive distillation, yields again propione. Propionic acid is one of the products of the action of hydrate of potassa in a melted state upon sugar, and is also generated by the fermentation of glycerin. The formation of this substance by the action of potassa upon cyanide of ethyl has been already mentioned, page 426. See also page 479.

KAKODYL AND ITS COMPOUNDS.

The substance long known under the name of *fuming liquor of Cadet*, prepared by distilling a mixture of dry acetate of potassa and arsenious acid, has been shown by M. Bunsen to be the oxide of an *isolable* organic basyl, capable of forming a vast number of combinations displacing other bodies, and being in turn displaced by them, in the same manner as a metal. The investigation of this difficult subject reflects the highest honour on the patience and skill of the discoverer. Kakodyl, so named from its poisonous and offensive nature, contains three elements, viz., carbon, hydrogen, and arsenic.

Table of the most important Kakodyl-Compounds.

Kakodyl (symbol Kd)	C_4H_6As .
Oxide of kakodyl	KdO.
Chloride of kakodyl	KdCl.
Chloride of kakodyl and copper	$KdCl + Cu_2Cl$.
Oxy-chloride of kakodyl	$3KdCl + KdO$.
Terchloride of kakodyl	$KdCl_3$.
Bromide of kakodyl	KdBr.
Iodide of kakodyl	KdI.
Cyanide of kakodyl	KdCy.
Kakodylic acid	KdO_3 .
Kakodylate of silver	AgO, KdO_3 .
Kakodylate of kakodyl	KdO, KdO_3 .
Sulphide of kakodyl	KdS.
Sulphide of kakodyl and copper	$KdS + 3CuS$.
Tersulphide of kakodyl	KdS_3 .
Sulphur-salts containing tersulphide of kakodyl.	}	$KdS, KdS_3—AuS, KdS_3$.
		$CuS, KdS_3—PbS, KdS_3$.
Selenide of kakodyl	KdSe.

OXIDE OF KAKODYL; CADET'S FUMING LIQUID; ALKARSIN; KdO.—Equal weights of acetate of potassa and arsenious acid are intimately mixed and introduced into a glass retort connected with a condenser and tubulated receiver, cooled by ice: a tube is attached to the receiver to carry away the permanently-gaseous products to some distance from the experimenter. Heat is then applied to the retort, which is gradually increased to redness. At the close of the operation, the receiver is found to contain two liquids, besides a quantity of reduced arsenic: the heavier of these is the oxide of kakodyl in a coloured and impure condition; the other chiefly consists of water, acetic acid, and acetone. The gas given off during distillation is principally carbonic acid. The crude oxide of kakodyl is repeatedly washed by agitation with water, previously freed from air by boiling, and afterwards re-distilled from hydrate of potassa in a vessel filled with pure hydrogen gas. All these operations must be conducted in the open air, and the strictest precautions adopted to avoid the accidental inhalation of the smallest quantity of the vapour or its products.

Oxide of kakodyl is a colourless, ethereal liquid of great refractive power; it is much heavier than water, having a density of 1.462. It is very slightly soluble in water, but easily dissolved by alcohol; its boiling-point approaches 302° (150°C), and it solidifies to a white crystalline mass at 9° (-12°C). The odour of this substance is extremely offensive, resembling that of arsenetted hydrogen; the minutest quantity attacks the eyes and the mucous membrane of the nose: a larger dose is highly dangerous. When exposed to the air, oxide of kakodyl emits a dense white smoke, becomes heated, and eventually takes fire, burning with a pale flame, and producing carbonic acid, water, and a copious cloud of arsenious acid. It explodes when brought into contact with strong nitric acid, and inflames spontaneously when thrown into chlorine gas. The density of the vapour of this body is about 7.5. Oxide of kakodyl is generated by the reaction of arsenious acid on the elements of acetone, carbonic acid being at the same time formed; the accompanying products are accidental:—

2 eq. acetone, $\text{C}_6\text{H}_6\text{O}_2$, and 1 eq. arsenious acid, $\text{AsO}_3=1$ eq. oxide kakodyl, $\text{C}_4\text{H}_6\text{AsO}$, and 2 eq. carbonic acid, C_2O_4 .

CHLORIDE OF KAKODYL, KdCl.—A dilute alcoholic solution of oxide of kakodyl is cautiously mixed with an equally dilute solution of corrosive sublimate, avoiding an excess of the latter; a white crystalline, inodorous precipitate falls, containing $\text{KdO}+2\text{HgCl}$; when this is distilled with concentrated liquid hydrochloric acid, it yields corrosive sublimate, water, and *chloride of kakodyl*, which distils over. The product is left some time in contact with chloride of calcium and a little quicklime, and then distilled alone in an atmosphere of carbonic acid. The pure chloride is a colourless liquid, which does not fume in the air, but emits a vapour even more fearful

in its effects, and more insupportable in odour than that of the oxide. It is heavier than water, and insoluble in that liquid, as also in ether; alcohol, on the other hand, dissolves it with facility. The boiling-point of this compound is a little above 212° (100°C); its vapour is colourless, spontaneously inflammable in the air, and has a density of 4.56. Dilute nitric acid dissolves the chloride without change; with the concentrated acid ignition and explosion occur. Chloride of kakodyl combines with subchloride of copper to a white, insoluble, crystalline double salt, containing $\text{KdCl} + \text{Cu}_2\text{Cl}$, and also with oxide of kakodyl.

KAKODYL IN A FREE STATE may be obtained by the action of metallic zinc, iron, or tin upon the above-described compound. Pure and anhydrous chloride of kakodyl is digested for three hours, at a temperature of 212° (100°C), with slips of clean metallic zinc contained in a bulb blown upon a glass tube, previously filled with carbonic acid gas, and hermetically sealed. The metal dissolves quietly without evolution of gas. When the action is complete, and the whole cool, the vessel is observed to contain a white saline mass, which, on the admission of a little water, dissolves, and liberates a heavy oily liquid, the kakodyl itself. This is rendered quite pure by distillation from a fresh quantity of zinc, the process being conducted in the little apparatus shown in the margin, which is made from a piece of glass tube, and is intended to serve the purpose both of retort and receiver. The zinc is introduced into the upper bulb, and the tube drawn out in the manner represented. The whole is then filled with carbonic acid, and the lower extremity put into communication with a little hand-syringe. On dipping the point *a* into the

Fig. 165.



crude kakodyl, and making a slight movement of exhaustion, the liquid is drawn up into the bulb. Both extremities are then sealed in the blowpipe flame, and after a short digestion at 212° (100°C) or a little above, the pure kakodyl is distilled off into the lower bulb, which is kept cool. It forms a colourless, transparent, thin liquid, much resembling the oxide in odour, and surpassing that substance in inflammability. When poured into the air, or into oxygen gas, it ignites instantly; the same thing happens with chlorine. With very limited access of air it throws off white fumes, passing into oxide, and eventually into kakodylic acid. Kakodyl boils at 338° (170°C), and when cooled to 21° (-6°C) crystallizes in large, transparent, square prisms. It combines directly with sulphur and chlorine, and, in fact, may readily be

made to furnish all the compounds previously derived from the oxide. It constitutes the most perfect type of an organic *quasi-metal* which chemistry yet possesses.

Kakodyl is decomposed by a temperature inferior to redness into metallic arsenic, and a mixture of 2 measures light carbonetted hydrogen, and 1 measure olefiant gas.

Chloride of kakodyl forms a *hydrate*, which is thick and viscid, and readily decomposable by chloride of calcium, which withdraws the water. In the preparation of the chloride, and also in other operations, a small quantity of a red amorphous powder is often obtained, called *erythrasin*. This is insoluble in water, alcohol, ether, and caustic potassa, but is gradually oxidized by exposure to the air, with production of arsenious acid. It contains $C_4H_6O_3As_3$.

IODIDE OF KAKODYL, KdI.—This is a thin, yellowish liquid, of offensive odour, and considerable specific gravity, prepared by distilling oxide of kakodyl with strong solution of hydriodic acid. A yellow crystalline substance is at the same time formed, which is an oxy-iodide. *Bromide* and *fluoride* of kakodyl have likewise been obtained and examined.

SULPHIDE OF KAKODYL, KdS, is prepared by distilling chloride of kakodyl with a solution of the bisulphide of barium and hydrogen. It is a clear, thin, colourless liquid, smelling at once of alkarsin and mercaptan, insoluble in water, and spontaneously inflammable in the air. Its boiling-point is high, but it distils easily with the vapour of water. The substance dissolves sulphur, and generates tersulphide of kakodyl, KdS_3 , which is a sulphur-acid, and combines with the sulphides of gold, copper, bismuth, lead, and antimony.

CYANIDE OF KAKODYL, KdCy.—The cyanide is easily formed by distilling alkarsin with strong hydrocyanic acid, or cyanide of mercury. Above 91° ($32^\circ 7C$) it is a colourless, ethereal liquid, but below that temperature it crystallizes in colourless, four-sided prisms, of beautiful diamond lustre. It boils at about 284° ($140^\circ C$), and is but slightly soluble in water. It requires to be heated before inflammation occurs. The vapour of this substance is most fearfully poisonous: the atmosphere of a room is said to be so far contaminated by the evaporation of a few grains, as to cause instantaneous numbness of the hands and feet, vertigo, and even unconsciousness.

KAKODYLIC ACID (ALKARGEN); KdO_3 .—This is the ultimate product of the action of oxygen at a low temperature upon kakodyl or its oxide: it is best prepared by adding oxide of mercury to that substance, covered with a layer of water, and artificially cooled, until the mixture loses all odour, and afterwards decomposing any kakodylate of mercury, that may have been formed, by the cautious addition of more alkarsin. The liquid furnishes, by evaporation to dryness and solution in alcohol, crystals of the new acid. The sulphide, and other compounds of kakodyl, yield, by exposure to air, the same substance. Kakodylic acid forms brilliant, colourless, brittle crystals, which have the form of a modified square prism; it is permanent in dry air, but deliquescent in a moist atmosphere. It is very soluble in water and in alcohol, but not in ether; the solution has an acid reaction.

When mixed with alkalis and evaporated, a gummy, amorphous mass results. With the oxides of silver and mercury, on the other hand, it yields crystallizable compounds. It unites with oxide of kakodyl, and forms a variety of combinations with metallic salts. Alkargen is exceedingly stable; it is neither affected by red, fuming nitric acid, aqua regia, nor even chromic acid in solution: it may be boiled with these substances without the least change. It is deoxidized, however, by phosphorous acid and protochloride of tin to oxide of kakodyl. Dry hydriodic acid gas decomposes it, with production of water, iodide of kakodyl, and free iodine; hydrochloric acid, under similar circumstances, converts it into a corresponding terchloride, which is solid and crystallizable. Lastly, what is extremely remarkable, this substance is not in the least degree poisonous.

PARAKAKODYLIC OXIDE.—When air is allowed access to a quantity of alkarsin, so slowly that no sensible rise of temperature follows, that body is gradually converted into a thick syrupy liquid, full of crystals of kakodylic acid. Long exposure to air, or the passage of a copious current through the mass, heated to 158° (70°C), fails to induce crystallization of the whole. If in this state water be added, everything dissolves, and a solution results which contains kakodylic acid, partly free, and partly in combination with the oxide of kakodyl. When this liquid is distilled, water, having the odour of alkarsin, passes over, and afterwards an oily liquid, which is the new compound. Impure kakodylic acid remains in the retort.

Parakakodylic oxide, purified by rectification from caustic baryta, is a colourless, oily liquid, strongly resembling alkarsin itself in odour, relations to solvents, and in the greater number of its reactions. It neither fumes in the air, however, nor takes fire at common temperatures; its vapour mixed with air, and heated to 190° (87°C), explodes with violence. By analysis, it is found to have exactly the same composition as ordinary oxide of kakodyl.

SECTION II.

SUBSTANCES MORE OR LESS ALLIED TO ALCOHOL.

WOOD-SPIRIT AND ITS DERIVATIVES.

IN the year 1812, Mr. P. Taylor discovered, among the liquid products of the destructive distillation of dry-wood, a peculiar volatile inflammable liquid, much resembling spirit of wine, to which allusion has already been made. This substance has been shown by MM. Dumas and Péligot to be a second alcohol, forming an ether and a series of compounds, exactly corresponding with those of vinous spirit, and even more complete, in some points, than the latter. Wood-spirit, like ordinary alcohol, may be regarded as an hydrated oxide of a body like ethyl, containing C_2H_3 , called *methyl*.*

A very great number of compound methyl-ethers have been described; they present the most complete parallelism of origin, properties, and constitution with those derived from common alcohol.

Wood-spirit Series.

Methyl (symbol, Me)	C_2H_3
Oxide of methyl	C_2H_3O
Hydride of methyl (marsh-gas)	C_2H_3H
Chloride of methyl	C_2H_3Cl
Iodide of methyl, &c.	C_2H_3I
Zinc-methyl	C_2H_3Zn
Wood-spirit	C_2H_3O, HO
Sulphate of oxide of methyl	C_2H_3O, SO_3
Nitrate of oxide of methyl, &c	C_2H_3O, NO_5
Sulphomethylic acid	$C_2H_3O, 2SO_3, HO$
Formic acid	$C_2H_3O_3, HO$
Chloroform	$C_2H_3Cl_3$

HYDRATED OXIDE OF METHYL; PYROXYLIC SPIRIT; WOOD-SPIRIT; MeO, HO .—The crude wood-vinegar probably contains about $\frac{1}{100}$ part of this substance, which is separated from the great bulk of the liquid


* From μέθυ, wine, and ὕλη, wood; the termination ὕλη, or *yl*, is very frequently employed in the sense of *matter, material*.

by subjecting the whole to distillation, and collecting apart the first portions which pass over. The acid solution thus obtained is neutralized by hydrate of lime, the clear liquid separated from the oil which floats on the surface, and, from the sediment at the bottom of the vessel, is again distilled. A volatile liquid, which burns like weak alcohol, is obtained; this may be strengthened in the same manner as ordinary spirit, by rectification, and ultimately rendered pure and anhydrous, by careful distillation from quicklime, by the heat of a water-bath. Pure wood-spirit is a colourless, thin liquid, of peculiar odour, quite different from that of alcohol, and burning, disagreeable taste: it boils at 152° (66°C), and has a density of 0.798 at 68° (20°C). The density of its vapour is 1.12. Wood-spirit mixes in all proportions with water, when pure; it dissolves resins and volatile oils as freely as alcohol, and is often substituted for alcohol in various processes in the arts, for which purpose it is prepared on a large scale. It may be burned instead of ordinary spirit in lamps; the flame is pale-coloured, like that of alcohol, and deposits no soot. Wood-spirit dissolves caustic baryta; the solution deposits, by evaporation *in vacuo*, acicular crystals, containing $\text{BaO} + \text{MeO}, \text{HO}$. Like alcohol, it dissolves chloride of calcium in large quantity, and gives rise to a crystalline compound, resembling that formed by alcohol, and containing, according to Kane, $\text{CaCl} + 2(\text{MeO}, \text{HO})$.

OXIDE OF METHYL; WOOD-ETHER; MeO .—One part of wood-spirit and 4 parts of concentrated sulphuric acid are mixed and exposed to heat in a flask fitted with a perforated cork and bent tube; the liquid slowly blackens, and emits large quantities of gas, which may be passed through a little strong solution of caustic potassa, and collected over mercury. This is the *wood-spirit ether*, a permanently gaseous substance, which does not liquefy at the temperature of 3° (-16°C). It is colourless, has an ethereal odour, and burns with a pale and feebly luminous flame. Its specific gravity is 1.617. Cold water dissolves about 33 times its volume of this gas, acquiring thereby the characteristic taste and odour of the substance; when boiled, the gas is again liberated. Alcohol, wood-spirit, and concentrated sulphuric acid, dissolve it in still larger quantity.

Under the head of *ether* it has been mentioned that the generally-received relation of this substance to the other ethyl-compounds had been rendered doubtful by recent researches. The same remark of course applies to methylic ether, which is in every respect analogous to common ether. It was first proposed by Berzelius, and has long been urged by MM. Laurent and Gerhardt, that the composition of alcohol being expressed by the formula $\text{C}_4\text{H}_6\text{O}_2$, the true formula of ether was $\text{C}_8\text{H}_{10}\text{O}_2$, and not $\text{C}_4\text{H}_5\text{O}$. The correctness of this view has lately been established by a series of beautiful experiments carried out by Prof. Williamson. He found that the substance produced by dissolving potassium in alcohol, which has the formula $\text{C}_4\text{H}_5\text{O}, \text{KO}$, when acted upon by iodide of ethyl, furnishes iodide of potassium

and perfectly pure ether. This reaction may be expressed by the two following equations:—



That in this reaction, not two equivalents of ether are formed, as represented in the first equation, but that a compound $\text{C}_8\text{H}_{10}\text{O}_2$ is formed, as expressed in the second, is clearly proved by substituting, when acting upon the compound $\text{C}_4\text{H}_5\text{O},\text{KO}$, for the iodide of ethyl, the corresponding methyl-compound. In this case neither common ether nor methyl-ether is formed, but an intermediate compound $\text{C}_6\text{H}_8\text{O}_2 = \text{C}_4\text{H}_5\text{O},\text{C}_2\text{H}_3\text{O}$. This substance is insoluble in water, and has a peculiar odour similar to that of ether, but boils at 50° (10°C).

It is very probable that the substances, which have been described by the terms ethyl and methyl, likewise are not C_4H_5 and C_2H_3 , but C_8H_{10} and C_4H_6 . The limits of this elementary work will not permit us at present to enter into the details of this question, which is still under the discussion of chemists.

CHLORIDE OF METHYL, MeCl .—This compound is most easily prepared by heating a mixture of 2 parts of common salt, 1 of wood-spirit, and 3 of concentrated sulphuric acid; it is a gaseous body, which may be conveniently collected over water, as it is but slightly soluble in that liquid. Chloride of methyl is colourless; it has a peculiar odour and sweetish taste, and burns, when kindled, with a pale flame, greenish towards the edges, like most combustible chlorine-compounds. It has a density of 1.731, and is not liquefied at 0° ($-17^\circ\cdot7\text{C}$). The gas is decomposed by transmission through a red-hot tube, with slight deposition of carbon, into hydrochloric acid gas and a carbonetted hydrogen, which has been but little examined.

IODIDE OF METHYL, MeI , is a colourless and feebly combustible liquid, obtained by distilling together 1 part of phosphorus, 8 of iodine, and 12 or 15 of wood-spirit. It is insoluble in water, has a density of 2.237, and boils at 111° ($43^\circ\cdot8\text{C}$). The density of its vapour is 4.883. The action of zinc upon iodide of methyl in sealed tubes furnishes a colourless gas, apparently a mixture of several substances, among which methyl may occur.* The residue contains iodide of zinc, together with a volatile substance of very disagreeable odour, which absorbs oxygen with so much avidity, that it takes fire when coming in contact with the air. It is zinc-methyl, $\text{C}_4\text{H}_5\text{Zn}$, corresponding to zinc-ethyl (see page 445), and may be obtained by distilling the residue of the reaction of zinc upon iodide of methyl in an apparatus filled with hydrogen. When mixed with water it yields oxide of zinc and light carbonetted hydrogen.

CYANIDE OF METHYL, MeCy .—If a dry mixture of sulphome-

* The same compound is believed to occur among the substances produced by the action of a galvanic current upon acetic acid. See valeric acid, page 477.

thylate of baryta and cyanide of potassium are heated in a retort, a very volatile liquid of a powerful odour distils over. It generally contains hydrocyanic acid and water, from which it is separated by distillation, first over red oxide of mercury, and then over anhydrous phosphoric acid. When thus purified, it has an agreeable aromatic odour, and boils at $170^{\circ}\cdot6$ (77°C). When boiled with potassa, it undergoes a decomposition analogous to that of cyanide of ethyl (see page 426); it absorbs 4 eq. of water, and yields acetic acid and ammonia.



It has been mentioned that this compound may be obtained by abstracting 4 eq. of water from acetate of ammonia by means of phosphoric acid. (See page 453.)

Compounds of methyl with bromine, fluorine, and sulphur have also been obtained.

SULPHATE OF OXIDE OF METHYL, MeO, SO_3 .—This interesting substance is prepared by distilling 1 part of wood-spirit with 8 or 10 of strong oil of vitriol: the distillation may be carried nearly to dryness. The oleaginous liquid found in the receiver is agitated with water, and purified by rectification from powdered caustic baryta. The product, which is the body sought, is a colourless oily liquid, of alliaceous odour, having a density of 1.324, and boiling at 370° ($187^{\circ}\cdot7\text{C}$). It is neutral to test-paper, and insoluble in water, but decomposed by that liquid, slowly in the cold, rapidly and with violence at a boiling temperature, into *sulphomethylic acid* and wood-spirit, which is thus re-produced by hydration of the liberated methylic ether. Anhydrous lime or baryta have no action on this substance; their hydrates, however, and those of potassa and soda, decompose it instantly, with production of a sulphomethylate of the base, and wood-spirit. When neutral sulphate of methyl is heated with common salt, it yields sulphate of soda and chloride of methyl; with cyanide of mercury or potassium, it gives a sulphate of the base, and cyanide of methyl; with dry formate of soda, sulphate of soda and formate of methyl. These reactions possess great interest.

NITRATE OF THE OXIDE OF METHYL, MeO, NO_3 .—One part of nitrate of potassa is introduced into a retort, connected with a tubulated receiver, to which is attached a bottle, containing salt and water, cooled by a freezing-mixture; a second tube serves to carry off the incondensable gases to a chimney. A mixture of one part of wood-spirit and 2 of oil of vitriol is made, and immediately poured upon the nitre; reaction commences at once, and requires but little aid from external heat. A small quantity of red vapour is seen to arise, and an ethereal liquid condenses, in great abundance, in the receiver, and also

in the bottle. When the process is at an end, the distilled products are mixed, and the heavy oily liquid obtained separated from the water. It is purified by several successive distillations by the heat of a water-bath from a mixture of ehloride of caleium and litharge, and, lastly, reetified alone in a retort, furnished with a thermometer passing through the tubulature. The liquor begins to boil at about 140° (60°C); the temperature soon rises to 150° ($65^{\circ}\cdot 5\text{C}$), at which point it remains constant; the product is then collected apart, the first and most volatile portions being contaminated with hydroeyanic acid and other impurities. Even with these preeautions, the nitrate of methyl is not quite pure, as the analytical results show. The properties of the substances, however, remove any doubts respecting its real nature.

Nitrate of methyl is colourless, neutral, and of feeble odour; its density is 1.182; it boils at 150° ($65^{\circ}\cdot 5\text{C}$), and burns, when kindled, with a yellow flame. Its vapour has a density of 2.64, and is eminently explosive; when heated in a flask or globe to 300° (149°C), or a little above, it explodes with fearful violence; the determination of the density of the vapour is, consequently, an operation of danger. Nitrate of methyl is decomposed by a solution of caustic potassa into nitrate of that base and wood-spirit.

OXALATE OF OXIDE OF METHYL. $\text{MeO}, \text{C}_2\text{O}_3$.—This beautiful and interesting substance is easily prepared by distilling a mixture of equal weights of oxalic acid, wood-spirit, and oil of vitriol. A spirituous liquid collects in the receiver, which, exposed to the air, quickly evaporates, leaving the oxalic methyl-ether in the form of rhombic transparent crystalline plates, which may be purified by pressure between folds of bibulous paper, and re-distilled from a little oxide of lead. The product is colourless, and has the odour of common oxalic ether; it melts at 124° ($51^{\circ}\cdot 1\text{C}$), and boils at 322° (161°C). It dissolves freely in alcohol and wood-spirit, and also in water, which, however, rapidly decomposes it, especially when hot, into oxalic acid and wood-spirit. The alkaline hydrates effect the same change even more easily. Solution of ammonia converts it into oxamide and wood-spirit. With dry ammoniacal gas it yields a white, solid substance, which crystallizes from alcohol in pearly cubes; this new body, designated *oxamethylane*, or oxamate of methyl, contains $\text{C}_6\text{H}_5\text{NO}_6 = \text{C}_2\text{H}_3\text{O}, \text{C}_4\text{H}_2\text{NO}_5$.

Many other salts of oxide of methyl have been formed and examined. The *acetate*, $\text{MeO}, \text{C}_4\text{H}_3\text{O}_3$, is abundantly obtained by distilling 2 parts of wood-spirit with 1 of crystallizable acetic acid, and 1 of oil of vitriol. It much resembles acetic ether, having a density of 0.919, and boiling at 136° ($57^{\circ}\cdot 8\text{C}$): the density of its vapour is 2.563. This compound is isomeric with formic ether. *Formate of methyl*, $\text{MeO}, \text{C}_2\text{HO}_3$, is prepared by heating in a retort equal weights of sulphate of methyl and dry formate of soda. It is very volatile, lighter than water, and is isomeric with hydrate of acetic acid. *Chloro-carbonic methyl-ether* is produced by the action of phos-

gene gas upon wood-spirit; it is a colourless, thin, heavy, and very volatile liquid, containing $C_4H_3ClO_4 = C_2H_3O, C_2ClO_3$. It yields with dry ammonia a solid crystallizable substance, called *urethylane*. (See page 432.)

SULPHOMETHYLIC ACID, $MeO, 2SO_3, HO$.—Sulphomethylate of baryta is prepared in the same manner as the sulphovinate; 1 part of wood-spirit is slowly mixed with 2 parts of concentrated sulphuric acid, the whole heated to ebullition, and left to cool, after which it is diluted with water and neutralized with carbonate of baryta. The solution is filtered from the insoluble sulphate, and evaporated, first in a water-bath, and afterwards *in vacuo* to the due degree of concentration. The salt crystallizes in beautiful square colourless tables, containing $BaO, C_2H_3O, 2SO_3 + 2HO$, which effloresce in dry air, and are very soluble in water. By exactly precipitating the base from this substance by dilute sulphuric acid, and leaving the filtered liquid to evaporate in the air, hydrated sulphomethylic acid may be procured in the form of a sour, syrupy liquid, or as minute acicular crystals, very soluble in water and alcohol. It is very instable, being decomposed by heat in the same manner as sulphovinic acid. *Sulphomethylate of potassa* crystallizes in small, nacreous, rhombic tables, which are deliquescent; it contains $KO, C_2H_3O, 2SO_3$. The lead-salt is also very soluble.

FORMIC ACID.—As alcohol by oxidation under the influence of finely-divided platinum gives rise to acetic acid, so wood-spirit, under similar circumstances, yields a peculiar acid product, produced by the substitution of 2 eq. of oxygen for 2 eq. of hydrogen, to which the term *formic acid* is given, from its occurrence in the animal kingdom, in the bodies of ants. The experiment may be easily made by enclosing wood-spirit in a glass jar with a quantity of platinum-black, and allowing moderate access of air; the spirit is gradually converted into formic acid. There has not been found an intermediate product corresponding to aldehyde. Anhydrous formic acid, as in the salts, contains C_2HO_3 , or the elements of 2 eq. carbonic oxide, and 1 eq. water.

Pure hydrate of formic acid, C_2HO_3, HO , is obtained by the action of sulphuretted hydrogen on dry formate of lead. The salt, reduced to fine powder, is very gently heated in a glass tube connected with a condensing apparatus, through which a current of dry sulphuretted hydrogen gas is transmitted. It forms a clear, colourless liquid, which fumes slightly in the air, of exceedingly penetrating odour, boiling at 209° ($98^\circ.5C$), and crystallizing in large brilliant plates when cooled below 32° ($0^\circ C$). The sp. gr. of the acid is 1.235; it mixes with water in all proportions; the vapour is inflammable, and burns with a blue flame. A second hydrate, containing 2 eq. of water, exists; its density is 1.11, and it boils at 223° ($106^\circ.1C$). In its concentrated form this blister is extremely corrosive; it attacks the skin, forming a blister or an ulcer, painful and difficult to heal. A more

dilute acid may be prepared by a variety of processes; starch, sugar, and many other organic substances often yield formic acid when heated with oxidizing agents; a convenient method is the following:—1 part of sugar, 3 of binoxide of manganese, and 2 of water, are mixed in a very capacious retort, or large metal still; 3 parts of oil of vitriol, diluted with an equal weight of water, are then added, and when the first violent effervescence from the disengagement of carbonic acid has subsided, heat is cautiously applied, and a considerable quantity of liquid distilled over. This is very impure; it contains a volatile oily matter, and some substance which communicates a pungency not proper to formic acid in that dilute state. The acid liquid is neutralized with carbonate of soda, and the resulting formate purified by crystallization, and, if needful, by animal charcoal. From this, or any other of its salts, solution of formic acid may be readily obtained by distillation with dilute sulphuric acid. It has an odour and taste much resembling those of acetic acid, reddens litmus strongly, and decomposes the alkaline carbonates with effervescence.

Another process for making formic acid consists in distilling dry oxalic acid, mixed with its own weight of sand or pumice-stone in a glass retort. Carbonic oxide and carbonic acid are disengaged, while a very acid liquid distils, which is formic acid contaminated with a small quantity of oxalic acid. By re-distilling this mixture pure formic acid is obtained. This process yields a very strong acid, but only a small quantity in proportion to the oxalic acid employed.

Formic acid, in quantity, may be extracted from ants by distilling the insects with water, or by simply macerating them in the cold liquid.

Formic acid is readily distinguished from acetic acid by heating it with a little solution of oxide of silver or mercury; the metal is reduced, and precipitated in a pulverulent state, while carbonic acid is evolved: this reaction is sufficiently intelligible. The protochloride of mercury is reduced, by the aid of the elements of water, to calomel, carbonic and hydrochloric acids being formed.

The most important salts of formic acid are the following:—*Formate of soda* crystallizes in rhombic prisms containing 2 eq. of water; it is very soluble, and is decomposed like the rest of the salts by hot oil of vitriol with evolution of pure carbonic oxide. Fused with many metallic oxides, it causes their reduction. *Formate of potassa* is with difficulty made to crystallize from its great solubility. *Formate of ammonia* crystallizes in square prisms; it is very soluble, and is decomposed by a high temperature into hydrocyanic acid and water, the elements of which it contains, $\text{NH}_4\text{O}, \text{C}_2\text{HO}_3 - 4\text{HO} = \text{C}_2\text{NH}$. This decomposition is perfectly analogous to that of acetate of ammonia (see page 453). The salts of *baryta*, *strontia*, *lime*, and *magnesia* form small prismatic crystals, soluble without difficulty. *Formate of lead* crystallizes in small, diverging, colourless needles, which require for solution 40 parts of cold water. The formates of *man-*

ganese, protoxide of iron, zinc, nickel, and cobalt are also crystallizable. That of *copper* is very beautiful, constituting bright blue rhombic prisms of considerable magnitude. Formate of *silver* is white, but slightly soluble, and decomposed by the least elevation of temperature.

CHLOROFORM.—This substance is produced, as already remarked, when an aqueous solution of caustic alkali is made to act upon chloral. It may be obtained with greater facility by distilling alcohol, wood-spirit, or acetone with a solution of chloride of lime. 1 part of hydrate of lime is suspended in 24 parts of cold water, and chlorine passed through the mixture until nearly the whole lime is dissolved. A little more hydrate is then added to restore the alkaline reaction, the clear liquid mixed with one part of alcohol or wood-spirit, and, after an interval of 24 hours, cautiously distilled in a very spacious vessel. A watery liquid containing a little spirit and a heavy oil collect in the receiver; the latter, which is the chloroform, is agitated with water, digested with chloride of calcium, and rectified in a water-bath. It is a thin, colourless liquid of agreeable ethereal odour, much resembling that of Dutch-liquid, and of a sweetish taste. Its density is 1.48, and it boils at $141^{\circ}.8$ (61°C); the density of its vapour is 4.116. Chloroform is with difficulty kindled, and burns with a greenish flame. It is nearly insoluble in water, and is not affected by concentrated sulphuric acid. Alcoholic solution of potassa decomposes it, with production of chloride of potassium and formate of potassa.

Chloroform may be prepared on a larger scale by cautiously distilling together good commercial chloride of lime, water, and alcohol. The whole product distils over with the first portions of water, so that the operation may be soon interrupted with advantage.

This substance has been called strongly into notice from its remarkable effects upon the animal system in producing temporary insensibility to pain when its vapour is inhaled.

Chloroform contains C_2HCl_3 , it is changed to formic acid by the substitution of 3 eq. of oxygen for the 3 eq. of chlorine removed by the alkaline metal.

Bromoform, C_2HBr_3 , is a heavy, volatile liquid, prepared by a similar process, bromine being substituted in the place of chlorine. It is converted by alkali into bromide of potassium and formate of potassa. *Iodoform*, C_2HI_3 , is a solid, yellow, crystallizable substance, easily obtained by adding alcoholic solution of potassa to tincture of iodine, avoiding excess, evaporating the whole to dryness, and treating the residue with water. Iodoform is nearly insoluble in water, but dissolves in alcohol, and is decomposed by alkalis in the same manner as the preceding compounds.

FORMOMETHYLAL.—This is a product of the distillation of wood-spirit with dilute sulphuric acid and binoxide of manganese. The distilled liquid is saturated with potassa, by which the new substance is separated as a light oily fluid. When purified by rectification, it

is colourless, and of agreeable aromatic odour; it has a density of 0.855, boils at 170° (41°C), and is completely soluble in three parts of water. It contains $\text{C}_6\text{H}_8\text{O}_4$. It corresponds to acetal, and may be viewed as a compound of 2 eq. of ether with 1 eq. of the yet unknown aldehyde of the methyl-series, $\text{C}_6\text{H}_8\text{O}_4 = 2\text{C}_2\text{H}_3\text{O}, \text{C}_2\text{H}_2\text{O}_2$.

METHYL-MERCAPTAN is prepared by a process similar to that recommended for ordinary mercaptan, sulphomethylate of potassa being substituted for the sulphovinate of lime. It is a colourless liquid, of powerful alliaceous odour, and lighter than water; it boils at 68° (20°C), and resembles mercaptan in its action on red oxide of mercury.

PRODUCTS OF THE ACTION OF CHLORINE ON THE COMPOUNDS OF METHYL.—Chlorine acts upon the methylic compounds in a manner strictly in obedience to the law of substitution; the carbon invariably remains intact, and every proportion of hydrogen removed is replaced by an equivalent quantity of chlorine. Methylic ether and chlorine, in a dry and pure condition, yield a volatile liquid product, containing $\text{C}_2\text{H}_2\text{ClO}$: the experiment is attended with great danger, as the least elevation of temperature gives rise to a violent explosion. This product in its turn furnishes, by the continued action of the gas, a second liquid containing $\text{C}_2\text{HCl}_2\text{O}$. The whole of the hydrogen is eventually lost, and a third compound, $\text{C}_2\text{Cl}_3\text{O}$, produced.

Chloride of methyl, $\text{C}_2\text{H}_3\text{Cl}$, in like manner gives rise to three successive products. The first, $\text{C}_2\text{H}_2\text{Cl}_2$, is a volatile liquid, much resembling chloride of olefant gas; the second, C_2HCl_3 , is no other than chloroform; the third is bichloride of carbon, C_2Cl_4 .

Some of these substances, especially chloroform and bichloride of carbon, have been obtained also by the action of chlorine on light carbonetted hydrogen (marsh-gas), which thus becomes connected with the methyl-series. It may be regarded as hydride of methyl, a view which is likewise supported by its formation from zinc-methyl (see page 465); thus we have the following series:—

Hydride of methyl	.	.	$\text{C}_2\text{H}_3\text{H}$.	Light carbonetted hydrogen.
Chloride of methyl	.	.	$\text{C}_2\text{H}_3\text{Cl}$.	
Chlorinnetted chloride of methyl			$\text{C}_2\text{H}_2\text{Cl}_2$.	
Bichlorinctted „	„	„	C_2HCl_3 .	Chloroform.
Trichlorinnetted „	„	„	C_2Cl_4 .	Bichloride of carbon.

The acetate of methyl, $\text{C}_6\text{H}_6\text{O}_4$, gives $\text{C}_6\text{H}_4\text{Cl}_2\text{O}_4$, and $\text{C}_6\text{H}_3\text{Cl}_3\text{O}_4$; the other methyl-ethers are without doubt affected in a similar manner.

Commercial wood-spirit is very frequently contaminated with other substances, some of which are with great difficulty separated. It sometimes contains aldehyde, often acetone and propione, and very frequently a volatile oil, which is precipitated by the addition of water, rendering the whole turbid. The latter is a mixture of se-

veral hydrocarbons, very analogous to those contained in coal-tar. A specimen of wood-spirit, from Wattwyl, in Switzerland, was found by Gmelin to contain a volatile liquid, differing in some respects from acetone, to which he gave the term *lignone*. A very similar substance is described by Schweizer and Weidmann, under the name of xylite. Lastly, Mr. Scanlan has obtained from wood-spirit a solid, yellowish-red, crystallizable substance, called *ebalanin*. It is left behind in the retort when the crude spirit is rectified from lime; it is insoluble in water, sublimes without fusion at 273° ($133^{\circ}\cdot9\text{C}$), and contains, according to Dr. Gregory, $\text{C}_{21}\text{H}_9\text{O}_4$.

AMYLIC ALCOHOL AND ITS DERIVATIVES.

In the manufacture of potato-brandy the crude spirit is found to be contaminated with an acrid volatile oil, called *fusel-oil*, which is extremely difficult to separate in a complete manner. Towards the end of the distillation, it passes over in considerable quantity; it may be collected apart, agitated with several successive portions of water to withdraw the spirit with which it is mixed, and re-distilled. According to the researches of M. Cahours, this substance exhibits properties indicative of a constitution analogous to that of alcohol; it may be considered as the hydrate of the oxide of the hydrocarbon, called *amyl*, containing $\text{C}_{10}\text{H}_{11}$. The ether of potato-oil, and a variety of other compounds, corresponding in every point to those of ordinary alcohol, have been formed, as will be manifest from an inspection of the following table:—

Amyl (symbol Ayl)	.	$\text{C}_{10}\text{H}_{11}$
Amyl-ether	.	$\text{C}_{10}\text{H}_{11}\text{O}$
Hydride of amyl	.	$\text{C}_{10}\text{H}_{11}\text{H}$
Potato-oil	.	$\text{C}_{10}\text{H}_{11}\text{O}, \text{NO}$
Chloride of amyl	.	$\text{C}_{10}\text{H}_{11}\text{Cl}$
Bromide of amyl	.	$\text{C}_{10}\text{H}_{11}\text{Br}$
Iodide of amyl	.	$\text{C}_{10}\text{H}_{11}\text{I}$
Zinc-amyl	.	$\text{C}_{10}\text{H}_{11}\text{Zn}$
Acetate of amyl	.	$\text{C}_{10}\text{H}_{11}\text{O}, \text{C}_2\text{H}_3\text{O}_3$
Sulphamylic acid	.	$\text{C}_{10}\text{H}_{11}\text{O}, 2\text{SO}_3, \text{HO}$
Amylene	.	$\text{C}_{10}\text{H}_{10}$
Anhydrous valeric acid	.	$\text{C}_{10}\text{H}_9\text{O}_3$
Valeric acid	.	$\text{C}_{10}\text{H}_9\text{O}_3, \text{HO}$.

HYDRATED OXIDE OF AMYL; FUSEL-OIL; AylO, HO .—The crude fusel-oil of potato-brandy is washed with water, and distilled in a retort furnished with a thermometer, the bulb of which dips into the liquid. The portion which distils between 260° ($126^{\circ}\cdot6\text{C}$) and

280° (137°·8C) is collected apart and re-distilled in the same manner, until an oil is obtained, having a fixed boiling-point at 268°—269° (131°·1C—131°·7C). Thus purified, it is a thin fluid oil, exhaling a powerful and peculiarly suffocating odour, and leaving a burning taste; it inflames with some difficulty, and then burns with a pure blue flame. Its density is 0·818. It undergoes little change by contact with air under ordinary circumstances; but when warmed, and dropped upon platinum-black, it oxidizes to *valeric acid*, which bears the same relation to this substance that acetic acid does to ordinary alcohol, or formic acid to methyl-alcohol.

The action of heat upon fusel-oil has been lately studied by Captain Reynolds. The vapour of this alcohol, when passed through a red-hot glass-tube, yields a mixture of gases, among which a carbon-hydrogen C_6H_6 predominates, which has the chemical character of olefiant gas, and to which the name *propylene* has been given. The separation of this gaseous mixture has hitherto failed, but on bringing the gas in contact with chlorine a compound $C_6H_6Cl_2$ is formed. This is a heavy liquid boiling at 217°·4 (103°C). It is in every respect analogous to the Dutch-liquid (see page 439), originating under similar circumstances from olefiant gas.

AMYL-ETHER, $AylO$.—If amyl-alcohol is distilled with concentrated sulphuric acid, a mixture of several substances is obtained, which has to be separated by distillation. After several rectifications, an oil is obtained, which has a sp. gr. 0·779 and boils at 348°·8 (176°C). This is amyl-ether. The composition is $C_{10}H_{11}O$, or, if we adopt the double formulæ for the ethers, $C_{20}H_{22}O_2$. Intermediate ethers between amyl- and ethyl-, and likewise between amyl- and methyl-ether, have been prepared. They contain respectively $C_{14}H_{16}O_2 = C_4H_5O$, $C_{10}H_{11}O$ and $C_{12}H_{14}O_2 = C_2H_3O$, $C_{10}H_{11}O$.

CHLORIDE OF AMYL, $Ayl\ Cl$.—The chloride is procured by subjecting to distillation equal weights of potato-oil and pentachloride of phosphorus, washing the product repeatedly with alkaline water, and rectifying it from chloride of calcium. Less pure it may be obtained by saturating fusel-oil with hydrochloric acid. It is a colourless liquid, of agreeable aromatic odour, insoluble in water, and neutral to test-paper; it boils at 215° (101°·7C), and ignites readily, burning with a flame green at the edges. By the long-continued action of chlorine, aided by powerful sunshine, a new product, *chlorinetted chloride of amyl*, was obtained in the form of a volatile colourless liquid, smelling like camphor, and containing $C_{10}H_3Cl_9$: the whole of the hydrogen could not, however, be removed.

BROMIDE OF AMYL, $Ayl\ Br$, is a volatile, colourless liquid, heavier than water. It is obtained by distilling fusel-oil, bromine and phosphorus together. (See bromide of ethyl, page 426.) Its odour is penetrating and alliaceous. The bromide is decomposed by an alcoholic solution of potassa, with production of bromide of the metal.

IODIDE OF AMYL, $Ayl\ I$, is procured by distilling a mixture of 15

parts of potato-oil, 8 of iodine, and 1 of phosphorus. It is colourless when pure, heavier than water, volatile without decomposition at $294^{\circ}\cdot 8$ (146°C), and resembles in other respects the bromide; it is partly decomposed by exposure to light. Iodide of amyl, when heated in sealed tubes with zinc to 374° (190°C), yields *amyl*, a colourless liquid of an ethereal odour containing $\text{C}_{10}\text{H}_{11}$, and boiling at 311° (155°C). Together with this substance there is formed iodide of zinc and zinc-amyl $\text{C}_{10}\text{H}_{11}\text{Zn}$, which, when coming in contact with water is decomposed into oxide of zinc and hydride of amyl, $\text{C}_{10}\text{H}_{12} = \text{C}_{10}\text{H}_{11}\text{H}$, an exceedingly volatile substance, boiling at 86° (30°C).

CYANIDE OF AMYL, *Ayl Cy*.—Colourless liquid of $0\cdot 806$ sp. gr., and boiling at $294^{\circ}\cdot 8$ (146°C), which is obtained by distilling cyanide of potassium with sulphamylate of potassa. Boiled with potassa, this compound acid undergoes a decomposition analogous to that of cyanide of ethyl and methyl (see pages 426 and 465); it absorbs 4 eq. of water, and furnishes ammonia and the potassa-salt of caproic acid, $\text{C}_{12}\text{H}_{12}\text{O}_4$, one of the constituents of butter, $\text{C}_{12}\text{H}_{11}\text{N} + 4\text{HO} = \text{C}_{12}\text{H}_{12}\text{O}_4 + \text{NH}_3$.

ACETATE OF OXIDE OF AMYL, *AylO*, $\text{C}_4\text{H}_9\text{O}_3$.—This interesting product is easily obtained by submitting to distillation a mixture of 1 part of potato-oil, 2 parts of acetate of potassa, and 1 part of concentrated sulphuric acid; it is purified by washing with dilute alkali, and distillation from chloride of calcium. It presents the appearance of a colourless, limpid liquid, which is insoluble in water, soluble in alcohol, boils at 272° ($133^{\circ}\cdot 3\text{C}$), and becomes converted by an alcoholic solution of potassa into an acetate of that base, with reproduction of fusel-oil. This ether possesses in a remarkable manner the odour of the Jargonelle-pear. It is now manufactured upon a large scale for flavouring liquors and confectionary.

CARBONATE OF OXIDE OF AMYL, *AylO*, CO_2 .—This ether has been lately obtained by Mr. Medlock by saturating fusel-oil with phosgene-gas (chloro-carbonic acid). A compound, *AylO*, C_2ClO_3 , analogous to chloro-carbonic ether is first produced, which, when treated with water, yields hydrochloric and carbonic acids, together with carbonate of amyl ($\text{AylO}, \text{C}_2\text{ClO}_3 + \text{HO} = \text{AylO}, \text{CO}_2 + \text{HCl} + \text{CO}_2$). Carbonate of amyl is a colourless liquid of an aromatic odour, boiling at $438^{\circ}\cdot 8$ (226°C). Alcoholic solution of potassa converts this ether into fusel-oil, carbonate of potassa being formed at the same time.

Sulphide of amyl, *amyl-mercaptan*, and numerous other compounds of like nature, have been described.

SULPHAMYLIC ACID.—When equal weights of potato-oil and strong sulphuric acid are mixed, heat is evolved, accompanied by blackening and partial decomposition. The mixture diluted with water, and saturated with carbonate of baryta, affords sulphate of that base, and a soluble salt corresponding to the sulphovinate. The latter may be obtained in a crystalline state by gentle evaporation, and purified by re-solution and the use of animal charcoal. It forms small, brilliant,

pearly plates, very soluble in water and alcohol, containing BaO , $\text{C}_{10}\text{H}_{11}\text{O}_2\text{SO}_3 + \text{HO}$. The baryta may be precipitated from the salt by dilute sulphuric acid, and the hydrated sulphamylic acid concentrated by spontaneous evaporation to a syrupy, or even crystalline state; it has an acid and bitter taste, strongly reddens litmus-paper, and is decomposed by ebullition into potato-oil and sulphuric acid. The potassa-salt forms groups of small radiated needles, very soluble in water. The sulphamylates of lime and protoxide of lead are also soluble and crystallizable.

AMYLENE.—By the distillation of potato-oil with anhydrous phosphoric acid, a volatile, colourless, oily liquid is procured, quite different in properties from the original substance. It is lighter than water, boils at $102^{\circ}\cdot 2$ (39°C), and contains no oxygen. Its composition is represented by the formula $\text{C}_{10}\text{H}_{10}$; consequently it not only corresponds to olefant gas in the alcohol-series, but is isomeric with that substance. Like olefant gas it combines directly with chlorine and bromine, giving rise to compounds $\text{C}_{10}\text{H}_{10}\text{Cl}_2$ and $\text{C}_{10}\text{H}_{10}\text{Br}_2$. The vapour, however, has a density of 2.68, which is $2\frac{1}{2}$ times that of olefant gas, every measure containing 5 measures of hydrogen.

Together with this substance several other hydrocarbons are formed, especially one to which the name *paramylene* has been given. It contains $\text{C}_{20}\text{H}_{20}$, and boils at 320° (160°C).

VALERIC OR VALERIANIC ACID.—M. Dumas has shown that when a mixture of equal parts quicklime and hydrate of potassa is moistened with alcohol, and the whole subjected to a gentle heat, out of contact of air, the alcohol is oxidized to acetic acid, with evolution of pure hydrogen gas. At a higher temperature the acetate of potassa produced is in turn decomposed, yielding carbonate of potassa and light carbonated hydrogen. Wood-spirit, by similar treatment, yields hydrogen and formate of potassa, which, as the heat increases, becomes converted into carbonate, with continued disengagement of hydrogen. In like manner potato-oil, the third alcohol, suffers, under similar circumstances, conversion into a new acid, bearing to it the same relation that acetic acid does to common alcohol and formic acid to wood-spirit, hydrogen being at the same time evolved. The body thus produced is found to be identical with a volatile oily acid distilled from the root of the *Valeriana officinalis*.

In preparing artificial valeric acid, the potato-oil is heated in a flask with about ten times its weight of the above-mentioned alkaline mixture during the space of 10 or 12 hours; the heat is applied by a bath of oil or fusible-metal raised to the temperature of 390 ($198^{\circ}\cdot 8\text{C}$) or 400° ($204^{\circ}\cdot 4\text{C}$). When cold, the nearly-white solid residue is mixed with water, an excess of sulphuric or phosphoric acid added, and the whole subjected to distillation. The distilled liquid is supersaturated with potassa, evaporated nearly to dryness, to dissipate any undecomposed potato-oil, and then mixed with somewhat diluted sulphuric acid in excess. The greater part of the valeric acid then

separates as an oily liquid, lighter than water: this is a terhydrate of the acid, containing three equivalents of water, one of which is basic. When this hydrate is distilled alone, it undergoes decomposition: water, with a little of the acid, first appears, and eventually the pure acid, in the form of a thin, fluid, colourless oil, of the persistent and characteristic odour of valerian-root. It has a sharp and acid taste, reddens litmus strongly, bleaches the tongue, and burns when inflamed with a bright, yet smoky light. Valeric acid has a density of 0.937; it boils at 370° (175°C). Placed in contact with water, it absorbs a certain quantity, and is itself to a certain extent soluble. The salts of this acid present but little interest, as few among them seem to be susceptible of crystallizing. The liquid acid is found by analysis to contain $\text{C}_{10}\text{H}_9\text{O}_3\cdot\text{HO}$, and the silver-salt, $\text{AgO}\cdot\text{C}_{10}\text{H}_9\text{O}_3$. The ether-compound of valeric acid has been already mentioned (page 430). By treatment with ammonia this ether is converted into *valeramide*, $\text{C}_{10}\text{H}_{11}\text{NO}_2 = \text{C}_{10}\text{H}_9\text{O}_2\cdot\text{NH}_2$ (analogous to acetamide), which, under the influence of anhydrous phosphoric acid, loses 2 more eq. of water, becoming valeronitrile, $\text{C}_{10}\text{H}_9\text{N} = \text{C}_8\text{H}_7\cdot\text{C}_2\text{N}$, or cyanide of butyl. The former is a fusible crystalline substance, the latter a volatile liquid, having a boiling-point of 257° (125°C). It was first obtained by the action of oxidizing agents upon gelatine. (See Section VIII., on the Components of the Animal Body).

A more advantageous mode of preparing valeric acid is the following:—4 parts of bichromate of potassa in powder, 6 parts of oil of vitriol, and 8 parts of water are mixed in a capacious retort; 1 part of pure potato-oil is then added by small portions, with strong agitation, the retort being plunged into cold water to moderate the violence of the reaction. When the change appears complete, the deep-green liquid is distilled nearly to dryness, the product mixed with excess of caustic potassa, and the aqueous solution separated mechanically from a pungent, colourless, oily liquid which floats upon it, and which is valerate of amyl. The alkaline solution is then evaporated to a small bulk, and decomposed by sulphuric acid, as already directed.

Valeric acid is found in *angelica root*, in the bark of *Viburnum opulus*, and probably exists in many other plants; it is generated by the spontaneous decomposition of azotized substances, animal and vegetable, and is produced in many chemical reactions in which oxidizing agents are employed.

If an open jar be set in a plate containing a little water, and having beneath it a capsule with heated platinum-black, upon which potato-oil is slowly dropped in such quantity as to be absorbed by the powder, the sides of the jar become speedily moistened with an acid liquid, which collects in the plate, and may be easily examined. This liquid, saturated with baryta-water, evaporated to dryness, and the product distilled with solution of phosphoric acid, yields valeric acid.


Some very beautiful, and for the progress of organic chemistry, highly-important results have lately been obtained by the action of

electricity upon valeric acid. By submitting a solution of valcrate of potassa to a galvanic current, produced by 4 elements of Bunsen's battery, Dr. Kolbe observed that potassa and pure hydrogen were evolved at the negative pole, while at the positive pole valeric and carbonic acids, an odorous inflammable gas, and an ethereal liquid, made their appearance. The inflammable gas obtained in this reaction is a carbohydrogen C_8H_8 , which had been previously isolated by Mr. Faraday from the oily products separated from compressed oil gas. This substance, to which the name *butylene* has been given, is perfectly analogous to olefiant gas (ethylene), propylene, and amylene, which have been previously described. It combines with chlorine and bromine, forming substances analogous to Dutch-liquid. The oily liquid formed together with butylene, in the electrolysis of valeric acid, is a mixture of several substances, among which a hydrocarbon, of the remarkable composition C_8H_9 , predominates. This body to which the name *butyl* or *valyl* has been given, is a colourless liquid, of an agreeable ethereal odour, and boils at $226^{\circ} \cdot 4$ ($108^{\circ}C$). Kolbe believes that this hydrocarbon must be viewed as a compound analogous to methyl, ethyl, and amyl, and that it forms the radical of an alcohol not discovered at the period of his rescarches, but since found by M. Wurtz, as a constituent of crude fusel-oil (see page 479); this alcohol has the formula C_8H_9O,HO , and is analogous to methyl-,ethyl-, and amyl-alcohols, and furnishes by oxidation the acid $C_8H_7O_3,HO$, i. e., butyric acid, just as the three alcohols mentioned are converted respectively into formic, acetic, and valeric acids. Kolbe considers butyl to be one of the proximate constituents of valeric acid, which he views as an intimate combination of butyl with oxalic acid, butyl-oxalic acid $C_{10}H_9O_3,HO = C_6H_9, C_2O_3,HO$. According to this view, the transformation of valeric acid under the influence of the galvanic current is readily explained. The oxygen evolved at the positive pole by the electrolysis of water oxidizes the oxalic to carbonic acid, and liberates the butyl, portions of which are farther attacked by the oxygen, and deprived of 1 eq. of hydrogen, thus giving rise to the simultancous evolution of butylene. If this view holds good for butyric acid, it must be equally true of propionic, acetic, and formic acid, and of a great number of analogous acids, which will be described in the subsequent chapters of this Manual.

Butyric acid will be propyl-oxalic acid, propionic acid ethyl-oxalic, acetic acid methyl-oxalic, and lastly, formic acid hydro-oxalic acid, thus—

Formic acid	$C_2HO_3,HO = H, C_2O_3,HO$
Acetic acid	$C_4H_3O_3,HO = C_2H_3, C_2O_3,HO$
Propionic acid	$C_6H_5O_3,HO = C_4H_5, C_2O_3,HO$
Butyric acid	$C_8H_7O_3,HO = C_6H_7, C_2O_3,HO$
Valeric acid	$C_{10}H_9O_3,HO = C_8H_9, C_2O_3,HO$

This view is borne out by the electrolytic decomposition of acetic acid, which yields a gas, considered by Kolbe to be methyl. Several collateral facts have furnished additional support to this theory; amongst which may be quoted the remarkable deportment of the ammonia-salts of these acids under the influence of anhydrous phosphoric acid. In this reaction, oxalic, formic, acetic, propionic, and valeric acids, yield respectively cyanogen and the cyanides of hydrogen, methyl, ethyl, and butyl.



We have seen, moreover, that the cyanides of methyl and ethyl, when treated with the alkalis, are readily reconverted into acetic and propionic acid, and in the section on cyanogen it will be shown that this substance and hydrocyanic acid are indeed easily convertible into oxalate and formate of ammonia. All these facts are readily intelligible by the view proposed by Dr. Kolbe.

TRICHLOROVALERIC ACID.—When dry chlorine is passed for a long time into pure valeric acid, in the dark, the gas is absorbed in great quantity, and much hydrochloric acid produced: towards the end of the operation a little heat becomes necessary. The product is a semi-fluid transparent substance, heavier than water, odourless, and of acrid burning taste. It does not congeal when exposed to a very low temperature, but acquires complete fluidity when heated to 86° (30°C). It cannot be distilled without decomposition. When put into water it forms a thin, fluid hydrate, which afterwards dissolves to a considerable extent. This body is freely soluble in alkalis, from which it is again precipitated by the addition of an acid. Trichlorovaleric acid contains $\text{C}_{10}(\text{H}_6\text{Cl}_3)\text{O}_3, \text{HO}$.

QUADRICHLOROVALERIC ACID.—This is the ultimate product of the action of chlorine on the preceding substance, aided by exposure to the sun. It resembles trichlorovaleric acid in appearance and properties, being semi-fluid and colourless, destitute of odour, of powerful pungent taste, and heavier than water. It can neither be solidified by cold, nor distilled without decomposition. In contact with water, it forms a hydrate containing 3 eq. of that substance, which is slightly soluble. In alcohol and ether it dissolves with facility. It forms salts with bases, of which the best defined is that of silver. Quadrichlorovaleric acid is composed of $\text{C}_{10}(\text{H}_5\text{Cl}_4)\text{O}_3, \text{HO}$.

FUSEL-OIL OF GRAIN-SPIRIT.—The fusel-oil, separated in large quantities from grain-spirit by the London rectifiers, consists chiefly of potato-oil (hydrated oxide of amyl) mixed with alcohol and water.—Sometimes it contains in addition more or less of the ethyl- or amyl-compounds of certain fatty acids thought to have been identified with

œnanthic and margaric acids. These last-named substances form the principal part of the nearly solid fat produced in this manner in whiskey-distilleries conducted on the old plan. Mulder has described, under the name of *corn-oil*, another constituent of the crude fusel-oil of Holland; it has a very powerful odour resembling that of some of the umbelliferous plants, and is unaffected by solution of caustic potassa. According to Mr. Rowney, the fusel-oil of the Scotch distilleries contains in addition a certain quantity of capric acid, $C_{20}H_{40}O_4$, which is one of the constituents of butter. Potato-oil has been separated from the spirit distilled from beet-molasses, and from artificial grape-sugar made by the aid of sulphuric acid. Although much obscurity yet hangs over the history of these substances, it is generally supposed that they are products of the fermentation of sugar, and have an origin contemporaneous with that of common alcohol.

PROPYLIC ALCOHOL.—The fusel-oil of *marc-brandy* of the south of France was found by M. Balard to contain potato-oil and œnanthic ether. M. Chamel has lately observed that this fusel-oil contains in addition a new alcohol, which he calls hydrated oxide of trityl, but which receives the more appropriate term propylic alcohol. By repeatedly rectifying the first products obtained in the distillation of the fusel-oil, a substance is at last procured, which boils at $204^{\circ} \cdot 8$ ($96^{\circ}C$), and the composition of which is represented by the formula $C_6H_8O_2 = C_6H_7O,HO$. It is very soluble in water, but does not dissolve in that liquid in all proportions. This liquid possesses all the properties of an alcohol: heated with concentrated sulphuric acid, it yields a conjugate acid analogous to sulphovinic acid, the potassa-salt of which has the formula C_6H_7O,SO_3,KO,SO_3 : when submitted to the action of oxidizing agents, it is readily converted into propiolic acid (see page 457). The fusel-oil of *marc-brandy* appears to contain moreover another alcohol.

BUTYLIC ALCOHOL.—This substance has been lately found by M. Wurtz to be present in certain varieties of potato-oil. In order to obtain it, the potato-oil is submitted to fractional distillation, and the liquid boiling between 226° and 244° (108 and $118^{\circ}C$) repeatedly rectified over hydrate of potassa, until the boiling-point becomes constant at $233 \cdot 6^{\circ}$ ($112^{\circ}C$). Pure butylic alcohol is a colourless liquid, of a powerful odour, lighter than water, in which it dissolves to a certain extent. Its formula is $C_8H_{10}O_2 = C_8H_9O,HO$, i. e., hydrated oxide of butyl. With sulphuric acid it furnishes a conjugate acid, analogous to sulphovinic acid, the potassa-salt of which contains C_8H_9O,SO_3,KO,SO_3 ; when fused with potassa, or submitted to the action of other oxidizing agents, butylic alcohol is converted into butyric acid, which has been noticed already in page 420, and which will be mentioned again in the section on Oils and Fats. The radical butyl, which may be assumed in this new alcohol, has been noticed in page 477.

It is impossible to leave the history of the alcohols without alluding to some results of great importance for the elucidation of organic compounds generally, which the study of these substances has elicited. When describing the several alcohols, discussed in the preceding chapter, we have repeatedly pointed out the remarkable analogy presented by the properties and the general deportment of these bodies. If we compare the composition of these alcohols,

Methyl-alcohol	$C_2 H_4 O_2$
Ethyl-alcohol	$C_4 H_6 O_2$
Propyl-alcohol	$C_6 H_8 O_2$
Butyl-alcohol	$C_8 H_{10} O_2$
Amyl-alcohol	$C_{10} H_{12} O_2$

we find that their formulæ present an unmistakable symmetry. All contain the same amount of oxygen, only the carbon and hydrogen vary. This variation, however, takes place in very simple relations. Thus we find the difference of ethyl- and methyl-alcohol to be $C_4 H_6 O_2 - C_2 H_4 O_2 = C_2 H_2$, the difference of methyl and propyl-alcohol to be $C_6 H_8 O_2 - C_2 H_4 O_2 = C_4 H_4 = 2C_2 H_2$, the difference of amyl- and methyl-alcohol to be $C_{10} H_{12} O_2 - C_2 H_4 O_2 = C_8 H_8 = 4C_2 H_2$. The same elementary difference of course prevails likewise between all the derivatives of the three alcohols:

Iodide of methyl	$C_2 H_3 I$
Iodide of ethyl	$C_4 H_5 I = C_2 H_3 I + C_2 H_2$
Iodide of propyl	$C_6 H_7 I = C_2 H_3 I + 2C_2 H_2$
Iodide of amyl	$C_{10} H_{11} I = C_2 H_3 I + 4C_2 H_2$
or		
Formic acid	$C_2 H O_3, HO$
Acetic acid	$C_4 H_3 O_3, HO = C_2 HO_3, HO + C_2 H_2$
Propionic acid	$C_6 H_5 O_3, HO = C_2 HO_3, HO + 2C_2 H_2$
Valeric acid	$C_{10} H_9 O_3, HO = C_2 HO_3, HO + 4C_2 H_2$

Methylic, ethylic, propylic, butylic, and amylic alcohols are by no means the only members of this class which are known. In the succeeding sections of this work will be noticed a series of compounds, evidently of a perfectly analogous character, which have been discovered in various departments of organic chemistry. By submitting castor-oil to a series of processes, M. Bouis has formed an alcohol, which has been called "caprylic alcohol." According to M. Dumas spermaceti contains another analogous substance, cetylic alcohol, which is a solid; and Mr. Brodie has prepared two alcohols, cerotyllic and mellisic, from ordinary bees' wax. The composition of these substances stands in exactly the same relation to that of the preceding alcohols, which we have pointed out, as will be seen from the following table:—

Caprylic alcohol	. . .	$C_{16}H_{18}O_2 = C_2H_4O_2 + 7C_2H_2$
Cetylic alcohol	. . .	$C_{32}H_{34}O_2 = C_2H_4O_2 + 15C_2H_2$
Cerotic alcohol	. . .	$C_{54}H_{56}O_2 = C_2H_4O_2 + 26C_2H_2$
Melissic alcohol	. . .	$C_{60}H_{62}O_2 = C_2H_4O_2 + 29C_2H_2$

These four alcohols, when submitted to the action of oxidizing agents, are converted into four acids, analogous to formic and acetic acid, and which stand to each other, and to formic and acetic acid, in exactly the same relation as the several alcohols do to each other.

Caprylic acid	. . .	$C_{16}H_{15}O_3, HO = C_2HO_3, HO + 7C_2H_2$
Cetylic acid	. . .	$C_{32}H_{31}O_3, HO = C_2HO_3, HO + 15C_2H_2$
Cerotic acid	. . .	$C_{54}H_{53}O_3, HO = C_2HO_3, HO + 26C_2H_2$
Melissic acid	. . .	$C_{60}H_{59}O_3, HO = C_2HO_3, HO + 29C_2H_2$

A glance at these tables shows that all the alcohols known differ from methyl-alcohol by C_2H_2 , or a multiple of it. At the same time, it is evident that the series by no means regularly ascends. Thus we perceive that between amylic and caprylic alcohols, two alcohols still remain to be discovered; in like manner between caprylic and cetylic alcohols, not less than eight different alcohols are wanting.

Even now the parallel series of volatile acids is far more complete than that of the alcohols. At present the following members of this group are known, which are placed in juxtaposition with the collateral alcohols:—

Methyl-alcohol	. $C_2 H_4 O_2$	Formic acid	. $C_2 H_2 O_4$
Ethyl-alcohol	. $C_4 H_6 O_2$	Acetic acid	. $C_4 H_4 O_4$
Propyl-alcohol	. $C_6 H_8 O_2$	Propionic acid	. $C_6 H_6 O_4$
Butyl-alcohol	. $C_8 H_{10} O_2$	Butyric acid	. $C_8 H_8 O_4$
Amyl-alcohol	. $C_{10} H_{12} O_2$	Valeric acid	. $C_{10} H_{10} O_4$
	$C_{12} H_{14} O_2$	Caproic acid	. $C_{12} H_{12} O_4$
	$C_{14} H_{16} O_2$	Enanthic acid	. $C_{14} H_{14} O_4$
Capryl-alcohol	. $C_{16} H_{18} O_2$	Caprylic acid	. $C_{16} H_{16} O_4$
	$C_{18} H_{20} O_2$	Pelargonic acid	. $C_{18} H_{18} O_4$
	$C_{20} H_{22} O_2$	Capric acid	. $C_{20} H_{20} O_4$
&c.	&c.	&c.	&c.

We might continue the series of acids uninterruptedly to $C_{38}H_{38}O_4$ (balenic acid), and with intervals even much higher up to acids containing 54 and even more equivalents of carbon. Most of the acids belonging to this series have been separated from fats, and hence this series is frequently designated by the name of the series of *fatty acids*.

A series of analogous substances whose composition varies by C_2H_2 , or a multiple of it, is called a series of *homologous* bodies—a name first used by M. Gerhardt, to whom we are much indebted for the elucidation of this subject. It is evident that there exist as many

such homologous series as there are derivatives of any one of the alcohols. We may construct a series of homologous radicals, or ethers, or hydrocarbons.

Methyl	C_2H_3	Methyl-ether	C_2H_3O		C_2H_2
Ethyl	C_4H_5	Ether.	C_4H_5O	Ethylene	C_4H_4
	C_6H_7		C_6H_7O	Propylene	C_6H_6
Butyl	C_8H_9		C_8H_9O	Butylene	C_8H_8
Amyl	$C_{10}H_{11}$	Amyl-ether	$C_{10}H_{11}O$	Amylene	$C_{10}H_{10}$
Caproyl	$C_{12}H_{13}$		$C_{12}H_{13}O$	Caproylene	$C_{12}H_{12}$
	$C_{14}H_{15}$		$C_{14}H_{15}O$		$C_{14}H_{14}$
	$C_{16}H_{17}$		$C_{16}H_{17}O$	Caprylene	$C_{16}H_{16}$

All these series of homologous bodies still present numerous gaps; none perhaps more than that of the alcohols which may be taken as the prototype of all the rest; but since the existence of these homologous series was first pointed out, many gaps have been filled, and it may be expected that before long the rapid strides of organic chemistry will render these series complete.

The properties of the various members belonging to homologous series gradually change as we ascend in the series. The most characteristic alteration is the diminution of volatility. A regular difference between the boiling-points of homologous substances was first pointed out by H. Kopp. As an example the series of fatty acids may be taken:—

		Boiling-points.		Differences.	
		F.	C.	F.	C.
Formic acid	$C_2H_2O_4$	209°	98°·5	}	37°
Acetic acid	$C_4H_4O_4$	246°	119°		20°·5
Propionic acid	$C_6H_6O_4$	284°	140°		38°
Butyric acid	$C_8H_8O_4$	314°·6	157°		30°
Valeric acid	$C_{10}H_{10}O_4$	347°	175°		33°·4
Caproic acid	$C_{12}H_{12}O_4$	388°·4	198°		41°·4
					17°
					18°
					23°

From this table it is evident that the boiling temperature of the homologous acids rises on an average $36°·3$ ($19°·9C$) for every increment of C_2H_2 . A similar regular difference has been observed in the boiling-points of many homologous compounds. As yet, however, the number of cases in which discrepancies occur is very considerable.

The substances discussed in the next three sections have but little relation to the alcohols; they may, however, be here most conveniently described.

BITTER-ALMOND OIL AND ITS PRODUCTS.

BENZOYL SERIES.

The volatile oil of bitter almonds possesses a very high degree of interest, from its study having, in the hands of MM. Liebig and Wöhler, led to the first discovery of a compound organic body capable of entering into direct combination with elementary principles, as hydrogen, chlorine, and oxygen, and playing in some degree the part of a metal. The oil is supposed to be the hydride of a salt-basyle, containing $C_{14}H_5O_2$, called *benzoyl*, from its relation to benzoic acid, which radical is to be traced throughout the whole series; it has been isolated, and will be described among the products of distillation of the benzoates.

Table of Benzoyl-Compounds.

Benzoyl, symbol Bz	.	.	.	$C_{14}H_5O_3$
Hydride of benzoyl; bitter-almond oil	.	.	.	$C_{14}H_5O_2H$
Oxide of benzoyl; anhydrous benzoic acid	.	.	.	$C_{14}H_5O_2O$
Hydrated oxide of benzoyl; benzoic acid	.	.	.	$C_{14}H_5O_2O,HO$
Chloride of benzoyl	.	.	.	$C_{14}H_5O_2Cl$
Bromide of benzoyl	.	.	.	$C_{14}H_5O_2Br.$
Iodide of benzoyl	.	.	.	$C_{14}H_5O_2I$
Sulphide of benzoyl	.	.	.	$C_{14}H_5O_2S.$
Benzoic alcohol	.	.	.	$C_{14}H_7O,HO$


HYDRIDE OF BENZOYL; BITTER-ALMOND OIL; BzH .—This substance is prepared in large quantities, principally for the use of the perfumer, by distilling with water the paste of bitter almonds, from which the fixed oil has been expressed. It certainly does not pre-exist in the almonds; the fat oil obtained from them by pressure is absolutely free from every trace of this principle; it is formed by the action of water upon a peculiar crystallizable substance, hereafter to be described, called *amygdalin*, aided in a very extraordinary manner by the presence of the pulpy albuminous matter of the seed. The crude oil has a yellow colour, and contains a very considerable quantity of hydrocyanic acid, the origin of which is contemporaneous with that of the oil itself: it is agitated with dilute solution of protochloride of iron mixed with hydrate of lime in excess, and the whole subjected to distillation; water passes over, accompanied by the purified essential oil, which is to be left for a short time in contact with a few fragments of fused chloride of calcium to free it from water.

Pure hydride of benzoyl is a thin, colourless liquid, of great refractive power, and peculiar and very agreeable odour; its density is 1.043, and its boiling-point 356° ($180^\circ C$): it is soluble in about 30 parts of water, and is miscible in all proportions with alcohol and ether. Exposed to the air, it greedily absorbs oxygen, and becomes

converted into a mass of crystallized benzoic acid. Heated with solid hydrate of potassa, it disengages hydrogen, and yields benzoate of the base. With the alkaline bisulphites it forms beautiful crystalline compounds. The vapour of the oil is inflammable, and burns with a bright flame and much smoke. It is very doubtful whether pure bitter-almond oil is poisonous; the crude product, sometimes used for imparting an agreeable flavour to puddings, custards, &c., and even publicly sold for that purpose, is in the highest degree dangerous.

OXIDE OF BENZOYL; BENZOIC ACID; BzO .—This is the sole product of the oxidation at a moderate temperature of bitter-almond oil; it is not, however, thus obtained for the purposes of experiment and of pharmacy. Several of the balsams yield benzoic acid in great abundance, more especially the concrete resinous variety known under the name of *gum-benzoin*. When this substance is exposed to a gentle heat in a subliming vessel, the benzoic acid is volatilized, and may be condensed by a suitable arrangement. The simplest and most efficient apparatus for this and all similar operations is the contrivance of Dr. Mohr: it consists of a shallow iron pan, over the bottom of

Fig. 166.



which the substance to be sublimed is thinly spread; a sheet of bibulous paper, pierced with a number of pin-holes, is then stretched over the vessel, and a cap made of thick, strong drawing or cartridge-paper, secured by a string or hoop over the whole. The pan is placed upon a sand-bath and slowly heated to the requisite temperature; the vapour of the acid condenses in the cap, and the crystals are kept by the thin paper diaphragm from falling back again into the pan. Benzoic acid thus obtained assumes the form of light, feathery, colourless crystals,

which exhale a fragrant odour, not belonging to the acid itself, but due to a small quantity of a volatile oil. A more productive method of preparing the acid is to mix the powdered gum-benzoin very intimately with an equal weight of hydrate of lime, to boil this mixture with water, and to decompose the filtered solution, concentrated by evaporation to a small bulk, with excess of hydrochloric acid; the benzoic acid crystallizes out on cooling in thin plates, which may be drained upon a cloth filter, pressed, and dried in the air. By sublimation, which is then effected with trifling loss, the acid is obtained perfectly white.

Benzoic acid is inodorous when cold, but acquires a faint smell when gently warmed; it melts just below 212° ($100^{\circ}C$), and sublimes at a temperature a little above; it boils at 462° ($238^{\circ}8C$), and emits a vapour of the density of 4.27. It dissolves in about 200 parts of cold, and 25 parts of boiling water, and with great facility in alcohol. Benzoic acid is not affected by ordinary nitric acid, even at


a boiling heat. The crystals obtained by sublimation, or by the cooling of a hot aqueous solution, contain an equivalent of water, which is basic, or $C_{14}H_5O_3.HO$. Quite recently M. Gerhardt has succeeded in obtaining anhydrous benzoic acid $C_{14}H_5O_3$. This substance crystallizes in beautiful oblique prisms, which fuse at 91.4° ($33^\circ C$), and are soluble in alcohol and ether, but insoluble in water. Boiled with water it is gradually reconverted into common benzoic acid. The mode of formation of this substance is mentioned under Chloride of Benzoyl, see page 488.

All the benzoates have a greater or less degree of solubility; they are easily formed, either directly or by double decomposition. *Benzoates of the alkalis* and of *ammonia* are very soluble, and somewhat difficult to crystallize. *Benzoate of lime* forms groups of small colourless needles, which require 20 parts of cold water for solution. The salts of *baryta* and *strontia* are soluble with difficulty in the cold. Neutral *benzoate of the sesquioxide of iron* is a soluble compound: but the basic salt obtained by neutralizing as nearly as possible by ammonia a solution of sesquioxide of iron, and then adding benzoate of ammonia, is quite insoluble. Sesquioxide of iron is sometimes thus separated from other metals in practical analysis. Neutral and basic *benzoate of lead* are freely soluble in the cold. *Benzoate of silver* crystallizes in thin transparent plates, which blacken on exposure to light. Some remarkable products, obtained by the action of chlorine upon a solution of benzoate of potassa, will be mentioned in the section on the Organic Bases.

NITROBENZOIC ACID.—When benzoic acid is boiled for several hours with fuming nitric acid, until red fumes cease to appear, it yields a new acid body, in which the elements of hyponitric acid are substituted for an equivalent of hydrogen of the original benzoic acid. Nitrobenzoic acid greatly resembles benzoic acid in character, and contains $C_{14}H_4NO_7.HO = C_{14}(H_4NO_4)O_3.HO$. The remarkable transformation of the amide of this acid, of *nitrobenzamide*, will be noticed under the head of aniline.


SULPHOBENZOIC ACID.—Benzoic acid is soluble without change in concentrated oil of vitriol, and is precipitated by the addition of water; it combines, however, with anhydrous sulphuric acid, generating a compound acid analogous to sulphovinic, but bibasic, forming a neutral and an acid series of salts. The baryta-compound is easily prepared by dissolving in water the viscid mass produced by the union of the two bodies, and saturating the solution with carbonate of baryta. On adding hydrochloric acid to the filtered liquid, and allowing the whole to cool, acid sulphobenzoate of baryta crystallizes out. This salt has an acid reaction, and requires 20 parts of cold water for solution; the neutral salt is much more soluble. The hydrated acid is easily obtained by decomposing the sulphobenzoate of baryta by dilute sulphuric acid; it forms a white, crystalline, deliquescent mass, very stable and permanent, which contains $C_{14}H_5O_3.2SO_3.2HO$.

BENZONE, BENZOPHENONE.—When dry benzoate of lime is distilled at a high temperature, it yields a thick, oily, colourless liquid, of peculiar odour. This is a mixture of several compounds, from which, however, a crystalline substance $C_{13}H_5O$, or $C_{26}H_{10}O_2$, may be isolated, to which the name *benzone* or *benzophenone* has been given. Carbonate of lime remains in the retort; the reaction is thus perfectly analogous to that by which acetone is produced by the distillation of a dry acetate.



The benzophenone is, however, always accompanied by secondary products, due to the irregular and excessive temperature, solid hydrocarbons, carbonic oxide, and *benzol*, a body next to be described.

BENZOL, or BENZINE.—If crystallized benzoic acid be mixed with three times its weight of hydrate of lime, and the whole distilled at a temperature slowly raised to redness in a coated glass or earthen retort, water, and a volatile oily liquid termed *benzol*, pass over, while carbonate of lime, mixed with excess of hydrate of lime, remains in the retort. The benzol separated from the water, and rectified, forms a thin, limpid, colourless liquid, of strong agreeable odour, insoluble in water, but miscible with alcohol, having a density of 0.885, and boiling at 176° ($80^\circ C$); the sp. gr. of its vapour is 2.738. Cooled to 32° ($0^\circ C$), it solidifies to a white, crystalline mass. Benzol contains carbon and hydrogen only, in the proportion of 2 eq. of the former to 1 of the latter, or probably $C_{12}H_6$. It is produced by the resolution of benzoic acid into benzol and carbonic acid, the water taking part in the reaction.



Benzol is identical with the bicarbide of hydrogen, many years ago discovered by Mr. Faraday in the curious liquid condensed during the compression of oil-gas, of which it forms the great bulk, being associated with an excessively volatile hydrocarbon, containing carbon and hydrogen in the ratio of the equivalents, the vapour of which required for condensation a temperature of 0° ($-17^\circ 7 C$). This is the substance which has been described under the name of *butylene*, when treating of valeric acid (see page 477).

A copious source of benzol has been lately shown by Mr. Mansfield to exist in the lightest and most volatile portions of coal-tar oil, which will be noticed in its place under the head of that substance.

SULPHOBENZIDE AND HYPOSULPHOBENZIC ACID.—Benzol combines directly with anhydrous sulphuric acid to a thick viscid liquid, soluble in a small quantity of water, but decomposed by a larger portion, with separation of a crystalline matter, the *sulphobenzide*, which may be washed with water, in which it is nearly insoluble, dissolved in ether, and left to crystallize by spontaneous evaporation. It is a colourless, transparent substance, fusible at 212° ($100^\circ C$), bearing

distillation without change, and resisting the action of acids and other energetic chemical agents. Sulphobenzide contains $C_{12}H_5SO_2$. It may be viewed as benzol in which 1 eq. of hydrogen has been replaced by 1 eq. of sulphurous acid. The acid liquid from which the preceding substance has been separated, neutralized by carbonate of baryta and filtered, yields *hyposulphobenzate of baryta*, which is a soluble salt, but crystallizes in an imperfect manner. By double decomposition with sulphate of copper, a compound of the oxide of that metal is obtained, which forms fine, large regular crystals. The hydrate of hyposulphobenzic acid is prepared by decomposing the copper-salt with sulphuretted hydrogen; a sour liquid is obtained, which furnishes, by evaporation, a crystalline residue, containing $C_{12}H_5SO_2 + HO, SO_3$. The salts of *potassa*, *soda*, *ammonia*, and of the oxides of *zinc*, *iron*, and *silver*, crystallize freely. This compound acid can be prepared by dissolving benzol in Nordhausen sulphuric acid.

NITROBENZOL.—Ordinary nitric acid, even at a boiling temperature, has no action on benzol; the red fuming acid attacks it, with the aid of heat, with great violence. The product, on dilution, throws down a heavy, oily, yellowish, and intensely-sweet liquid, which has an odour resembling that of bitter-almoud oil. Its density is 1.209; it boils at 415° ($212^\circ.8C$), and distils but not without being slightly changed. It is but little affected by acids, alkalis, or chlorine, and is quite insoluble in water. Nitrobenzol contains $C_{12}H_5NO_4$, and may be viewed as benzol, in which 1 eq. of hydrogen is replaced by 1 eq. of hyponitric acid. When nitrobenzol is heated with an alcoholic solution of caustic potassa, and the product subjected to distillation, a red oily liquid passes over: this is a mixture of several substances from which, on cooling, large red crystals separate, which are nearly insoluble in water, but dissolve with facility in ether and alcohol. This compound, which is called *azobenzol*, melts at 149° ($48^\circ.3$), and boils at 379° ($192^\circ.2C$); it contains $C_{12}H_5N$. Together with the azobenzol an oil is produced, which contains $C_{12}H_7N$, and has, like ammonia, the power of combining with acids. It has received the name of *aniline*, and will be described in the section on Organic Bases. The reaction which gives rise to azobenzol and aniline in this case, is not yet perfectly understood, several other substances being simultaneously produced, and a large quantity of nitrobenzol being charred. Nitrobenzol may, however, be entirely converted into aniline, by a most elegant process, discovered by Zinin, namely, by the action of sulphide of ammonium, which will be noticed when treating of aniline.

BINITROBENZOL.—If benzol is dissolved in a mixture of equal volumes of concentrated nitric and sulphuric acids, and the liquid be boiled for some minutes, it solidifies on cooling to a mass of crystals, which are easily fusible, insoluble in water, and readily soluble in alcohol. They contain $C_{12}H_4N_2O_8 = C_{12}(H_4 2NO_4)$, and may be

viewed as benzol, in which 2 eq. of hydrogen are replaced by 2 eq. of hyponitric acid.

Benzol and chlorine combine when exposed to the rays of the sun; the product is a solid, crystalline, fusible substance, insoluble in water, containing $C_{12}H_6Cl_6$, called *chlorobenzol*. When this substance is distilled, it is decomposed into hydrochloric acid, and a volatile liquid, *chlorobenzide*, composed of $C_{12}H_3Cl_3$.


In its chemical relations, benzol exhibits the character of a substance analogous to hydride of methyl (marsh-gas), hydride of ethyl, and hydride of amyl.

Benzol	$C_{12}H_6H =$ Hydride of phenyl.
Sulphobenzol . .	$C_{12}H_5SO_2$.
Nitrobenzol . . .	$C_{12}H_5NO_4$.


The alcohol belonging to this hydride is known; it contains $C_{12}H_6O_2 = C_{12}H_5O, HO$, and will be described among the volatile principles of coal-tar.

CHLORIDE OF BENZOYL, $BzCl$.—This compound is prepared by passing *dry* chlorine gas through pure bitter-almond oil, as long as hydrochloric acid continues to be formed; the excess of chlorine is then expelled by heat. Chloride of benzoyl is a colourless liquid of peculiar, disagreeable, and pungent odour. Its density is 1.106. The vapour is inflammable, and burns with a tint of green. It is decomposed slowly by cold, and quickly by boiling water, into benzoic and hydrochloric acids; with an alkaline hydrate, benzoate of the base, and chloride of the metal, are generated.

Chloride of benzoyl has lately become very interesting on account of some important researches of M. Gerhardt, who succeeded by the aid of this substance in obtaining anhydrous benzoic acid. This compound is produced by the action of chloride of benzoyl upon benzoate of soda.



This reaction is of considerable interest, since it is of general application for the separation of anhydrous acids; and has furnished already a very large number of new bodies. If chloride of benzoyl is made to act upon the soda-salt of another organic acid, peculiar anhydrous double acids are produced. Thus chloride of benzoyl and valerate of potassa furnish on distillation an oily liquid of a pungent odour, which excites tears.



When submitted to distillation, valero-benzoic acid splits into anhydrous benzoic and valeric acids. The latter is a colourless liquid which boils at 419° (215°C). M. Gerhardt is of opinion that the so-called anhydrous acids, obtained by his process, are far from being the anhydrous acids, which chemists are in the habit of assuming in the salts. He considers them as a sort of saline bodies, as the common hydrate, in which the hydrogen is replaced by an organic radical.

Hydrated benzoic acid . . .	$(\text{C}_{14}\text{H}_5\text{O}_2)\text{O}, \text{HO}$
Benzoate of soda . . .	$(\text{C}_{14}\text{H}_5\text{O}_2)\text{O}, \text{NaO}$
Benzoate of benzoyl . . .	$(\text{C}_{14}\text{H}_5\text{O}_2)\text{O}, (\text{C}_{14}\text{H}_5\text{O}_2)\text{O}$
(Anhydrous benzoic acid)	
Valero-benzoic acid . . .	$(\text{C}_{14}\text{H}_5\text{O}_2)\text{O}, (\text{C}_{10}\text{H}_9\text{O}_2)\text{O}$
Hydrated valeric acid . . .	$(\text{C}_{10}\text{H}_9\text{O}_2)\text{O}, \text{HO}$
Valerate of soda . . .	$(\text{C}_{10}\text{H}_9\text{O}_2)\text{O}, \text{NaO}$
Valerate of valeryl . . .	$(\text{C}_{10}\text{H}_9\text{O}_2)\text{O}, (\text{C}_{10}\text{H}_9\text{O}_2)\text{O}$
(Anhydrous valeric acid)	

BENZAMIDE.—When pure chloride of benzoyl and dry ammoniacal gas are presented to each other, the ammonia is energetically absorbed, and a white, solid substance produced, which is a mixture of sal-ammoniac and a highly-interesting body, *benzamide*. The sal-ammoniac is removed by washing with cold water, and the benzamide dissolved in boiling water, and left to crystallize. It forms colourless, transparent, prismatic, or platy crystals, fusible at 239° (115°C), and volatile at a higher temperature. It is but slightly soluble in cold, freely in boiling water, also in alcohol and ether. Benzamide corresponds to oxamide, both in composition and properties; it contains $\text{C}_{14}\text{H}_7\text{NO}_2 = \text{C}_{14}\text{H}_5\text{O}_2, \text{NH}_2$, or benzoate of oxide of ammonium, *minus* 2 eq. of water, and it suffers decomposition by both acids and alkaline solutions, yielding, in the first case, a salt of ammonia and benzoic acid, and, in the second, free ammonia and a benzoate. When distilled it loses again 2 eq. of water, and becomes benzonitrile. (See farther on.)

IODIDE OF BENZOYL, BzI.—This is prepared by distilling the chloride of benzoyl with iodide of potassium; it forms a colourless, crystalline, fusible mass, decomposed by water and alkalis, in the same manner as the chloride. The *bromide* of benzoyl, BzBr, has very similar properties. The *sulphide*, BzS, is a yellow oil, of offensive smell, which solidifies at a low temperature, to a soft, crystalline mass. *Cyanide* of benzoyl, BzCy, obtained by heating the chloride with cyanide of mercury, forms a colourless, oily, inflammable liquid, of pungent odour, somewhat resembling that of cinnamon. All these compounds yield benzamide with dry ammonia.

BENZOIC ALCOHOL.—Quite recently M. Cannizzaro has made the interesting discovery that the action of an alcoholic solution of potassa on oil of bitter-almonds gives rise to the formation of an oily body, heavier than water, and boiling at 400° (204°C), which contains

$C_{14}H_8O_2$, and exhibits in every respect the deportment of an alcohol. When treated with oxidizing agents it furnishes benzoic acid. The action of hydrochloric acid gives rise to the formation of a chloride of the formula $C_{14}H_5Cl$, which boils about 356° ($180^\circ C$). Distillation with acetic and sulphuric acid converts benzoic alcohol into a compound ether of the formula $C_{16}H_{10}O_4 = C_{14}H_7O, C_4H_3O_3$ which has an aromatic pear odour, and boils at 410° ($210^\circ C$). The relation of this new group of substances with ethyl alcohol and its derivatives will become obvious from the following formulæ:—

Ethyl-series.		Benzoyl-series.	
Ethyl alcohol . .	C_4H_5O, HO	Benzoic alcohol	$C_{14}H_7O, HO$
Acetic acid . .	$C_4H_3O_3, HO$	Benzoic acid .	$C_{14}H_5O_3, HO$
Chloride of ethyl	C_4H_5Cl	Chloride .	$C_{14}H_7Cl$
Benz. of ethyl	$C_4H_5O, C_{14}H_5O_3$	Acetate .	$C_{14}H_7O, C_4H_3O_3$

FORMOBENZOIC ACID.—Crude bitter-almond oil is dissolved in water, mixed with hydrochloric acid, and evaporated to dryness: the residue is boiled with ether, which dissolves out the new substance, and leaves sal-ammoniac. Formobenzoic acid forms small, indistinct, white crystals, which fuse, and afterwards suffer decomposition by heat, evolving an odour resembling that of the flowers of the hawthorn, and leaving a bulky residue of charcoal. It is freely soluble in water, alcohol, and ether, has a strongly acid taste and reaction, and forms a series of crystallizable salts with metallic oxides. This substance contains $C_{16}H_7O_5, HO = C_{14}H_6O_2 + C_2HO_3, HO$, or the elements of bitter-almond oil and formic acid: it owes its origin to the peculiar action of strong mineral acids on the hydrocyanic acid of the crude oil, by which that body suffers resolution into formic acid and ammonia. It is decomposed by oxidizing bodies, as binoxide of manganese, nitric acid, and chlorine, into bitter-almond oil and carbonic acid.

HYDROBENZAMIDE.—Pure bitter-almond oil is digested for some hours at about 120° ($49^\circ C$) with a large quantity of strong solution of ammonia: the resulting white crystalline product is washed with cold ether, and dissolved in alcohol; the solution, left to evaporate spontaneously, deposits the *hydrobenzamide* in regular, colourless crystals, which have neither taste nor smell. This substance melts at a little above 212° ($100^\circ C$), is readily decomposed by heat, dissolves with ease in alcohol, but is insoluble in water: the alcoholic solution is resolved by boiling into ammonia and bitter-almond oil; a similar change happens with hydrochloric acid. Hydrobenzamide contains $C_{42}H_{18}N_2$, or the elements of 3 equivalents of bitter-almond oil, and 2 of ammonia, *minus* 6 equivalents of water. When impure bitter-almond oil is employed in this experiment, the products are different, several other compounds being obtained. But even with the pure oil frequently a great variety of substances are formed. Hydroben-

zamide when submitted to the action of chemical processes furnishes a great number of derivatives, of which, however, only one substance, namely, *amarine*, will be described in the section on the Organic Bases.

BENZOIN.—This substance is found in the residue contained in the retort from which bitter-almond oil has been distilled with lime and oxide of iron, to free it from hydrocyanic acid; it is a product of the action of alkalis and alkaline earths on the crude oil, and is said to be only generated in the presence of hydrocyanic acid. It is easily extracted from the pasty mass, by dissolving out the lime and oxide of iron by hydrochloric acid, and boiling the residue in alcohol. Benzoin forms colourless, transparent, brilliant, prismatic crystals, tasteless and inodorous; it melts at 248° (120°C), and distils without decomposition. Water, even at a boiling heat, dissolves but a small quantity of this body; boiling alcohol takes it up in a larger proportion; it dissolves in cold oil of vitriol, with violet colour. Benzoin contains $\text{C}_{14}\text{H}_6\text{O}_2$, or $\text{C}_{28}\text{H}_{12}\text{O}_4$, and is, consequently, an isomeric modification of bitter-almond oil.

BENZILE.—This curious compound is a product of the action of chlorine on benzoin; the gas is conducted into the fused benzoin as long as hydrochloric acid continues to be evolved. It is likewise formed by treating benzoin with fuming nitric acid. The crude product is purified by solution in alcohol. It forms large, transparent, sulphur-yellow crystals, fusible at 200° ($93^{\circ}\cdot 3\text{C}$), unaltered by distillation, and quite insoluble in water. It dissolves freely in alcohol, ether, and concentrated sulphuric acid, from which it is precipitated by water. Benzile is composed of $\text{C}_{14}\text{H}_5\text{O}_2$, or $\text{C}_{28}\text{H}_{10}\text{O}_4$, and is therefore *isomeric with the radical of the benzoyl-series*.

BENZILIC ACID.—Benzoin and benzile dissolve with violet tint in an alcoholic solution of caustic potassa. By long boiling the liquid becomes colourless, and is then found to contain a salt of a peculiar acid, called the *benzilic*, which is easily obtained by adding hydrochloric acid to the filtered liquid, and leaving the whole to cool. Benzilic acid forms small, colourless, transparent crystals, slightly soluble in cold, more readily in boiling water; it melts at 248° (120°C), and cannot be distilled without decomposition. It dissolves in cold concentrated sulphuric acid with a fine carmine-red colour. Benzilic acid contains $\text{C}_{28}\text{H}_{11}\text{O}_3$, HO , or 2 eq. benzile and 2 eq. water.

BENZONITRILE.—When benzoate of ammonia is exposed to destructive distillation, among other products a yellowish volatile oil makes its appearance, having exactly the odour of bitter-almond oil. It is heavier than water, slightly soluble in that liquid, boils at 376° ($191^{\circ}\cdot 1\text{C}$), and contains $\text{C}_{11}\text{H}_5\text{N}$. It is benzoate of ammonia, — 4 eq. of water, (NH_4O , $\text{C}_{11}\text{H}_5\text{O}_3 - 4\text{HO} = \text{C}_{11}\text{H}_5\text{N}$), and stands to this salt in the same relation as cyanogen to oxalate, hydrocyanic acid to formate, and cyanide of methyl to acetate, of ammonia. Benzo-

nitrile likewise may be viewed as a cyanide, when it becomes a member of the phenyl-series, $C_{14}H_5N = C_{12}H_5C_2N$.

BENZOYL.—Benzoate of copper, by dry distillation cautiously conducted, gives a residue containing salicylic and benzoic acid, and an oily distillate which crystallizes on cooling. This substance possesses the odour of the geranium, melts at 158° ($70^{\circ}C$), and contains $C_{14}H_5O_2$. It was discovered by Ettling, and subsequently studied by Stenhouse, and is evidently the radical of the benzoyl-series. By heating with hydrate of potassa it is instantly converted into benzoic acid with disengagement of hydrogen.

BENZIMIDE.—This is a white, inodorous, shining, crystalline substance, occasionally found in crude bitter-almond oil. It is insoluble in water, and but slightly dissolved by boiling alcohol and ether. Oil of vitriol dissolves it with dark indigo-blue colour, becoming green by the addition of a little water. This reaction is characteristic. Benzimide contains $C_{23}H_{11}NO_4$. It may be viewed as derived from an acid benzoate of ammonia by the separation of 4 eq. of water.

A great number of other compounds derived from bitter-almond oil, directly or indirectly, have been described by M. Laurent and others. Many of these contain sulphur; sulphuretted hydrogen and sulphide of ammonium being employed in their preparation.


HIPPURIC ACID.—This interesting substance is in some measure related to the benzoyl-compounds. It occurs, often in large quantity, in combination with potassa or soda, in the urine of horses, cows, and other graminivorous animals. It is prepared by evaporating in a water-bath perfectly fresh cows' urine to about a tenth of its volume, filtering from the deposit, and then mixing the liquid with excess of hydrochloric acid. Cows' urine frequently deposits hippuric acid without concentration, when mixed with a considerable quantity of hydrochloric acid, in which the acid is less soluble than in water. The brown crystalline mass which separates on cooling is dissolved in boiling water, and treated with a stream of chlorine gas until the liquid assumes a light amber colour, and begins to exhale the odour of that substance; it is then filtered, and left to cool. The still impure acid is re-dissolved in water, neutralized with carbonate of soda, and boiled for a short time with animal charcoal; the hot filtered solution is, lastly, decomposed by hydrochloric acid.

Hippuric acid in a pure state crystallizes in long, slender, milk-white, and exceedingly delicate square prisms, which have a slightly bitter taste, fuse on the application of heat, and require for solution about 400 parts of cold water; it also dissolves in hot alcohol. It has an acid reaction, and forms salts with bases, many of which are crystallizable. Exposed to a high temperature, hippuric acid undergoes decomposition, yielding benzoic acid, benzoate of ammonia, and a fragrant oily matter, with a coaly residue. With hot oil of vitriol,

it gives off benzoic acid; boiling hydrochloric acid converts it into benzoic acid and glycocine (gelatin-sugar), which is described in the Section on Animal Chemistry. Hippuric acid contains $C_{18}H_9NO_5, HO$.

The constitution of hippuric acid has been frequently discussed by chemists. Very different views have been proposed. The most probable one is, that it is the amidogen-compound of a peculiar acid—glycobenzoic acid. If hippuric acid be treated with nitrous acid, it undergoes the decomposition peculiar to amidogen-compounds, which has been explained when treating of oxamide (page 412). A new non-nitrogenous acid is formed together with water and pure nitrogen $C_{18}H_8NO_5, HO + NO_3 = C_{18}H_7O_7, HO + HO + 2N$. Glycobenzoic acid is a crystalline substance, slightly soluble in water, but readily dissolved by alcohol and ether. It may be viewed as a conjugate acid, containing benzoic and glycolic acids—2 eq. of water $C_{18}H_7O_7, HO = C_{14}H_6O_4, C_4H_4O_6 - 2HO$. Under the influence of boiling water it splits indeed into benzoic and glycolic acids. Glycocine must be considered as glycolamide $NH_4O, C_4H_5O_5 - 2HO = C_4H_5NO_4$, and this explains the conversion of hippuric acid into benzoic acid and glycocine.

Quite recently M. Dessaignes has succeeded in regenerating hippuric acid by the action of chloride of benzoyl upon the zinc-compound of glycocine.



If, in the preparation of hippuric acid, the urine be in the slightest degree putrid, the hippuric acid is all destroyed during the evaporation, ammonia is disengaged in large quantity, and the liquid is then found to yield nothing but benzoic acid, not a trace of which can be discovered in the unaltered secretion. Complete putrefaction effects the same change; benzoic acid might thus be procured to almost any extent.

When benzoic acid is taken internally, it is rejected from the system in the state of hippuric acid, which is then found in the urine.

HOMOLOGUES OF THE BENZOYL-SERIES.

Toluylic Acid, $C_{16}H_7O_3, HO$.—This substance, which differs from benzoic acid by C_2H_2 , has been lately discovered by Mr. Noad, who obtained it by the action of very dilute nitric acid upon cymol, a carbon-hydrogen occurring in cumin-oil. It is a substance exhibiting the closest analogy with benzoic acid both in its physical characters and in its chemical relations. Like benzoic acid, when treated with fuming

nitric acid, it yields a nitro-acid, nitrotoluylic acid, $C_{16}H_6NO_7, HO = C_{16}(H_6NO_4)O_3, HO$: distilled with lime or baryta, it furnishes a hydrocarbon $C_{14}H_8$, homologous to benzol. The latter substance, which has received the name of *toluol*, is also obtained from other sources, especially from coal-tar and Tolu balsam.

An acid of the formula $C_{18}H_8O_3, HO$, is not yet known, but we may confidently expect that the progress of science will not fail to elicit this substance: even now we are acquainted with a hydrocarbon $C_{16}H_{10}$, homologous to benzol and toluol. This substance, which is called *xytol*, is found in wood-tar and coal-gas naphtha, and stands to the unknown acid $C_{18}H_8O_3, HO$, in the same relation as benzol to benzoic acid. Should the above acid be discovered, we may with certainty predict that, when distilled with excess of lime, it will yield xytol.

Cumic acid, $C_{20}H_{11}O_3, HO$. Another acid, homologous to benzoic acid, was discovered some time ago by MM. Cahours and Gerhardt. It is formed by the oxidation of one of the constituents of cumin-oil, cuminol $C_{20}H_{12}O_2$, which corresponds to oil of bitter almonds. It likewise yields a nitro-acid, nitro-cumic acid $C_{20}H_{10}NO_7, HO = C_{20}(H_{10}NO_4)O_3, HO$, and when distilled is converted into cumol $C_{18}H_{12}$, a hydrocarbon, homologous to benzol, toluol, and xytol.

Of the next series only the hydrocarbon is known. This is cymol $C_{20}H_{14}$, the substance which, as has been mentioned above, is the source of toluyllic acid.

The homology of these substances is clearly exhibited by the following table:—

	Hydrides.	Acids.	Hydrocarbons derived from the acid.
Benzoyl-series	$C_{14}H_5O_2H$	$C_{14}H_5O_3, HO$	$C_{12}H_6$
Toluylic-series .		$C_{16}H_7O_3, HO$	$C_{14}H_8$
Xylyl-series .			$C_{16}H_{10}$
Cumyl-series .	$C_{20}H_{11}O_2H$	$C_{20}H_{11}O_3, HO$	$C_{18}H_{12}$
Cymyl-series .			$C_{20}H_{14}$

This table shows that up to the present moment only the series of hydrocarbons is without a gap, while two acids and three hydrides remain to be discovered.

SALICYL, AND ITS COMPOUNDS.

SALICIN.—The leaves and young bark of the poplar, willow, and several other trees contain a peculiar crystallizable, bitter principle, called *salicin*, which in some respects resembles the vegeto-alkalis cinchonine and quinine, being said to have febrifuge properties. It differs essentially, however, from these bodies in being destitute of nitrogen, and in not forming salts with acids. Salicin may be prepared by exhausting the bark with boiling water, concentrating the solution to a small

bulk, digesting the liquid with powdered protoxide of lead, and then, after freeing the solution from lead by a stream of sulphuretted hydrogen gas, evaporating until the salicin crystallizes out on cooling. It is purified by treatment with animal charcoal and re-crystallization.

Salicin forms small, white, silky needles, of an intensely bitter taste, which have no alkaline reaction. It melts and decomposes by heat, burning with a bright flame, and leaving a residue of charcoal. It is soluble in 5.6 parts of cold water, and in a much smaller quantity when boiling hot. Oil of vitriol colours it deep red. The last experiments of M. Piria give for salicin the formula $C_{26}H_{18}O_{14}$.

When salicin is distilled with a mixture of bichromate of potassa and sulphuric acid, it yields, among other products, a yellow, sweet-scented oil, *which is found to be identical with the volatile oil distilled from the flowers of the Spiræa ulmaria, or common meadow-sweet.* This substance appears to be the hydride of a compound salt-radical, *salicyl*, containing $C_{14}H_5O_4$; it has the properties of a hydrogen-acid.

Table of Salicyl-Compounds.

Salicyl (symb. Sl)	$C_{14}H_5$	O_4
Hydrosalicylic acid	$C_{14}H_5$	O_4H
Salicylide of potassium	$C_{14}H_5$	O_4K
Hydrochlorosalicylic acid	$C_{14}(H_4Cl)$	O_4H
Hydriodosalicylic acid	$C_{14}(H_4I)$	O_4H
Hydrobromosalicylic acid	$C_{14}(H_4Br)$	O_4H
Salicylic acid	$C_{14}H_5$	O_5HO

HYDROSALICYLIC ACID; SALICYLOUS ACID; ARTIFICIAL OIL OF MEADOW-SWEET, SIH.—One part of salicin is dissolved in 10 of water, and mixed in a retort with 1 part of powdered bichromate of potassa, and $2\frac{1}{2}$ parts of oil of vitriol diluted with 10 parts of water; gentle heat is applied, and after the cessation of the effervescence first produced, the mixture is distilled. The yellow oily product is separated from the water, and purified by rectification from chloride of calcium. It is thin, colourless, and transparent, but acquires a red tint by exposure to the air. Water dissolves a sensible quantity of this substance, acquiring the fragrant odour of the oil, and the characteristic property of striking a deep violet colour with a salt of sesquioxide of iron, a property however which is also enjoyed by salicylic acid. Alcohol and ether dissolve it in all proportions. It has a density of 1.173, and boils at 385° ($166^\circ.1C$), when heated alone. Hydrosalicylic acid decomposes the alkaline carbonates even in the cold; it is acted upon with great energy by chlorine and bromine. By analysis it is found to contain $C_{14}H_5O_4$, or the same elements as crystallized benzoic acid; and the density of its vapour is also the same, being 4.276.

SALICYLIDE OF POTASSIUM, KSl.—This compound is easily prepared by mixing the oil with a strong solution of caustic potassa: it separates, on agitation, as a yellow crystalline mass, which may be pressed between folds of blotting-paper, and re-crystallized from alcohol. It forms large, square, golden-yellow tables, which have a greasy feel, and dissolve very easily both in water and alcohol: the solution has an alkaline reaction. When quite dry, the crystals are permanent in the air; but in a humid state they soon become greenish, and eventually change to a black, soot-like substance, insoluble in water, but dissolved by spirit and by solution of alkali, called *melanic acid*. Acetate of potassa is formed at the same time. Melanic acid contains $C_{20}H_8O_{10}$. The crystals of salicylide of potassium contain water which cannot be expelled without partial decomposition of the salt.

SALICYLIDE OF AMMONIUM, NH_4Sl . crystallizes in yellow needles, which are quickly destroyed with production of ammonia and the hydride. *Salicylide of barium*, $BaC_{14}H_5O_4 + 2HO$, forms fine yellow acicular crystals, which are but slightly soluble in the cold. *Salicylide of copper* is a green insoluble powder, containing $CuC_{14}H_5O_4$.

Salicylide of copper by destructive distillation gives, among other products, hydride of salicyl and a solid body forming colourless prismatic crystals, fusible and volatile. It is insoluble in water, but dissolved by alcohol and ether. Nitric acid converts it into anilic and picric acids. (See Indigo). It contains $C_{14}H_5O_3$, and is isomeric with anhydrous benzoic acid.

CHLOROHYDRO-SALICYLIC ACID, $C_{14}(H_4Cl)O_4, H$.—Chlorine acts very strongly upon the hydride of salicyl; the liquid becomes heated, and disengages large quantities of hydrochloric acid. The product is a slightly yellowish crystalline mass, which, when dissolved in hot alcohol, yields colourless tabular crystals of the pure compound, having a pearly lustre. This substance is insoluble in water; it dissolves freely in alcohol, ether, and solutions of the fixed alkalis; from the latter it is precipitated unaltered by the addition of an acid. It is not even decomposed by long ebullition with a concentrated solution of caustic potassa. Heated in a retort, it melts and volatilizes, condensing in the cool part of the vessel in long, snow-white needles. The odour of this substance is peculiar and by no means agreeable, and its taste is hot and pungent.


Chlorohydro-salicylic acid combines with the metallic oxides; with potassa it forms small red crystalline scales, very soluble in water. The corresponding compound of barium, prepared from the foregoing, by double decomposition, is an insoluble crystalline, yellow powder, containing $BaC_{14}(H_4Cl)O_4$.

BROMOHYDRO-SALICYLIC ACID, $C_{14}(H_4Br)O_4, H$.—The bromine-compound is prepared by the direct action of bromine on the hydride of salicyl: it crystallizes in small colourless needles, and very closely

resembles in properties the chloride. The hydride of salicyl dissolves a large quantity of iodine, acquiring thereby a brown colour, but forming no combination; the iodide may, however, be procured by distilling iodide of potassium with chlorohydro-salicylic acid. It sublimes as a blackish-brown fusible mass.

CHLOROSAMIDE.—The action of dry ammoniacal gas on pure chlorohydro-salicylic acid is very remarkable; the gas is absorbed in large quantity, and a solid yellow, resinous-looking compound produced, which dissolves in boiling ether, and separates as the solution cools in fine yellow iridescent crystals: this and a little water are the only products, not a trace of sal-ammoniac can be detected. Chlorosamide is nearly insoluble in water; it dissolves without change in ether, and in absolute alcohol; with hot rectified spirit it is partially decomposed, with disengagement of ammonia. Boiled with an acid, it yields an ammoniacal salt of the acid and chlorohydro-salicylic acid; with an alkali, on the other hand, it gives free ammonia, while chlorohydro-salicylic acid remains dissolved. Chlorosamide contains $C_{24}(H_{15}Cl_3)N_2O_6$; it is formed by the addition of 2 eq. of ammonia to 3 eq. of chlorohydro-salicylic acid, and the subsequent separation of 6 eq. of water. A corresponding and very similar substance, *bromosamide*, is formed by the action of ammonia on bromohydro-salicylic acid.

SALIGENIN.—This curious substance is a product of the decomposition of salicin under the influence of the emulsion or synaptase of sweet almonds; it is also generated by the action of dilute acids. In both cases the salicin is resolved into saligenin and grape-sugar. Saligenin forms colourless, nacreous scales, freely soluble in water, alcohol, and ether. It melts at 180° ($82^\circ C$), and decomposes at a higher temperature. Dilute acids at a boiling heat convert it into a resinous-looking substance $C_{14}H_8O_2$, called *saliretin*. Many oxidizing agents, as chromic acid and oxide of silver, convert this substance into hydride of salicyl: even platinum-black produces this effect. Its aqueous solution gives a deep indigo-blue colour with salts of sesquioxide of iron. Saligenin contains $C_{14}H_8O_4$. Hence the transformation of salicin is represented by the equation:—




Salicin yields with chlorine substitution-compounds containing that element, which are susceptible of decomposition by synaptase, with production of bodies termed *chloro-* and *bichlorosaligenin*. Chlorosaligenin very closely resembles normal saligenin, and contains $C_{14}(H_7Cl)O_4$. Certain products, called by M. Piria *helicin*, *helicoidin*, and *anilotic acid* are described as resulting from the action of dilute nitric acid upon salicin. With strong acid at a high temperature *nitro-salicylic acid* (anilic acid) $C_{14}(H_4HO_4)O_5, HO$, is produced.

SALICYLIC ACID, SiO, HO .—This compound is obtained by heating hydride of salicyl with excess of solid hydrate of potassa; the mix-

ture is at first brown, but afterwards becomes colourless; hydrogen gas is disengaged during the reaction. On dissolving the melted mass in water, and adding a slight excess of hydrochloric acid, the salicylic acid separates in crystals, which are purified by re-solution in hot water. This substance very much resembles benzoic acid; it is very feebly soluble in cold water, is dissolved in large quantities by alcohol and ether, and may be sublimed with the utmost ease. It is charred and decomposed by hot oil of vitriol, and attacked with great violence by strong, heated nitric acid. Salicylic acid contains $C_{11}H_5O_5, HO$.

Salicylic acid can also be prepared with great ease by fusing salicin with excess of hydrate of potassa, and also by the action of a concentrated and hot solution of potassa upon the volatile oil of *Gaultheria procumbens*, which is the methyl-compound of this acid occurring in nature (see essential oils containing oxygen). When salicylic acid is mixed with powdered glass or sand, and exposed to strong and sudden heat in a retort, it is almost entirely converted into carbonic acid and hydrate of phenyl, $C_{12}H_6O_2$, a substance found in considerable proportion in coal-tar-naphtha,—and the same change happens to many of its salts with even greater facility.

PHLORIDZIN.—This is a substance bearing a great likeness to salicin, found in the root-rind of the apple and cherry-tree, and extracted by boiling alcohol. It forms fine, colourless, silky needles, soluble in 1000 parts of cold water, but freely dissolved by that liquid when hot; it is also soluble without difficulty in alcohol. It contains $C_{42}H_{24}O_{20} + 4HO$. Dilute acids convert phloridzin into grape-sugar and a crystallizable sweet substance called *phloretin*, $C_{30}H_{14}O_{10}$.



CUMARIN.—This is the odoriferous principle of the *tonka-bean*. It may be often seen forming minute colourless crystals under the skin of the seed, and between the cotyledons. It is best extracted by macerating the sliced beans in hot alcohol, and, after straining through cloth, distilling off the greater part of the spirit. The syrupy residue deposits on standing crystals of cumarin, which must be purified by pressure from a fat oil which abounds in the beans, and then crystallized from hot water. So obtained, cumarin forms slender, brilliant, colourless needles, fusible at 122° ($50^\circ C$), and distilling without decomposition at a higher temperature. It has a fragrant odour and burning taste; it is very slightly soluble in cold water, more freely in hot water, and also in alcohol. It is unaffected by dilute acids and alkalis, which merely dissolve it. Boiling nitric acid converts it into picric acid, and a hot concentrated solution of potassa into *cumaric*, and eventually into salicylic acid. Cumarin exists in several other plants, as the *Melilotus officinalis*, the *Asperula odorata*, and the *Anthoxanthum odo-*

ratum. According to M. Bleibtreu it contains $C_{18}H_6O_4$. Cumaric acid is $C_{18}H_8O_6$.

CINNAMYL AND ITS COMPOUNDS.

The essential oil of cinnamon seems to possess a constitution analogous to that of bitter-almoud oil; it passes by oxidation into a volatile acid, the *cinnamic*, which resembles in the closest manner benzoic acid. The radical assumed in these substances bears the name of *cinnamyl*; it has not been isolated.

Table of Cinnamyl-Compounds.

Cinnamyl (symbol Ci)	$C_{18}H_7O_2$
Chloride of cinnamyl	$C_{18}H_7O_2Cl$
Hydride of cinnamyl; oil of cinnamon	$C_{16}H_7O_2H$
Hydrated oxide of cinnamyl; cinnamic acid	$C_{18}H_7O_2O, HO$
Cinnamylic alcohol	$C_{18}H_9O, HO$
Cinnamate of cinnamylic ether	$C_{18}H_9O, C_{18}H_7O_8$

HYDRIDE OF CINNAMYL; OIL OF CINNAMON, CIH .—Cinnamon of excellent quality is crushed, infused twelve hours in a saturated solution of common salt, and then the whole subjected to rapid distillation. Water passes over, milky from essential oil, which after a time separates. It is collected and left for a short time in contact with chloride of calcium. This fragrant and costly substance has, like most of the volatile oils, a certain degree of solubility in water; it is heavier than that liquid, and sinks to the bottom of the receiver in which the distilled products have been collected. It contains, according to M. Dumas, $C_{18}H_8O_2$.

CINNAMIC ACID, $CI O, HO$.—When pure oil of cinnamon is exposed to the air, or enclosed in a jar of oxygen, it is quickly converted by absorption of the gas into a mass of white crystalline matter, which is hydrated cinnamic acid: this is the only product. Cinnamic acid is found in Peruvian and Tolu balsams, associated with benzoic acid, and certain oily and resinous substances: it may be procured by the following process in great abundance, and in a state of perfect purity. Old, hard Tolu balsam is reduced to powder and intimately mixed with an equal weight of hydrate of lime; this mixture is boiled for some time in a large quantity of water, and filtered hot. On cooling, cinnamate of lime crystallizes out, while benzoate of lime remains in solution. The impure salt is re-dissolved in boiling water, digested with animal charcoal, and, after filtration, suffered to crystallize. The crystals are drained and pressed; once more dissolved in hot water, and an excess of hydrochloric acid being added, the whole is allowed to cool; the pure cinnamic acid separates in small plates or needle-formed crystals of perfect whiteness. From the original mother-liquor much benzoic acid can be procured.

The crystals of cinnamic acid are smaller and less distinct than those

of benzoic acid, which in most respects it very closely resembles. It melts at 248° (120°C), and enters into ebullition and distils without change at 560° ($293^{\circ}\cdot 3\text{C}$); the vapour is pungent and irritating. Cinnamic acid is much less soluble, both in hot and cold water, than benzoic; a hot saturated solution becomes on cooling a soft-solid mass of small nacreous crystals. It dissolves with perfect ease in alcohol. Boiling nitric acid decomposes cinnamic acid with great energy, and with production of copious red fumes; bitter-almond oil distils over, and benzoic acid remains in the retort in which the experiment is made. When cinnamic acid is heated in a retort with a mixture of strong solution of bichromate of potassa and oil of vitriol, it is almost instantly converted into benzoic acid, which afterwards distils over with the vapour of water: the odour of bitter-almond oil is at the same time very perceptible. The action of chlorine is different; no benzoic acid is formed, but other products, which have not been perfectly studied.

Cinnamic acid forms with bases a variety of salts which are very similar to the benzoates. The crystallized acid contains $\text{C}_{18}\text{H}_7\text{O}_3$, HO. When distilled with an excess of lime or baryta, cinnamic acid undergoes a decomposition analogous to that of benzoic acid; an oily liquid, *cinnamol*, C_{16}H_8 , distils over, whilst a carbonate of the alkaline earth remains behind, $\text{C}_{16}\text{H}_8\text{O}_4 + 2\text{BaO} = 2(\text{BaO}, \text{CO}_2) + \text{C}_{18}\text{H}_6$. This oil is also found in liquid storax, and is frequently described by the term *styröl*. (See resins and balsams.)

CHLOROCINNOSE.—This is the ultimate product of the action of chlorine on oil of cinnamon by the aid of heat. When purified by crystallization from alcohol, it forms brilliant, colourless needles, fusible, and susceptible of volatilization without change. It is not affected by boiling oil of vitriol, and may be distilled without decomposition in a current of ammoniacal gas. Chlorocinnose contains $\text{C}_{18}\text{H}_4\text{Cl}_4\text{O}_2$; it is formed by the substitution in the oil of cinnamon of 4 eq. of chlorine for 4 eq. of hydrogen. The true *chloride of cinnamyl*, $\text{C}_6\text{H}_5\text{Cl}$, seems to be first formed in considerable quantity, and subsequently decomposed by the continued action of the chlorine; it has not been separated in a pure state; it appears as a very thin, fluid oil, convertible into a crystalline mass by strong solution of potassa.

When cinnamon-oil is treated with hot nitric acid, it undergoes decomposition, being converted into hydride of benzoyl and benzoic acid. With a boiling solution of chloride of lime the same thing happens, a benzoate of the base being generated. If the oil be heated with solution of caustic potassa it remains unaffected; with the solid hydrate, however, it disengages pure hydrogen, and forms a potassa-salt, which appears to be the cinnamate. When brought into contact with cold concentrated nitric acid, a crystalline, yellowish, scaly compound is obtained, which is decomposed by water with separation of the oil. With ammonia a solid substance is produced, which also appears to be a direct compound of the two bodies.

Two varieties of oil of cinnamon are met with in commerce of very unequal value, viz., that of China and that of Ceylon; the former being considered the better: both are, however, evidently impure. The pure oil may be extracted from them by an addition of cold, strong nitric acid; the crystalline matter which forms after the lapse of a few hours, separated and decomposed by water, yields pure hydride of cinnamyl.

There can be no doubt that the cinnamic acid in Tolu and Peru balsams is gradually formed by the oxidation of a substance very closely related to the alcohols. When these balsams are first imported they are nearly fluid, but gradually acquire consistence by keeping. By the aid of an alcoholic solution of potassa, a compound sometimes oily, sometimes solid, may be separated from these balsams, which cannot be distilled without partial decomposition. This compound described respectively under the name of *cinnamein* (when oily), and *styracin* (when solid), when distilled with hydrate of potassa, is converted into cinnamic acid and a neutral substance, which likewise occurs in an oily and crystalline modification, and has been called, respectively, *peruvin* and *styrone*. These substances are related to each other in a very remarkable manner. Peruvin may be viewed as the alcohol of cinnamic acid, when cinnamcin becomes the compound ether, consisting of this alcohol and cinnamic acid. This relation will become obvious by the following formulæ:—

Ethyl-series.		Cinnamyl-series.	
Alcohol	. . . C_4H_5O, HO	Peruvin	. . . $C_{18}H_9O, HO$
Acetic acid	. . . $C_4H_3O_3, HO$	Cinnamic acid	$C_{18}H_7O_3, HO$
Acetic ether	. . . $C_4H_5O, C_4H_3O_3$	Cinnamcin	. . . $C_{18}H_9O, C_{18}H_7O_3$

When treated with oxidizing agents, peruvin yields cinnamic acid, or its products of decomposition, oil of bitter-almonds and benzoic acid.

SECTION III.

VEGETABLE ACIDS.

THE vegetable acids constitute a very natural and important family or group of compounds, many of which possess the property of acidity, *i.e.*, acid reaction to litmus-paper, and power of forming stable, neutral, and often crystallizable compounds with bases, to an extent comparable with that of the mineral acids. Some of these bodies are very widely diffused through the vegetable kingdom; others are of much more limited occurrence, being found in some few particular plants only, and very frequently in combination with organic alkaline bases, in conjunction with which certain of them will be found described. Many of the vegetable acids are polybasic; and it is remarkable that in the new products, or pyro-acids, to which they often give rise under the influence of heat, this character is usually lost.

The particular acids now to be described are for the most part of extensive and general occurrence; mention will be made of some of the rarer ones in connection with their respective sources.

Table of Vegetable Acids.

Tartaric acid	$C_8 H_4 O_{10}, 2HO$
Racemic acid	$C_8 H_4 O_{10}, 2HO$
Citric acid	$C_{12} H_5 O_{11}, 3HO$
Aconitic, or equisetic acid	$C_4 H O_3, HO$
Malic acid	$C_8 H_4 O_8, 2HO$
Fumaric acid	$C_4 H O_3, HO$
Tannic acid	$C_{12} H_5 O_9, 3HO$
Gallic acid	$C_7 H O_3, 2HO$

TARTARIC ACID.—This is the acid of grapes, of tamarinds, of the pine-apple, and of several other fruits, in which it occurs in the state of an acid potassa-salt; tartrate of lime is also occasionally met with. The tartaric acid of commerce is wholly prepared from the *tartar* or *argol*, an impure acid tartrate of potassa, deposited from wine, or rather grape-juice, in the act of fermentation. This substance is purified by solution in hot water, the use of a little pipe-clay, and animal charcoal to remove the colouring-matter of the wine, and subsequent crystallization; it then constitutes *cream of tartar*, and serves for the preparation of the acid. The salt is dissolved in boiling water, and

powdered chalk added as long as effervescence is excited, or the liquid exhibits an acid reaction; tartrate of lime and neutral tartrate of potassa result; the latter is separated from the former, which is insoluble, by filtration. The solution of tartrate of potassa is then mixed with excess of chloride of calcium, which throws down all the remaining acid in the form of lime-salt; this is washed, added to the former portion, and then the whole digested with a sufficient quantity of dilute sulphuric acid to withdraw the base and liberate the organic acid. The filtered solution is cautiously evaporated to a syrupy consistence and placed to crystallize in a warm situation.

Tartaric acid forms colourless, transparent crystals, often of large size, which have the figure of an oblique rhombic prism more or less modified: these are permanent in the air, and inodorous; they dissolve with great facility in water, both hot and cold, and are soluble also in alcohol. The solution reddens litmus strongly, and has a pure acid taste. The aqueous solution, as has been mentioned (page 65), possesses right-handed polarization. This solution is gradually spoiled by keeping. Tartaric acid is bibasic; the crystals contain $C_8H_4O_{10}$, $2HO$. This substance is consumed in large quantities by the calico-printer, being employed to evolve chlorine from solution of bleaching-powder in the production of white or *discharged* patterns upon a coloured ground.

TARTRATES OF POTASSA; NEUTRAL TARTRATE; SOLUBLE TARTAR; $2KO, C_8H_4O_{10}$.—The neutral salt may be procured by neutralizing cream of tartar with chalk, as in the preparation of the acid, or by adding carbonate of potassa to cream of tartar to saturation; it is very soluble, and crystallizes with difficulty in right rhombic prisms, which are permanent in the air, and have a bitter, saline taste.

ACID TARTRATE OF POTASSA; CREAM OF TARTAR; $KO, HO, C_8H_4O_{10}$.—The origin and mode of preparation of this substance have been already described. It forms small transparent or translucent prismatic crystals, irregularly grouped together, which grit between the teeth. It dissolves pretty freely in boiling water, but the greater part separates as the solution cools, leaving about $\frac{1}{80}$ or less dissolved in the cold liquid. The salt has an acid reaction, and a sour taste. When exposed to heat in a close vessel, it is decomposed with evolution of inflammable gas, leaving a mixture of finely-divided charcoal and pure carbonate of potassa, from which the latter may be extracted by water. Cream of tartar is almost always produced when tartaric acid in excess is added to a moderately-strong solution of a potassa-salt, and the whole agitated.

TARTRATES OF SODA.—Two compounds of tartaric acid with soda are known: a *neutral salt*, $2NaO, C_8H_4O_{10} + 4HO$; and an *acid salt*, $NaO, HO, C_8H_4O_{10} + 2HO$. Both are easily soluble in water, and crystallize. Tartaric acid and bicarbonate of soda form the ordinary *effervescing draughts*.

TARTRATE OF POTASSA AND SODA; ROCHELLE or SEIGNETTE

SALT; $\text{KO}, \text{NaO}, \text{C}_8\text{H}_4\text{O}_{10} + 8\text{HO}$.—This beautiful salt is made by neutralizing with carbonate of soda a hot solution of cream of tartar, and evaporating to the consistence of thin syrup. It separates in large, transparent, prismatic crystals, the faces of which are unequally developed; these effloresce slightly in the air, and dissolve in $1\frac{1}{2}$ parts of cold water. Acids precipitate cream of tartar from the solution. Rochelle salt has a mild, saline taste, and is used as a purgative.

TARTRATES OF AMMONIA.—The *neutral* tartrate is a soluble and efflorescent salt containing $2\text{NH}_4\text{O}, \text{C}_8\text{H}_4\text{O}_{10} + 2\text{HO}$. The *acid* tartrate, $\text{NH}_4\text{O}, \text{HO}, \text{C}_8\text{H}_4\text{O}_{10}$, closely resembles ordinary cream of tartar. A salt corresponding to Rochelle salt also exists, having oxide of ammonium in place of soda.

The tartrates of *lime*, *baryta*, *strontia*, *magnesia*, and of the oxides of most of the metals proper, are insoluble, or nearly so, in water. Tartrate of *antimony and potassa*, or *tartar-emetic*, is easily made by boiling tetroxide of antimony in solution of cream of tartar; it is deposited from a hot and concentrated solution in crystals derived from an octahedron with rhombic base, which dissolve without decomposition in 15 parts of cold and 3 of boiling water, and have an acid and extremely disagreeable metallic taste. The solution is incompatible with, and decomposed by, both acids and alkalis: the former throw down a mixture of cream of tartar and tetroxide of antimony, and the latter the tetroxide, which is again dissolved by great excess of the reagent. Sulphuretted hydrogen separates all the antimony in the state of tersulphide. Heated in a dry state on charcoal before the blowpipe, it yields a globule of metallic antimony. The crystals contain $\text{KO}, \text{SbO}_3, \text{C}_8\text{H}_4\text{O}_{10} + 2\text{HO}$.*

An analogous compound containing arsenious acid (AsO_3) in place of tetroxide of antimony has been described. It has the same crystalline form as tartar-emetic.

A solution of tartaric acid dissolves hydrated sesquioxide of iron in large quantity, forming a brown liquid which has an acid reaction, and dries up by gentle heat to a brown, transparent, glassy substance, destitute of all traces of crystallization. It is very soluble in water, and the solution is not precipitated by alkalis, fixed or volatile. Indeed, tartaric acid added in sufficient quantity to a solution of sesquioxide of iron or alumina, entirely prevents the precipitation of the bases by excess of ammonia. Tartrate and ammoniacal tartrate of iron are used in medicine, these compounds having a less disagreeable taste than most of the iron-preparations.

* According to Dumas, $\text{KO}, \text{SbO}_3, \text{C}_8\text{H}_4\text{O}_{10} + \text{HO}$. Dried at 212° (100°C), an equivalent of water is lost, and at 428° (220°C), two additional equivalents, leaving the compound $\text{KO}, \text{SbO}_3, \text{C}_8\text{H}_2\text{O}_8$, which can no longer contain ordinary tartaric acid. Nevertheless, when dissolved in water, the crystals again take up the elements of water and reproduce the original salt.

Solution of tartaric acid gives white precipitates with lime- and baryta-water, and with acetate of lead, which dissolve in excess of the acid; with neutral salts of lime and baryta no change is produced. The effect on solutions of potassa-salts has been already noticed.

ACTION OF HEAT ON TARTARIC ACID.—When crystallized tartaric acid is exposed to a temperature of 400° ($204^{\circ}\cdot5\text{C}$) or thereabouts, it melts, loses water, and passes through three different modifications, called in succession *tartralic*, *tartrelic*, and *anhydrous tartaric acid*. The two first are soluble in water, and form salts which have properties completely different from those of ordinary tartaric acid. The third substance, or the anhydrous acid, is a white insoluble powder. All three, in contact with water slowly pass into common tartaric acid. Their composition is thus expressed:—

Ordinary tartaric acid	$\text{C}_8\text{H}_4\text{O}_{10}, 2\text{HO}$
Tartralic acid	$2\text{C}_8\text{H}_4\text{O}_{10}, 3\text{HO}$
Tartrelic acid	$\text{C}_8\text{H}_4\text{O}_{10}, \text{HO}$
Anhydrous acid	$\text{C}_8\text{H}_4\text{O}_{10}$

The analogy borne by these bodies to the several modifications of phosphoric acid will be at once evident.

PYROTARTARIC ACID.—When crystallized tartaric acid is subjected to destructive distillation, a heavy acid liquid containing this substance passes over, accompanied by a large quantity of carbonic acid; in the retort is left a semi-fluid black mass, which, by farther heating, gives combustible gases, an empyrenmatic oil, and a residue of charcoal. The distilled product exhales a powerful odour of acetic acid, and is with great difficulty purified. Pyrotartaric acid forms a series of salts, and an ether; it is supposed to contain $\text{C}_6\text{H}_3\text{O}_5, \text{HO}$. A second pyro-acid sometimes separates in crystals from the preceding compound, and may be obtained in larger quantity by the destructive distillation of cream of tartar; it is composed of $\text{C}_5\text{H}_3\text{O}_3, \text{HO}$.

When tartaric acid is heated to 400° ($204^{\circ}\cdot5\text{C}$) with excess of hydrate of potassa, it is resolved without charring or secondary decomposition into oxalic and acetic acids, which remain in union with the base, and only undergo decomposition at a much higher temperature.

RACEMIC ACID; PARATARTARIC ACID.—The grapes cultivated in certain districts of the Upper Rhine, and also in the Vosges, in France, contain, in association with tartaric acid, another and peculiar acid body, to which the term *racemic acid* is given; it is rather less soluble than tartaric acid, and separates first from the solution of that substance. Between these two acids, however, the greatest possible resemblance exists; they have exactly the same composition, and yield, when exposed to heat, the same products; the salts of racemic acid

correspond also, in the closest manner, with the tartrates. A solution of this acid precipitates a neutral salt of lime, which is not the case with tartaric acid. A solution of racemic acid does not rotate the plane of polarization.

Racemic acid has been lately the subject of some exceedingly interesting researches by M. Pasteur, which have thrown much light upon the relation of this acid to tartaric acid. If racemic acid be saturated with potassa, or soda, or with most other bases, crystals are obtained, which are identical in form and physical properties. By saturating racemic acid, however, with two bases, by forming, for instance, compounds corresponding to Rochelle-salt, which contain potassa and soda or ammonia and soda, and allowing the solution to crystallize slowly, two varieties of crystals are produced, which may be distinguished by their form, namely, as the image and the reflection of the image, or as right-handed and left-handed. If the two kinds of crystals are carefully selected and separately crystallized, in each case crystals of the one variety only are deposited. The composition, the specific gravity, and, in fact, most of the physical properties of these two varieties of racemate of potassa and soda, are invariably the same. They differ, however, somewhat in their chemical characters, and especially in one point, they rotate the plane of polarization in opposite directions. (See page 65.) M. Pasteur assumes in the two varieties of crystals the existence of two modifications of the same acid, which he distinguishes, according as the salts possess right- or left-handed polarization, by the terms *dextroracemic* and *levoracemic acids*. These acids can be separated by converting the above compounds into lead- or baryta-salts, and decomposing them by means of sulphuric acid. In this manner two crystalline acids are obtained, identical in every respect excepting in their deportment with polarized light, and in their crystals behaving as image and reflection. Dextroracemic acid is nothing but common tartaric acid. A mixture of equal parts of the two acids has no longer the slightest effect on polarized light, and exhibits in every respect the deportment of racemic acid.

Within the last few months M. Pasteur, in continuing his beautiful researches, has made the important discovery that racemic acid may be artificially produced by the action of heat upon certain compounds of tartaric acid, which are capable of resisting a high temperature. If tartrate of cinchonine (see further on, the article on cinchonine in the section of the *Vegeto-alkalis*) or tartaric ether be exposed to a temperature of about 338° (170°C), and the product thus formed be repeatedly boiled with water, a solution is obtained, which yields when mixed, after cooling, with an excess of chloride of calcium, a considerable precipitate of racemate of lime. Compounds of levoracemic acid, when submitted to the action of heat, likewise furnish racemic acid. The formation of racemic acid in these reactions is accompanied by the production of a fourth modification of tartaric acid, which M. Pasteur calls inactive

tartaric acid. Like racemic acid it has no action on polarized light, but cannot, like the latter, be resolved into levo- and dextro-racemic acids.

CITRIC ACID.—Citric acid is obtained in large quantity from the juice of limes and lemons; it is found in many other fruits, as in gooseberries, currants, &c., in conjunction with another acid, the malic. In the preparation of this acid, the juice is allowed to ferment a short time, in order that mucilage and other impurities may separate and subside; the clear liquor is then carefully saturated with chalk, which forms, with the citric acid, an insoluble compound. This is thoroughly washed, decomposed by the proper quantity of sulphuric acid, diluted with water, and the filtered solution evaporated to a small bulk, and left to crystallize. The product is drained from the mother-liquor, re-dissolved, digested with animal charcoal, and again concentrated to the crystallizing-point. Citric acid forms colourless, prismatic crystals, which have a pure and agreeably acid taste; they dissolve, with great ease, in both hot and cold water; the solution strongly reddens litmus, and, when long kept, is subject to spontaneous change.

Citric acid is tribasic; its formula in the gently dried and anhydrous silver-salt is $C_{12}H_5O_{11}$. The hydrated acid crystallizes with two different quantities of water, assuming two different forms. The crystals, which separate by spontaneous evaporation from a cold saturated solution, contain $C_{12}H_5O_{11}, 3HO + 2HO$, the last being water of crystallization; while, on the other hand, those which are deposited from a hot solution contain but 4 equivalents of water altogether, three of which are basic. Citric acid is entirely decomposed when heated with sulphuric and nitric acids; the latter converts it into oxalic acid. Caustic potassa, at a high temperature, resolves it into acetic and oxalic acids.* When subjected to the action of chlorine, the alkaline citrates yield among other products chloroform.

The citrates are very numerous, the acid forming, like ordinary phosphoric acid, three classes of salts, which contain respectively 3 eq. of a metallic oxide, 2 eq. of oxide, and 1 eq. of basic water, and 1 eq. oxide and 2 eq. basic water, besides true basic salts, in which the water of crystallization is perhaps replaced by a metallic oxide.

The citrates of the *alkalis* are soluble and crystallizable with greater or less facility; those of *baryta*, *strontia*, *lime*, *lead*, and *silver* are insoluble.

Citric acid resembles tartaric acid in its relations to sesquioxide of iron; it prevents the precipitation of that substance by excess of

* The easy conversion of tartaric and citric acids into a mixture of oxalic and acetic acids by the action of heat, aided by the presence of a powerful base, has led to the idea of the possible pre-existence of these last-named bodies in the two vegetable acids, which may thus be compounded of two acids of simpler constitution, forming *coupled* or *conjugate* acids, of which several have been supposed to exist. These views, although sometimes useful, are not at present supported by evidence of great importance.

ammonia. The citrate, obtained by dissolving the hydrated sesquioxide in solution of citric acid, dries up to a pale-brown, transparent, amorphous mass, which is not very soluble in water; an addition of ammonia increases the solubility. Citrate and ammonio-citrate of iron are elegant medicinal preparations. Very little is known respecting the composition of these curious compounds; the absence of crystallization is a great bar to inquiry.

Citric acid is sometimes adulterated with tartaric; the fraud is easily detected by dissolving the acid in a little cold water, and adding to the solution a small quantity of acetate of potassa. If tartaric acid be present, a white, crystalline precipitate of cream of tartar will be produced on agitation.


ACONITIC, OR EQUISETIC ACID.—When crystallized citric acid is heated in a retort until it begins to become coloured, and to undergo decomposition, and the fused, glassy product, after cooling, dissolved in water, an acid is obtained, differing completely in properties from citric acid, but identical with an acid extracted from the *Aconitum napellus* and the *Equisetum fluviatile*. Aconitic acid forms a white, confusedly-crystalline mass, permanent in the air, and very soluble in water, alcohol, and ether; the solution has an acid and astringent taste. The salts of aconitic acid possess but little interest; that of *baryta* forms an insoluble gelatinous mass; *aconitate of lime*, which has a certain degree of solubility, is found abundantly in the expressed juice of the monkshood, and *aconitate of magnesia* in that of the *equisetum*.

Hydrated aconitic acid contains $C_4H_3O_3.HO$; it is formed in the artificial process above described, by the breaking up of 1 eq. of hydrated citric acid, $C_{12}H_8O_{14}$, into 2 eq. of water and 3 eq. of hydrated aconitic acid. There are, however, invariably many secondary products formed, such as acetone, carbonic oxide, and carbonic acid. The farther action of heat upon aconitic acid gives rise to several new acids, especially *citraconic* and *itaconic* acids, both expressed by the formula $C_5H_2O_3.HO$. The limits of this elementary work will not permit us to enter into a description of these farther products of decomposition.

MALIC ACID.—This is the acid of apples, pears, and various other fruits; it is often associated, as already observed, with citric acid. An excellent process for preparing the acid in question is that of Mr. Everitt, who has demonstrated its existence, in great quantity, in the juice of the common garden rhubarb; it is there accompanied by acid oxalate of potassa. The rhubarb stalks are peeled, and ground or grated to pulp, which is subjected to pressure. The juice is heated to the boiling-point, neutralized with carbonate of potassa, and mixed with acetate of lime; insoluble oxalate of lime falls, which is removed by filtration. To the clear and nearly colourless liquid, solution of acetate of lead is added as long as a precipitate continues to be produced. The malate of lead is collected on a filter, washed, diffused


through water, and decomposed by sulphuretted hydrogen.* The filtered liquid is carefully evaporated to the consistence of syrup, and left in a dry atmosphere until it becomes converted into a solid and somewhat crystalline mass of malic acid: regular crystals have not been obtained. From the berries of the mountain-ash (*Sorbus aucuparia*), in which malic acid is likewise present in considerable quantity, especially at the time they commence to ripen, the acid may be prepared by the same process.

Malic acid is bibasic, its formula being $C_8H_4O_8, 2HO$; it forms a variety of salts, some of which are neutral, others acid. In the presence of fermenting substances, especially of putrefying casein, it is itself decomposed, yielding succinic, acetic, and carbonic acid.




Sometimes also butyric acid and hydrogen are observed among the products of this decomposition. Malic acid is colourless, slightly deliquescent, and very soluble in water; alcohol also dissolves it. The aqueous solution has an agreeably acid taste; it becomes mouldy, and spoils by keeping. The most characteristic of the malates are the *acid malate of ammonia*, $NH_4O, HO, C_8H_4O_8$, which crystallizes remarkably well, and the *malate of lead*, which is insoluble in pure water, but dissolves, to a considerable extent, in warm dilute acid, and separates, on cooling, in brilliant, silvery crystals, which contain water. The acid may, by this feature, be distinguished. The *acid malate of lime*, $CaO, HO, C_8H_4O_8 + 6HO$, is also a very beautiful salt, freely soluble in warm water. It is prepared by dissolving the sparingly soluble *neutral malate of lime* in hot dilute nitric acid, and leaving the solution to cool.

Recent researches of M. Piria have established a most intimate relation between malic acid and two substances—asparagin and aspartic acid, which will be described in one of the succeeding sections. These compounds may be viewed as malamide and malamic acid, analogous to oxamide and oxamic acid.




* If the acid be required pure, crystallized malate of lead must be used, the freshly-precipitated salt invariably carrying down a quantity of lime, which cannot be removed by simple washing.

† We have here doubled the formula of oxalic acid, when it becomes bibasic, like malic acid. There are, in fact, many features in the history of oxalic acid, which render it probable that it is bibasic. In the text we have still retained the generally received formula.



Hitherto neither asparagin nor aspartic acid have been actually obtained from malic acid. On the contrary, these substances are converted with the greatest facility into malic acid. On passing a current of nitrous acid into a solution of asparagin or aspartic acid, pure nitrogen is evolved, malic being liberated.



FUMARIC AND MALEIC ACIDS.—If malic acid be heated in a small retort, nearly filled, it melts, emits water, and enters into ebullition; a volatile acid passes over, which dissolves in the water of the receiver. After a time, small solid, crystalline scales make their appearance in the boiling liquid, and increase in quantity, until the whole becomes solid. The process may now be interrupted, and the contents of the retort, after cooling, treated with cold water; unaltered malic acid is dissolved out, and the new substance, having a smaller degree of solubility, is left behind; it is called *fumaric acid* from its identity with an acid extracted from the common fumitory.

Fumaric acid forms small, white, crystalline laminae, which dissolve freely in hot water and alcohol, but require for that purpose about 200 parts of cold water; it is unchanged by hot nitric acid. When heated in a current of air it sublimes, but in a retort undergoes decomposition. This is a phenomenon often observed in organic bodies of small volatility. Fumaric acid forms salts, which have been examined by M. Rieckher, and an ether, which, by the action of ammonia, yields a white, amorphous, insoluble powder, called *fumaramide*, corresponding in properties and constitution with oxamide. Hydrated fumaric acid contains $\text{C}_4\text{HO}_3, \text{HO}$; hence it is isomeric with aconitic acid.

The volatile acid produced simultaneously with the fumaric acid is called *maleic acid*; it may be obtained in crystals by evaporation in a warm place. It is very soluble in water, alcohol, and ether; it has a strongly acid taste and reaction, and is convertible by heat into fumaric acid. Hydrated maleic acid contains $\text{C}_8\text{H}_2\text{O}_6, 2\text{HO}$. Maleic and fumaric acids are thus seen to have precisely the same composition; they are formed by the separation of 2 eq. of water from hydrated malic acid.

TANNIC AND GALLIC ACIDS.—These are substances in which the acid character is much less strongly marked than in the preceding bodies; they constitute the astringent principles of plants, and are widely diffused, in one form or other, through the vegetable kingdom. It is possible that there may be several distinct modifications of

tannic acid, which differ among themselves in some particulars. The astringent principle of oak-bark and nut-galls, for example, is found to precipitate salts of sesquioxide of iron bluish-black, while that from the leaves of the sumach and tea-plant, as well as infusions of the substances known in commerce under the names of *kino* and *catechu*, are remarkable for giving, under similar circumstances, precipitates which have a tint of green. The colour of a precipitate is, however, too much influenced by external causes to be relied upon as a proof of essential difference. Unfortunately, the tannic acid or acids refuse to crystallize; one most valuable test of individuality is therefore lost.

After the reaction with salts of sesquioxide of iron, the most characteristic feature of tannic acid and the other astringent infusions referred to, is that of forming insoluble compounds with a great variety of organic, and especially animal substances, as solutions of starch and gelatin, solid muscular fibre and skin, &c., which then acquire the property of resisting putrefaction; it is on this principle that leather is manufactured. Gallic acid, on the contrary, is useless in the operation of tanning.

Tannic Acid of the Oak.—This substance may be prepared by the elegant and happy method of M. Pelouze, from nut-galls, which are excrescences produced on the leaves of a species of oak, the *Quercus infectoria*, by the puncture of an insect. A glass vessel, having somewhat the figure of that represented in the margin, is loosely stopped at its lower extremity by a bit of cotton wool, and half or two-thirds filled with powdered Aleppo-galls. Ether, prepared in the usual manner by rectification, and containing, as it invariably does, a little water, is then poured upon the powder, and the vessel loosely stopped. The liquid, which after some time collects in the receiver below, consists of two distinct strata: the lower, which is almost colourless, is a very strong solution of nearly pure tannic acid in water; the upper consists of ether holding in solution gallic acid, colouring matter, and other impurities. The carefully-separated heavy liquid is placed to evaporate over a surface of oil of vitriol in the vacuum of the air-pump. Tannic acid, or *tannin*, thus obtained, forms a slightly yellowish, friable, porous mass, without the slightest tendency to crystallization. It is very soluble in water, less so in alcohol, and very slightly soluble in ether. It reddens litmus, and possesses a pure astringent taste without bitterness.

A strong solution of this substance mixed with mineral acids gives rise to precipitates, which consist of combinations of the tannic acid

Fig. 167.



with the acids in question: these compounds are freely soluble in pure water, but scarcely so in acid solutions. Tannic acid precipitates albumin, gelatin, salts of the vegeto-alkalis, and several other substances; it forms soluble compounds with the alkalis, which, if excess of base be present, rapidly attract oxygen, and become brown by destruction of the acid; the tannates of *baryta*, *strontia*, and *lime* are sparingly soluble, and those of the oxides of *lead* and *antimony* insoluble. Salts of protoxide of iron are unchanged by solution of tannic acid; salts of the sesquioxide, on the contrary, give with it a deep bluish-black precipitate, which is the basis of writing-ink; hence the value of an infusion of tincture of nut-galls as a test for the presence of that metal. The action of acids upon tannic acid gives rise to the formation of gallic acid, which will be presently described, with simultaneous separation of grape-sugar. Hence tannic acid would appear to be a conjugated sugar-compound.

Tannic acid, carefully dried, contains $C_{18}H_5O_9 + 3HO$.*

Tannic acid, closely resembling that obtained from galls, may be extracted by cold water from *catechu*; hot water dissolves out a substance having feebly acid properties, termed *catechin*. This latter compound, when pure, crystallizes in fine colourless needles, which melt when heated, and dissolve very freely in boiling water, but scarcely at all in the cold. Catechin dissolves also in hot alcohol and ether. The aqueous solution acquires a red tint by exposure to air, and precipitates acetate of lead and corrosive sublimate white, reduces nitrate of silver on the addition of ammonia, but fails to form insoluble compounds with gelatin, starch, and the vegeto-alkalis. It strikes a deep-green colour with the salts of sesquioxide of iron. This body is said to be convertible by heat into tannic acid.


The formula which has been assigned to catechin is $C_{15}H_6O_6$.

Japonic and *rubic* acids are formed by the action of alkali in excess upon catechin; the first in the caustic condition, and the second when in the state of carbonate. Japonic acid is a black and nearly insoluble substance, soluble in alkalis and precipitated by acids, containing $C_{12}H_4O_4, HO$; it is perhaps identical with a black substance of acid properties, formed by M. Peligot by heating grape-sugar with hydrate of baryta. Rubic acid has been but little studied; it is said to form red insoluble compounds with the earths and certain oxides of the metals.

Several acids closely allied to tannic acid have been found in coffee and Paraguay tea.

GALLIC ACID.—Gallic acid is not nearly so abundant as tannic

* This formula is scarcely established beyond a doubt. M. Strecker, who has observed the formation of sugar from tannic acid, represents this substance by the formula $C_{40}H_{18}O_{26}$, and its change under the influence of acids by the equation




acid; it is produced by an alteration of the latter. A solution of tannic acid in water exposed to the air, gradually absorbs oxygen, and deposits crystals of gallic acid, formed by the destruction of the tannic acid. The simplest method of preparing this acid in quantity is to take powdered nut-galls, which, when fresh and of good quality, contain 30 or 40 per cent. of tannic acid, with scarcely more than a trace of gallic, to mix this powder with water to a thin paste, and to expose the mixture to the air in a warm situation for the space of two or three months, adding water from time to time to replace that lost by drying up. The mouldy, dark-coloured mass produced may then be strongly pressed in a cloth, and the solid portion boiled in a considerable quantity of water. The filtered solution deposits on cooling abundance of gallic acid, which may be drained and pressed, and finally purified by re-crystallization. It forms small, feathery, and nearly colourless crystals, which have a beautiful silky lustre; it requires for solution 100 parts of cold and only 3 parts of boiling water; the solution has an acid and astringent taste, and is gradually decomposed by keeping. Gallic acid does not precipitate gelatin; with salts of protoxide of iron no change is produced, but with those of the sesquioxide a deep bluish-black precipitate falls, which disappears when the liquid is heated, from the reduction of the sesquioxide to the protoxide at the expense of the gallic acid.

The salts of gallic acid present but little interest; those of the alkalis are soluble, and readily destroyed by oxidation in presence of excess of base, the solution acquiring after some time a nearly black colour; the gallates of most of the other metallic oxides are insoluble.

Gallic acid, dried at 212° (100°C), contains $\text{C}_7\text{H}_5\text{O}_3, 2\text{H}_2\text{O}$; the crystals contain an additional equivalent of water.

The insoluble residue of woody fibre and other matters from which the gallic acid has been withdrawn by boiling water, contains a small quantity of another acid substance, which may be extracted by an alkali, and afterwards precipitated by an addition of hydrochloric acid, as a greyish insoluble powder. It contains $\text{C}_7\text{H}_2\text{O}_4$, when dried at 248° (120°C), or gallic acid *minus* 1 eq. of water. The term *ellagic acid* is given to this substance. M. Pelouze once observed its conversion into ordinary gallic acid.

The conversion of tannic into gallic acid by oxidation is accompanied by a disengagement of carbonic acid, the volume of which equals that of the oxygen absorbed; the oxidizing action must therefore be confined to the carbon, and may perhaps be thus represented:—




Much of the gallie acid is subsequently destroyed, in all probability only a part of that first produced escaping.

The changes which gallie acid suffers when exposed to heat are very interesting. Heated in a retort by means of an oil-bath, the temperature of which is steadily maintained at 420° (215°C), or thereabouts, it is resolved into carbonic acid, and a new acid which sublimes into the neck of the retort in brilliant, crystalline plates, of the most perfect whiteness; an insignificant residue of black matter remains behind. The term *pyrogallie acid* is given to the volatile product. It dissolves with facility in water, but the solution cannot be evaporated without blackening and decomposition; it communicates a blackish-blue colour to salts of the protoxide of iron, and reduces those of the sesquioxide to the state of protoxide. An alkaline solution of this acid absorbs a very considerable quantity of oxygen, and has lately been employed with great advantage by Professor Liebig for the purpose of determining the amount of oxygen in atmospheric air. (See page 126.) The acid characters of this substance are very indistinct. Pyrogallie acid contains $\text{C}_6\text{H}_3\text{O}_3$.

When dry gallie acid is suddenly heated to 480° (249°C), or above, it is decomposed into carbonic acid, water, and a second new acid, the *metagallie*, which remains in the retort as a black, shining mass, resembling charcoal; a few crystals of pyrogallie acid are formed at the same time. Metagallie acid is insoluble in water, but dissolves in alkalis, and is again precipitated as a black powder by the addition of an acid. It combines with the oxides of lead and silver, and is composed of $\text{C}_6\text{H}_2\text{O}_2$. Pyrogallie acid, also, exposed to the requisite temperature, yields metagallie acid, with separation of water.

Tannic acid, under similar circumstances, furnishes the same products as gallie acid. Dr. Stenhouse has shown that pyrogallie acid may be procured in considerable quantity by carefully heating the dried aqueous extract of gall-nuts in Dr. Mohr's subliming apparatus, already described. All these changes admit of simple explanation.



These phenomena present admirable illustrations of the production of pyrogen-acids by the agency of heat.

SECTION IV.

AZOTIZED ORGANIC PRINCIPLES OF SIMPLE CONSTITUTION.

CYANOGEN, ITS COMPOUNDS AND DERIVATIVES.

CYANOGEN* forms the most perfect type of a quasi-simple salt-radical that chemistry presents, as kakodyl does of the basyle class; it is interesting also from being the first-discovered body of the kind.

Cyanogen may be prepared with the utmost ease by heating in a small retort of hard glass the salt called *cyanide of mercury*, previously reduced to powder, and well dried. The cyanide undergoes decomposition, like the oxide under similar circumstances, yielding metallic mercury, a small quantity of a brown substance of which mention will again be made, and cyanogen itself, a colourless, permanent gas, which must be collected over mercury. It has a pungent and very peculiar odour, remotely resembling that of peach-kernels, or hydrocyanic acid; exposed while at the temperature of 45° ($7^{\circ} \cdot 2^{\circ}\text{C}$) to a pressure of 3.6 atmospheres, it condenses to a thin, colourless, transparent liquid. Cyanogen is inflammable; it burns with a beautiful purple, or peach-blossom-coloured flame, generating carbonic acid and liberating nitrogen. The specific gravity of this gas is 1.806; it is composed of carbon and nitrogen in the proportion of 2 equivalents of the former to 1 equivalent of the latter, or C_2N : this is easily proved by mixing it with twice its measure of pure oxygen, and firing the mixture in the eudiometer; carbonic acid is formed equal in volume to the oxygen employed, and a volume of nitrogen equal to that of the cyanogen is set free. Cyanogen, in its capacity of quasi-element, is designated by the symbol Cy. Water dissolves 4 or 5 times its volume of cyanogen-gas, and alcohol a much larger quantity; the solution rapidly decomposes, yielding oxalate of ammonia, $\text{C}_2\text{N} + 4\text{HO} = \text{NH}_4\text{O}, \text{C}_2\text{O}_3$, brown insoluble matter, and other products.

PARACYANOGEN.—This is the brown or blackish substance above referred to, which is always formed in small quantity when cyanogen is prepared by heating the cyanide of mercury, and probably, also, by the decomposition of solutions of cyanogen and of hydrocyanic acid. It is insoluble in water and alcohol, is dissipated by a very high tem-

* So called from *κύανος*, blue, and *γεννάω*, I generate.

perature, and contains, according to Professor Johnston, carbon and nitrogen in the same proportions as in cyanogen.


CYANIDE OF HYDROGEN; HYDROCYANIC or PRUSSIC ACID, HCy .—This very important compound, so remarkable for its poisonous properties, was discovered as early as 1782 by Scheele. It may be prepared in a state of purity, and anhydrous, by the following process:—A long glass tube, filled with dry cyanide of mercury, is connected by one extremity with an arrangement for furnishing dry sulphuretted hydrogen gas, while a narrow tube attached to the other end is made to pass into a narrow-necked phial plunged into a freezing-mixture. Gentle heat is applied to the tube, the contents of which suffer decomposition in contact with the gas, sulphide of mercury and cyanide of hydrogen being produced; the latter is condensed in the receiver to the liquid form. A little of the cyanide of mercury should be left undecomposed, to avoid contamination of the product by sulphuretted hydrogen. The pure acid is a thin, colourless, and exceedingly volatile liquid, which has a density of 0.7058 at 45° ($7^{\circ}\cdot6\text{C}$), boils at 79° ($26^{\circ}\cdot1\text{C}$), and solidifies, when cooled to 0° ($-17^{\circ}\cdot8\text{C}$); its odour is very powerful and most characteristic, much resembling that of peach-blossoms or bitter-almond oil; it has a very feeble acid reaction, and mixes with water and alcohol in all proportions. In the anhydrous state this substance constitutes one of the most formidable poisons known, and even when largely diluted with water, its effects upon the animal system are exceedingly energetic; it is employed, however, in medicine in very small doses. The inhalation of the vapour should be carefully avoided in all experiments in which hydrocyanic acid is concerned, as it produces headache, giddiness, and other disagreeable symptoms; ammonia and chlorine are the best antidotes.

The acid in its pure form can seldom be preserved: even when enclosed in a carefully-stopped bottle it is observed after a very short time to darken, and eventually to deposit a black substance containing carbon, nitrogen, and perhaps hydrogen; ammonia is formed at the same time, and many other products. Light favours this decomposition. Even in a dilute condition it is apt to decompose, becoming brown and turbid, but not always with the same facility, some samples resisting change for a great length of time, and then suddenly solidifying to a brown, pasty mass in a few weeks.


When hydrocyanic acid is mixed with concentrated mineral acids, the hydrochloric for example, the whole solidifies to a crystalline paste of sal-ammoniac and hydrated formic acid; a reaction which is explained in a very simple manner, 1 eq. of hydrocyanic acid and 4 eq. water, yielding 1 eq. of ammonia and 1 eq. of formic acid.



On the other hand, when dry formate of ammonia is heated to 392° (200°C), it is almost entirely converted into hydrocyanic acid and water.



Aqueous solution of hydrocyanic acid may be made by various means. The most economical, and by far the best, where considerable quantities are wanted, is to decompose at a boiling-heat the yellow ferrocyanide of potassium by diluted sulphuric acid. For example, 500 grains of the powdered ferrocyanide may be dissolved in four or five ounces of warm water, and introduced into a capacious flask or globe capable of being connected by a perforated cork and wide bent tube with a Liebig's condenser well supplied with cold water; 300 grains of oil of vitriol are diluted with three or four times as much water and added to the contents of the flask; distillation is carried on until about one-half of the liquid has distilled over, after which the process may be interrupted. The theory of this process has been carefully studied by Mr. Everitt;* it is sufficiently complicated.



The substance described in the above diagram as *insoluble yellow salt* remains in the flask after the reaction, together with the bisulphate of potassa; it contains the elements of 2 eq. cyanide of iron, and 1 eq. cyanide of potassium, but its constitution is unknown. On exposure to the air, it rapidly becomes blue.

When hydrocyanic acid is wanted for purposes of pharmacy, it is best to prepare a strong solution in the manner above described, and then, having ascertained its exact strength, to dilute it with pure water to the standard of the Pharmacopœia, viz., 2 per cent. of real acid. This examination is best made by precipitating with excess of nitrate of silver a known weight of the acid to be tried, collecting the insoluble cyanide of silver upon a small filter previously weighed, washing, drying, and lastly re-weighing the whole. From the weight of the cyanide that of the hydrocyanic acid can be easily calculated, an equivalent of the one corresponding to an equivalent of the other; or the weight of the cyanide of silver may be divided by 5, which will give a close approximation to the truth.

* Phil. Magazine, Feb. 1835.

Another very elegant method for determining the amount of hydrocyanic acid in a liquid has been lately suggested by Prof. Liebig. It is based upon the property possessed by cyanide of potassium of dissolving a quantity of chloride of silver sufficient to produce with it a double cyanide containing equal equivalents of cyanide of silver and of potassium (KCy, AgCy). Hence a solution of hydrocyanic acid, which is super-saturated with potassa, and mixed with a few drops of solution of common salt, will not yield a permanent precipitate with nitrate of silver before the whole of the hydrocyanic acid is converted into the above double salt. If we know the amount of silver in a given volume of the nitrate-solution, it is easy to calculate the quantity of hydrocyanic acid, for this quantity will stand to the amount of silver in the nitrate consumed, as 2 eq. of hydrocyanic acid to 1 eq. of silver, *i. e.*

$$108 : 54 = \text{silver consumed} : x.$$

It is a common remark, that the hydrocyanic acid made from ferrocyanide of potassium keeps better than that made by other means. The cause of this is ascribed to the presence of a trace of mineral acid. Mr. Everitt actually found that a few drops of hydrochloric acid, added to a large bulk of the pure dilute acid, preserved it from decomposition, while another portion, not so treated, became completely spoiled.


A very convenient process for the extemporaneous preparation of an acid of definite strength, is to decompose a known quantity of cyanide of potassium by solution of tartaric acid: 100 grains of crystallized tartaric acid in powder, 44 grains of cyanide of potassium, and 2 measured ounces of distilled water, shaken up in a phial for a few seconds, and then left at rest, in order that the precipitate may subside, will yield an acid of very nearly the required strength. A little alcohol may be added to complete the separation of the cream of tartar; no filtration or other treatment need be employed.

The production of hydrocyanic acid from bitter almonds has been already mentioned in connection with the history of the volatile oil. Bitter-almonds, the kernels of plums and peaches, the seeds of the apple, the leaves of the cherry-laurel, and various other parts of plants belonging to the great natural order *rosaceæ*, yield on distillation with water a sweet-smelling liquid, containing hydrocyanic acid. This is probably due in all cases to the decomposition of the *amygdalin*, pre-existent in the organic structure. The change in question is brought about, in a very singular manner, by the presence of a soluble azotized substance, called *emulsin* or *synaptase*, which forms a large proportion of the white pulp of both bitter and sweet almonds. This substance bears a somewhat similar relation to amygdalin, that diastase, which it closely resembles in many particulars, does to starch. Hydrocyanic acid exists ready-formed to a considerable extent in the juice of the bitter cassava.

AMYGDALIN is prepared with facility by the following process:—The paste of bitter-almonds, from which the fixed oil has been expressed, is exhausted with boiling alcohol: this coagulates and renders inactive the synaptase, while at the same time it dissolves out the amygdalin. The alcoholic liquid is distilled in a water-bath, by which much of the spirit is recovered, and the syrupy residue diluted with water, mixed with a little yeast, and set in a warm place to ferment: a portion of sugar, present in the almonds, is thus destroyed. The filtered liquid is then evaporated to a syrupy state in a water-bath, and mixed with a quantity of alcohol, which throws down the amygdalin as a white crystalline powder; the latter is collected on a cloth filter, pressed, re-dissolved in boiling alcohol, and left to cool. It separates in small crystalline plates, of pearly whiteness, which are inodorous and nearly tasteless; it is decomposed by heat, leaving a bulky coal, and diffusing the odour of the hawthorn. In water, both hot and cold, amygdalin is very insoluble: a hot saturated solution deposits, on cooling, brilliant prismatic crystals, which contain water. In cold alcohol it dissolves with great difficulty. Heated with dilute nitric acid, or a mixture of dilute sulphuric acid and binocide of manganese, it is resolved into ammonia, bitter-almond oil, benzoic acid, formic acid, and carbonic acid; with permanganate of potassa, it yields a mixture of cyanate and benzoate of that base.

Amygdalin is composed of $C_{40}H_{27}NO_{22}$.

Synaptase itself has never been obtained in a state of purity, or fit for analysis; it is described as a yellowish-white, opaque, brittle mass, very soluble in water, and coagulable, like albumin, by heat, in which case it loses its specific property. In solution it very soon becomes turbid, and putrefies. The decomposition of amygdalin under the influence of this body may be elegantly studied by dissolving a portion in a large quantity of water, and adding a little emulsion of sweet-almond; the odour of the volatile oil immediately becomes apparent, and the liquor yields, on distillation, hydrocyanic acid. The nature of the decomposition may be thus *approximately* represented:—



It may be observed, that in preparing bitter-almond oil the paste should be well mixed with about 20 parts of warm water, and the whole left to stand some hours before distillation; the heat must be gently raised, to avoid coagulating the synaptase before it has had

time to act upon the amygdalin. Almond-paste, thrown into boiling water, yields little or no bitter-almond oil.

AMYGDALIC ACID.—When amygdalin is boiled with an alkali or an alkaline earth, it is decomposed into ammonia, and a new acid called the *amygdalic*, which remains in union with the base. This is best prepared by means of baryta-water, the ebullition being continued as long as ammonia is evolved. From the solution thus obtained, the baryta may be precipitated by dilute sulphuric acid; the filtered liquid is evaporated in a water-bath. Amygdalic acid forms a colourless, transparent, amorphous mass, very soluble in water, and deliquescent in moist air; the solution has an acid taste and reaction. It is converted by oxidizing agents into bitter-almond oil, formic, and benzoic acids. The amygdalates are mostly soluble, but have been but little studied; the acid contains $C_{40}H_{26}O_{24}, HO$.

The presence of hydrocyanic acid is detected with the utmost ease; its remarkable odour and high degree of volatility almost sufficiently characterize it. With solution of nitrate of silver it gives a dense curdy white precipitate, much resembling the chloride, but differing from that substance in not blackening so readily by light, in being soluble in boiling nitric acid, and in suffering complete decomposition when heated in a dry state, metallic silver being left: the chloride, under the same circumstances, merely fuses, but undergoes no chemical change. The production of Prussian blue by "Scheele's test" is an excellent and most decisive experiment, which may be made with a very small quantity of acid. The liquid to be examined is mixed with a few drops of solution of sulphate of protoxide of iron and an excess of caustic potassa, and the whole exposed to the air for 10 or 15 minutes, with agitation; hydrochloric acid is then added in excess, which dissolves the oxide of iron, and, if hydrocyanic acid be present, leaves Prussian blue as an insoluble powder. The reaction becomes quite intelligible when the production of a ferrocyanide, described a few pages hence, is understood. See page 531.

Another elegant process for detecting hydrocyanic acid is mentioned in the article upon hydrosulphocyanic acid.

The most important of the metallic cyanides are the following; they bear the most perfect analogy to the haloid-salts.

CYANIDE OF POTASSIUM, KCy .—When potassium is heated in cyanogen gas, it takes fire and burns in a very beautiful manner, yielding cyanide of the metal; the same substance is produced when potassium is heated in the vapour of hydrocyanic acid, hydrogen being liberated. If pure nitrogen gas be transmitted through a white-hot tube, containing a mixture of carbonate of potassa and charcoal, a considerable quantity of cyanide of potassium is formed, which settles in the cooler portions of the tube as a white amorphous powder; carbonic oxide is at the same time evolved. If azotized organic matter of any kind, capable of furnishing ammonia by destructive distillation, as

horn-shavings, parings of hides, &c., be heated to redness with carbonate of potassa in a close vessel, a very abundant production of cyanide of potassium results, which cannot, however, be advantageously extracted by direct means, but in practice is always converted into ferrocyanide, which is a much more stable substance, and crystallizes better.

There are several methods by which cyanide of potassium may be prepared for use. It may be made by passing the vapour of hydrocyanic acid into a cold alcoholic solution of potassa; the salt is deposited in a crystalline form, and may be separated from the liquid, pressed and dried. Ferrocyanide of potassium, heated to whiteness in a nearly close vessel, evolves nitrogen and other gases, and leaves a mixture of charcoal, carbide of iron, and cyanide of potassium, which latter salt is not decomposed unless the temperature be excessively high. Mr. Donovan recommends the use in this process of a wrought-iron mercury-bottle, which is to be half filled with the ferrocyanide, and arranged in a good air-furnace, capable of giving the requisite degree of heat; a bent iron tube is fitted to the mouth of the bottle and made to dip half an inch into a vessel of water; this serves to give exit to the gas. The bottle is gently heated at first, but the temperature ultimately raised to whiteness; when no more gas issues, the tube is stopped with a cork, and, when the whole is completely cold, the bottle is cut asunder in the middle by means of a chisel and sledge-hammer, and the pure white fused salt carefully separated from the black spongy mass below, and preserved in a well-stopped bottle: the black substance contains much cyanide, which may be extracted by a little cold water. It would be better, perhaps, in the foregoing process to deprive the ferrocyanide of potassium of its water of crystallization before introducing it into the iron vessel.

Professor Liebig has published a very easy and excellent process for making cyanide of potassium, which does not, however, yield it pure, but mixed with cyanate of potassa. For most of the applications of cyanide of potassium, as, for example, electro-plating and gilding, for which a considerable quantity is now required, this impurity is of no consequence. 8 parts of ferrocyanide of potassium are rendered anhydrous by gentle heat, and intimately mixed with 3 parts of dry carbonate of potassa: this mixture is thrown into a red-hot earthen crucible, and kept in fusion, with occasional stirring, until gas ceases to be evolved, and the fluid portion of the mass becomes colourless. The crucible is left at rest for a moment, and then the clear salt decanted from the heavy black sediment at the bottom, which is principally metallic iron in a state of minute division. In this experiment, 2 eq. of ferrocyanide of potassium and 2 eq. carbonate of potassa yield 5 eq. cyanide of potassium, 1 eq. cyanate of potassa, 2 eq. iron, and 2 eq. carbonic acid. The product may be advantageously used, instead of ferrocyanide of potassium, in the preparation of hydrated hydrocyanic acid, by distillation with diluted oil of vitriol.

Cyanide of potassium forms colourless cubic or octahedral crystals, deliquescent in the air, and exceedingly soluble in water; it dissolves in boiling alcohol, but separates in great measure on cooling. It is readily fusible, and undergoes no change at a moderate red, or even white-heat, when excluded from air; otherwise, oxygen is absorbed and the cyanide of potassium becomes cyanate of potassa. Its solution always has an alkaline reaction, and exhales when exposed to the air the smell of hydrocyanic acid; it is decomposed by the feeblest acids, even the carbonic acid of the atmosphere, and when boiled in a retort is slowly converted into formate of potassa with separation of ammonia. This salt is anhydrous: it is said to be as poisonous as hydrocyanic acid itself.

Cyanide of potassium has been derived from a curious and unexpected source. In some of the iron furnaces in Scotland, where raw-coal is used for fuel with the hot blast, a saline-looking substance is occasionally observed to issue in a fused state from the tuyere-holes of the furnace, and concrete on the outside. This proved, on examination by Dr. Clark, to be principally cyanide of potassium.

CYANIDE OF SODIUM, NaCy , is a very soluble salt, corresponding closely with the foregoing, and obtained by similar means.

CYANIDE OF AMMONIUM, NH_4Cy .—This is a colourless, crystallizable, and very volatile substance, prepared by distilling a mixture of cyanide of potassium and sal-ammoniac, or by mingling the vapour of anhydrous hydrocyanic acid with ammoniacal gas, or, lastly, according to the observation of M. Langlois, by passing ammonia over red-hot charcoal. It is very soluble in water, subject to spontaneous decomposition, and is highly poisonous.


CYANIDE OF MERCURY, HgCy .—One of the most remarkable features in the history of cyanogen is its powerful attraction for certain of the less oxidable metals, as silver, and more particularly mercury and palladium. Dilute hydrocyanic acid dissolves finely-powdered red oxide of mercury with the utmost ease; the liquid loses all odour, and yields on evaporation crystals of cyanide of mercury. Cyanide of potassium is in like manner decomposed by red oxide of mercury, hydrate of potassa being produced. Cyanide of mercury is generally prepared from common ferrocyanide of potassium; 2 parts of the salt are dissolved in 15 parts of hot water, and 3 parts of dry sulphate of mercury added; the whole is boiled for 15 minutes, and filtered hot from the oxide of iron, which separates. The solution, on cooling, deposits the new salt in crystals. Cyanide of mercury forms white, translucent prisms, much resembling those of corrosive sublimate; it is soluble in 8 parts of cold water, and in a much smaller quantity at a higher temperature, and also in alcohol. The solution has a disagreeable metallic taste, is very poisonous, and is not precipitated by alkalis. Cyanide of mercury is used in the laboratory as a source of cyanogen.

CYANIDE OF SILVER, AgCy , has been already described. *Cyanide*

of zinc, ZnCy , is a white insoluble powder, prepared by mixing acetate of zinc with hydrocyanic acid. *Cyanide of cobalt*, CoCy , is obtained by similar means; it is dirty white, and insoluble. *Cyanide of palladium* forms a pale, whitish precipitate when the chloride of that metal is mixed with a soluble cyanide, including that of mercury. *Tercyanide of gold*, AuCy_3 , is yellowish-white and insoluble, but freely dissolved by solution of cyanide of potassium. *Protocyanide of iron* has not been obtained, from the tendency of the metal to pass into the radical, and generate a *ferrocyanide*. An insoluble green compound containing $\text{FeCy}, \text{F}_2\text{Cy}_3$ was formed by M. Pelouze by passing chlorine gas into a boiling solution of ferrocyanide of potassium.

CYANIC AND CYANURIC ACIDS.—These are two remarkable isomeric bodies related in a very close and intimate manner, and presenting phenomena of great interest. Cyanic acid is the true oxide of cyanogen; it is formed in conjunction with cyanide of potassium, when cyanogen gas is transmitted over heated hydrate or carbonate of potassa, or passed into a solution of the alkaline base, the reaction resembling that by which chlorate of potassa and chloride of potassium are generated when the oxide and the salt-radical are presented to each other. Cyanate of potassa is, moreover, formed when the cyanide is exposed to a high temperature with access of air; unlike the chlorate, it bears a full red-heat without decomposition.

Hydrated Cyanic Acid, CyO, HO , is procured by heating to dull redness in a hard glass retort connected with a receiver cooled by ice, cyanuric acid, deprived of its water of crystallization. The cyanuric acid is resolved, without any other product, into hydrated cyanic acid, which condenses in the receiver to a limpid, colourless liquid, of exceedingly pungent and penetrating odour, like that of the strongest acetic acid; it even blisters the skin. When mixed with water, it decomposes almost immediately, giving rise to bicarbonate of ammonia.



This is the reason why the hydrated acid cannot be separated from a cyanate by a stronger acid. A trace of cyanic acid, however, always escapes decomposition, and communicates to the carbonic acid evolved a pungent smell similar to that of sulphurous acid. The cyanates may be easily distinguished by this smell, and by the simultaneous formation of an ammonia-salt, which remains behind.

The pure hydrated cyanic acid cannot be preserved: shortly after its preparation it changes spontaneously, with sudden elevation of temperature into a solid, white, opaque, amorphous substance, called *cyanelide*. This curious body has the same composition as hydrated cyanic acid; it is insoluble in water, alcohol, ether, and dilute acids; it dissolves in strong oil of vitriol by the aid of heat, with evolution of carbonic acid and production of ammonia; boiled with solution of caustic alkali, it dissolves, ammonia is disengaged, and a mixture of

cyanate and cyanurate of the base generated. By dry distillation it is again converted into the hydrate of cyanic acid.

CYANATE OF POTASSA, KO, CyO .—The best method of preparing this salt is, according to Liebig, to oxidize cyanide of potassium by means of litharge. The cyanide, already containing a portion of cyanate, described, p. 521, is remelted in an earthen crucible, and finely-powdered protoxide of lead added by small portions; the oxide is instantaneously reduced, and the metal, at first in a state of minute division, ultimately collects to a fused globule at the bottom of the crucible. The salt is poured out, and, when cold, powdered and boiled with alcohol; the hot filtered solution deposits crystals of cyanate of potassa on cooling. The great deoxidizing power exerted by cyanide of potassium at a high temperature promises to render it a valuable agent in many of the finer metallurgical operations.

Another method of preparing the cyanate is to mix dried and finely-powdered ferrocyanide of potassium with half its weight of equally dry binoxide of manganese; to heat this mixture in a shallow iron ladle with free exposure to air and frequent stirring until the tinder-like combustion is at an end, and to boil the residue in alcohol, which extracts the cyanate of potassa.

This salt crystallizes from alcohol in thin, colourless, transparent plates, which suffer no change in dry air, but on exposure to moisture become gradually converted, without much alteration of appearance, into bicarbonate of potassa, ammonia being at the same time disengaged. Water dissolves the cyanate of potassa in large quantity; the solution is slowly decomposed in the cold, and rapidly at a boiling heat, into bicarbonate of potassa and ammonia. When a concentrated solution is mixed with a small quantity of dilute mineral acid, a precipitate falls, which consists of acid cyanurate of potassa. Cyanate of potassa is reduced to cyanide of potassium by ignition with charcoal in a covered crucible.

Cyanate of potassa, mixed with solutions of lead and silver, gives rise to insoluble cyanates of the oxides of those metals, which are white.

CYANATE OF AMMONIA; UREA.—When the vapour of hydrated cyanic acid is mixed with excess of ammoniacal gas, a white, crystalline, solid substance is produced, which has all the characters of a true, although not neutral, cyanate of ammonia. It dissolves in water, and, if mixed with an acid, evolves carbonic acid gas; with an alkali, it yields ammonia. If the solution be heated, or if the crystals be merely exposed a certain time to the air, a portion of ammonia is dissipated, and the properties of the compound completely changed. It may now be mixed with acids without the least symptoms of decomposition, while cold caustic alkali, on the other hand, fails to disengage the smallest trace of ammonia. The result of this curious metamorphosis of the cyanate is a substance called *urea*, a product of the animal body, the chief and characteristic constituent of urine. This artificial forma-

tion of one of the products of organic life cannot fail to possess great interest. Its discovery is due to Prof. Wöhler. The properties of urca, and the most advantageous methods of preparing it, will be found described a few pages hence.

CYANURIC ACID.—The substance called *melam*, of which farther mention will be made, is dissolved by gentle heat in concentrated sulphuric acid, the solution mixed with 20 or 30 parts of water, and the whole maintained at a temperature approaching the boiling-point, until the specimen of the liquid, on being tried by ammonia, no longer gives a white precipitate: several days are required. The liquid, concentrated by evaporation, deposits on cooling cyanuric acid, which is purified by re-crystallization. Another, and perhaps simpler method, is to heat dry and pure urea in a flask or retort: the substance melts, boils, disengages ammonia in large quantity, and at length becomes converted into a dirty white, solid, amorphous mass, which is impure cyanuric acid. This is dissolved by the aid of heat in strong oil of vitriol, and nitric acid added by little and little until the liquid becomes nearly colourless; it is then mixed with water, and suffered to cool, whereupon the cyanuric acid separates. The urca may likewise be decomposed very conveniently by gently heating it in a tube, while dry chlorine gas passes over it. A mixture of cyanuric acid and sal-ammoniac results, which is separated by dissolving in water.

Cyanuric acid in a pure state forms colourless crystals, seldom of large size, derived from an oblique rhombic prism, which effloresce in a dry atmosphere from loss of water. It is very little soluble in cold water, and requires 24 parts for solution at a boiling heat; it reddens litmus feebly, has no odour, and but little taste. This acid is tribasic; the crystals contain $C_6N_3O_3, 3HO + 4HO$, and are easily deprived of the 4 eq. of water of crystallization. In point of stability, it offers a most remarkable contrast to its isomer, cyanic acid; it dissolves, as above indicated, in hot oil of vitriol, and even in strong nitric acid, without decomposition, and in fact crystallizes from the latter in an anhydrous state, containing $C_6N_3O_3, 3HO$. Long-continued boiling with these powerful agents resolves it into ammonia and carbonic acid.


The connection between cyanic acid, urea, and cyanuric acid may be thus recapitulated:—

Cyanate of ammonia is converted by heat into urca.

Urea is decomposed by the same means into cyanuric acid and ammonia.

Cyanuric acid is changed by a very high temperature into hydrated cyanic acid.

In the latter reaction, 1 eq. of hydrated cyanuric acid splits into 3 eq. hydrated cyanic acid.




CYANATE AND CYANURATE OF OXIDE OF ETHYL.—If a dry mixture of cyanate of potassa and sulphovinate of potassa be distilled, a product is obtained which consists of a mixture of the above ethers. They are separated without difficulty, the cyanate boiling at 140° (60°C), while the boiling-point of the cyanurate is much higher, namely, $528^{\circ}\cdot 8$ (276°C). Cyanate of ethyl is a mobile liquid, the vapour of which excites a flow of tears. The composition of cyanate of ethyl is $\text{C}_6\text{H}_5\text{NO}_2 = \text{C}_4\text{H}_5\text{O}, \text{C}_2\text{NO} = \text{AeO}, \text{CyO}$. The formation is represented by the equation $\text{KO}, \text{CyO} + \text{KO}, \text{AeO}, 2\text{SO}_3 = \text{AeO}, \text{CyO} + 2(\text{KO}, \text{SO}_3)$. The cyanurate of ethyl contains $3\text{AeO}, \text{C}_6\text{N}_3\text{O}_3$; it arises in this reaction from the coalescence of 3 eq. of cyanate of ethyl. It may be likewise obtained by distilling a mixture of sulphovinate of potassa with cyanurate of potassa. Cyanurate of ethyl is a crystalline mass, slightly soluble in water, readily soluble in alcohol and ether, fusing at 185° (85°C). By substituting for sulphovinate of potassa, salts of sulphomethylic and sulphamylic acid, the corresponding methyl- and amyl-compounds may be obtained.

The study of the cyanic and cyanuric ethers, which were discovered by Wurtz, has led to very important results, which will be fully described in the section on the Organic Bases.

FULMINIC ACID.—This remarkable compound, which is isomeric both with cyanic and cyanuric acids, originates in the peculiar action exercised by nitrous acid upon alcohol in presence of a salt of silver or mercury. Neither absolute fulminic acid nor its hydrate has ever been obtained.

Fulminate of silver is prepared by dissolving 40 or 50 grains of silver, which need not be pure, in $\frac{3}{4}$ oz. by measure of nitric acid of sp. gr. 1.37 or thereabouts, by the aid of a little heat; a sixpence answers the purpose very well. To the highly-acid solution, while still hot, 2 measured ounces of alcohol are added, and heat applied until reaction commences. The nitric acid oxidizes part of the alcohol to aldehyde and oxalic acid, becoming itself reduced to nitrous acid, which in turn acts upon the alcohol in such a manner as to form nitrous ether, fulminic acid, and water, 1 eq. nitrous ether and 1 eq. of nitrous acid containing the elements of 1 eq. fulminic acid and 5 eq. water.



The fulminate of silver slowly separates from the hot liquid in the form of small, brilliant, white, crystalline plates, which may be washed with a little cold water, distributed upon separate pieces of filter-paper in portions not exceeding a grain or two each, and left to dry in a warm place. When dry, the papers are folded up and preserved in a box or bottle. This is the only safe method of keeping the salt. Fulminate of silver is soluble in 36 parts of boiling water, but the greater part crystallizes out on cooling: it is one of the most dangerous substances to handle that chemistry presents; it explodes

when strongly heated, or when rubbed or struck with a hard body, or when touched with concentrated sulphuric acid, with a degree of violence almost indescribable; the metal is reduced, and a large volume of gaseous matter suddenly liberated. Strange to say, it may, when very cautiously mixed with oxide of copper, be burned in a tube with as much facility as any other organic substance. Its composition thus determined is expressed in the formula $2\text{AgO}, \text{C}_4\text{N}_2\text{O}_2$.

The acid is evidently bibasic; when fulminate of silver is digested with caustic potassa, one-half of the oxide is precipitated, and a compound produced containing $\text{AgO}, \text{KO}, \text{C}_4\text{N}_2\text{O}_2$, which resembles the neutral silver-salt, and detonates by a blow. Corresponding compounds containing soda and oxide of ammonium exist; but a pure fulminate of an alkaline metal has never been formed. If fulminate of silver be digested with water and copper, or zinc, the silver is entirely displaced, and a fulminate of the new metal produced. The zinc-salt mixed with baryta-water gives rise to a precipitate of oxide of zinc, while *fulminate of zinc and baryta*, $\text{ZnO}, \text{BaO}, \text{C}_4\text{N}_2\text{O}_2$, remains in solution. *Fulminate of mercury* is prepared by a process very similar to that by which the silver-salt is obtained: one part of mercury is dissolved in 12 parts of nitric acid, and the solution mixed with an equal quantity of alcohol; gentle heat is applied, and if the reaction becomes too violent, it may be moderated by the addition from time to time of more spirit: much carbonic acid, nitrogen, and red vapours are disengaged, together with a large quantity of nitrous ether and aldehyde; these are sometimes condensed and collected for sale, but are said to contain hydrocyanic acid. The fulminate of mercury separates from the hot liquid, and after cooling may be purified from an admixture of reduced metal by solution in boiling water and recrystallization. It much resembles the silver-salt in appearance, properties, and degree of solubility, and contains $2\text{Hg}_2\text{O}, \text{C}_4\text{N}_2\text{O}_2$. It explodes violently by friction or percussion, but, unlike the silver-compound, merely burns with a sudden and almost noiseless flash when kindled in the open air. It is manufactured on a large scale for the purpose of charging *percussion-caps*; sulphur and chlorate of potassa, or more frequently nitre, are added, and the powder, pressed into the cap, is secured by a drop of varnish.

The relations of composition between the three isomeric acids are beautifully seen by comparing their silver-salts; the first acid is monobasic, the second bibasic, and the third tribasic.

Cyanate of silver	$\text{AgO}, \text{CN}_2\text{O}.$
Fulminate of silver	$2\text{AgO}, \text{C}_4\text{N}_2\text{O}_2.$
Cyanurate of silver	$3\text{AgO}, \text{C}_6\text{N}_3\text{O}_3.$

Until quite recently, beyond the accidental one of identity of composition, no relation existed between fulminic acid and its isomers. Mr. Gladstone has, however, shown that, when a solution of fulminate of copper is mixed with excess of ammonia, filtered, treated with


sulphuretted hydrogen in excess, and again filtered from the insoluble sulphide of copper, the liquid obtained is a mixed solution of urea and sulphocyanide of ammonium.

CHLORIDES OF CYANOGEN.—Chlorine forms two compounds with cyanogen, or its elements, which are isomeric, and correspond to cyanic and cyanuric acids. *Gaseous chloride of cyanogen*, CyCl , is formed by conducting chlorine gas into strong hydrocyanic acid, or by passing chlorine over moist cyanide of mercury contained in a tube sheltered from the light. It is a permanent and colourless gas at the temperature of the air, of insupportable pungency, and soluble to a very considerable extent in water, alcohol, and ether. At 0° (-17°C) it congeals to a mass of colourless crystals, which at 5° (-15°C) melt to a liquid whose boiling-point is 11° ($-11^\circ\cdot60$). At the temperature of the air it is condensed to the liquid form under a pressure of four atmospheres, and when long preserved in this condition in hermetically-sealed tubes it gradually passes into the solid modification. *Solid chloride of cyanogen* is generated when anhydrous hydrocyanic acid is put into a vessel of chlorine gas, and the whole exposed to the sun; hydrochloric acid is formed at the same time. It forms long colourless needles, which exhale a powerful and offensive odour, compared by some to that of the excrement of mice; it melts at 284° (140°C), and sublimes unchanged at a higher temperature. When heated in contact with water, it is decomposed into cyanuric and hydrochloric acids. This compound may be represented by the formula Cy_3Cl_3 , or $\text{C}_6\text{N}_3\cdot\text{Cl}_3$. It dissolves in alcohol and ether without decomposition.

BROMIDE AND IODIDE OF CYANOGEN correspond to the first of the preceding compounds, and are prepared by distilling bromine or iodine with cyanide of mercury. They are colourless, volatile, solid substances, of powerful odour.

FERROCYANOGEN AND ITS COMPOUNDS.

When a solution of cyanide of potassium is digested with iron filings at a gentle heat in an open vessel, oxygen is absorbed from the air, the iron dissolves quietly and disappears, and a highly alkaline, yellow liquid is obtained, which on evaporation deposits lemon-yellow crystals containing potassium in combination with a new salt-radical composed of the metal iron and the elements of cyanogen; in the mother-liquid hydrate of potassa is found. 3 eq. cyanide of potassium, 1 eq. iron, and 1 eq. oxygen, yield 1 eq. of the new salt, and 1 eq. of potassa.



The new substance is called *ferrocyanogen*, and is designated by the symbol C_f ; it is bibasic, neutralizing 2 equivalents of metal or

hydrogen, and contains *the elements* of 3 equivalents of cyanogen combined with 1 eq. of iron. It has never been isolated.

When iron in filings is heated in a small retort with a solution of cyanide of potassium, it is dissolved with evolution of hydrogen, caustic potassa and the new substance being generated; the oxygen in this case is derived from the decomposition of water. Sulphide of iron and cyanide of potassium give rise, under similar circumstances, to sulphide of potassium and ferrocyanide of potassium.

HYDROFERROCYANIC ACID, H_2Cfy .—Ferrocyanide of lead or copper, both of which are insoluble, may be suspended in water, and decomposed by a stream of sulphuretted hydrogen gas. The filtered solution evaporated in the vacuum of the air-pump over a surface of oil of vitriol, furnishes the acid in a solid form. If the aqueous solution be agitated with ether, nearly the whole of the acid separates in colourless, crystalline laminae; it may even be made in large quantity by adding hydrochloric acid to a strong solution of ferrocyanide of potassium in water free from air, and shaking the whole with ether. The crystals may be dissolved in alcohol, and the acid again thrown down by ether, which possesses the remarkable property of precipitating this substance from solution. Hydroferrocyanic acid differs completely from hydrocyanic acid; its solution in water has a powerfully acid taste and reaction, and decomposes alkaline carbonates with effervescence; it refuses to dissolve oxide of mercury in the cold, but when heat is applied, undergoes decomposition, forming cyanide of mercury and a peculiar compound of iron, cyanogen, and oxygen, with reduction of some of the oxide. In a dry state the acid is very permanent, but when long exposed to the air in contact with water it becomes entirely converted into Prussian blue. This interesting substance was discovered by Mr. Porrett.

FERROCYANIDE OF POTASSIUM, frequently called *Yellow prussiate of potash*, $K_2Cfy + 3HO$, or $K_2C_6N_3Fe + 3HO$.—This most beautiful salt is manufactured on a large scale by the following process, which will now be easily intelligible:—Dry refuse animal matter of any kind is fused at a red-heat with impure carbonate of potassa and some iron-filings in a large iron vessel, from which the air should be excluded as much as possible: cyanide of potassium is generated in large quantity. The melted mass is afterwards treated with hot water, which dissolves out the cyanide and other salts; the cyanide being quickly converted by the oxide or sulphide* of iron into ferrocyanide. The filtered solution is evaporated, and the first-formed crystals purified by re-solution. If a sufficient quantity of iron be not present, great loss is incurred by the decomposition of the cyanide into formate of potassa and ammonia.

Ferrocyanide of potassium forms large, transparent, yellow crystals, derived from an octahedron with a square base; they cleave with

* The sulphur is derived from the reduced sulphate of the crude pearl-ashes used in this manufacture.

facility in a direction parallel to the base of the octahedron, and are tough and difficult to powder. They dissolve in 4 parts of cold, and in 2 of boiling water, and are insoluble in alcohol. They are permanent in the air, and have a mild saline taste. The salt has no poisonous properties, and in small doses, at least, is merely purgative. Exposed to a gentle heat, it loses 3 eq. of water and becomes anhydrous; at a high temperature it yields cyanide of potassium, carbide of iron, and various gaseous products; if air be admitted, the cyanide becomes cyanate.

The ferrocyanides are often described as double salts, in which proto-cyanide of iron is combined with other metallic cyanides, or with hydrogen. Thus hydroferrocyanic acid is written $\text{FeCy}, 2\text{HCy}$, and ferrocyanide of potassium, $\text{FeCy}, 2\text{KCy} + 3\text{HO}$; the oxygen and hydrogen of the water of crystallization being respectively adequate to convert the metals into protoxides and the cyanogen into hydro-cyanic acid. This view has the merit of simplicity, and will often prove a useful aid to the memory; but there are insuperable objections to its adoption as a sound and satisfactory theory.


Ferrocyanide of potassium is a chemical reagent of great value: when mixed in solution with neutral or slightly-acid salts of the metals proper, it gives rise to precipitates which very frequently present highly-characteristic colours. In most of these compounds the potassium of the base is simply displaced by the new metal: the beautiful brown ferrocyanide of copper contains, for example, Cu_2Cfy or $\text{Cu}_2\text{C}_6\text{N}_3\text{Fe}$, and that of lead, Pb_2Cfy . With salts of protoxide of iron it gives a bluish precipitate, which becomes rapidly dark blue by exposure to air: this appears to be a compound of the neutral ferrocyanide of iron, Fe_2Cfy , with ferrocyanide of potassium.

When a ferrocyanide is added to a solution of a salt of sesquioxide of iron, *Prussian blue* is produced. Although this remarkable substance has now been long known, and many elaborate researches have been made with a view of determining its exact composition, the problem cannot yet be said to be completely solved. This difficulty arises in great measure from the existence of several distinct deep-blue compounds formed under different circumstances, and having many properties in common, which have been frequently confounded. The following is a summary of the account given by Berzelius, who has paid much attention to this subject.

Ordinary Prussian Blue, $\text{C}_{18}\text{N}_9\text{Fe}_7$, or Fe_4Cfy_3 .—This is best prepared by adding nitrate of sesquioxide of iron to solution of ferrocyanide of potassium, keeping the latter in slight excess. It forms a bulky precipitate of the most intense blue, which shrinks to a comparatively small compass when well washed and dried by gentle heat. In a dry state it is hard and brittle, much resembling in appearance the best indigo; the freshly-fractured surfaces have a beautiful coppered lustre, similar to that produced by rubbing indigo with a hard body. Prussian blue is quite insoluble in water and dilute acids,

with the exception of oxalic acid, in a solution of which it dissolves, forming a deep-blue liquid, which is sometimes used as ink; concentrated oil of vitriol converts it into a white, pasty mass, which again becomes blue on the addition of water. Alkalis destroy the colour instantly; they dissolve out a ferrocyanide, and leave sesquioxide of iron. Boiled with water and red oxide of mercury, it yields a cyanide of the metal, and sesquioxide of iron. Heated in the air, Prussian blue burns like tinder, leaving a residue of sesquioxide of iron. Exposed to a high temperature in a close vessel, it disengages water, cyanide of ammonium, and carbonate of ammonia, and leaves carbide of iron. This substance forms a very beautiful pigment, both an oil and a water colour, but has little permanency. The Prussian blue of commerce is always exceedingly impure; it contains alumina and other matters, which greatly diminish the brilliancy of the colour.

The production of Prussian blue by mixing a salt of sesquioxide of iron and ferrocyanide of potassium or sodium may thus be elucidated:—



In the above formula no account is taken of the elements of water which Prussian blue certainly contains; in fact, it must be looked upon as still requiring examination.

The theory of the beautiful test of Scheele for the discovery of hydrocyanic acid, or any soluble cyanide, will now be clearly intelligible. The liquid is mixed with a salt of protoxide of iron and excess of caustic alkali; the protoxide of iron quickly converts the alkaline cyanide into ferrocyanide. By exposure for a short time to the air, another portion of the hydrated oxide becomes peroxidized; when excess of acid is added, this is dissolved, together with the unaltered protoxide; and thus presented to the ferrocyanide in a state fitted for the production of Prussian blue.

Basic Prussian Blue, $Fe_4Cfy_3 + Fe_2O_3$.—This is a combination of Prussian blue with sesquioxide of iron: it is formed by exposing to the air the white or pale-blue precipitate caused by a ferrocyanide in a solution of protosalt of iron. It differs from the preceding in being soluble in pure water, although not in a saline solution.

The blue precipitate, obtained by adding nitrate of sesquioxide of iron to a large excess of ferrocyanide of potassium, is a mixture of insoluble Prussian blue with a compound containing that substance in union with ferrocyanide of potassium, or $Fe_4Cfy_3 + 2K_2Cfy$. This

also dissolves in water as soon as the salts have been removed by washing.

The other ferrocyanides may be despatched in a few words.

The *soda-salt*, $\text{Na}_2\text{Cfy} + 12\text{HO}$, crystallizes in yellow four-sided prisms, which are efflorescent in the air and very soluble.

Ferrocyanide of ammonium $(\text{NH}_4)_2\text{Cfy} + 3\text{HO}$, is isomorphous with ferrocyanide of potassium; it is easily soluble, and is decomposed by ebullition. *Ferrocyanide of barium*, Ba_2Cfy , prepared by double decomposition, or by boiling Prussian blue in baryta-water, forms minute yellow, anhydrous crystals, which have but a small degree of solubility even in boiling water. The corresponding compounds of *strontium*, *calcium*, and *magnesium* are more freely soluble. The ferrocyanides of *silver*, *lead*, *zinc*, *manganese*, and *bismuth* are white and insoluble; those of *nickel* and *cobalt* are pale green, and insoluble; and, lastly, that of *copper* has a beautiful reddish-brown tint.

Ferrocyanides with two basic metals are occasionally met with; when, for example, concentrated solutions of chloride of calcium and ferrocyanide of potassium are mixed, a sparingly-soluble crystalline precipitate falls, containing KCaCfy , the salt-radical being half saturated with potassium and half with calcium; many similar compounds have been formed.

FERRI-, OR FERRIDCYANOGEN, $\text{C}_{12}\text{N}_6\text{Fe}_2$; or Cfdy .—This name is given to a substance, by some thought to be a new salt-radical, isomeric with ferrocyanogen, but differing in capacity of saturation; it has never been isolated. *Ferrocyanide of potassium* is thus prepared:—Chlorine is slowly passed, with agitation, into a somewhat dilute and cold solution of ferrocyanide of potassium, until the liquid acquires a deep reddish-green colour, and ceases to precipitate a salt of the sesquioxide of iron. It is then evaporated until a skin begins to form upon the surface, filtered, and left to cool; the salt is purified by re-crystallization. It forms regular prismatic, or sometimes tabular crystals, of a beautiful ruby-red tint, permanent in the air, and soluble in 4 parts of cold water; the solution has a dark-greenish colour. The crystals burn when introduced into the flame of a candle, and emit sparks.


Ferricyanide of potassium contains K_3Cfdy ; hence the radical is tribasic; the salt is formed by the abstraction of an equivalent of potassium from 2 eq. of the yellow ferrocyanide of potassium. It is decomposed by excess of chlorine, and by deoxidizing agents, as sulphuretted hydrogen. The term *red prussiate of potash* is often, but very improperly, given to this substance.

Ferricyanide of hydrogen is obtained in the form of a reddish-brown acid liquid, by decomposing ferricyanide of lead with sulphuric acid, it is very instable, and is resolved, by boiling, into a hydrated sesquicyanide of iron, an insoluble dark green powder, containing $\text{Fe}_2\text{Cy}_3 + 3\text{HO}$, and hydrocyanic acid. The ferricyanides of *sodium*, *am-*

monium, and of the alkaline earths are soluble: those of most of the other metals are insoluble. Ferricyanide of potassium, added to a salt of the *sesquioxide* of iron, occasions no precipitate, but merely a darkening of the reddish-brown colour of the solution; with protoxide of iron, on the other hand, it gives a deep-blue precipitate, containing Fe_3Cfy , which, when dry, has a brighter tint than that of Prussian blue; it is known under the name of *Turnbull's blue*. Hence, ferricyanide of potassium is as excellent a test for protoxide of iron, as the yellow ferrocyanide is for the sesquioxide.

COBALTOCYANOGEN.—A series of compounds analogous to the preceding, containing cobalt in place of iron, have been formed and studied; a hydrogen-acid has been obtained, and a number of salts, which much resemble those of ferricyanogen. Several other metals of the same isomorphous family are found capable of replacing iron in these circumstances.

NITROPRUSSIDES.—The action of nitric acid upon ferrocyanides and ferricyanides gives rise to the formation of a very interesting series of new salts, which were discovered by Dr. Playfair. The general formula of these salts appears to be $\text{M}_2\text{Fe}_2\text{Cy}_5\text{NO}$, which exhibits a close relation with those of the ferro- and ferricyanides.




According to this formula, the formation of the nitroprusside would consist in the reduction of the nitric acid to the state of protoxide of nitrogen, which replaces 1 eq. of cyanogen in 2 eq. of ferrocyanide. The formation of these salts is attended by the production of a variety of secondary products, such as cyanogen, oxamide, hydrocyanic acid, nitrogen, carbonic acid, &c. One of the finest compounds of this series is the nitroprusside of sodium, $\text{Na}_2\text{Fe}_2\text{Cy}_5\text{NO} + 4\text{HO}$, which is readily obtained by treating 2 parts of the powdered ferrocyanide with 5 parts of common nitric acid, previously diluted with its own volume of water. The solution, after the evolution of gas has ceased, is digested on the water-bath, until salts of protoxide of iron no longer yield a blue but a slate-coloured precipitate. The liquid is now allowed to cool, when much nitrate of potassa, and occasionally oxamide, is deposited: it is filtered and neutralized with carbonate of soda, which yields a green or brown precipitate, and furnishes a ruby-coloured filtrate. This, on evaporation, gives a crystallization of nitrate of potassa and soda, together with the new salt. The crystals of the latter are selected and purified by crystallization; they are rhombic, and of a splendid ruby colour. The soluble nitroprussides strike a most beautiful violet tint with soluble sulphides. This reaction is recommended by Dr. Playfair as the most delicate test for alkaline sulphides.

SULPHOCYANOGEN, ITS COMPOUNDS AND DERIVATIVES

The elements of cyanogen combine with sulphur, forming a very important and well-defined salt-radical, called *sulphocyanogen*, which contains C_2NS_2 , and is monobasic; it is expressed by the symbol Csy.

SULPHOCYANIDE OF POTASSIUM, KCsy.—Yellow ferrocyanide of potassium, deprived of its water of crystallization, is intimately mixed with half its weight of sulphur, and the whole heated to tranquil fusion in an iron pot, and kept for some time in that condition. When cold, the melted mass is boiled with water, which dissolves out a mixture of sulphocyanide of potassium and sulphocyanide of iron, leaving little behind but the excess of sulphur employed in the experiment. This solution, which becomes red on exposure to the air from the oxidation of the iron, is mixed with carbonate of potassa, by which the oxide of iron is precipitated, and potassium substituted: an excess of the carbonate must be, as far as possible, avoided. The filtered liquid is concentrated, by evaporation over an open fire, to a small bulk, and left to cool and crystallize. The crystals are drained, purified by re-solution, if necessary, or dried by enclosing them, spread on filter-paper, over a surface of oil of vitriol, covered by a bell-jar.

The reaction between the sulphur and the elements of the yellow salt is easily explained: 1 eq. of ferrocyanide of potassium, and 6 eq. sulphur, yielded 2 eq. of sulphocyanide of potassium, and 1 eq. of sulphocyanide of iron.



Another and perhaps simpler process consists in gradually heating to low redness in a covered vessel a mixture of 46 parts of dried ferrocyanide of potassium, 32 of sulphur, and 17 of pure carbonate of potassa. The mass is exhausted by water, the aqueous solution evaporated to dryness and extracted with alcohol. The alcoholic liquid deposits splendid crystals on cooling or evaporation.

The new salt crystallizes in long, slender, colourless prisms, or plates, which are anhydrous; it has a bitter saline taste, and is destitute of poisonous properties; it is very soluble in water and alcohol, and deliquesces when exposed to a moist atmosphere. When heated, it fuses to a colourless liquid, at a temperature far below that of ignition.

When chlorine is passed into a strong solution of sulphocyanide of potassium, a large quantity of a bulky, deep yellow, insoluble substance, resembling some varieties of chromate of lead, is produced, together with chloride of potassium, which tends to choke up the tube delivering the gas; the liquid sometimes assumes a deep-red tint, and disengages a pungent vapour, probably chloride of cyanogen.

This yellow matter may be collected on a filter, well washed with boiling water, and dried: it retains its brilliancy of tint. The term *sulphocyanogen* has generally been applied to this substance, from its supposed identity with the radical of the sulphocyanides: it is, however, invariably found to contain both oxygen and hydrogen; and a formula much more complex than that belonging to the true sulphocyanogen, namely, $C_8H_2N_4S_8O$, has been lately assigned to it. The yellow substance is quite insoluble in water, alcohol, and ether; it dissolves in concentrated sulphuric acid, from which it is precipitated by dilution. Caustic potassa also dissolves it, with decomposition; acids throw down from this solution a pale-yellow, insoluble body, having acid properties. When heated in a dry state, the so-called sulphocyanogen evolves sulphur and bisulphide of carbon, and leaves a curious, pale straw-yellow substance, called *mellon*, which contains C_6N_4 , and is known to combine with hydrogen, and the metals. Mellon bears a dull red-heat without decomposition, but is resolved by strong ignition into a mixture of cyanogen and nitrogen gases. It is quite insoluble in water, alcohol, and dilute acids.

HYDROSULPHOCYANIC ACID, $HCsy$, is obtained by decomposing sulphocyanide of lead, suspended in water, by sulphuretted hydrogen. The filtered solution is colourless, very acid, and not poisonous; it is easily decomposed, in a very complex manner, by ebullition; and by exposure to the air. By neutralizing the liquid with ammonia, and evaporating very gently, to dryness, *sulphocyanide of ammonium*, NH_4Csy , is obtained as a deliquescent, saline mass. This salt may be conveniently prepared by digesting hydrocyanic acid with yellow sulphide of ammonium, and boiling off the excess of the latter ($NH_4S_3 + HCy = NH_4Csy + HS$). The sulphocyanides of *sodium*, *barium*, *strontium*, *calcium*, *manganese*, and *iron* are colourless, and very soluble: those of *lead* and *silver* are white and insoluble. A soluble sulphocyanide, mixed with a salt of the sesquioxide of iron, gives no precipitate, but causes the liquid to assume a deep blood-red tint, exactly like that caused under similar circumstances by meconic acid: hence the occasional use of sulphocyanide of potassium as a test for iron in the state of sesquioxide. The great facility with which hydrocyanic acid may be converted into sulphocyanide of ammonium enables us to ascertain its presence by the iron-test just described. The cyanide to be examined is mixed in a watch-glass with some hydrochloric acid and covered with another watch-glass, to which a few drops of yellow sulphide of ammonium adhere. On heating the mixture, hydrocyanic acid is disengaged, which combines with the sulphide of ammonium, and produces sulphocyanide of ammonium; this, after expulsion of the excess of sulphide, yields the red colour with solution of sesquichloride of iron.

SELENOCYANOGEN.—A series of salts containing selenium, and corresponding in their composition and properties with the sulphocyanides, exist. They have been lately studied by Mr. Crookes.

MELAM.—Such is the name given by Liebig to a curious buff-coloured, insoluble, amorphous substance, obtained by the distillation at a high temperature of sulphocyanide of ammonium. It may be prepared in large quantity by intimately mixing 1 part of perfectly dry sulphocyanide of potassium with 2 parts of powdered sal-ammoniac, and heating the mixture for some time in a retort or flask; bisulphide of carbon, sulphide of ammonium, and sulphuretted hydrogen are disengaged and volatilized, while a mixture of melam, chloride of potassium, and some sal-ammoniac remains: the two latter substances are removed by washing with hot water. Melam contains $C_{12}H_9N_{11}$; it dissolves in concentrated sulphuric acid, and gives, by dilution with water and long boiling, cyanuric acid. The same substance is produced with disengagement of ammonia when melam is fused with hydrate of potassa. When strongly heated, melam is resolved into mellon and ammonia.

If melam be boiled for a long time in a moderately-strong solution of caustic potassa, until the whole has dissolved, and the liquid be then concentrated, a crystalline substance separates on cooling, which is called *melamine*. By re-crystallization it is obtained in colourless crystals, having the figure of an octahedron with rhombic base; it is but slightly soluble in cold water, fusible by heat, and volatile with trifling decomposition. It contains $C_6H_6N_6$, and acts as a base, combining with acids to crystallizable compounds. A second basic substance called *ammeline*, very similar in properties to melamine, is found in the alkaline mother-liquor from which the melamine has separated; it is thrown down on neutralizing the liquid with acetic acid. The precipitate, dissolved in dilute nitric acid, yields crystals of nitrate of ammeline, from which the pure ammeline may be separated by ammonia. It forms a brilliant white powder of minute needles, insoluble in water and alcohol, and contains $C_6H_5N_5O_2$. When ammeline is dissolved in concentrated sulphuric acid, and the solution mixed with a large quantity of water, or, better, spirit of wine, a white, insoluble powder falls, which is designated *ammelide*, and is found to contain $C_{12}H_9N_9O_6$. When long boiled with dilute sulphuric acid, melamine, ammeline, and ammelide are converted into cyanuric acid and ammonia.

UREA ; URIC ACID AND ITS PRODUCTS.

These bodies are closely connected with the cyanogen-compounds, and may be most conveniently discussed in the present place.

UREA.—Urea may be extracted from its natural source, the urine, or it may be prepared by artificial means. Fresh urine is concentrated in a water-bath, until reduced to an eighth or a tenth of its original volume, and filtered through cloth from the insoluble deposit of urates and phosphates. The liquid is mixed with about an equal quantity

of a strong solution of oxalic acid in hot water, and the whole vigorously agitated and left to cool. A very copious fawn-coloured crystalline precipitate of *oxalate of urea* is obtained, which may be placed upon a cloth filter, slightly washed with cold water, and pressed. This is to be dissolved in boiling-hot water, and powdered chalk added until effervescence ceases, and the liquid becomes neutral. The solution of urea is filtered from the insoluble oxalate of lime, warmed with a little animal charcoal, again filtered, and concentrated by evaporation, avoiding ebullition, until crystals form on cooling: these are purified by a repetition of the last part of the process. Urea can be extracted in great abundance from the urine of horses and cattle duly concentrated, and from which the hippuric acid has been separated by the addition of hydrochloric acid; oxalic acid then throws down the oxalate in such quantity as to render the whole semi-solid. Another process consists in precipitating the evaporated urine with concentrated nitric acid, when *nitrate of urea* is precipitated, which is purified by re-crystallization with animal charcoal, and lastly decomposed by carbonate of baryta. A mixture of nitrate of baryta and urea is formed, which is evaporated to dryness on the water-bath, and exhausted with alcohol, from which the urea crystallizes on cooling.

By artificial means urea is produced by heating solution of cyanate of ammonia. The following method of proceeding yields it in any quantity that can be desired. Cyanate of potassa, prepared by Liebig's process,* is dissolved in a small quantity of water, and a quantity of dry neutral sulphate of ammonia, equal in weight to the cyanate, added. The whole is evaporated to dryness in a water-bath, and the dry residue boiled with strong alcohol, which dissolves out the urea, leaving the sulphate of potassa and the excess of sulphate of ammonia untouched. The filtered solution, concentrated by distilling off a portion of the spirit, deposits the urea in beautiful crystals of considerable magnitude.

Urea forms transparent, colourless, four-sided prisms, which are soluble in an equal weight of cold water, and in a much smaller quantity at a high temperature. It is also readily dissolved by alcohol. It is inodorous, has a cooling saline taste, and is permanent in the air, unless the latter be very damp. When heated it melts, and at a higher temperature decomposes with evolution of ammonia and cyanate of ammonia; cyanuric acid remains, which bears a much greater heat without change. The solution of urea is neutral to test-paper; it is not decomposed in the cold by alkalis or by hydrate of lime, but at a boiling heat emits ammonia, and forms a carbonate of the base. The same change happens by fusion with the alkaline hydrates. Brought into contact with nitrous acid, it is decomposed instantly into a mixture of nitrogen and carbonic acid gases: this decomposition explains the use of urea in preparing nitric ether (see page 427). With chlorine it yields hydrochloric acid, nitrogen,

* See page 524.

and carbonic acid. Crystallized urea is anhydrous; it contains $C_2H_4N_2O_2$, or the *elements of cyanate of oxide of ammonium*. It differs from carbonate of ammonia by the elements of water; hence it might with some propriety be called *carbamide*. It is easily converted into carbonate of ammonia by assimilating the oxygen and hydrogen of 2 eq. of water. A solution of pure urea shows no tendency to change by keeping, and is not decomposed by boiling; in the urine, on the other hand, where it is associated with putrefiable organic matter, as mucus, the case is different. In putrid urine no urea can be found, but enough carbonate of ammonia to cause brisk effervescence with an acid; and if urine in a recent state, be long boiled, it gives off ammonia and carbonic acid from the same source.

Urea acts as a salt-base; with nitric acid it forms a sparingly soluble compound, which crystallizes, when pure, in small, indistinct, colourless plates, containing single equivalents of urea, nitric acid, and water. When colourless nitric acid is added to urine, concentrated to a fourth or a sixth of its volume, and cold, the nitrate crystallizes out in large, brilliant yellow laminæ, which are very insoluble in the acid liquid. The production of this nitrate is highly characteristic of urea. The oxalate, when pure, crystallizes in large, transparent colourless plates, which have an acid reaction, and are sparingly soluble; it contains an equivalent of water. Urea forms several compounds with metallic salts, e. g., with those of mercury. On mixing a liquid containing urea with a solution of nitrate of protoxide of mercury, a white precipitate takes place, which is a compound of urea with 4 eq. of protoxide of mercury. If the nitric acid, which is thus set free, be neutralized by the addition of an alkali or baryta-water, the whole of the urea is removed from the liquid in the form of the above compounds. Prof. Liebig, to whom we are indebted for this observation, has based upon this department a process of determining the amount of urea in urine. The details of this method, which is equally interesting to the chemist and the physiologist, have just been published.*

A series of substances analogous to urea which have lately been discovered and described under the name of methylamine-urea, ethylamine-urea, biethylamine-urea, &c., will be noticed in the section on the Vegeto-alkalis.

URIC, or LITHIC ACID.—This is a product of the animal organism, and has never been formed by artificial means. It may be prepared from human urine by concentration, and addition of hydrochloric acid; it crystallizes out after some time in the form of small, reddish, translucent grains, very difficult to purify. A much preferable method is, to employ the solid white excrement of serpents, which can be easily procured; this consists almost entirely of uric acid and urate of ammonia. It is reduced to powder, and boiled in dilute solution of caustic potassa; the liquid, filtered from the insignificant residue of feculent matter and earthy phosphates, is mixed with ex-

* Journal of the Chemical Society, vol. vi. p. 1.

cess of hydrochloric acid, boiled for a few minutes, and left to cool. The product is collected on a filter, washed until free from chloride of potassium, and dried by gentle heat.

Uric acid, thus obtained, forms a glistening, snow-white powder, tasteless, inodorous, and *very* sparingly soluble. It is seen under the microscope to consist of minute, but regular crystals. It dissolves in concentrated sulphuric acid without apparent decomposition, and is precipitated by dilution with water. By destructive distillation, uric acid yields cyanic, hydrocyanic, and carbonic acids, carbonate of ammonia, and a black coaly residue, rich in nitrogen. By fusion with hydrate of potassa, it furnishes carbonate and cyanate of the base, and cyanide of the alkaline metal. When treated with nitric acid and with binoxide of lead, it undergoes decomposition in a manner to be presently described.

Uric acid is found by analysis to contain $C_{10}H_2N_4O_4, 2HO$. It is a bibasic acid.


The only salts of uric acid that have attracted any attention are those of the alkalis: acid *urate of potassa* contains $KO, HO, C_{10}H_2N_4O_4$; it is deposited from a hot, saturated solution of uric acid in the dilute alkali as a white, sparingly soluble concrete mass, composed of minute needles; it requires about 500 parts of cold water for solution, is rather more soluble at a high temperature, and much more soluble in excess of alkali. *Urate of soda* resembles the salt of potassa; it forms the chief constituent of the gouty concretions in the joints called *chalk-stones*. *Urate of ammonia* is also a sparingly soluble compound, requiring for the purpose about 1000 parts of cold water; the solubility is very much increased by the presence of a small quantity of certain salts, as chloride of sodium. This is the most common of the urinary deposits, forming a buff-coloured or pinkish cloud or muddiness, which disappears by re-solution when the urine is warmed; the secretion from which this is deposited has an acid reaction. It occurs also as a calculus.

The following substances result from the oxidation of uric acid by binoxide of lead and nitric acid: they are some of the most beautiful and interesting bodies known, most of which have been discovered by Liebig and Wöhler.

ALLANTOIN.—Allantoin occurs ready-formed in the allantoic liquid of the foetal calf. It is produced artificially by boiling together water, uric acid, and pure, freshly-prepared binoxide of lead; the filtered liquid, duly concentrated by evaporation, deposits crystals of allantoin on cooling, which are purified by re-solution and the use of animal charcoal. It forms small but most brilliant prismatic crystals, which are transparent and colourless, destitute of taste, and without action on vegetable colours. Allantoin dissolves in 160 parts of cold water, and in a smaller quantity at the boiling temperature. It is decomposed by boiling with nitric acid, and by oil of vitriol when concentrated and hot, being in this case resolved into ammonia, carbonic

acid, and carbonic oxide. Heated with concentrated solution of caustic alkalis, it is decomposed into ammonia and oxalic acid, which latter combines with the base. These reactions are explained by the analysis of the substance, which shows it to be composed of the elements of two equivalents of oxalate of ammonia *minus* those of five equivalents of water, or $C_4H_3N_2O_3$.

The production of allantoin from uric acid and binoxide of lead is also perfectly intelligible; 1 eq. of uric acid, 2 eq. of oxygen from the binoxide, and 3 eq. of water, contain the elements of allantoin, 2 eq. of oxalic acid, and 1 eq. of urea.




The insoluble matter from which the solution of allantoin is filtered consists in great part of oxalate of lead; and the mother-liquor from which the crystals of allantoin have separated, yields, on farther evaporation, a large quantity of pure urea.

ALLOXAN.—This is the characteristic product of the action of concentrated nitric acid on uric acid in the cold. An acid is prepared, of sp. gr. 1.45, or thereabouts, and placed in a shallow open basin: into this a third of its weight of dry uric acid is thrown, by small portions, with constant agitation, care being taken that the temperature never rises to any considerable extent. The uric acid at first dissolves with copious effervescence of carbonic acid and nitrogen, and eventually, the whole becomes a mass of white, crystalline, pasty matter. This is left to stand some hours, drained from the acid liquid in a funnel whose neck is stopped with powder and fragments of glass, and afterwards more effectually dried upon a porous tile. This is *alloxan* in a crude state; it is purified by solution in a small quantity of water, and crystallization.


Alloxan crystallizes with facility from a hot and concentrated solution, slowly suffered to cool, in solid, hard, anhydrous crystals of great regularity, which are transparent, nearly colourless, have a high degree of lustre, and the figure of a modified rhombic octahedron. A cold solution, on the other hand, left to evaporate spontaneously, deposits large foliated crystals, which contain 6 eq. of water; they effloresce rapidly in the air. Alloxan is very soluble in water; the solution has an acid reaction, a disagreeably astringent taste, and stains the skin, after a time, red or purple. It is decomposed by alkalis, and both by oxidizing and deoxidizing agents; its most characteristic property is that of forming a deep-blue compound with a salt of protoxide of iron and an alkali.

Alloxan contains $C_8H_4N_2O_{10}$; its production is thus illustrated: 1 eq. of uric acid, 4 eq. of water, and 2 eq. of nitric acid contain the elements of alloxan, 2 eq. carbonic acid, 2 eq. of free nitrogen, and 1 eq. of nitrate of ammonia.



When to a solution of alloxan, heated to 140° (60°C), baryta-water is added, as long as the precipitate first produced re-dissolves, and the filtered solution is then left to cool, a substance is deposited in small, colourless, pearly crystals, which consists of baryta in combination with a new acid, the *alloxanic*. From this salt the base may be separated by the cautious addition of dilute sulphuric acid: the filtered liquid by gentle evaporation yields alloxanic acid in small radiated needles. It has an acid taste and reaction, decomposes carbonates, and dissolves zinc with disengagement of hydrogen. It is a bibasic acid, and contains in the hydrated state $\text{C}_8\text{H}_2\text{N}_2\text{O}_8, 2\text{HO}$; hence it is isomeric with alloxan. The alloxanates of the alkalis are freely soluble; those of the earths dissolve in a large quantity of tepid water, and that of silver is quite insoluble and anhydrous.

If a warm saturated solution of alloxanate of baryta be heated to ebullition, a precipitate falls, which is a mixture of carbonate and alloxanate of baryta, with an insoluble salt of a second new acid, the *mesoxalic*; the solution is found to contain unaltered alloxanate of baryta and urea. Mesoxalic acid is best prepared by slowly adding solution of alloxan to a boiling-hot solution of acetate of lead: the heavy granular precipitate of mesoxalate of lead thus produced is washed and decomposed by sulphuretted hydrogen; urea is also formed in this experiment. Hydrate of mesoxalic acid is crystallizable; it has a sour taste and powerfully acid reaction, and resists a boiling heat; it forms sparingly soluble salts with baryta and lime, and a yellowish insoluble compound with oxide of silver, which is reduced with effervescence when gently heated. This remarkable acid contains as hydrate $\text{C}_3\text{O}_4, 2\text{HO}$, and is consequently bibasic; it is formed by the re-resolution of alloxan into urea, and 2 eq. of mesoxalic acid:—



When ammonia in excess is added to a solution of alloxan, the whole heated to ebullition, and afterwards supersaturated with dilute sulphuric acid, a yellow, light precipitate falls, which increases in quantity as the liquid cools. This is *mykomelinic acid*; it is but feebly soluble in water, easily dissolved by alkalis, and forms a yellow compound with oxide of silver. Mykomelinic acid contains $\text{C}_8\text{H}_5\text{N}_4\text{O}_5$; it is produced by the conversion of alloxan and 2 eq. of ammonia into 1 eq. of mykomelinic acid and 5 eq. of water.

PARABANIC ACID.—This is the characteristic product of the action of moderately strong nitric acid on uric acid or alloxan, *by the aid of heat*; it is conveniently prepared by heating together 1 part of uric acid and 8 parts of nitric acid until the reaction has nearly ceased; the liquid is evaporated to a syrupy state, and left to cool; the acid

is drained from the mother-liquor and purified by re-crystallization. Parabanic acid forms beautiful colourless, transparent, thin, prismatic crystals, which are permanent in the air; it is easily soluble in water, has a pure and powerfully acid taste, and reddens litmus strongly. Neutralized with ammonia, and mixed with nitrate of silver, it gives a white precipitate. Crystallized parabanic acid contains $C_6N_2O_4 \cdot 2HO$; its production is thus explained: 1 eq. of uric acid, 4 eq. of water, and 4 eq. of oxygen from the nitric acid, yield 1 eq. of parabanic acid, 4 eq. of carbonic acid, and 2 eq. of ammonia; or, alloxan and 2 additional equivalents of oxygen furnish 1 eq. of parabanic acid, 2 eq. of carbonic acid, and 2 eq. of water.

The alkaline parabanates undergo a singular change by exposure to heat; if a solution of the acid be saturated with ammonia, boiled for a moment, and then left to cool, a substance separates in tufts of beautiful colourless needles; this is the ammonia-salt of an acid called the *oxaluric*. The hydrated acid is procured by adding an excess of dilute sulphuric acid to a hot and strong solution of oxalurate of ammonia, and cooling the whole rapidly. It forms a white, crystalline powder, of acid taste and reaction, capable of combining with bases: the salts of *baryta* and *lime* are sparingly soluble; that of *silver* crystallizes from the mixed hot solution of nitrate of silver and oxalurate of ammonia in long, silky needles. Oxaluric acid is composed of $C_6H_3N_2O_7 \cdot HO$; or the elements of 1 eq. of parabanic acid, and 2 eq. of water. A solution of oxaluric acid is resolved by ebullition into free oxalic acid and oxalate of urea.

THIONURIC ACID.—A cold solution of alloxan is mixed with a saturated solution of sulphurous acid in water, in such quantity that the odour of the gas remains quite distinct; an excess of carbonate of ammonia mixed with a little caustic ammonia is then added, and the whole boiled for a few minutes. On cooling, *thionurate of ammonia* is deposited in great abundance, forming beautiful colourless, crystalline plates, which by solution in water and re-crystallization acquire a fine pink tint. A solution of this salt gives with acetate of lead a precipitate of insoluble thionurate of the oxide of that metal, which is at first white and gelatinous, but shortly becomes dense and crystalline; from this compound the hydrated acid may be obtained by the aid of sulphuretted hydrogen. It forms a white, crystalline mass, permanent in the air, very soluble in water, of acid taste and reaction, and capable of combining directly with bases. When its solution is heated to the boiling-point it undergoes decomposition, yielding sulphuric acid and a very peculiar and nearly insoluble substance, called *uramile*. Thionuric acid is bibasic; the hydrate contains $C_8H_5N_3S_2O_{12} \cdot 2HO$; or the elements of alloxan, an equivalent of ammonia, and 2 eq. of sulphurous acid.

URAMILE.—The product of the decomposition by heat of hydrated thionuric acid. Thionurate of ammonia is dissolved in hot water, mixed with a small excess of hydrochloric acid, and the whole boiled

in a flask; a white, crystalline substance begins in a few moments to separate, which increases in quantity until the contents of the vessel often become semi-solid: this is *uramile*. After cooling, it is collected on a filter, washed with cold water to remove the sulphuric acid, and dried by gentle heat, during which it frequently becomes pinkish. Examined by a lens, it is seen to consist of minute acicular crystals. It is tasteless and nearly insoluble in water, but dissolves in ammonia and the fixed alkalis. The ammoniacal solution becomes purple in the air. It is decomposed by strong nitric acid, alloxan and nitrate of ammonia being generated. Uramile contains $C_8H_5N_3O_6$; or thionuric acid *minus* the elements of 2 eq. of sulphuric acid.

URAMILIC ACID.—When a cold saturated solution of thionurate of ammonia is mixed with dilute sulphuric acid, and evaporated in a water-bath, instead of uramile, another substance, *uramilic acid*, is formed and deposited in slender, colourless prisms, soluble in 8 parts of cold water. Uramilic acid dissolves in concentrated sulphuric acid without apparent decomposition; it has a feebly acid taste and reaction, and combines with bases. The salts of the alkalis are easily soluble; those of the earths much less so, and that of the oxide of silver is insoluble. Uramilic acid contains $C_{16}H_{10}N_5O_{15}$; 2 eq. of uramile and 3 eq. of water contain the elements of uramilic acid and 1 eq. of ammonia. It is a substance difficult of preparation.


ALLOXANTIN.—This is the chief product of the action of hot *dilute* nitric acid upon uric acid: the surest and best method of preparing it, however, is by passing a stream of sulphuretted hydrogen gas through a moderately-strong and cold solution of alloxan. The impure mother-liquor from which the crystals of alloxan have separated answers the purpose perfectly well; it is diluted with a little water, and a copious stream of gas transmitted through it. Sulphur is deposited in large quantity, mixed with a white, crystalline substance, which is the alloxantin. The product is drained upon a filter, slightly washed, and then boiled in water: the filtered solution deposits the alloxantin on cooling. Alloxantin forms small, four-sided, oblique rhombic prisms, colourless and transparent; it is soluble with difficulty in cold water, but more freely at a boiling temperature. The solution reddens litmus, gives with baryta-water a violet-coloured precipitate, which disappears on heating, and when mixed with nitrate of silver produces a black precipitate of metallic silver. Heated with chlorine or nitric acid, it is changed by oxidation to alloxan. The crystals become red when exposed to ammoniacal vapours. Alloxantin contains $C_8H_5N_2O_{10}$; or alloxan *plus* 1 equivalent of hydrogen.

This substance is readily decomposed: when a stream of sulphuretted hydrogen is passed through a boiling solution, sulphur is deposited and an acid liquid produced, supposed to contain a new acid, to which the term *dialuric* is applied. When neutralized by ammonia

it yields a salt which crystallizes in colourless, silky needles, containing $\text{NH}_4\text{O}_2\text{C}_8\text{N}_2\text{O}_4 + 3\text{HO}$. They become deep-red when heated to 212° (100°C) in the air. A hot saturated solution of alloxantin mixed with a neutral salt of ammonia instantly assumes a purple colour, which however quickly vanishes, and the liquid becomes turbid from the formation of uramile; the liquid is then found to contain alloxan and free acid. With oxide of silver alloxantin disengages carbonic acid, reduces a portion of the metal, and converts the remainder of the oxide into oxalurate. Boiled with water and binoxide of lead, alloxantin gives urea and carbonate of lead.


MUREXIDE; PURPURATE OF AMMONIA OF DR. PROUT.—There are several different methods of preparing this magnificent compound. It may be made directly from uric acid, by dissolving that substance in dilute nitric acid, evaporating to a certain point, and then adding to the warm, but not boiling liquid, a very slight excess of ammonia. In this experiment alloxantin is first produced, which becomes afterwards partially converted into alloxan; the presence of both is requisite to the production of murexide. This process is, however, very precarious, and often fails altogether. An excellent method is to boil for a few minutes in a flask a mixture of 1 part of dry uramile, 1 part of red oxide of mercury, and 40 parts of water, to which two or three drops of ammonia have been added; the whole assumes in a short space of time an intensely-deep purple tint, and when filtered boiling-hot, deposits, on cooling, splendid crystals of murexide, unmixed with any impurity. A third, and perhaps even still better process is that of Dr. Gregory: 7 parts of alloxan and 4 parts of alloxantin are dissolved in 240 parts of boiling-water, and the solution added to about 80 parts of cold, strong solution of carbonate of ammonia; the liquid instantly acquires such a depth of colour as to become opaque, and gives on cooling a large quantity of murexide; the operation succeeds best on a small scale.

Murexide* crystallizes in small square prisms, which by reflected light exhibit a splendid green metallic lustre, like that of the wing-cases of the rose-beetle and other insects: by transmitted light they are deep purple-red. It is soluble with difficulty in cold water, much more easily at a boiling temperature, and is insoluble in alcohol and ether. Mineral acids decompose it with separation of *murexan*, and caustic potassa dissolves it, with production of a most magnificent purple colour, which disappears when the solution is boiled. Murexide contains, according to Liebig and Wöhler, $\text{C}_{12}\text{H}_6\text{N}_5\text{O}_8$; its production may be thus explained:—2 eq. of uramile and 3 eq. of oxygen from the protoxide of mercury give rise to murexide, 1 eq. of alloxanic acid, and 2 eq. of water.



* So called from the Tyrian dye, said to have been prepared from a species of *murex*, a shell-fish.

Or, on the other hand, 1 eq. of alloxan, 2 eq. of alloxantin, and 4 eq. of ammonia, yield 2 eq. of murexide and 14 eq. of water.



MUREXAN; PURPURIC ACID OF DR. PROUT.—Liebig directs this substance to be prepared by dissolving murexide in caustic potassa, heating the liquid until the colour disappears, and then adding an excess of dilute sulphuric acid. It separates in colourless or slightly yellowish scales, nearly insoluble in cold water. In ammonia it dissolves, and the solution acquires a purple colour by exposure to the air, the murexide being then produced. Murexan is said to contain $\text{C}_6\text{H}_4\text{N}_2\text{O}_5$. This substance and its relation to murexide require re-examination.

A series of substances closely related to the derivatives of uric acid, will be noticed under the head of Caffeine (see page 556).

Connected with uric acid by similarity of origin, but not otherwise, are two curious and exceedingly rare substances called *xanthic oxide* and *cystic oxide*.

Xanthic oxide was discovered by Dr. Marcet: it occurs as an urinary calculus, of pale-brown colour, foliated texture, and waxy lustre, and is extracted by boiling the pulverized stone in dilute caustic potassa and precipitating by carbonic acid. The xanthic oxide falls as a white precipitate, which, on drying, becomes pale yellow, and resembles wax when rubbed. It is nearly insoluble in water and dilute acids. Its characteristic property is to dissolve without evolution of gas in nitric acid, and to give on evaporation a deep-yellow residue, which becomes yellowish-red on the addition of ammonia or solution of potassa. Xanthic oxide gives on analysis $\text{C}_5\text{H}_2\text{N}_2\text{O}_2$.

Cystic oxide.—Cystic oxide calculi, although very rare, are more frequently met with than those of the preceding substance: they have a pale colour, a concentric structure, and often a waxy external crust. The powdered calculus dissolves in great part without effervescence in dilute acids and alkalis, including ammonia; the ammoniacal solution deposits, by spontaneous evaporation, small but beautifully colourless crystals, which have the form of six-sided prisms and square tables. It forms a saline compound with hydrochloric acid. Caustic alkalis disengage ammonia from this substance by continued ebullition. Cystic oxide contains sulphur; it is composed of $\text{C}_6\text{H}_6\text{NS}_2\text{O}_4$.

Uric acid is perfectly well characterized, even when in very small quantity, by its behaviour with nitric acid. A small portion heated with a drop or two of nitric acid in a small porcelain capsule dissolves with copious effervescence. When this solution is cautiously evaporated nearly to dryness, and, after the addition of a little water,

mixed with a slight excess of ammonia, the deep-red tint of murexide is immediately produced.

Impure uric acid, in a remarkable state of decomposition, is now imported into this country, in large quantities, for use as a manure, under the name of *guano* or *huano*. It comes from the barren and uninhabited islets of the western coast of South America, and is the production of the countless birds that dwell undisturbed in those regions. The people of Peru have used it for ages. Guano usually appears as a pale-brown powder, sometimes with whitish specks; it has an extremely offensive odour, the strength of which, however, varies very much. It is soluble in great part in water, and the solution is found to be extremely rich in oxalate of ammonia, the acid having been generated by a process of oxidation. Guano also contains a peculiar substance called *guanine*, which closely corresponds with xanthic oxide. Like urea it combines with acids forming a series of crystallizable salts. Guanine contains $C_{10}H_5N_5O_2$.

SECTION V.

THE VEGETO-ALKALIS.

THE vegeto-alkalis, *alkaloids*, or *organic bases*, constitute a remarkable and most interesting group of bodies: they are met with in various plants, always in combination with an acid, which is in many cases of peculiar nature, not occurring elsewhere in the vegetable kingdom. They are, for the most part, sparingly soluble in water, but dissolve in hot alcohol, from which they often crystallize in a very beautiful manner on cooling. Several of them, however, are oily, volatile liquids. The taste of these substances, when in solution, is usually intensely bitter, and their action upon the animal economy exceedingly energetic. They all contain a considerable quantity of nitrogen, and are very complicated in constitution, having high combining numbers. This class of bodies is very numerous.

None of the organic bases occurring in plants have yet been formed by artificial means; analogous substances have, however, been thus produced.

MORPHINE, OR MORPHIA.—This is the chief active principle of opium; it is the best and most characteristic type of the group, and the earliest known, dating back to the year 1803.

Opium, the inspissated juice of the poppy-capsule, is a very complicated substance, containing besides morphine a host of other alkaloids in very variable quantities, combined with sulphuric acid and an organic acid called *meconic acid*. In addition to these, there are gummy, resinous, and colouring matters, caoutchouc, &c., besides mechanical impurities, as chopped leaves. The opium of Turkey is the most valuable, and contains the largest quantity of morphine; that of Egypt and of India are considerably inferior. It has been produced in England of the finest quality, but at great cost.

If ammonia be added to a clear, aqueous infusion of opium, a very abundant buff-coloured or brownish-white precipitate falls, which consists principally of morphine and narcotine, rendered insoluble by the withdrawal of the acid. The product is too impure, however, for use. The chief difficulty in the preparation of these substances is to get rid of the colouring matter, which adheres with great obstinacy, redissolving with the precipitates, and being again in part thrown down when the solutions are saturated with an alkali. The following method, which succeeds well upon a small scale, will serve to give the

student some idea of a process very commonly pursued when it is desired to isolate at once an insoluble organic base, and the acid with which it is in combination:—A filtered solution of opium in tepid water is mixed with acetate of lead in excess; the precipitated meconate of lead is separated by a filter, and through the solution containing acetate of morphine, now freed to a considerable extent from colour, a stream of sulphuretted hydrogen is passed. The filtered and nearly-colourless liquid, from which the lead has been thus removed, may be warmed to expel the excess of gas, once more filtered, and then mixed with a slight excess of caustic ammonia, which throws down the morphine and narcotine: these may be separated by boiling ether, in which the latter is soluble. The meconate of lead, well washed, suspended in water, and decomposed by sulphuretted hydrogen, yields solution of meconic acid.

Morphine and its salts are advantageously prepared, on the large scale, by the process of Dr. Gregory. A strong infusion of opium is mixed with a solution of chloride of calcium, free from iron; meconate of lime, which is nearly insoluble, separates, while the hydrochloric acid is transferred to the alkaloids. By duly concentrating the filtered solution, the hydrochlorate of morphine may be made to crystallize, while the narcotine, and other bodies, are left behind. Repeated recrystallization, and the use of animal charcoal, then suffice to whiten and purify the salt, from which the base may be precipitated in a pure state by ammonia. Other processes have been proposed, as that of M. Thibouméry, which consists in adding hydrate of lime in excess to an infusion of opium, by which the meconic acid is rendered insoluble, while the morphine is taken up with ease by the alkaline earth. By *exactly* neutralizing the filtered solution with hydrochloric acid, the morphine is precipitated, but in a somewhat coloured state.

Morphine, when crystallized from alcohol, forms small but very brilliant prismatic crystals, which are transparent and colourless. It requires at least 1000 parts of water for solution, tastes slightly bitter, and has an alkaline reaction. These effects are much more evident in the alcoholic solution. It dissolves in about 30 parts of boiling alcohol, and with great facility in dilute acids; it is also dissolved by excess of caustic potassa or soda, but scarcely by excess of ammonia. When heated in the air, morphine melts, inflames like a resin, and leaves a small quantity of charcoal, which easily burns away.

Morphine in powder, strikes a deep-bluish colour with neutral salts of sesquioxide of iron, decomposes iodic acid with liberation of iodine, and forms a deep-yellow or red compound with nitric acid: these reactions are by some considered characteristic.

Crystallized morphine contains $C_{34}H_{19}NO_6 + 2HO$.

The most characteristic and best-defined salt of this substance is the *hydrochlorate*. It crystallizes in slender, colourless needles, arranged in tufts or stellated groups, soluble in about 20 parts of cold water, and in its own weight at a boiling temperature. The crystals

contain 6 eq. of water. The *sulphate*, *nitrate*, and *phosphate* are crystallizable salts; the *acetate* crystallizes with great difficulty, and is usually sold in the state of a dry powder. The artificial *meconate* is sometimes prepared for medicinal use.

NARCOTINE.—The *marc*, or insoluble portion of opium, contains much narcotine, which may be extracted by boiling with dilute acetic acid. From the filtered solution the narcotine is precipitated by ammonia, and afterwards purified by solution in boiling alcohol, and filtration through animal charcoal. Narcotine crystallizes in small, colourless brilliant prisms, which are nearly insoluble in water. The basic powers of narcotine are very feeble; it is destitute of alkaline reaction, and, although freely soluble in acids, refuses, for the most part, to form with them crystallizable compounds.

According to Dr. Blyth narcotine contains $C_{48}H_{25}NO_{14}$.

Narcotine yields some curious products by the action of oxidizing agents, as a mixture of dilute sulphuric acid and binoxide of manganese, or a hot solution of bichloride of platinum. They have been chiefly studied by Wöhler and Blyth, and lately also by Anderson. The most important of these is *opianic acid*, a substance forming colourless, prismatic, reticulated crystals, sparingly soluble in cold water, easily in hot. It melts when heated, but does not sublime. After fusion it becomes quite insoluble in dilute alkalis, but without change of composition. This acid forms crystallizable salts and an ether; it contains $C_{20}H_9O_9, HO$. The ammonia-salt, by evaporation to dryness, yields a nearly-white insoluble powder, called *opiammon*, containing $C_{40}H_{19}NO_{16}$, convertible by strong acids into opianic acid and ammonia. Sulphurous acid yields with opianic acid two products containing sulphur. A mixture of binoxide of lead, opianic acid, and sulphuric acid, gives rise to a crystallizable bibasic acid termed *hemipinic acid*, containing $C_{20}H_8O_{10}, 2HO$. A basic substance, *coturnine*, $C_{26}H_{13}NO_6$, is contained in the mother-liquor from which opianic acid has crystallized; it forms a yellow crystalline mass, very soluble, of bitter taste, and feebly alkaline reaction. Its hydrochlorate is a well-defined salt. Another basic substance, *narcogenine*, was accidentally produced in an attempt to prepare cotarnine by bichloride of platinum. It formed long orange-coloured needles, and contained $C_{36}H_{19}NO_{10}$.

CODEINE.—Hydrochlorate of morphine, prepared directly from opium as in Gregory's process, contains codeine-salt. When dissolved in water, and mixed with a slight excess of ammonia, the morphine is precipitated, and the codeine left in solution. Pure codeine crystallizes, by spontaneous evaporation, in colourless transparent octahedra; it is soluble in 80 parts of cold, and 17 of boiling water, has a strongly alkaline reaction, and forms crystallizable salts.

Codeine is composed of $C_{36}H_{21}NO_6$. This base has lately been the subject of a careful investigation by Dr. Anderson, who has prepared

a great number of its derivatives, all of which establish the formula given.

THEBAINE OR PARAMORPHINE.—This substance is contained in the precipitate formed by hydrate of lime in a strong infusion of opium in Thibouméry's process for morphine. The precipitate is well washed, dissolved in dilute acid, and mixed with ammonia in excess, and the thebaine thrown down crystallized from alcohol. It forms when pure colourless needles like those of narcotine, but sparingly soluble in water, readily soluble in the cold in alcohol and ether. It melts when heated, and decomposes at a high temperature. With dilute acid it forms crystallizable compounds, and when isolated and in solution has a powerfully alkaline reaction. The composition of thebaine is $C_{38}H_{21}NO_6$.

A series of other bases, *pseudo-morphine*, *narceine*, *meconine*, *papaverine*, *opianine*, and *porphyroxine*, are also, at least occasionally, contained in opium; they are of small importance, and comparatively little is known respecting them.

MECONIC ACID is obtained from the impure meconate of lead, as already mentioned. The solution is evaporated in the vacuum of the air-pump. A more advantageous method is to decompose the impure meconate of lime, obtained in Dr. Gregory's morphine-process, by warm dilute hydrochloric acid; to separate the crystals of acid meconate of lime, which form on cooling, and to repeat this operation until the whole of the base has been removed, which may be known by the acid being entirely combustible, without residue, when heated in the flame of a spirit-lamp upon platinum foil. It is with the greatest difficulty obtained free from colour.

Meconic acid crystallizes in little colourless, pearly scales, which dissolve in 4 parts of hot water. It has an acid taste and reaction, forms soluble compounds with the alkalis, and insoluble salts with lime, baryta, and the oxides of lead and silver. The most remarkable feature of this substance is its property of striking a deep blood-red colour with a salt of the sesquioxide of iron, exactly resembling that developed, under similar circumstances, by a sulphocyanide. The meconate of iron may, however, be distinguished from the latter compound, as Mr. Everitt has shown, by an addition of corrosive sublimate, which bleaches the sulphocyanide, but has little effect upon the meconate. This is a point of considerable practical importance, as in medico-legal inquiries, in which evidence of the presence of opium is sought for in complex organic mixtures, the detection of meconic acid is usually the object of the chemist; and since traces of alkaline sulphocyanide are to be found in the saliva, it becomes very desirable to remove that source of error and ambiguity.

Crystallized meconic acid contains $C_{14}HO_{11}, 3HO + 6HO$.

When a solution of meconic acid in water, or, still better, in a mineral acid, is boiled, or when the dry acid is exposed in a retort to a temperature of 400° ($204^{\circ}.5C$), it is decomposed, yielding a new

bibasic acid, the *comenic*, containing $C_{12}H_2O_8, 2HO$, which much resembles in properties meconic acid. Water and carbonic acid are at the same time evolved. At a higher temperature comenic acid itself is resolved into a second new acid, the *pyromeconic*, which sublimes, and afterwards condenses in brilliant colourless plates. It is monobasic, and contains $C_{10}H_3O_5, HO$. The salts of meconic acid and comenic acid, together with several derivatives of these substances, have been lately studied by Mr. How,* but our space will not permit us to describe these compounds.

An acid much resembling the meconic has been extracted from the *Chelidonium majus*; it is combined with lime, and associated with malic and fumaric acids. Chelidonic acid is bibasic, forming three classes of salts, and a pyro-acid with evolution of water and carbonic acid when exposed to a high temperature. It crystallizes in slender colourless needles, of considerable solubility, containing $C_{14}H_2O_{10}, 2HO + 3HO$.

CINCHONINE AND QUININE.—It is to these vegeto-alkalis that the valuable medicinal properties of the Peruvian barks are due. They are associated in the bark with sulphuric acid, and with a special acid, not found elsewhere, called the *kinic*. Cinchonine is contained in largest quantity in the pale bark, or *Cinchona condaminca*; quinine in the yellow bark, or *Cinchona cordifolia*; the *Cinchona oblongifolia* contains both.

The simplest, but not the most economical, method of preparing these substances, is to add a slight excess of hydrate of lime to a strong decoction of the ground bark, in acidulated water; to wash the precipitate which ensues, and boil it in alcohol. The solution, filtered while hot, deposits the vegeto-alkali on cooling. When both bases are present, they may be separated by converting them into sulphates; the salt of quinine is the least soluble of the two, and crystallizes first.

Pure cinchonine, or cinchonia, crystallizes in small, but beautifully brilliant, transparent four-sided prisms. It is but very feebly soluble in water, dissolves readily in boiling alcohol, and has but little taste, although its salts are excessively bitter. It is a powerful base, neutralizing acids completely, and forming a series of crystallizable salts. Cinchonine turns the plane of polarization to the right.

Quinine, or quina, much resembles cinchonine; it does not crystallize so well, however, and is much more soluble in water; its taste is intensely bitter. Quinine turns the plane of polarization towards the left.

Cinchonine is composed of	.	$C_{20}H_{12}NO$, and
Quinine of	.	$C_{20}H_{12}NO_2$.†

* Chem. Soc. Quar. Jour. Vol. iv. page 363.

† Some doubts are still hanging over the composition of cinchonine and quinine. According to M. Laurent these substances contain respectively

Sulphate of quinine is manufactured on a very large scale for medicinal use; it crystallizes in small white needles, which give a neutral solution. Nevertheless, this substance is a basic salt, and contains $2C_{20}H_{12}NO_2 \cdot SO_3 + 8HO$. The solubility of this compound is much increased by the addition of a little sulphuric acid, whereby the neutral salt $C_{20}H_{12}NO_2 \cdot SO_3 + 8HO$ is formed. A very interesting compound has been recently produced by Dr. Herapath, by the action of iodine upon the sulphate of quinine. It is a crystalline substance of a brilliant emerald colour, which appears to consist of 1 eq. of the sulphate of quinine, and 1 eq. of iodine. This remarkable compound possesses the optical properties of the mineral tourmaline. (See page 64.)

Quinidine.—In manufacturing sulphate of quinine, a new base has been lately obtained, which differs from quinine in some of its physical properties, but is said to have the same composition as quinine. It has been described under the name of *quinidine*, and appears to have the same medicinal properties, as quinine. This substance has lately been carefully examined by M. Pasteur, and his researches have led to the following interesting results.

The substance which is found in commerce under the name of quinidine is generally a mixture of two alkaloids, of which the one is isomeric with quinine, and the other isomeric with cinchonine. M. Pasteur designates these two substances respectively as *quinidine* and *cinchonidine*. They differ from quinine and cinchonine in several minor properties, but particularly in their deportment with polarized light, for while quinine turns the plane of polarization considerably towards the *left*, quinidine exerts a powerful action towards the *right*. Again, while cinchonine deflects considerably towards the *right*, the action of the isomeric cinchonidine is in the opposite direction, namely, towards the *left*. It is evident that quinine and quinidine on the one hand, and cinchonine and cinchonidine on the other, stand to each other in about the same relation as levo- and dextro-racemic acids (see page 506). Nor are the terms wanting which correspond to racemic acid itself. M. Pasteur has in fact proved, that both quinine and quinidine, and likewise cinchonine and cinchonidine, are peculiarly modified by the action of heat, exposed for several hours to a temperature varying between 248° and 266° (120° and $130^\circ C$), quinine and quinidine are converted into a third isomeric alkaloid, which M. Pasteur terms *quinicine*, while cinchonine and cinchonidine furnish an isomeric *cinchonicine* under the same circumstances. In racemic acid the right-handed action of dextro-racemic, and the left-handed action of levo-racemic acid, are exactly balanced, racemic acid possessing no longer any action upon polarized light; in the two new products, in

$C_{36}H_{24}N_2O_4$, and $C_{36}H_{24}N_2O_2$. If these formulas be adopted, the basic sulphate of commerce would become a neutral, the neutral an acid-salt.

Commercial sulphate	$C_{36}H_{24}N_2O_2 \cdot SO_3 + 8HO$.
Soluble sulphate	$C_{36}H_{24}N_2O_2 \cdot SO_3 + HO, SO_3 + 15HO$.

quinicine and cinchonine, such a perfect balance is not observed, both still exert a feeble right-handed action, which is, however, very slight when compared with the powers of the alkaloid, which give rise to them. The following table exhibits the relations of the six alkaloids, and their analogy with the racemic group, in a more conspicuous manner :—

Quinine	Quinicine	Quinidine
<i>Left-handed,</i>	<i>Right-handed,</i>	<i>Right-handed,</i>
<i>powerfully.</i>	<i>feebly.</i>	<i>very powerfully.</i>
Cinchonine	Cinchonine	Cinchonidine
<i>Right-handed,</i>	<i>Right-handed,</i>	<i>Left-handed,</i>
<i>very powerfully.</i>	<i>feebly.</i>	<i>powerfully.</i>
Dextro-racemic	Racemic acid	Levo-racemic
(tartaric) acid	<i>neutral.</i>	acid
<i>Right-handed.</i>		<i>Left-handed.</i>

Chinoidine, *quinoidine*, or *amorphous quinine*, is contained in the refuse, or mother-liquors of the quinine manufacture. In its purest state it forms a yellow or brown resin-like mass, insoluble in water, freely soluble in alcohol and ether. It is easily soluble also in dilute acids, and is thence precipitated by ammonia. Quinoidine possesses powerful febrifuge properties, and is identical in composition with quinine. It evidently bears to quinine the same relation that uncrySTALLIZABLE syrup does to ordinary sugar, being produced from quinine by the heat employed in the preparation.

From *Cuseo*, or *Arieda-bark*, and likewise from the *Cinchona ovata*, or *white quinquina* of Condamine, a substance denominated *aricine* or *cinchovatine* has been extracted; it closely resembles cinchonine, and contains $C_{20}H_{12}NO_3$ i. e., 1 eq. of oxygen more than quinine, and 2 eq. more than cinchonine.

This substance is useless in medicine.

KINIC ACID.—Kinate of lime is found in the solution from which the bark-alkalis have been separated by hydrate of lime, and is easily obtained by evaporation, and purified by animal charcoal. From the lime-salt the acid can be extracted by decomposing it by diluted sulphuric acid. The clear solution evaporated to a syrupy consistence deposits large, distinct crystals, which resemble those of tartaric acid. It is soluble in 2 parts of water, and contains $C_{14}H_{11}O_{11},HO$.

When kinic acid is heated with a mixture of sulphuric acid and binoxide of manganese, it furnishes a very volatile substance termed *kinone*, the vapour of which is exceedingly irritating to the eyes. This new body forms crystals both by sublimation and by solution in boiling water; it melts with gentle heat, and crystallizes on cooling, colours the skin permanently brown, and contains $C_{12}H_4O_4$.

By destructive distillation, kinic acid yields numerous and interesting products, which have been studied by M. Wöhler, as benzoic acid, carbolic acid, hydride of salicyl, benzol, a tarry substance not exa-

mined, and a new body, *colourless hydrokinone*, which possesses very curious relations with the kinone above described. It forms colourless six-sided prismatic crystals; is neutral, destitute of taste and odour, fusible, and easily soluble both in water and alcohol. With care it may be sublimed unchanged. It contains $C_{12}H_6O_4$.

Colourless hydrokinone can be easily and directly produced from kinone by the assimilation of hydrogen, as by addition of hydriodic acid to a solution of the latter, when iodine is set free, or by sulphurous acid, or telluretted hydrogen.

An intermediate product of reduction is *green hydrokinone*. This is obtained by the incomplete action of sulphurous acid upon kinone, or by the action of sesquichloride of iron, chlorine, nitrate of silver, or chromic acid upon colourless hydrokinone; or by mixing together solutions of kinone and colourless hydrokinone. It forms slender green crystals of the colour of the wing-case of the rose-beetle, and of the greatest brilliancy and beauty. It is fusible, has but little odour, and dissolves freely in boiling water, crystallizing out on cooling. This substance contains $C_{12}H_5O_4$.

If kinic acid be submitted to distillation with an ordinary chlorine-mixture, an acid liquid and a crystalline sublimate are formed. The former is a solution of formic acid, the latter a mixture of 4 chlorinnetted compounds, which are chlorokinone $C_{12}(H_3Cl)O_4$, bichlorokinone $C_{12}(H_2Cl_2)O_4$, trichlorokinone $C_{12}(HCl_3)O_4$, and tetrachlorokinone $C_{12}Cl_4O_4$. They are all yellow crystalline substances, which can be separated only with great difficulty. Like kinone itself, they possess the faculty of combining with 1 or 2 eq. of hydrogen, producing 2 series of substances analogous to green and colourless hydrokinone. Tetrachlorokinone, better known by the name *chloranile*, likewise occurs among the products of decomposition of indigo.

Other products were obtained by the action of sulphuretted hydrogen and strong hydrochloric acid upon kinone, which possess less interest than the preceding.

STRYCHNINE AND BRUCINE, also called strychnia and brucia, are contained in *Nux vomica*, in *St Ignatius' bean*, and in *false Angustura bark*; they are associated with a peculiar acid, called the *igasuric*. *Nux-vomica* seeds are boiled in dilute sulphuric acid until they become soft; they are then crushed, and the expressed liquid mixed with excess of hydrate of lime, which throws down the alkalis. The precipitate is boiled in spirit of wine of sp. gr. 0·850, and filtered hot. Strychnine and brucine are deposited together in a coloured and impure state, and may be separated by cold alcohol, in which the latter dissolves readily.

Pure strychnine crystallizes under favourable circumstances in small but exceedingly brilliant octahedral crystals, which are transparent and colourless. It has a very bitter, somewhat metallic taste (1 part in 1,000,000 parts of water is still perceptible), is slightly soluble in water, and is fearfully poisonous. It dissolves in hot, and

somewhat dilute spirit, but neither in absolute alcohol, ether, nor in solution of caustic alkali. This alkaloid may be readily identified by moistening a crystal with concentrated sulphuric acid, and adding to the liquid a crystal of bichromate of potassa, when a deep violet tint is produced, which disappears after some time. Strychnine forms with acids a series of well-defined salts, lately examined by Messrs. Nicholson and Abel, who established for strychnine the formula $C_{42}H_{22}N_2O_4$.

Brucine is easily distinguished from the preceding substance, which it much resembles in many respects, by its ready solubility in alcohol, both hydrate and absolute. It dissolves also in about 500 parts of hot water. The salts of brucine are, for the most part, crystallizable.

Brucine contains $C_{46}H_{26}N_2O_8$.

VERATRINE (or veratria) is obtained from the seeds of *Veratrum sabadilla*. In its purest state it is a white or yellowish-white powder, which has a sharp burning taste, and is very poisonous. It is remarkable for occasioning violent sneezing. It is insoluble in water, but dissolves in hot alcohol, in ether, and in acids; the solution has an alkaline reaction. Veratrine contains nitrogen, but its composition is yet doubtful.

A substance called *colchicine*, extracted from the *Colchicum autumnale*, and formerly confounded with veratrine, is now considered distinct; its history is yet imperfect.

CONINE (CONICINE, or CONIA), NICOTINE, and SPARTEINE differ from the other vegetable bases in physical characters; they are volatile oily liquids. The first is extracted from hemlock, the second from tobacco, and the third from broom (*Spartium scoparium*). They agree in most of their characters, having high boiling-points, very poisonous properties, strong alkaline reaction, and the power of forming with acids crystallizable salts. The formula of nicotine is $C_{10}H_7N$; that of conine, $C_{16}H_{15}N$, and that of sparteine $C_{15}H_{13}N$. A series of substances as it appears closely related to nicotine will be mentioned among the artificial organic bases.

The basic substance contained in the juice of animal flesh, *kreatinine*, will be found described among the components of the animal body.

HARMALINE.—This compound is extracted by dilute acetic acid from the seeds of the *Peganum harmala*, a plant which grows abundantly in the Steppes of Southern Russia, and the seeds of which are used in dyeing. When pure, it forms yellowish prismatic crystals, soluble in alcohol and dilute acids, but scarcely forming crystallizable salts. By oxidation it gives rise to another compound, *harmine*, which itself possesses basic properties. The seeds are used for dyeing. Harmaline probably contains $C_{28}H_{14}N_2O_2$, and harmine $C_{28}H_{12}N_2O_2$.

CAFFEINE, or THEINE.—This remarkable substance occurs in four articles of domestic life, infusions of which are used as beverages over

the greater part of the known world, namely, tea and coffee, and in the leaves of *Guarana officinalis*, or *Paullinia sorbilis*, and in those of *Ilex paraguayensis*; it will probably be found in other plants. A decoction of common tea, or of raw coffee-berries, previously crushed, is mixed with excess of solution of basic acetate of lead. The solution, filtered from the copious yellow or greenish precipitate, is treated with sulphuretted hydrogen to remove the lead, filtered, evaporated to a small bulk, and neutralized by ammonia. The caffeine crystallizes out on cooling, and is easily purified by animal charcoal. It forms tufts of delicate, white, silky needles, which have a bitter taste, melt when heated with loss of water, and sublime without decomposition. It is soluble in about 100 parts of cold water, and much more easily at a boiling-heat, or if an acid be present. Alcohol also dissolves it, but not easily. Caffeine contains $C_{16}H_{10}N_4O_4$. The basic properties are feeble. The salts with hydrochloric and sulphuric acid are obtained only with difficulty. It forms, however, splendid double-salts with bichloride of platinum and trichloride of gold. The products of oxidation of caffeine, which have been lately studied by Rochleder, are of considerable interest, inasmuch as both their composition and their properties establish a close connection of these products with the derivatives of uric acid. Under the influence of chlorine, caffeine yields a substance of feebly acid properties, which contains $C_{12}H_7N_2O_8$. This compound, which has received the name *amalic acid*, is homologous to alloxantin. When treated with oxidizing agents, it yields *cholestrophane*, $C_{10}H_6N_2O_6$, corresponding to parabanic acid of the uric-acid-series. The murexide of the caffeine-series lastly is formed by the treatment of amalic acid with ammonia, exactly as the murexide *par excellence* is formed by the action of ammonia upon alloxantin. The new murexide imitates its prototype not only in composition, but likewise in the green metallic lustre of its crystals, and the deep-crimson colour of its solutions. The homology of these compounds with the members of the uric-acid-series is well illustrated by a comparison of their formulæ:—

Alloxantin	$C_8H_3N_2O_8 + 2C_2H_2 = C_{12}H_7N_2O_8$	Amalic acid.
Parabanic acid	$C_6H_2N_2O_6 + 2C_2H_2 = C_{10}H_6N_2O_6$	Cholestrophane.
Murexide	$C_{12}H_6N_5O_8 + 3C_2H_2 = C_{18}H_{12}N_5O_8$	Caffeine-murexide.

THEOBROMINE.—The seeds of the *Theobroma cacao*, or cacao-nuts, from which chocolate is prepared, contain a crystallizable principle to which the preceding name is given. It is extracted in the same manner as caffeine, and forms a white, crystalline powder, which is much less soluble than the last-named substance. It contains, according to Glasse, $C_{14}H_8N_4O_4$. Accordingly it is homologous to caffeine. The products obtained from theobromine by oxidation appear to be likewise homologous with several terms of the uric-acid-series.

BERBERINE.—A substance crystallizing in fine yellow needles, slightly soluble in water, extracted from the root of the *Berberis vul-*

garis. It has feeble basic properties, and contains $C_{42}H_{18}NO_9$. This must not be confounded with *beberine*, an uncrystallizable basic substance, from the bark of the *green-heart* timber of Guiana, which has the composition $C_{33}H_{21}NO_6$.

PIPERINE.—A colourless, or slightly-yellow crystallizable principle, extracted from pepper by the aid of alcohol. It is insoluble in water. Formula $C_{34}H_{19}NO_6$. Piperine readily dissolves in acid; definite compounds, however, are obtained only with difficulty.

There are very many other bodies, more or less perfectly known, having to a certain extent the properties of salt-bases; the following statement of the names and mode of occurrence of a few of these must suffice.

Hyoscyamine (*Daturine*).—A white, crystallizable substance, from *Hyoscyamus niger*; it occurs likewise in *Datura stramonium*.

Atropine.—Colourless needles, from *Atropa belladonna*, formula $C_{34}H_{23}NO_6$.

Solanine.—A pearly, crystalline substance, from various solanaceous plants.

Aconitine.—A glassy, transparent mass, from *Aconitum napellus*; formula $C_{60}H_{27}NO_{14}$.

Delphinine.—A yellowish, fusible substance, from the seeds of *Delphinium staphisagria*.


Emetine.—A white and nearly tasteless powder from ipecacuanha root.

Curarine.—The arrow-poison of Central America.

There exists an extensive series of neutral, usually bitter, and sometimes poisonous vegetable principles, which are allied in some measure to the vegetable-alkalis. Some of these are destitute of nitrogen. Two of the number, salicin and phloridzin, have been already described (see pages 494 and 498); the most important of the remainder are the following:—

GENTIANIN.—The bitter principle of the gentian-root, extracted by ether. It crystallizes in golden-yellow needles, is sparingly soluble in cold water, more soluble in hot water, and freely dissolved by alcohol and ether. Its composition is $C_{14}H_5O_5$.

POPULIN.—This substance closely resembles salicin in appearance and solubility, but has a penetrating sweet taste: it is found accompanying salicin in the bark and leaves of the aspen. According to recent researches of Piria, populin contains $C_{40}H_{22}O_{16} + 4HO$. It is a conjugate compound of salicin and benzoic acid.



By the action of reagents it is converted into benzoic acid, and the products of decomposition of salicin. With dilute acid it yields

benzoic acid, grape-sugar, and saliretin; when treated with a mixture of sulphuric acid and bichromate of potassa, it furnishes a considerable quantity of hydride of salicyl.

DAPHNIN.—Extracted from the bark of the *Daphne mezereum*; it forms colourless, radiated needles, freely soluble in hot water, alcohol, and ether.

HESPERIDIN.—A white, silky, tasteless substance, obtained from the spongy part of oranges and lemons. It dissolves in 60 parts of hot water: also in alcohol and ether.

ELATERIN.—The active principle of *Momordica elaterium*. It is a white, silky, crystalline powder, insoluble in water. It has a bitter taste, and excessively violent purgative properties. Alcohol, ether, and oils dissolve it. Exposed to heat, it melts and afterwards volatilizes. It contains $C_{20}H_{14}O_5$.

ANTIARIN.—The poisonous principle of the *Upas antiar*. It forms small pearly crystals, soluble in 27 parts of boiling water, and also in alcohol, but scarcely so in ether; it cannot be sublimed without decomposition. Introduced into a wound, it rapidly brings on vomiting, convulsions, and death. Antiarin contains $C_{14}H_{10}O_5$.


PIROTOXIN.—It is to this substance that *Cocculus indicus* owes its active properties. Picrotoxin forms small, colourless, stellated needles, of inexpressibly bitter taste, which dissolve in 25 parts of boiling alcohol. It contains $C_{10}H_6O_4$.

ASPARAGIN.—This, and the two following, are azotized bodies. Asparagin is found in the root of the marsh-mallow, in asparagus sprouts, and in several other plants. The mallow-roots are chopped small, and macerated in the cold with milk of lime; the filtered liquid is precipitated by carbonate of ammonia, and the clear solution evaporated in a water-bath to a syrupy state. The impure asparagin, which separates after a few days, is purified by re-crystallization. Asparagin forms brilliant, transparent, colourless crystals, which have a faint cooling taste, and are freely soluble in water, especially when hot. When dissolved in a saccharine liquid, which is afterwards made to ferment, when heated with water under pressure in a close vessel, or when boiled with an acid or an alkali, it is converted into ammonia and a new acid, the *aspartic*. Asparagin contains $C_8H_8N_2O_6$, and aspartic acid $C_8H_7NO_8$. The remarkable relation in which these substances stand to malic acid has been already noticed under the head of malic acid (see page 509).

SANTONIN.—This substance is the crystalline principle of several varieties of *Artemisia*. In order to obtain it, the seeds are crushed, and digested with lime and spirit of wine, when a yellow liquid is obtained, from which the alcohol is separated by distillation. The residuary liquid is saturated with acetic acid, when the santonin crystallizes. This substance is easily soluble in water and alcohol, and contains $C_{30}H_{18}O_6$. Santonin possesses the character of a weak acid.

ORGANIC BASES OF ARTIFICIAL ORIGIN.


The constitution of the alkaloids, which occur ready formed in nature, is not yet clearly understood. The fact that all these substances contain nitrogen,—the alkaline reaction, which the greater part of them exhibits with vegetable colours, and especially their faculty of combining with acids to crystallizable salts, establish an obvious relation between the alkaloids and ammonia. This has never been doubted, and the views of chemists have been divided only as to the nature of this relation. At a certain time Berzelius assumed that all the alkaloids contained ammonia ready formed, and that their basic properties were due to this ammonia. According to this view the formulæ of quinine and morphine would be—



This view, in the general form in which it was proposed, is certainly inadmissible. It is supported by very scanty experimental evidence, and was never universally adopted. There may be some alkaloids so constituted as represented by the theory of Berzelius. There are, however, a great many, the constitution of which is obviously different. Several of these substances have been lately the subject of extensive and careful inquiries; but these researches, although they have established their formulæ and increased our knowledge regarding their salts, have as yet elicited but few facts which promise to afford a clearer insight into the nature of these bodies.


On the other hand, the labours of the last ten years have brought to light a very numerous group of substances perfectly analogous to the alkaloids which are found in plants, but produced by artificial processes in the laboratory. These bodies, which are termed *artificial alkaloids* or *artificial organic bases*, are mostly volatile. Their constitution is much simpler than that of the native bases. The very processes which give rise to their formation often permit a very clear insight into the mode in which the elements are grouped, and in the relation existing between these substances and ammonia.

In a former section of this volume (page 271), it has been stated that the majority of chemists are inclined to assume in the ammoniacal salts the existence of a compound metal ammonium NH_4 ,



Now, recent researches have shown, that in these salts, 1, 2, 3, or even the 4 eq. of hydrogen may be replaced by compound radicals, containing variable proportions of carbon and hydrogen, without any change in their fundamental properties. It is evident that we obtain in this

manner, in addition to the ammoniacal salts, four new series of compounds very closely allied to the former. Let A B C D represent a series of such radicals capable of replacing hydrogen, then the following series of salts may be formed :—



It need scarcely be mentioned that it is by no means necessary that the several hydrogen-equivalents in ammonia should be replaced by different radicals, as assumed in the preceding table. Substances of the formulæ—




are even more easily prepared and more frequently met with.

This synopsis shows that the number of salts capable of being derived from the ordinary ammoniacal salts must be very considerable. Even now a very extensive series has been prepared, although the number of radicals at our disposal at present is still comparatively limited.


It has been mentioned that all attempts at isolating both ammonium and its oxide have hitherto failed (see page 271). On treating chloride of ammonium or sulphate of ammonia with mineral oxides, such as potassa, lime, and baryta, decomposition ensues, chloride of potassium or sulphate of potassa, &c., is formed, and the separated

oxide of ammonium splits into ammonia-gas and water, $\text{NH}_4\text{O} = \text{NH}_3 + \text{HO}$ (see page 180).

The compound ammonia-salts are likewise decomposed by mineral oxides. With the first three classes the change is perfectly analogous to that of ammoniacal salts, the separated oxide is decomposed into water and a volatile base, the properties of which, according to the nature of the replacing radicals, are more or less closely approximated to those of ammonia itself. We arrive in this manner at three groups of organic bases, differing from one another by the amount of hydrogen which is replaced; they have been distinguished by the terms *amidogen*-, *imidogen*-, and *nitrile*-bases.



The last group of ammoniacal salts, in which the 4 eq. of hydrogen are replaced by radicals, differ in their deportment from the former classes. These salts are not decomposed by potassa, but yield, by appropriate treatment, a series of substances of a very powerfully alkaline character, which are expressed by the general formulæ:—



and are evidently analogous to hydrated oxide of ammonium; from which they differ, however, in a remarkable manner by their great stability.


These general statements will become more intelligible if we elucidate them by the description of several individual substances: the limits of this work compel us, however, to confine ourselves to the more important members of this already very numerous group, which is moreover daily increasing.

It may at once be stated that by far the greater number of these compounds are derived from the alcohols or substances analogous to them; and that the radicals which in the preceding sketch have been designated by the letters A, B, C, and D, are chiefly the hydrocarbons previously described under the names *ethyl*, *methyl*, and *amyl*.


BASES OF THE ETHYL-SERIES.

ETHYLAMINE, *Ethyl-ammonia*, $\text{C}_4\text{H}_7\text{N} = \text{N}(\text{H}_2\text{C}_4\text{H}_5) = \text{N}(\text{H}_2\text{Ae})$. — On digesting bromide or iodide of ethyl (see page 426) with an alcoholic solution of ammonia, the alkaline reaction of the ammonia gradually disappears. On evaporating the solution on the water-bath,

a white crystalline mass is obtained, which consists chiefly of bromide of ethyl-ammonium, $\text{AeI} + \text{NH}_3 = \text{N}(\text{H}_3\text{Ae})\text{I}$. On distilling this salt in a retort provided with a good condenser, with caustic lime, the ethylamine is liberated and distils over.



Another method of preparing this compound, and indeed the method by which this remarkable substance was first obtained by M. Wurtz, consists in submitting cyanate of ethyl to the action of hydrate of potassa. In describing cyanic acid (see page 523), the interesting change has been mentioned, which this substance undergoes when treated with boiling solution of potassa. In this case cyanic acid splits into 2 eq. of carbonic acid and 1 eq. of ammonia; cyanate of ethyl (see page 526) suffers a perfectly analogous decomposition, and instead of ammonia we obtain ethylamine.



Cyanurate of ethyl, isomeric with the cyanate, likewise furnishes ethylamine.

Ethylamine is a very mobile liquid, of 0.6964 sp. gr., at $46^\circ.4$ (8°C), which boils at $64^\circ.4$ (18°C). The sp. gr. of the vapour is 1.57. It has a most powerfully ammoniacal odour, and restores the blue colour to reddened litmus paper. It produces white clouds, with hydrochloric acid, and is absorbed by water with great avidity. With the acids it forms a series of neutral crystallizable salts perfectly analogous to those of ammonium.

This substance imitates, moreover, in a remarkable manner, the deportment of ammonia with metallic salts. It precipitates the salts of magnesia, alumina, iron, manganese, bismuth, chromium, uranium, tin, lead, and mercuric. Zinc-salts yield a white precipitate which is soluble in excess. Like ammonia, ethylamine dissolves chloride of silver, and yields with copper-salts a blue precipitate, which is soluble in an excess of ethylamine. On adding ethylamine to oxalic ether, a white precipitate of *ethyl-oxamide*, $\text{N}(\text{HAe})_2\text{C}_2\text{O}_2$, is produced; even a compound analogous to oxamic acid (see page 412) has been obtained. Ethylamine may, however, be readily distinguished from ammonia; its vapour is inflammable, and it produces, with bichloride of platinum, a salt $\text{N}(\text{H}_3\text{Ae})\text{Cl}, \text{PtCl}_2$, crystallizing in golden scales, which are rather soluble in water. If ethylamine be treated with chlorine, it furnishes chloride of ethyl-ammonium and a yellow liquid of a penetrating odour exciting tears, which contains NCl_2Ae . This sub-

stance is *bichlorethylamine*. When treated with potassa it is converted into ammonia, acetate of potassa, and chloride of potassium, $\text{NCl}_2, \text{C}_4\text{H}_5 + 3\text{KO} + \text{HO} = \text{KO}, \text{C}_4\text{H}_3\text{O}_3 + \text{NH}_3 + 2\text{KCl}$.

Ethylamine-urea.—On passing into a solution of ethylamine, the vapour of hydrated cyanic acid, the liquid becomes hot, and deposits, after evaporation, fine crystals of ethylamine-urea, $\text{C}_4\text{H}_7\text{N} + \text{C}_2\text{NO}, \text{HO} = \text{C}_6\text{H}_8\text{N}_2\text{O}_2 = \text{C}_2(\text{H}_3, \text{C}_4\text{H}_5)\text{N}_2\text{O}_2 = \text{C}_2(\text{H}_3\text{Ae})\text{N}_2\text{O}_2$. This substance, which may be viewed as ordinary urea (see page 536), in which 1 eq. of hydrogen is replaced by ethyl, may be prepared also by treating cyanic ether with ammonia, $\text{C}_4\text{H}_5\text{O}, \text{C}_2\text{NO} + \text{NH}_3 = \text{C}_6\text{H}_8\text{N}_2\text{O}_2$. Ethylamine-urea is very soluble in water and alcohol: the concentrated aqueous solution, unlike that of ordinary urea, yields no precipitate with nitric acid; but on gently evaporating the mixture, a very soluble crystalline nitrate of ethylamine-urea is obtained. Boiled with potassa, this substance yields a mixture of equal equivalents of ammonia and ethylamine, $\text{C}_2(\text{H}_3\text{Ae})\text{N}_2\text{O}_2 + 2(\text{KO}, \text{HO}) = 2(\text{KO}, \text{CO}_2) + \text{NH}_3 + \text{N}(\text{H}_2\text{Ae})$.

BIETHYLAMINE, *Biethyl-ammonia*, $\text{C}_8\text{H}_{11}\text{N} = \text{NH}, 2\text{C}_4\text{H}_5 = \text{N}(\text{HAe}_2)$.—A mixture of solution of ethylamine and bromide of ethyl, heated in a sealed tube for several hours, solidifies to a crystalline mass of bromide of biethyl-ammonium, $\text{N}(\text{H}_2\text{Ae}) + \text{AeBr} = \text{N}(\text{H}_2\text{Ae}_2)\text{Br}$. The bromide, when distilled with potassa, furnishes a colourless liquid, still very alkaline, and soluble in water, but less so than ethylamine. This compound boils at 133° (55°C). It forms beautifully crystallizable salts with acids. A solution of chloride of biethyl-ammonium furnishes with bichloride of platinum, a very soluble double salt, $\text{N}(\text{H}_2\text{Ae}_2)\text{Cl}, \text{PtCl}_2$, crystallizing in orange-red grains, very different from the orange-yellow leaves of the corresponding ethyl-ammonium-salt.

Biethylamine-urea.—Biethylamine probably behaves with cyanic acid like ammonia and ethylamine, giving rise to biethylamine-urea. This substance has been produced by the action of cyanic ether upon ethylamine, $\text{C}_4\text{H}_5\text{O}, \text{C}_2\text{NO} + \text{C}_5\text{H}_7\text{N} = \text{C}_{10}\text{H}_{12}\text{N}_2\text{O}_2 = \text{C}_2(\text{H}_2, 2\text{C}_4\text{H}_5)\text{N}_2\text{O}_2 = \text{C}_2(\text{H}_2\text{Ae}_2)\text{N}_2\text{O}_2$. Biethylamine-urea is very crystallizable, and readily forms a crystalline nitrate. Boiled with potassa, biethylamine-urea yields pure ethylamine, $\text{C}_2(\text{H}_2\text{Ae}_2)\text{N}_2\text{O}_2 + 2(\text{KO}, \text{HO}) = 2(\text{KO}, \text{CO}_2) + 2\text{N}(\text{H}_2\text{Ae})$.

TRIETHYLAMINE, *Triethyl-ammonia*, $\text{C}_{12}\text{H}_{15}\text{N} = \text{N}3(\text{C}_4\text{H}_5) = \text{NAe}_3$.—The formation of this body is perfectly analogous to those of ethylamine and biethylamine. On heating for a short time a mixture of biethylamine with bromide of ethyl in a sealed glass tube, a beautiful fibrous mass of bromide of triethyl-ammonium is obtained, from which the triethylamine is separated by potassa. Triethylamine is a colourless, powerfully alkaline liquid, boiling at $195^\circ.8$ (91°C). The salts of this base crystallize remarkably well. With bichloride of platinum it forms a very soluble double salt, $\text{N}(\text{HAe}_3)\text{Cl}, \text{PtCl}_2$, which crystallizes in magnificent large orange-red rhombs.

Hydrated Oxide of Tetrethyl-ammonium, $\text{C}_{20}\text{H}_{21}\text{NO}_2 = \text{N}4(\text{C}_4\text{H}_5)$

$O,HO=NAe_4O,HO$.—When anhydrous triethylamine is mixed with dry iodide of ethyl, a powerful reaction ensues, the mixture enters into ebullition, and solidifies on cooling to a white crystalline mass of iodide of tetrethyl-ammonium, $NAe_3 + AeI = NAe_4I$. The new iodide is readily soluble in hot water, from which it crystallizes on cooling in beautiful crystals of considerable size. This substance is not decomposed by potassa; it may be boiled with the alkali for hours without yielding a trace of volatile base. The iodine may, however, be readily removed by treating the solution with silver-salts. If in this case sulphate or nitrate of silver be employed, we obtain, together with iodide of silver, the sulphate or nitrate of oxide of tetrethyl-ammonium, which crystallize on evaporation; on the other hand, if the iodide be treated with freshly-precipitated protoxide of silver, the oxide of tetrethyl-ammonium itself is separated. On filtering off the silver-precipitate, a clear colourless liquid is obtained, which contains the isolated base in solution. It is of a strongly alkaline reaction, and has an intensely bitter taste. Solution of oxide of tetrethyl-ammonium has a remarkable analogy to potassa and soda. Like the latter substance, it destroys the epidermis and saponifies fatty substances with the formation of true soaps. With the salts of the metals, this substance exhibits exactly the same reactions as potassa. On evaporating a solution of the base *in vacuo*, long slender needles are deposited, which are evidently the hydrate of the base, with an additional amount of water of crystallization. After some time these needles disappear again, and a semi-solid mass is left, which is the hydrate of oxide tetrethyl-ammonium. A concentrated solution of this substance in water may be boiled without decomposition, but on heating the dry substance, it is decomposed into pure triethylamine and olefant gas:



Oxide of tetrethyl-ammonium forms neutral-salts with the acids. They are mostly very soluble; several yield beautiful crystals. The platinum-salt, $NAe_4Cl, PtCl_2$, forms orange-yellow octahedrons, which are of about the same solubility as the corresponding bichloride of platinum and potassium.

Oxide of tetrethyl-ammonium is obviously perfectly analogous to the hitherto hypothetical oxide of ammonium. It is a compound of remarkable stability, the existence and properties of which must be regarded as powerful supports of the ammonium-theory.

BASES OF THE METHYL-SERIES.

METHYLAMINE, *Methyl-ammonia*, $C_2H_5N = N(H_2, C_2H_5) = N(H_2, Me)$.—The formation and the method of preparing this compound from the cyanate of methyl are perfectly analogous to those of ethylamine (see page 561); however, methylamine being a gas at the common

temperature, it is necessary to cool the receiver by a freezing mixture. The distillate, which is an aqueous solution of methylamine, is saturated with hydrochloric acid, and evaporated to dryness. The crystalline residue, which is the chloride of methylammonium, when distilled with dry lime, yields methylamine gas, which, like ammonia gas, has to be collected over mercury. It is distinguished from ammonia by a slightly-fishy odour, and by the facility with which it burns. Methylamine is liquefied at about $-17^{\circ}\cdot8$ (0°C); its sp. gr. is 1.08. This substance is the most soluble of all gases at $53^{\circ}\cdot6$ (12°C); 1 volume of water absorbs 1040 volumes of gas. It is likewise very readily absorbed by charcoal. In its chemical deportment with acids and other substances, methylamine resembles in every respect ammonia and ethylamine. Methylamine appears to be produced in a great number of processes of destructive distillation; it has been formed by distilling several of the natural organic bases, such as codeine, morphine, caffeine, and several others, with caustic potassa; frequently a mixture of several bases is produced in this manner.

Among the numerous derivatives already obtained with this substance, *methylamine-urea*, $\text{C}_2(\text{H}_3\text{Me})\text{N}_2\text{O}_2$ and *bimethylamine-urea*, $\text{C}_2(\text{H}_2\text{Me})\text{N}_2\text{O}_2$, and even a *methyl-ethylamine-urea*, $\text{C}_2(\text{H}_2\text{MeAe})\text{N}_2\text{O}_2$ may be quoted. The latter substance has been produced by the action of cyanate of ethyl upon methylamine. Even a series of platinum-bases, analogous to those produced by the action of ammonia upon protochloride of platinum (see page 369), has been obtained with methylamine.

BIMETHYLAMINE has not yet been prepared in a pure state.

TRIMETHYLAMINE, *trimethyl-ammonia*, $\text{C}_6\text{H}_9\text{N} = \text{N}3(\text{C}_2\text{H}_3) = \text{NMe}_3$. This substance is readily obtained in a state of perfect purity, by submitting oxide of tetramethyl-ammonium (see the following compound) to the action of heat. It is gaseous at the common temperature, but liquefies at about $48^{\circ}\cdot2$ (9°C) to a mobile fluid of very powerfully alkaline reaction. Trimethylamine produces with acids very soluble salts. The platinum-salt $\text{N}(\text{HMe}_3)\text{Cl}\cdot\text{PtCl}_2$, is likewise very soluble and crystallizes in splendid orange-red octahedrons. According to Mr. Winkles large quantities of trimethylamine are found in the liquor in which salt herrings are preserved.

HYDRATED OXIDE OF TETRAMETHYL-AMMONIUM, $\text{C}_8\text{H}_{13}\text{NO}_2 = \text{N}4(\text{C}_2\text{H}_3)\cdot\text{O}\cdot\text{HO} = \text{NMe}_4\cdot\text{O}\cdot\text{HO}$.—The corresponding iodide may be obtained by adding iodide of methyl to the preceding compound. Both substances unite with a sort of explosion. The same iodide is prepared, however, with less difficulty, simply by digesting iodide of methyl with an alcoholic solution of ammonia. In this reaction, a mixture of the iodides of ammonium, methyl-ammonium, bimethyl-ammonium, trimethyl-ammonium, and tetramethyl-ammonium is produced. The first and last compound form in largest quantity, and may be separated by crystallization, the iodide of tetramethyl-ammonium being

rather difficultly soluble in water. From the iodide the base itself is separated by means of protoxide of silver. The properties are similar to those of the corresponding ethyl-compound. It differs, however, from oxide of tetrethyl-ammonium in its behaviour when heated (see page 564), yielding as it does trimethylamine, and pure methyl-alcohol, $\text{NMe}_4\text{O}, \text{HO} = \text{NMe}_3 + \text{MeO}, \text{HO}$.

BASES OF THE AMYL-SERIES.

The formation of these bodies being perfectly analogous to that of the corresponding terms in the ethyl-series, we refer to the more copious statement given in page 561, and confine ourselves to a brief description of their principal properties.

AMYLAMINE, *amyl-ammonia*, $\text{C}_{10}\text{H}_{13}\text{N} = \text{N}(\text{H}_2, \text{C}_{10}\text{H}_{11}) = \text{N}(\text{H}_2\text{Ayl})$, colourless liquid of a peculiar penetrating aromatic odour, slightly soluble in water, to which it imparts a strongly alkaline reaction. With the acids it forms crystalline salts, which have a fatty lustre. Amylamine boils at $199^{\circ}\cdot 4$ (93°C).

An *amylamine-urea* has been prepared.

BIAMYLAMINE, *biamyl-ammonia*, $\text{C}_{20}\text{H}_{23}\text{N} = \text{N}(\text{H}, 2\text{C}_{10}\text{H}_{11}) = \text{N}(\text{H Ayl}_2)$, aromatic liquid, less soluble in water, and less alkaline than amylamine. It boils at about 338° (170°C).

TRIAMYLAMINE, *triamyl-ammonia*, $\text{C}_{30}\text{H}_{33}\text{N} = \text{N}3(\text{C}_{10}\text{H}_{11}) = \text{N Ayl}_3$, colourless liquid of properties similar to those of the two preceding bases, but boiling at $494^{\circ}\cdot 6$ (257°C). The salts of triamylamine are very insoluble in water, and fuse, when heated, to colourless liquids, floating upon water.


HYDRATED OXIDE OF TETRAMYL-AMMONIUM, $\text{C}_{40}\text{H}_{45}\text{NO}_2 = \text{N}4\text{C}_{10}\text{H}_{11}, \text{O}, \text{HO} = \text{N Ayl}_4\text{O}, \text{HO}$.—This substance is far less soluble than the corresponding bases of the methyl- and ethyl-series. On adding potassa to the aqueous solution the compound separates as an oily layer. On evaporating the solution in an atmosphere free from carbonic acid, the alkali may be obtained in splendid crystals of considerable size. When submitted to distillation it splits into water, triamylamine, and amylene (see page 475), $\text{N AylO}, \text{HO} = 2\text{HO} + \text{N Ayl}_3 + \text{C}_{10}\text{H}_{10}$.

BASES OF THE PHENYL-SERIES.


ANILINE, *phenylamine*, $\text{C}_{12}\text{H}_7\text{N} = \text{N}(\text{H}_2, \text{C}_{12}\text{H}_5) = \text{N}(\text{H}_2\text{Py})$.—Under the head of salicylic acid a volatile crystalline substance has been noticed by the name of hydrated oxide of phenyl. This substance, of which a fuller description is given in Section IX., imitates to a certain extent the deportment of an alcohol, but several very characteristic transformations of the alcohols, and especially the conversion into the corresponding acid, have not as yet been realized. The organic base, however, which is derived from this alcohol in the same manner as methylamine, ethylamine, and

amylamine, from methyl-, ethyl-, and amyl-alcohol is known under the term *aniline*, a name given to it on account of its relation to the indigo-series. Aniline cannot be produced from phenyl-alcohol by the same processes which have furnished the bases of the other alcohols, neither bromide nor iodide of phenyl having as yet been obtained. However, on heating phenyl-alcohol with ammonia in sealed tubes, aniline is produced, $\text{PyIO}, \text{HO} + \text{NH}_3 = 2\text{HO} + \text{N}(\text{H}_2\text{PyI})$. This process, however, although interesting as establishing clearly the relation of aniline and phenyl-alcohol, is not calculated to yield large quantities of this substance. Aniline is invariably obtained either from indigo or from nitrobenzol.

Powdered indigo boiled with a highly-concentrated solution of hydrate of potassa dissolves with evolution of hydrogen gas to a brownish-red liquid containing a peculiar acid, the *chrysanic*, which becomes gradually converted into another acid, the *anthranilic* (see page 586). If this matter be transferred to a retort and still farther heated, it swells up and disengages aniline, which condenses in the form of oily drops in the neck of the retort and in the receiver. Separated from the ammoniacal water by which it is accompanied, and re-distilled, it is obtained nearly colourless. The formation of aniline from indigo is represented by the following equation :—



In order to prepare aniline from nitrobenzol (see page 487), this substance is submitted to a process discovered by Zinin, which has proved a very abundant source of artificial organic bases. An alcoholic solution of nitrobenzol is treated with ammonia and sulphuretted hydrogen, until after some hours a precipitate of sulphur takes place. The brown liquid is now saturated again with sulphuretted hydrogen, and the process repeated until sulphur is no longer separated. The reaction may be remarkably accelerated by occasionally heating or distilling the mixture. The liquid is then mixed with excess of acid, filtered, boiled to expel alcohol and unaltered nitrobenzol, and then distilled with excess of caustic potassa. The transformation of nitrobenzol into aniline is represented by the equation :—



If the aniline be required quite pure, it must be converted into oxalate, the salt several times crystallized from alcohol, and again decomposed by hydrate of potassa.

Aniline exists among the products of the distillation of coal, and probably of other organic matters; it is formed in the distillation of anthranilic acid (see page 586), and occasionally in other reactions.

When pure, aniline forms a thin, oily, colourless liquid, of faint vinous odour, and aromatic, burning taste. It is very volatile, but

has, nevertheless, a high boiling-point, $359^{\circ}\cdot6$ (182°C). In the air it gradually becomes yellow or brown, and acquires a resinous consistence. Its density is 1.028. Water dissolves aniline to a certain extent, and also forms with it a kind of hydrate; alcohol and ether are miscible with it in all proportions. It is destitute of alkaline reaction to test-paper, but is quite remarkable for the number and beauty of the crystallizable compounds it forms with acids. Two extraordinary reactions characterise this body and distinguish it from all others, viz., that with chromic acid, and that with solution of hypochlorite of lime. The former gives with aniline a deep-greenish or bluish-black precipitate, and the latter an extremely beautiful violet-coloured compound, the fine tint of which is, however, very soon destroyed.

Substitution-products of aniline.—Under the head of indigo, "a product of oxidation of this substance will be noticed, to which the name *isatin* has been given. When isatin is distilled with an exceedingly concentrated solution of caustic potassa, it is, like indigo, resolved into aniline, carbonic acid, and free hydrogen. In like manner, when *chlorisatin* or *bichlorisatin*, two chloro-substitutes of isatin, are similarly treated, they yield products analogous to aniline, but containing one or two equivalents of chlorine respectively in the place of hydrogen. The *chloraniline*, $\text{C}_{12}(\text{H}_6\text{Cl})\text{N}$, and *bichloraniline*, $\text{C}_{12}(\text{H}_5\text{Cl}_2)\text{N}$, thus produced, cannot, however, be obtained directly from aniline by the action of chlorine, thus differing from ordinary substitution-compounds; but aniline may be reproduced from them by the same reagent, which is capable of reconverting chloracetic acid into ordinary acetic acid, namely, an amalgam of potassium (see page 456). They are the first cases on record of organic bases containing chlorine.

Chloraniline forms large, colourless octahedra, having exactly the odour and taste of aniline, very volatile, and easily fusible; it distils without decomposition at a high temperature, and burns, when strongly heated, with a red smoky flame with greenish border. It is heavier than water, indifferent to vegetable colours, and, except in being solid at common temperatures, resembles aniline in the closest manner. It forms numerous and beautiful crystallizable salts. If aniline be treated with chlorine-gas, the action goes farther, *trichloraniline*, $\text{C}_{12}(\text{H}_4\text{Cl}_3)\text{N}$, being produced, a volatile crystalline body which has no longer any basic properties. The corresponding bromine-compounds have also been formed and described.

Nitraniline.—If nitrobenzol be heated with fuming nitric acid, or, still better, with a mixture of that acid and oil of vitriol, it is converted into a substance called *binitrobenzol*, containing $\text{C}_{12}\text{H}_4\text{N}_2\text{O}_8$, or nitrobenzol in which an additional equivalent of hydrogen is replaced by the elements of hyponitric acid. When this is dissolved in alcohol, and subjected to the reducing action of sulphide of ammonium in Zinin's process, it furnishes a new

substance of basic properties, *nitraniline*, having the constitution of a hyponitric acid substitution-product of ordinary aniline. The attempts to prepare it direct from aniline by means of nitric acid were unsuccessful, the principal product being usually carbazotic acid. Nitraniline forms yellow, acicular crystals, but little soluble in cold water, although easily dissolved by alcohol and ether. When warmed it exhales an aromatic odour, and melts. At a higher temperature it distils unchanged. By very gentle heat it may be sublimed without fusion. It is heavier than water, does not affect test-paper, and like chlor- and bromaniline fails to give with hypochlorite of lime the characteristic reaction of the normal compound. Nitraniline forms crystallizable salts, of which the hydrochlorate is the best known. This substance contains the elements of aniline with an equivalent of hydrogen replaced by hyponitric acid, or $C_{12}H_6N_2O_4 = C_{12}(H_6NO_4)N$.

Cyaniline is formed by the action of cyanogen upon aniline; it is a crystalline substance capable of combining with acids like aniline, but very prone to decomposition. Cyaniline contains $C_{14}H_7N_2 = C_{12}H_7NCy$. Hence it is formed by the direct union of 1 eq. of cyanogen and 1 eq. of aniline.

Melaniline.—The action of dry chloride of cyanogen upon anhydrous aniline gives rise to the formation of a resinous substance, which is the chlorine-compound of a very peculiar basic substance to which the name *melaniline* has been given. Dissolved in water and mixed with potassa, the above salt furnishes melaniline in the form of an oil, which rapidly solidifies to a beautiful crystalline mass. Melaniline contains $C_{26}H_{13}N_3$. The following equation represents its formation:—






Melaniline, when treated with chlorine, bromine, iodine, or nitric acid, yields basic substitution-products, in which invariably 2 eq. of hydrogen are replaced. It combines with 2 eq. of cyanogen.

The constitution of the substitution-products of aniline is readily intelligible: it is evident that these substances owe their origin to a double substitution, namely, first, of 1 equivalent of hydrogen in ammonia by phenyl; and, secondly, of one or several equivalents of hydrogen in phenyl by chlorine, bromine, &c. The arrangement of the elements may be conveniently illustrated by the following formulæ:—


Ammonia	NH_3
Aniline	$NH_2, C_{12}H_5$
Chloraniline	$NH_2, C_{12}(H_4Cl)$
Bromaniline	$NH_2, C_{12}(H_4Br)$
Bibromaniline	$NH_2, C_{12}(H_3Br_2)$
Tribromaniline	$NH_2, C_{12}(H_2Br_3)$
Nitraniline	$NH_2, C_{12}(H_4NO_4).$

The constitution of cyaniline and melaniline is more complicated.

Aniline-compounds corresponding to the amides and amidogen-acids, &c.—In describing the ammonia-salts of various acids, attention has been repeatedly called to the power possessed by many of them to yield several new groups of compounds by the loss of a certain amount of water (see pages 412 and 509). These groups are perhaps best elucidated by the derivatives of oxalic acid.




The terms corresponding to oxamide and oxamic acid have also been obtained in the aniline-series; they are produced by the distillation of neutral and acid oxalate of aniline, and have been called *oxanilide* and *oxanilic acid*.



Compounds analogous to the nitriles have not been obtained in the aniline-series, and the reason is intelligible if we glance at the formula of oxalate of aniline, $\text{N}(\text{H}_3\text{Pyl})\text{O}, \text{C}_2\text{O}_3$. It is obvious that 4 eq. of water cannot be eliminated from this salt without touching the hydrogen of the phenyl, i. e., without destroying the compound altogether. A great many anilides and anilic acids have been formed.

Aniline-urea.—On passing the vapour of cyanic acid into aniline, the substance becomes hot, and solidifies on cooling to a crystalline mass, containing $\text{C}_{14}\text{H}_8\text{N}_2\text{O}_2 = \text{C}_2(\text{H}_3\text{Pyl})\text{N}_2\text{O}_2$. This is the composition of aniline-urea. This substance, however, does not combine with acids like the ureas (see pages 537 and 563), it is only isomeric with the true aniline-urea, which is obtained by another process. Among the derivatives of benzoic acid, *nitrobenzoic acid*, $\text{C}_{14}(\text{H}_4\text{NO}_4)\text{O}_3, \text{HO}$, has been mentioned. The ether of this acid, $\text{C}_4\text{H}_5\text{O}, \text{C}_{14}(\text{H}_4\text{NO}_4)\text{O}_3$, like oxalic ether, and many other ethers, furnishes an amide when treated with ammonia. This substance, *nitrobenzamide*, $\text{C}_{14}(\text{H}_4\text{NO}_4)\text{O}_2, \text{NH}_2$, under the influence of sulphide of ammonium suffers a change, which is perfectly analogous to that of nitrobenzol under similar conditions (see page 567). The mixture soon

deposits sulphur, and yields on evaporation crystals of aniline-urea.



This substance, which was discovered by M. Chancel, combines with nitric and hydrochloric acid, and even with bichloride of platinum.

Bases homologous to Aniline.

In a former section of this Manual (page 494), a series of hydrocarbons have been mentioned, which are homologous to benzol. Each of these substances, when treated with fuming nitric acid, yields a nitro-substitute corresponding to nitrobenzol, which, under the influence of sulphuretted hydrogen, is converted into a basic compound homologous to aniline. We thus obtain the following group :—

Benzol, C_{12}H_6 Nitrobenzol, $\text{C}_{12}\text{H}_5\text{NO}_2$ Aniline, $\text{N}(\text{H}_2, \text{C}_{12}\text{H}_5)$
 Toluol, C_{14}H_8 Nitrotoluol, $\text{C}_{14}\text{H}_7\text{NO}_2$ Toluidine, $\text{N}(\text{H}_2, \text{C}_{14}\text{H}_7)$
 Xylol, $\text{C}_{16}\text{H}_{10}$ Nitroxylol, $\text{C}_{16}\text{H}_9\text{NO}_2$ Xylidine, $\text{N}(\text{H}_2, \text{C}_{16}\text{H}_9)$
 Cumol, $\text{C}_{18}\text{H}_{14}$ Nitrocumol, $\text{C}_{18}\text{H}_{13}\text{NO}_2$ Cumidine, $\text{N}(\text{H}_2, \text{C}_{18}\text{H}_{13})$.

TOLUIDINE, $\text{C}_{14}\text{H}_9\text{N} = \text{N}(\text{H}_2, \text{C}_{14}\text{H}_7) = \text{N}(\text{H}_2\text{Tyl})$.—This is prepared exactly like aniline.

Toluidine forms colourless platy crystals, very sparingly soluble in water, but easily in alcohol, ether, and oils; it is heavier than water, has an aromatic taste and odour, and a very feebly alkaline reaction. At 104° (40°C) it melts, and at 388° (198°C), boils and distils unchanged; it forms a series of beautiful crystallizable salts.

XYLIDINE, $\text{C}_{16}\text{H}_{11}\text{N} = \text{N}(\text{H}_2, \text{C}_{16}\text{H}_9) = \text{N}(\text{H}_2\text{Xyl})$. Of this compound little more than its existence is known.

CUMIDINE, $\text{C}_{18}\text{H}_{13}\text{N} = \text{N}(\text{H}_2, \text{C}_{18}\text{H}_{11}) = \text{N}(\text{H}_2\text{Cyl})$.—This substance is an oil which boils at 437° (225°C). It forms magnificent salts with the acids.

The following two bases are likewise closely allied to the group of aniline-bases, both by their mode of formation and by their constitution.

NAPHTHALIDINE, $\text{C}_{20}\text{H}_9\text{N} = \text{N}(\text{H}_2, \text{C}_{20}\text{H}_7) = \text{N}(\text{H}_2\text{Nyl})$.—This substance is interesting, as being one of the first of its kind produced by Zinin's process.

It is obtained by the action of sulphide of ammonium upon an alcoholic solution of *nitronaphthalase*, one of the numerous products of the action of nitric acid upon the hydrocarbon *naphthalin*, which will be noticed in the last section of the Manual. When pure it forms colourless silky needles, fusible, and volatile without decomposition. It has a powerful, not disagreeable odour and burning taste,

is nearly insoluble in water; but readily dissolves in alcohol and ether; the solution has no alkaline reaction. Naphthalidine forms numerous crystallizable salts.

CHLORONICINE, $C_{10}(H_6Cl)N=NH_2, C_{10}(H_4Cl)$.—A substance of the above composition has been lately discovered by Saint Evre, and deserves special notice, because it may be viewed as a chloro-substitute of the natural alkaloid nicotine (see page 555), which contains $C_{10}H_7N$. It is obtained by the following rather complicated series of reactions. A stream of chlorine is passed through a solution of benzoate of potassa to which some free alkali has been added, when a deposit forms consisting of chlorate of potassa and the potassa-salt of a new chlorinetted acid $C_{12}(H_5Cl)O_3.HO$. This acid, which is derived from benzoic acid by the removal of 2 eq. of carbon in the form of carbonic acid, and by the introduction of 1 eq. of chlorine in the place of 1 eq. of hydrogen, has received the name of *chloroniceic acid*. It forms canliflower-like crystals, fusible at 302° ($150^\circ C$), and boiling at 419° ($215^\circ C$). It is volatile without decomposition; when submitted to distillation with lime it yields a chlorinetted hydrocarbon chloronicene, $C_{10}(H_5Cl)$, which is converted into *nitrochloronicene*, $C_{10}(H_4ClNO_4)$ by the action of fuming nitric acid. This, lastly, when treated with sulphide of ammonium, furnishes *chloronidine*. It forms brown flakes, which dissolve in a great deal of water; the solution however has no alkaline reaction. It forms crystallizable salts with hydrochloric and acetic acids, and a fine platinum-salt. The perfect analogy in the derivatives from chloroniceic acid to that of aniline from benzoic acid, is obvious from the following table:—

Benzoic acid	$C_{14}H_6O_4$	Chloroniceic acid	$C_{12}(H_5Cl)O_4$
Benzol	$C_{12}H_6$	Chloronicene	$C_{10}(H_5Cl)$
Nitrobenzol	$C_{12}(H_5NO_4)$	Nitrochloronicene	$C_{10}(H_4ClNO_4)$
Aniline	$C_{12}H_5, H_2N$	Chloronidine	$C_{10}(H_4Cl)H_2N$

Up to the present moment chloronidine has not yet been converted into nicotine, nor has nicotine been transformed into chloronidine.

MIXED BASES.

In one of the preceding paragraphs it has been mentioned that the several hydrogen-equivalents in ammonium may be replaced by *different* hydro-carbon radicals. In fact, on treating aniline or toluidine with bromide, or iodide of ethyl, as described under the head of ethylamine, the following series of compounds are obtained:—

Aniline	$N(H_2Pyl)$	Toluidine	$N(H_2Tyl)$
Ethylaniline	$N(HPylAc)$	Ethyltoluidine	$N(HTylAc)$
Biethylaniline	$N(PylAc_2)$	Biethyltoluidine	$N(TylAc_2)$
Ammonium-base	$N(PylAc_3)O, HO$	Ammonium-base*	$N(TylAc_3)O, HO$

* Unpublished researches of Messrs. R. Morley and John Abel.

ETHYLANILINE (ethylophenylamine) and BETHYLAmine (diethylophenylamine) are liquids greatly resembling aniline. They boil respectively at 335°C (294°C) and $416^{\circ}\cdot5$ ($243^{\circ}\cdot5^{\circ}\text{C}$). The ammonium-base, to which the name *diethylophenyl-ammonium* may be given, is soluble in water, with a powerful alkaline reaction, corresponding in its general properties to oxide of tetraethyl-ammonium (see page 563). The series of bases which may be possibly obtained by changing the radicals is almost without limits; even now a considerable variety has been produced, of which however only a few will be mentioned here, as remarkable for the diversity of the materials with which they are constructed.

HYDRATED OXIDE OF TRIETHYL-AMYL-AMMONIUM, $\text{C}_{22}\text{H}_{27}\text{NO}_2 = \text{N}(\text{C}_2\text{H}_5\text{C}_4\text{H}_9\text{C}_6\text{H}_{11})\text{O}_2\cdot\text{HO} = \text{N}(\text{Ac}_3\text{Ayl})\text{O}_2\cdot\text{HO}$. Triethylamine (see page 563), when boiled with iodide of amyl, is slowly converted into a crystalline mass of iodide of *Triethylamyl-ammonium*. The base liberated with protoxide of silver and submitted to distillation yields olefiant gas, and

TRIETHYLAMYLAMINE, $\text{C}_{18}\text{H}_{21}\text{N} = \text{N}(\text{C}_2\text{H}_5\text{C}_4\text{H}_9\text{C}_6\text{H}_{11}) = \text{N}(\text{Ac}_3\text{Ayl})$ a liquid boiling at 309°C (154°C). This compound is most powerfully attacked by iodide of methyl. Both substances immediately solidify to a beautifully crystalline iodide, from which protoxide of silver separates,

HYDRATED OXIDE OF METHYL-TRIETHYL-AMYL-AMMONIUM, $\text{C}_{26}\text{H}_{30}\text{NO}_2 = \text{N}(\text{C}_2\text{H}_5\text{C}_4\text{H}_9\text{C}_6\text{H}_{11})\text{O}_2\cdot\text{HO} = \text{N}(\text{MeAc}_2\text{Ayl})\text{O}_2\cdot\text{HO}$. This substance, which is a powerfully alkaline base, soluble in water, when distilled undergoes the same decomposition as the other members of the fourth group of bases, yielding olefiant gas, and

METHYL-ETHYL-AMYL-AMINE, or ammonia, in which 1 eq. of hydrogen is replaced by methyl, another by ethyl, and a third by amyl, $\text{C}_{14}\text{H}_{14}\text{N} = \text{N}(\text{C}_2\text{H}_5\text{C}_4\text{H}_9\text{C}_6\text{H}_{11}) = \text{N}(\text{MeAc}_2\text{Ayl})$. This is a basic oil of a peculiar aromatic odour, boiling at 275° (135°C), and forming crystallizable salts with the acids.

ETHYL-AMYL-ANILINE, $\text{C}_{26}\text{H}_{21}\text{N} = \text{N}(\text{C}_{12}\text{H}_5\text{C}_4\text{H}_9\text{C}_6\text{H}_{11}) = \text{N}(\text{PylAcAyl})$. Ethylaniline (see page 572) treated with iodide of amyl yields the iodide of the above base, which is separated by distillation with potassa. It is an aromatic oil, boiling at $503^{\circ}\cdot5$ (262°C). The action of iodide of methyl upon this substance gives rise to a new iodide, from which protoxide of silver separates,

HYDRATED OXIDE OF METHYL-ETHYL-AMYL-PHENYL-AMMONIUM, $\text{C}_{26}\text{H}_{26}\text{NO}_2 = \text{N}(\text{C}_2\text{H}_5\text{C}_4\text{H}_9\text{C}_{10}\text{H}_{11}\text{C}_{12}\text{H}_5)\text{O}_2\cdot\text{HO} = \text{N}(\text{MeAc}_2\text{AylPyl})\text{O}_2\cdot\text{HO}$. This compound is very soluble in water, is powerfully alkaline, and of an extremely bitter taste. The composition, established by the examination of a platinum-salt, is certainly remarkable, for this compound contains the radicals of not less than four different alcohols.

BASES OF UNCERTAIN CONSTITUTION.

In addition to the artificial bases which have just been described, several others have been formed by processes less simple and less calculated to afford a clear insight into their constitution. The destructive distillation of nitrogenous substances has furnished a rich harvest of similar substances. A few of the most interesting may be briefly mentioned.

CHINOLEINE (LEUCOLINE) $C_{18}H_8N$.—Quinine, eichonine, strychnine, and probably other bodies of this class, when distilled with a very concentrated solution of potassa, yield an oily product resembling aniline in many respects, and possessing strong basic powers; it is, however, less volatile than that substance, and boils at 460° ($235^\circ C$). When pure it is colourless and has a faint odour of bitter almonds. Its density is 1.081. It is slightly soluble in water, and miscible in all proportions with alcohol, ether, and essential oils. Chinoleine has no alkaline reaction, but forms salts with acids, which, generally speaking, do not crystallize very freely.

Bases from Coal-tar Oil.

KYANOL and LEUKOL.—The volatile basic bodies described under these names have been identified, the first with aniline and the second with chinoleine. They are separated from the coal-oil by agitating large quantities of that liquid with hydrochloric or diluted sulphuric acid, and then distilling the acid liquid with excess of potassa or lime. They are readily separated by distillation.

PICOLINE, $C_{12}H_7N$.—Dr. Anderson has described under the foregoing name a third volatile, oily base, present in certain varieties of coal-tar-naphtha, being there associated with aniline, chinoleine, and several other volatile substances but imperfectly understood. It is separated without difficulty from the two bases mentioned by distillation, in virtue of its superior volatility. Picoline, when pure, is a colourless, transparent, limpid liquid, of powerful and persistent odour, and aetid, bitter taste. It is unaffected by a cold of 0° ($-17^\circ 7 C$). It is extremely volatile, evaporates rapidly in the air, and does not become brown like aniline when kept in an ill-stopped bottle. Picoline has a sp. gr. of 0.955, and boils at 272° ($133^\circ 3 C$). It mixes in all proportions with pure water, but is insoluble in caustic potassa and most saline solutions. The alkalinity of this substance is exceedingly well marked; it restores the blue colour of reddened litmus, and forms a series of crystallizable salts. This substance, as seen from the above formula, is isomeric with aniline, but numerous characteristic reactions completely distinguish it from this body.

Bases from Animal Oil.

The oily liquid obtained by the distillation of bones and animal matter generally, frequently designated by the term Dippel's oil, contains several volatile organic bases. Together with some of the substances already described, such as methylamine, ethylamine, picoline, and aniline, Dr. Anderson has found in it a peculiar base.

PETININE, $C_8H_{11}N$.—The properties of this substance are very analogous to those of biethylamine and triethylamine. It has the same composition as biethylamine, but differs from it by its higher boiling-point, which is 175° ($79^\circ\cdot5C$), that of biethylamine being 133° ($55^\circ C$) (see page 563). Some chemists are inclined to explain this difference by assuming that petinine is an ammonia-base, containing the radical *butyl*, which was mentioned under the head of valeric acid (see page 477); in one word, that it is *butylamine* $N(H_2, C_4H_9)$, homologous to ethylamine. This assumption may be correct, but is not as yet supported by any experimental evidence. The true butylamine has lately been obtained by M. Wurtz from butyl-alcohol (page 479), in the same manner as ethylamine is obtained from common alcohol (page 562).

Bases obtained by the action of Ammonia upon Volatile Oils.

FURFURINE.—When sulphuric acid diluted with an equal bulk of water is carefully mixed with twice its weight of wheat-bran, and the adhesive pasty mass obtained exposed in a proper vessel to the action of a current of steam, which is afterwards condensed by a worm or refrigerator, a liquid is obtained which holds in solution a peculiar volatile oil, to which the term *furfurole* has been given. By re-distillation several times repeated, the first half of the liquid only being collected, the furfurole can be extracted from the water, and then by distillation alone obtained in a state of purity. It has a pale yellow colour, and a fragrant odour like that of oil of cassia; its specific gravity is 1.165, and it boils at 325° ($162^\circ\cdot8C$), distilling unchanged. It dissolves in all proportions in alcohol and to a very considerable extent in water, and is readily destroyed by strong acids and caustic alkalis, especially when aided by heat. Furfurole contains $C_5H_2O_2$. The specific gravity of its vapour is 3.493.

The product of furfurole is very greatly increased, and the operation much facilitated, by previously depriving the bran of all starch, gluten, and soluble matter, by steeping it in a cold dilute solution of caustic potassa, and washing and drying by gentle heat or in the sun. Maceration in cold water for some time answers the same purpose, owing to the lactic acid formed in that case.

In contact with solution of ammonia, furfurole becomes converted in the space of a few hours into a yellowish-white, crystalline, insoluble substance, *furfurolamide*, $C_{15}H_6NO_3$: this body is slowly decom-

posed in contact with water, and instantly by an acid into ammonia and furfurole. It may be crystallized from alcohol, however, in which it dissolves without much change. When boiled with a somewhat dilute solution of caustic potassa, no ammonia is disengaged, but the substance is slowly dissolved if the quantity of liquid be considerable, and the solution deposits on cooling small, white, silky needles of a substance having the same composition as furfurolamide itself. There is no other product. This new body, to which the name *furfurine* has been given, is a powerful organic base, forming with acids a series of beautiful crystallizable salts, and decomposing at a boiling heat the saline compounds of ammonia. Furfurine is very sparingly soluble in cold water, but dissolves in about 135 parts at 212° (100°C). Alcohol and ether dissolve it freely; the solutions have a strongly alkaline reaction. It melts below the boiling-point of water, and when strongly heated inflames and bursts with a red and smoky light, leaving but little charcoal. Its salts are intensely bitter. Furfurine contains in 1 equivalent $\text{C}_{30}\text{H}_{12}\text{N}_2\text{O}_6$.*

FUCUSINE.—By treating several varieties of fucus with sulphuric acid in exactly the same manner as in the preparation of furfurole, Dr. Stenhouse obtained a series of substances, which he designates by the terms *fucusol*, *fucusamide*, and *fucusine*. They have exactly the same composition as the corresponding terms in the furfurol-series, and also most of their properties, but differ in some details.

AMARINE (BENZOLINE).—The hydrobenzamide of M. Laurent, $\text{C}_{42}\text{H}_{18}\text{N}_2$, produced by the action of ammonia on pure bitter-almond oil (see page 490), when long boiled with a solution of caustic potassa, suffers the same kind of change as furfurolamide, becoming entirely converted into a new body isomeric with hydrobenzamide, having the characters of a salt base, and to which the preceding name has been given. Precipitated by ammonia from a cold solution of the hydrochlorate or sulphate, *amarine* separates in white curdy masses, which when washed and dried become greatly reduced in volume. In this state it is singularly electric by friction with a spatula. It is insoluble in water, but dissolves abundantly in alcohol; the solution is highly alkaline to test-paper, and if sufficiently concentrated deposits the amarine on standing in the form of small, colourless, prismatic crystals. Below 212° (100°C) it melts, and on cooling assumes a glassy or resinous condition. Strongly heated in a retort it decomposes with production of ammonia, and a volatile oil not yet examined, and a new body, *pyrobenzolin*, which appears to be a neutral substance, insoluble in water, soluble in boiling alcohol, and containing a large quantity of nitrogen. It is fusible by moderate heat, and on cooling becomes a mass of colourless radiating needles or plates. The salts of amarine are mostly sparingly soluble; the sulphate, nitrate,

* This remarkable substance, the nearest approach to the native alkaloids yet made, was discovered by the author of this Manual.—Eds.

and hydrochlorate are crystallizable and very definite. Amarine contains $C_{42}H_{18}N_2$.

THIOSINNAMINE.—The volatile oil distilled from black mustard-seed, $C_8H_5NS_2$, which will be noticed farther on, in contact with solution of ammonia, yields a compound having the characters of an organic base, and forming colourless, prismatic crystals, bitter in taste and soluble in water. The solution does not affect test-paper. It melts when heated, but cannot be sublimed. Acids combine with it, but form no crystallizable salts: the double salts of the hydrochlorate with bichloride of platinum and corrosive sublimate are the most definite. This substance contains sulphur; its formula is $C_8H_8N_2S_2$. It is the only product of the action of ammonia on the oil.

Thiosinamine is decomposed by metallic oxides, as protoxide of lead, with production of a metallic sulphide and a new body of basic properties, free from sulphur, called *sinnamine*. This latter substance crystallizes very slowly from a concentrated aqueous solution in brilliant, colourless crystals which contain water. It has a powerfully bitter taste, is strongly alkaline to test-paper, and decomposes ammoniacal salts by boiling. With the exception of the oxalate, it forms no crystallizable salts. Sinnamine contains in the crystallized state $C_8H_6N_2, HO$.

When mustard-oil is treated with protoxide of lead or baryta, the whole of the sulphur is withdrawn, and carbonic acid and another basic substance produced, which, when pure, crystallizes in colourless plates, soluble in water and in alcohol; the solution has a distinctly alkaline reaction. *Sinapoline*, the body so formed, contains $C_{14}H_{12}N_2O_2$.


Bases from Aldehyde.

THIALDINE.—The crystalline compound of aldehyde with ammonia (see page 448) is dissolved in 12 to 16 parts of water, mixed with a few drops of caustic ammonia, and then the whole subjected to a feeble stream of sulphuretted hydrogen. After a time the liquid becomes turbid, and deposits a white crystalline substance, which is the body in question. It is separated, washed, dissolved in ether, and the solution mixed with alcohol and left to evaporate spontaneously, by which means the base is obtained in large, regular, rhombic crystals, having the figure of those of common gypsum. The crystals are heavier than water, transparent and colourless. They refract light strongly. The substance has a somewhat aromatic odour, melts at 110° ($43^\circ.3C$), and volatilizes slowly at common temperatures. It distils unchanged with the vapour of water, but decomposes when heated alone. It is very sparingly soluble in water, easily in alcohol and ether. It has no action on vegetable colours, but dissolves freely in acids, forming crystallizable salts.


Heated with hydrate of lime it yields chinoline. Thialdine contains $C_{12}H_{13}NS_4$.

A very similar compound containing selenium exists.

ALANINE.—This substance is likewise obtained from aldehyde. It has been only recently discovered by Strecker, who obtained it in a reaction, which promises many interesting results. If an aqueous solution of the ammonia-compound of aldehyde be treated with hydrocyanic and hydrochloric acid, chloride of ammonium is formed, together with hydrochlorate of *alanine*. On adding to this solution a mixture of alcohol and ether, the greater portion of the chloride of ammonium is precipitated; the filtrate is then treated with protoxide of lead to remove a small quantity of ammonium and hydrochloric acid, and separated from the lead by sulphuretted hydrogen. The liquid thus obtained deposits feathery crystals of alanine. The composition of alanine is $C_6H_7NO_4$, and its formation represented by the equation:—



Alanine crystallizes in rhombic prisms of the lustre of mother-of-pearl. They are pretty soluble in cold, but more so in boiling water; they dissolve but little in alcohol, and not at all in ether; the solution has a sweetish taste, but no effect upon vegetable colours. Alanine is a weak base: as yet only a crystalline nitrate has been obtained, but several combinations with metallic oxides have been produced. This substance has the same composition as lactamide (see page 422), urethane (see page 431), and sarcosine, which will be described in the section on the Components of the Animal Body. But it is only isomeric with these substances from which it differs in its physical and chemical properties. The most interesting feature in the history of alanine is its behaviour with nitrous acid. Under the influence of this reagent it is converted into lactic acid, identical in every respect with that obtained in the fermentation of sugar (see page 420). This reaction is represented by the following equation:—



APPENDIX TO THE ORGANIC BASES.

All the numerous members of this extensive group which have been considered in the preceding section, invariably contain nitrogen. Recent researches, however, have shown that two series of analogous substances exist which contain phosphorus and antimony,

in the place of nitrogen. These remarkable compounds, which are not yet sufficiently known, will be briefly noticed in the subsequent paragraphs.

Phosphorus-bases.

If a current of chloride of methyl (see page 465) be passed over a layer of phosphide of calcium (see page 281), heated to about 356° (180°C), a mixture of several phosphoretted bodies is produced, which are partly liquid and partly solid. M. Paul Thénard, who has investigated this subject, has separated from this mixture three compounds, containing carbon, hydrogen, and phosphorus, which he believes to correspond to the three hydrides of phosphorus (see page 186).

Phosphoretted
hydrogens.



Phosphoretted
methyl-bodies

As far as can be seen from the results obtained by M. Thénard, which have not yet been published in detail, the two last substances are powerful bases analogous to the bases of the nitrogen-series. These substances are very readily decomposed, one of them is even spontaneously inflammable, so that their preparation and study have been attended with great difficulty and even danger—circumstances which sufficiently account for the insufficiency of the description. It is evident that the last body is the phosphoretted analogue of trimethylamine, triethylamine, and triamylamine, and the question arises whether the second may not be viewed as the phosphoretted dimethylamine, and whether farther researches will not establish the existence of the whole series of the phosphoretted bases corresponding to the compound ammonias previously described.

Antimony-bases.

Among the derivatives of alcohol, a compound of antimony with 3 eq. of ethyl has been briefly noticed (see page 447) under the name of *stibethyl*. The composition of this remarkable compound approximates it to triethylamine.



A closer examination has shown that this substance differs in many points from triethylamine; but that, in one very essential character, the two substances agree in the most perfect manner,

The properties of stibethyl are the following: it is a transparent,

very mobile liquid, of a penetrating odour of onions. It boils at 317° (158°C). In contact with atmospheric air, it emits a dense white fume, and frequently even takes fire, burning with a white brilliant flame. It combines directly with 2 eq. of oxygen, sulphur, chlorine, and iodine.



Binoxide of stibethyl, SbAe_3O_2 , forms a viscid transparent mass soluble in water and alcohol. It is extremely bitter and not poisonous. This substance cannot be volatilized without decomposition. Binoxide of stibethyl combines with acids, giving rise to the formation of crystallizable salts containing 2 eq. of acid.

Bisulphide of stibethyl, SbAe_3S_2 .—Beautiful crystals of silvery lustre, soluble in water and alcohol. Their taste is bitter, and their odour similar to that of mercaptan. The solution of this compound exhibits the deportment of an alkaline sulphide; it precipitates the solution of the metals as sulphides, a soluble salt of stibethyl being formed at the same time. This deportment, indeed, affords the simplest means of preparing the salts of stibethyl.

Bichloride of stibethyl, SbAe_3Cl_2 .—Colourless liquid of the odour of oil of turpentine.

Biniiodide of stibethyl, SbAe_3I_2 .—Colourless needles of intensely bitter taste.

The analogy of stibethyl with triethylamine is best exhibited in its deportment with iodide of ethyl. The two substances combine to a new iodide, containing SbAe_4I , from which a powerful alkaline base may be separated by the action of protoxide of silver. This substance, which must evidently be analogous to oxide of tetrethyl-ammonium,



has not yet been minutely examined.

A series of analogous substances exist in the methyl-series. They have been examined by M. Landolt, who has described several of its compounds, and separated the methyl-antimony-base corresponding to oxide of tetrethyl-ammonium.

The *iodide*, SbMe_4I , produced by the action of iodide of methyl upon stibmethyl, crystallizes in white six-sided tables, which are easily soluble in water and alcohol, and slightly soluble in ether. It has a very bitter taste, and is decomposed by the action of heat. When treated with protoxide of silver, it yields a powerfully alkaline solution, exhibiting all the properties of potassa, from which, on evaporation, a white crystalline mass, the hydrate of the base, $\text{SbMe}_4\text{O}, \text{HO}$, crystallizes. This compound forms an acid salt with sulphuric acid, which crystallizes in tables. It contains $\text{SbMe}_4\text{O}, \text{SO}_3 + \text{HO}, \text{SO}_3$.

SECTION VI.

ORGANIC COLOURING PRINCIPLES.

THE organic colouring principles are substances of very considerable practical importance in relation to the arts: several of them, too, have been made the subjects of extensive and successful chemical investigation. With the exception of one red dye, cochineal, they are all of vegetable origin.

The art of dyeing is founded upon an affinity or attraction existing between the colouring matter of the dye and the fibre of the fabric. In woollen and silk this affinity is usually very considerable, and to such tissues a permanent stain is very easily communicated, but with cotton and flax it is much weaker. Recourse is then had to a third substance, which does possess in a high degree such affinity, and with this the cloth is impregnated. Alumina, sesquioxide of iron, and oxide of tin are bodies of this class.

When an infusion of some dye-wood, as logwood, for example, is mixed with alum and a little alkali, a precipitate falls, consisting of alumina in combination with colouring matter, called a *lake*; it is by the formation of this insoluble substance within the fibre that a permanent dyeing of the cloth is effected. Such applications are termed *mordants*. Sesquioxide of iron usually gives rise to dull, heavy colours; alumina and oxide of tin, especially the latter, to brilliant ones. It is easy to see that, by applying the mordant *partially* to the cloth, by a wood-block or otherwise, a pattern may be produced, as the colour will be removed by washing from the other portions.

INDIGO.

Indigo is the most important member of the group of blue colouring matters. It is the product of several species of the genus *indigofera*, which grow principally in warm climates. When the leaves of these plants are placed in a vessel of water and allowed to ferment, a yellow substance is dissolved out, which by contact of air becomes deep blue and insoluble, and finally precipitates. This, washed and carefully dried, constitutes the indigo of commerce. It is not contained ready-formed in the plant, but is produced by the oxidation of some substance there present. Neither is the fermentation essential, as a mere

infusion of the plant in hot water deposits indigo by standing in the air.

Indigo comes into the market in the form of cubic cakes, which, rubbed with a hard body, exhibit a copper-red appearance; its powder has an intensely deep-blue tint. The best is so light as to swim upon water. In addition to the blue colouring matter, or true indigo, it contains at least half its weight of various impurities, among which may be noticed a red resinous matter, the *indigo-red* of Berzelius; these may be extracted by boiling the powdered indigo in dilute acid, alkali, and afterwards in alcohol.

Pure indigo is quite insoluble in water, alcohol, oils, dilute acids, and alkalis; it dissolves in about 15 parts of concentrated sulphuric acid, forming a deep-blue pasty mass, entirely soluble in water, and often used in dyeing: this is *sulphindyllic* or *sulphindigotic acid*, a compound analogous to sulphovinic acid, capable of forming with alkaline bases blue salts, which, although easily soluble in pure water, are insoluble in saline solutions. If an insufficient quantity of sulphuric acid has been employed, or digestion not long enough continued, a purple powder is left on diluting the acid mass, soluble in a large quantity of pure water. The Nordhausen acid answers far better for dissolving indigo than ordinary oil of vitriol. Indigo may, by cautious management, be volatilized; it forms a fine purple vapour, which condenses in brilliant copper-coloured needles. The best method of subliming this substance is, according to Mr. Taylor, to mix it with plaster of Paris, make the whole into a paste with water, and spread it upon an iron plate. 1 part indigo, and 2 parts plaster, answer very well. This, when quite dry, is heated by a spirit-lamp; the volatilization of the indigo is aided by the vapour of water disengaged from the gypsum, and the surface of the mass becomes covered with beautiful crystals of pure indigo, which may be easily removed by a thin spatula. At a higher temperature, charring and decomposition take place.

In contact with deoxidizing agents, and with an alkali, indigo suffers a very curious change; it becomes soluble and nearly colourless, perhaps returning to the same state in which it existed in the plant. It is on this principle that the dyer prepares his *indigo-vat*:—5 parts of powdered indigo, 10 parts of green vitriol, 15 parts of hydrate of lime, and 60 parts of water, are agitated together in a close vessel, and then left to stand. The hydrated protoxide of iron, in conjunction with the excess of lime, reduces the indigo to the soluble state; a yellowish liquid is produced, from which acids precipitate the *white* or *deoxidized* indigo as a flocculent insoluble substance, which absorbs oxygen with the greatest avidity, and becomes blue. Cloth, steeped in the alkaline liquid, and then exposed to the air, acquires a deep and most permanent blue tint by the deposition of solid insoluble indigo in the substance of the fibre. Instead of the iron salt and lime, a mixture of dilute caustic soda and grape-

sugar dissolved in alcohol may be used; the sugar becomes oxidized to formic acid, and the indigo reduced. On allowing a solution of this description to remain in contact with the air, it absorbs oxygen and deposits the indigo in the crystalline condition.

The following formulæ represent the composition of the bodies described:—

Blue insoluble indigo . . .	$C_{16}H_5N O_2$
White, or reduced indigo* . .	$C_{16}H_6N O_2$
Sulphindyllic acid . . .	$C_{16}H_4N O, 2SO_3, HO.$

Products of the Decomposition of Indigo.

The products of the destructive modification of indigo by powerful chemical agents of an oxidizing nature are both numerous and interesting, inasmuch as they connect this substance in a very curious manner with several other groups of organic bodies, especially with those of the salicyl- and phenyl-series. Many of them are exceedingly beautiful, and possess very remarkable properties.

ISATIN.—One part of indigo reduced to fine powder, and rubbed to a paste with water, is gently heated with a mixture of one part of sulphuric acid and one part of bichromate of potassa dissolved in 20 or 30 parts of water. The indigo dissolves with very slight disengagement of carbonic acid towards the end, forming a yellow-brown solution, which, on standing, deposits impure *isatin* in crystals. These are collected, slightly washed and re-dissolved in boiling water: the filtered solution deposits on cooling the isatin in a state of purity. Or, powdered indigo may be mixed with water to a thin paste, heated to the boiling-point in a large capsule, and nitric acid added by small portions until the colour disappears; the whole is then largely diluted with boiling water, and filtered. The impure isatin which separates on cooling is washed with water containing a little ammonia, and re-crystallized. Both these processes require careful management, or the oxidizing action proceeds too far, and the product is destroyed.

Isatin forms deep yellowish-red prismatic crystals of great beauty and lustre; it is sparingly soluble in cold water, freely in boiling water, and also in alcohol. The solution colours the skin yellow, and causes it to emit a very disagreeable odour. It cannot be

* Properly *hydrogenized* indigo, if the above be the correct view; white indigo may, however, be viewed as a *hydrate*, and blue indigo as an oxide, of one and the same substance.

White indigo	$C_{16}H_5N O + HO$
Blue indigo	$C_{16}H_5N O + O.$

sublimed. Isatin contains the elements of indigo *plus* 2 eq. of oxygen, or $C_{16}H_5NO_4$.

A solution of potassa dissolves isatin with purple colour: from this solution acids precipitate the isatin unchanged. When boiled, however, the colour is destroyed, and the liquid furnishes on evaporation crystals of the potassa-salt of a new acid, the *isatic*, containing $C_{16}H_6NO_5, HO$. In the free state this is a white and imperfectly crystalline powder, soluble in water, and easily decomposed into isatin and water.

By chlorine isatin is converted into the substitution-product *chlor-isatin*, $C_{16}(H_4Cl)NO_4$, a body closely resembling isatin itself in properties. If an alcoholic solution and excess of chlorine be employed, other products make their appearance, as *chloranile*, $C_{12}Cl_4O_4$, *trichlorophenol*, $C_{12}(H_3Cl_3)O_2$, and a resinous substance. The former of these substances, the position of which in the kinone-series has been already noticed (page 554), yields other products with potassa and ammonia. *Bromisatin* is easily formed. The change which isatin, and its chlorinetted and brominetted congeners, undergo when submitted to the action of fusing hydrate of potassa has been already considered in the section on the Artificial Organic Bases (see page 568).

Exposed to the action of sulphuretted hydrogen and sulphide of ammonium, isatin furnishes several new compounds, as *isathyde*, *sulfesathyde*, *sulfasathyde*.

A hot solution of isatin, when treated with sulphide of ammonium, gives rise to a deposit of sulphur, a white crystallized substance being produced at the same time; it has received the name of *isathyde*, and contains $C_{16}H_6NO_4$. It is obvious that it bears to isatin the same relation as white to blue indigo. If the sulphide of ammonium be replaced by sulphuretted hydrogen, *bisulphisathyde*, $C_{16}H_8NO_2S_2$, is produced, which is the former, 2 eq. of oxygen, being replaced by 2 eq. of sulphur. An alcoholic solution of potassa converts this into *sulphisathyde*, $C_{16}H_6NO_3S$, in which only one quarter of the oxygen in isatin is replaced by sulphur. Under the influence of cold aqueous solution of potassa, bisulphisathyde yields *indin*, $C_{16}H_6NO_2$, which is isomeric with white indigo. When treated with boiling potassa, indin fixes the elements of 2 eq. of water, and becomes indic acid, $C_{16}H_7NO_3, HO$, the potassa-salt of which forms fine black needles.

Ammoniacal gas and solution of ammonia yield with isatin a series of interesting substances, containing the nitrogen of the ammonia in addition to that of the isatin.

ACTION OF CHLORINE ON INDIGO.—In the dry state chlorine has no action whatever on indigo, even at the temperature of 212° ($100^\circ C$). In contact with water, the blue colour is instantly destroyed, and cannot again be restored. The same thing happens with the blue solution of sulphindyllic acid. When chlorine is passed into a mixture of powdered indigo and water until the colour dis-

appears, and the product is then distilled in a retort, water containing hydrochloric acid and a mixture of two volatile bodies, trichloraniline, $C_{12}(H_4Cl_3)N$, and trichlorophenol, $C_{12}(H_3Cl_3)O_2$, pass over into the receiver, while the residue in the retort is found to contain chlorisatin, already mentioned, and *bichlorisatin*, $C_{16}(H_3Cl_2)NO_4$, much resembling the former but more freely soluble in alcohol. Both these bodies yield acids in contact with boiling solution of potassa, by assimilating the elements of water.

The action of bromine on indigo is very similar.

ANILIC AND PICRIC ACIDS.—Anilic or indigotic acid is prepared by adding powdered indigo to a boiling mixture of 1 part of nitric acid and 10 parts of water, until the disengagement of gas ceases, filtering the hot dark-coloured liquid, and allowing it to stand. The impure anilic acid so obtained is converted into the lead-salt, which is purified by crystallization and the use of animal charcoal, and then decomposed by sulphuric acid. Anilic acid forms fine white or yellowish needles, which have a feebly acid taste, and very sparing degree of solubility in cold water. In hot water and in alcohol it dissolves easily. It melts when heated, and on cooling assumes a crystalline structure. By careful management it may be sublimed unchanged. Anilic acid contains $C_{14}H_4NO_9, HO = C_{14}(H_4NO_4)O_5, HO$. It has been mentioned that the same acid is readily prepared from salicylic acid (see p. 497). Hence it is more appropriately called *nitro-salicylic acid*.

Picric, carbazotic, or nitrophenisic acid, is one of the ultimate products of the action of nitric acid upon indigo and numerous other substances, as silk, wool, several resins, especially that of *Xanthorrhæa hastilis* (yellow gum of Botany Bay), salicin and some of its derivatives, cumarin, and certain bodies belonging to the phenyl-series. It may be prepared from indigo by adding that substance in coarse powder, and by small portions to 10 or 12 times its weight of boiling nitric acid of sp. gr. 1.43. When the last of the indigo has been added, and the action, at first extremely violent, has become moderated, an additional quantity of nitric acid may be poured upon the mixture, and the boiling kept up until the evolution of red fumes nearly ceases. When cold, the impure picric acid obtained may be removed, converted into potassa-salt, several times re-crystallized, and, lastly, decomposed by nitric acid. In the pure state it forms beautiful pale-yellow scaly crystals, but slightly soluble in cold water, and of insupportably bitter taste. Picric acid is used in dyeing; it forms a series of crystallizable salts of a yellow or orange colour: that of potassa forms brilliant needles, and is so little soluble in cold water, that a solution of picric acid is occasionally used as a precipitant for that base. The alkaline salts of this acid explode by heat with extraordinary violence. The crystals of picric acid contain $C_{12}H_2N_3O_{13}, HO$.

If a solution of picric acid be distilled with hypochlorite of lime,

or a mixture of chlorate of potassa and hydrochloric acid, an oily liquid of a penetrating odour is obtained, having a sp. gr. of 1.665, and boiling between 237° and 239° (114° and 115°C). This substance, *chloropicrin*, was discovered by Stenhouse, who gives the formula $\text{C}_4\text{Cl}_7\text{N}_2\text{O}_{10}$; MM. Gerhardt and Cahours assign to it the formula $\text{C}_2\text{Cl}_3\text{NO}_4$. According to the latter formula, which is more probable, chloropicrin would be chloroform, in which the hydrogen is replaced by the elements of hyponitric acid.

Chloroform $\text{C}_2(\text{HCl}_3)$; Chloropicrin $\text{C}_2(\text{NO}_4\text{Cl}_3)$.

PRODUCTS OF THE ACTION OF HYDRATE OF POTASSA UPON INDIGO.
—One of the most remarkable of these, aniline, has been already described (see page 566). When powdered indigo is boiled with a very concentrated solution of caustic potassa, it is gradually dissolved, with the exception of some brownish flocculent matter, and the liquid on cooling deposits yellow crystals of the potassa-salt of a new acid, the *chrysanic*, which can be procured in a purer state, by dissolving the crystals in water, filtering from reproduced indigo, and adding a slight excess of mineral acid. Chrysanic acid can be obtained in indistinct crystals from weak alcohol: it is supposed to contain $\text{C}_{29}\text{H}_{10}\text{N}_2\text{O}_5, \text{HO}$; but it is very probable that it is a mixture of several substances, especially isatic acid.

When this substance is boiled with mineral acids, it is decomposed into another new acid, the *anthranilic*, which remains in solution, and a blue insoluble matter resembling indigo: a similar effect is slowly produced by the action of the air upon an alcoholic solution of chrysanic acid. Anthranilic acid is colourless, sparingly soluble in cold water, easily soluble in alcohol. It melts when heated, sublimes under favourable circumstances, but decomposes entirely when heated in a narrow tube into carbonic acid and aniline. It contains $\text{C}_{14}\text{H}_6\text{NO}_3, \text{HO}$. By treatment with nitrous acid, anthranilic acid is converted into salicylic acid, $\text{C}_{14}\text{H}_6\text{NO}_3, \text{HO} + \text{NO}_3 = \text{C}_{14}\text{H}_5\text{O}_5, \text{HO} + \text{HO} + 2\text{N}$.

According to M. Cahours, pure indigo can also be converted into salicylic acid by fusion with hydrate of potassa: a particular temperature is required, somewhat above 570° (298°C), and the operation is by no means always successful.

LICHENS.

Litmus is used by the dyer as a red colouring matter; the chemist employs it in the blue state as a test for the presence of acid, by which it is instantly reddened.

In preparing test-papers for chemical use with infusion of litmus,

good writing or drawing paper, free from alum and other acid salts, should be chosen. Those sheets which after drying exhibit red spots, or patches, may be reddened completely by a little dilute acetic acid, and used, with much greater advantage than turmeric-paper, to discover the presence of free alkali, which restores the blue colour.

Many lichens, when exposed in a moistened state to the action of ammonia, yield purple or blue colouring principles, which, like indigo, do not pre-exist in the plant itself. Thus, the *Roccella tinctoria*, the *Variolaria orcina*, the *Leeanora tartarea*, &c., when ground to paste with water, mixed with putrid urine or solution of carbonate of ammonia, and left for some time freely exposed to the air, furnish the *archil*, *litmus*, and *cudbear* of commerce, very similar substances, differing chiefly in the details of the preparation. From these the colouring matter is easily extracted by water or very dilute solution of ammonia.

The lichens have been extensively examined by Schunk, Stenhouse, and several other chemists. The whole subject has been lately revised by Dr. Strecker, whose formulæ have been adopted in the following succinct account:—


ERYTHRIC ACID.—The lichen *Roccella tinctoria*, from which the finest kind of archil is prepared, is boiled with milk of lime, the filtered solution is precipitated by hydrochloric acid, and the precipitate dried and dissolved in warm, not boiling, alcohol, from which on cooling crystals of erythric acid are deposited. This is a very feeble acid, colourless, inodorous, difficultly soluble in cold and even in boiling water, readily soluble in ether. Its solution, when mixed with chloride of lime, assumes a blood-red colour. Boiled with water for some time, erythric acid absorbs 2 eq. and yields picro-erythrin, a crystallizable, bitter principle, and a new acid presently to be described, which is termed by some chemists *lecanoric*, by others *orsellinic* acid. If the ebullition be continued, the orsellinic acid undergoes a farther change, being converted into a crystalline substance, *orcina*, of which mention will shortly be made.

The composition of these various substances is expressed by the following formulæ:—


Erythric acid	$C_{20}H_{11}O_{10}$
Orsellinic acid	$C_{16}H_8O_8$
Picro-erythrin	$C_{24}H_{16}O_{14}$
Orcin	$C_{14}H_8O_4$

And the successive changes which occur by ebullition are represented by the following equations:—





ALPHAORSELLIC ACID is obtained from the South American variety of *Roccella tinctoria*. The preparation and the properties of this substance are perfectly analogous to those of erythric acid. Alphaorsellic acid contains $C_{32}H_{14}O_{14}$; by boiling with baryta-water it likewise furnishes orsellinic acid.




If the ebullition be continued too long, a great portion of the orsellinic acid is converted into orcin.

ORSELLINIC ACID, formerly frequently called licanoric acid, whether prepared from erythric or alphaorsellic acid, forms crystals which are far more soluble in water than either of the acids from which it has been prepared. Its taste is somewhat bitter. Boiled with water, it yields, as has been stated, orcin; under the influence of air and ammonia, it assumes a beautiful purple colour.

If the lichens, instead of being treated with milk of lime, be exhausted with boiling alcohol, the erythric and alphaorsellic acids are likewise decomposed; but instead of orsellinic acid, the ether of this substance, $C_4H_5O, C_{16}H_7O_7$ is formed. This ether was formerly described under the name *pseudo-erythrin*, until Mr. Schenk pointed out the true nature of the substance. Orsellinate of ethyl may be likewise produced by boiling pure orsellinic acid with alcohol. It crystallizes in colourless lustrous plates, which are readily soluble in boiling water, alcohol, and ether.


BETAORSELLIC ACID is found in *Roccella tinctoria* grown at the Cape; it is obtained like erythric and alphaorsellic acid, which it resembles in properties. Betaorsellic acid contains $C_{34}H_{16}O_{15}$; by boiling with water, it yields likewise orsellinic acid, together with hair-like crystals of a silvery lustre, of a substance called *roccellinin*, which has the composition $C_{18}H_8O_7$.



The decomposition of betaorsellic acid is obviously analogous to that of erythric acid, the roccellinin representing the picro-erythrin.

Evernic acid is extracted by milk of lime from *Evernia prunastri*, which was formerly believed to contain orsellinic acid. Evernic acid is very difficultly soluble even in boiling water; it assumes a yellow

colour with chloride of lime. When boiled with the alkalis, it yields another crystalline acid, *everninic acid*, differing from the preceding by its free solubility in boiling water. The composition of evernie acid is represented by the formula $C_{34}H_{16}O_{14}$, that of everninic acid by $C_{13}H_{10}O_8$. Evernie acid, when boiled for a considerable time with baryta, yields orcin: everninic acid does not give a trace of this substance; it is therefore probable that evernie acid, under the influence of alkalis, yields in addition to everninic acid likewise orsellinic acid, from which the orcin is derived, and that this decomposition is represented by the equation:—




PARELLIC ACID.—*Lecanora parella* contains an acid probably analogous to erythrie, alphaorsellic, betaorsellic, and evernie acids, the composition of which is, however, still unknown. By boiling with baryta it yields orsellinic acid and *parellic acid*, $C_{18}H_6O_8$.

ORCIN is the general product of decomposition of the acids previously described under the influence of heat or alkaline earths.


Orcin is best prepared by boiling lecanorie or orsellinic acid, pure or impure, with baryta-water, precipitating the excess of baryta by carbonic acid, and evaporating the filtered liquid to a small bulk. It forms, when pure, large, square prisms, which have a slightly yellowish tint, an intensely sweet taste, and a high degree of solubility both in water and alcohol. When heated, orcin loses water and melts to a syrupy liquid which distils unchanged. The crystals of orcin contain $C_{14}H_8O_4, 2HO$.

ORCEIN.—When ammonia is added to a solution of orcin, and the whole exposed to the air, the liquid assumes a dark-red or purple tint by absorption of oxygen; a slight excess of acetic acid then causes the precipitation of a deep-red powder, not very soluble in water, but freely dissolving in ammonia and fixed alkalis, with a purple or violet colour. This is an azotized substance, formed from the elements of the ammonia and the orcin, called *orcein*; it probably constitutes the chief ingredient of the red dye-stuff of the commercial articles before mentioned. The composition of orcein is less certain than that of orcin; it probably contains $C_{14}H_7NO_6$, when its formation from orcin, under the joint influence of oxygen and ammonia, would be represented by the equation:—



Other substances are occasionally present in lichens: thus, the

Usnea barbata and several other lichens contain *usnic acid*, a substance crystallizing from alcohol in fine yellowish-white needles with metallic lustre, having the formula $C_{34}H_{18}O_{14}$. It gives no orcin by distillation, but a substance similar to it, which probably contains $C_{38}H_{18}O_6$, and has been designated by the name of *betaorcin*. Its formation, which is attended by an evolution of carbonic acid, is represented by the equation:—



The *Parmelia parietina* furnished another new substance, *chrysophanic acid*, crystallizing in fine golden-yellow needles, and containing $C_{10}H_4O_3$. It is a very stable substance, and may be sublimed without much decomposition.

RED AND YELLOW DYES.

COCHINEAL.—This is a little insect, the *Coccus cacti*, which lives on several species of *cactus*, which are found in warm climates, and cultivated for the purpose, as in Central America. The dried body of the insect yields to water and alcohol a magnificent red colouring matter, precipitable by alumina and oxide of tin; *carmine* is a preparation of this kind. In cochineal the colouring matter is associated with several inorganic salts, especially phosphates and nitrogenous substances. Mr. Warren De La Rue, who has published a very elaborate investigation of cochineal,* has separated the pure colouring matter, which he calls *carminic acid*, by the following process. The aqueous decoction of the insect is precipitated by acetate of lead, and the impure carminate of lead washed and decomposed by hydro-sulphuric acid: the colouring matter thus separated is submitted again to the same treatment. A solution of carminic acid is thus obtained, which is evaporated to dryness, re-dissolved in absolute alcohol, and digested with crude carminate of lead, whereby a small quantity of phosphoric acid is separated, and lastly mixed with ether, which separates a trace of a nitrogenous substance. The residuc now obtained on evaporation is pure carminic acid. It is a purple-brown mass, yielding a fine red powder, soluble in water and alcohol in all proportions, slightly soluble in ether. It is soluble without decomposition in concentrated sulphuric acid, but readily attacked by chlorine, bromine, and iodine, which change its colour to yellow. It resists a temperature of $276^{\circ}\cdot 8$ (136°C), but is charred when heated more strongly. Carminic acid is a feeble acid. The composition of the substance, dried at 248° (120°C), is represented

* Mem. of the Chem. Soc. vol. iii. p. 454.

by $C_{29}H_{14}O_{16}$, which formula is corroborated by the analysis of a copper compound, $CuO, C_{28}H_{12}O_{16}$.


By the action of nitric acid upon carminic acid, together with oxalic acid, a splendid nitrogenated acid, crystallizing in yellow rhombic plates, is obtained. This substance, to which the name *nitrococcusic acid* was given, is bibasic; it contains $C_{16}H_3N_3O_{16}, 2HO$. It is soluble in cold, more so in boiling water, and readily soluble in alcohol and ether. Nitrococcusic acid is evidently derived from a non-nitrogenous compound, in which part of the hydrogen is replaced by the elements of hyponitric acid. Like the substances of this class, it explodes when heated.

In the mother-liquor, from which the carminic acid has been separated, Mr. Warren De La Rue discovered a white, crystalline, nitrogenous substance, for which he established the formula $C_{18}H_{11}NO_6$. This substance is identical with *tyrosine*, which will be mentioned in the section on Animal Chemistry.

MADDER.—The root of the *Rubia tinctorum*, cultivated in southern France, the Levant, &c., is the most permanent and valuable of the red dye-stuffs. In addition to several yellow colouring matters, which are of little importance for the purposes of the dyer, madder contains two red pigments which are called *alizarin* and *purpurin*. These substances have been the subject of very extensive researches by Debus, Higgins, and especially by Schunk. The latest papers on madder have been published by Wolff and Strecker, whose formulæ are quoted in the following abstract.

ALIZARIN.—The aqueous decoction of madder is precipitated by sulphuric acid, and the precipitate washed and boiled with sesquichloride of aluminum, which dissolves the red pigments; an insoluble brownish residue remaining behind. The solution, when mixed with hydrochloric acid, yields a precipitate consisting chiefly of alizarin, however, still contaminated with purpurin. The impure alizarin thus obtained may be farther purified by again throwing down the alcoholic solution with hydrate of alumina, and boiling the precipitate with a concentrated solution of soda, which leaves a pure compound of alumina and alizarin behind. From this the alizarin is separated by hydrochloric acid, and re-crystallized from alcohol. Pure alizarin crystallizes in splendid red prisms, which may be sublimed. It is but slightly soluble in water and in alcohol, but dissolves in concentrated sulphuric acid with a deep-red colour. On addition of water, the colouring matter is re-precipitated unchanged. It is also soluble in alkaline liquids, to which it imparts a magnificent purple colour. It is insoluble in cold solution of alum. Alizarin is the chief colouring matter of madder; it contains $C_{40}H_6O_6 + 4HO$, and is a feeble acid; but a few definite compounds with mineral oxides have been prepared, among which a lime-compound, $C_{40}H_6O_6, 3CaO + 3HO$, may be quoted. The action of nitric acid upon alizarin gives rise to the formation of oxalic acid and phthalic acid, a substance which will

again be mentioned among the products of decomposition of naphthalin.



PURPURIN.—Madder is allowed to ferment and then boiled with a strong solution of alum. The solution, when mixed with sulphuric acid, yields a red precipitate, which is purified by re-crystallization from alcohol. Purpurin thus obtained crystallizes in red needles, which contain $\text{C}_{18}\text{H}_6\text{O}_6 + 2\text{HO}$, i. e., 2 eq. of carbon less than alizarin. When treated with nitric acid, purpurin, like alizarin, furnishes oxalic and phthalic acids. Purpurin likewise contributes to the tinctorial properties of madder, but less so than alizarin. Together with alizarin and purpurin several other substances occur in madder, among which may be noticed an orange pigment, *rubiacin*, convertible by oxidizing agents into a peculiar acid, *rubiatic acid*, a yellow pigment, *xanthin*, a bitter principle, *rubian*, sugar, pectic acid, and several resins, &c.

Garancin is a colouring material, which is produced by the action of sulphuric acid upon madder. This substance possesses a higher tinctorial power than madder itself.

The beautiful *Turkey red* of cotton cloth is a madder-colour; it is given by a very complicated process, the theory of which is not perfectly elucidated.

SAFFLOWER.—This substance contains a yellow and a red colouring matter, the latter being insoluble in water, but soluble in alkaline liquids. The safflower may be exhausted with water acidulated with acetic acid, and the solution mixed with acetate of lead, and filtered from the dark-coloured impure precipitate. The lead-compound of the yellow pigment may then be thrown down by addition of ammonia, and decomposed by sulphuric acid. In its purest form the yellow matter forms a deep-yellow, uncrystallizable, and very soluble substance, very prone to oxidation. In its lead-compound it has probably the composition $\text{C}_{24}\text{H}_{12}\text{O}_{13}$.

The red matter or *carthamin* is obtained from the residual safflower by a dilute solution of carbonate of soda; pieces of cotton wool are immersed in the liquid, and acetic acid gradually added. The dried cotton is then digested in a fresh quantity of the alkaline solution, and the liquid supersaturated with citric acid, which throws down the carthamin in carmine-red flocks. It forms, when pure and dry, an amorphous, brilliant, green powder, nearly insoluble in water, but soluble in alcohol with splendid purple colour. It contains $\text{C}_{14}\text{H}_8\text{O}_7$.

Brazil-wood and *logwood* give red and purple infusions, which are

largely used in dyeing: the colouring principle of logwood is termed *hematoxylin*, and has been obtained in crystals. This substance contains $C_{40}H_7O_{15} + 8HO$. Acids brighten these colours, and alkalis render them purple or blue.

Among yellow dyes, *quercitron-bark*, *fustic-wood*, and *saffron* may be mentioned, and also *turmeric*; these all give yellow infusions to water, and furnish more or less permanent colours.

Purree or *Indian yellow*, a body of unknown origin, used in water-colour painting, according to the researches of Stenhouse and Erdmann, is a compound of magnesia with a substance termed *purreic* or *euxanthic acid*. The latter, when pure, crystallizes in nearly colourless needles, sparingly soluble in cold water, and of sweetish-bitter taste. It forms yellow compounds with the alkalis and earths, and is decomposed by heat, with production of a neutral crystalline sublimate, *purrenone* or *euxanthone*. Purreic acid contains $C_{40}H_{16}O_{21}$, purrenone $C_{13}H_4O_4$. By the action of chlorine, bromine, and nitric acid, a series of substitution-products are formed.

Certain of the products of the action of nitric acid upon *aloes* resemble very much some of the derivatives of indigo, without, however, it seems, being identical with them. Powdered aloes, heated for a considerable time with excess of moderately-strong nitric acid, yields a deep red solution, which deposits on cooling a yellow crystalline mass. This, purified by suitable means, constitutes *chrysammic acid*; it crystallizes in golden-yellow scales, which have a bitter taste, and are but sparingly soluble in water. Its potassa-salt has a carmine-red tint, and exhibits a green metallic lustre, like that of murexide. The formula of chrysammic acid is not perfectly established. It is probably $C_{14}HN_2O_{11}, HO$. Like picric acid, it yields with chloride of lime, *chloropicrin*. The mother-liquor from which the chrysammic acid has been deposited contains a second acid, the *chrysolepic*, which also forms golden-yellow, sparingly soluble, scaly crystals. The potassa-salt forms small, yellow prisms, of little solubility. It explodes by heat. Chrysolepic acid contains $C_{12}H_2N_3O_{13}, HO$; it is isomeric and possibly identical with picric acid.

To these may be added the *styphnic acid* described by MM. Boettger and Will, produced by the action of nitric acid of sp. gr. 1.2 upon *assafœtida* and several other gum-resins and extracts. Purree, when treated with excess of nitric acid, likewise yields styphnic acid. It crystallizes, when pure, in slender, yellowish-white prisms, sparingly soluble in water, readily dissolved in alcohol and ether. It has a purely astringent taste, and stains the skin yellow. By a gentle heat it melts, and on cooling becomes crystalline; suddenly and strongly heated, it burns like gunpowder. It also furnishes chloropicrin. The salts of this substance mostly crystallize in

orange-yellow needles, and explode with great violence by heat. Styphnic acid contains $C_{12}H_2N_3O_{15},HO$, i. e., picric acid + 2 eq. of oxygen. It may be viewed as a nitro-substitute of the same acid, $C_{12}H_5O_3,HO$, which, by the introduction of chlorine in the place of hydrogen, furnishes chloroniceic acid (see page 572).

Hypothetical niceic acid	.	.	$C_{12}H_5O_3,HO$
Chloroniceic acid	.	.	$C_{12}H_4ClO_3,HO$
Trinitroniceic acid	.	.	$C_{12}H_2(NO_2)_3O_3,HO.$

SECTION VII.

OILS AND FATS.

THE oils and fats form an interesting and very natural group of substances, which have been studied with great success. The vegetable and animal fats agree so closely in every respect, that it will be convenient to discuss them under one head.

Oily bodies are divided into *volatile* and *fixed*: the former are capable of being distilled without decomposition, the latter are not. When dropped or spread upon paper, they all produce a greasy stain: in the case of a volatile oil, this stain disappears when the paper is warmed, which never happens with a fixed fatty substance. All these bodies have an attraction, more or less energetic, for oxygen: this in some cases reaches such a height as to occasion spontaneous inflammation, as in the instance of large masses of cotton or flax moistened with rape or linseed oil. The effect of this absorption of oxygen leads to a farther classification of the fixed oils into *drying* and *non-drying* oils, or those which become hard and resinous by exposure to air, and those which thicken slightly, become sour and rancid, but never solidify. To the first class belong the oils used in painting, as linseed, rape, poppy-seed, and walnut; and to the second, olive and palm-oils, and all the oils and fats of animal origin. The parts of plants which contain the largest quantities of oil are, in general, the seeds. Olive-oil is, however, obtained from the fruit itself. The leaves of many plants are varnished on their upper surface with a covering of waxy fat. Among the natural orders, that of the *cruciferae* is conspicuous for the number of oil-bearing species.

The fixed oils in general have but a feeble odour, and scarcely any taste; whenever a sapid oil or fat is met with, it is invariably found to contain some volatile oily principle, as in the case of common butter. They are all insoluble in water, and but slightly soluble in alcohol, with the exception of castor-oil; in ether and in the essential oils, on the other hand, they dissolve in large quantity.

The consistence of these substances varies from that of the thinnest olive-oil to that of solid, compact suet; and this difference proceeds from the variable proportions in which the proximate solid and fluid fatty principles are associated in the natural product. All these bodies may, in fact, by mere mechanical means, or by the application of a low temperature, be separated into two, or sometimes three, dif-

ferent substances, which dissolve in, or mix with, each other, in all proportions. Thus, olive-oil exposed to a cold of 40° ($4^{\circ}\cdot5\text{C}$) deposits a large quantity of a crystalline solid fat, which may be separated by filtration and pressure; this is termed *margarin*, from its pearly aspect. That portion of the oil which retains its fluidity at this, or even a greater degree of cold, has received the name *olein* or *elain*. Again, a solid animal fat may, by pressure between folds of blotting-paper, be made much harder, more brittle, and more difficult of fusion. The paper becomes impregnated with a permanently fluid oil, or *olein*, while the solid part is found to consist of a mixture of two solid fats, one resembling the *margarin* of olive-oil, and the other having a much higher melting-point, and other properties which distinguish it from that substance; it is called *stearin*.

These remarks apply to all ordinary oils and fats: it is, however, by no means proved that the *olein* and *margarin* of all vegetable and animal oils are identical; it is very possible that there may be essential differences among them, more especially in the case of the first-named substance.

Fixed fatty bodies, in contact with alkaline solutions at a high temperature, undergo the remarkable change termed *saponification*. When *stearin*, *margarin*, or *olein* are boiled with a strong solution of caustic potassa or soda, they gradually combine with the alkali, and form a homogeneous, viscid, transparent mass, or *soap*, freely soluble in warm water, although insoluble in saline solutions. If the soap so produced be afterwards decomposed by the addition of an acid, the fat which separates is found completely changed in character; it has acquired a strongly-acid reaction when applied in a melted state to test-paper, and it has become soluble with the greatest facility in warm alcohol; it is in fact a new substance, a true *acid*, capable of forming salts, and a compound ether, and has been generated out of the elements of the neutral fat under the influence of the base. *Stearin*, when thus treated, yields *stearic acid*, *margarin* gives *margaric acid*, *olein* gives *oleic acid*, and common animal fat, which is a mixture of the three neutral bodies, affords by saponification by an alkali and subsequent decomposition of the soap, a mixture of the three fatty acids in question. These bodies are not, however, the only products of saponification; the change is always accompanied by the formation of a very peculiar sweet substance, called *glycerin*, which remains in the mother-liquor from which the acidified fat has been separated. The process of saponification itself proceeds with perfect facility in a close vessel; no gas is disengaged; the neutral fat, of whatsoever kind, is simply resolved into an alkaline salt of the fatty acid, or soap, and into *glycerin*.*

* We are indebted to M. Chevreul for the first series of scientific researches on the fixed oils and fats, and on the theory of saponification. These admirable investigations are detailed in the early volumes of the "*Annales de Chimie et de Physique*," and were afterwards published in a separate form in 1823, under the title of "*Recherches Chimiques sur les Corps gras d'Origine animale*."

Hence the neutral fats may be viewed as a species of salt, in which the glycerin plays the part of base, similarly to oxide of methyl and ethyl, &c., in the compound ethers.

STEARIN AND STEARIC ACID.—Pure animal stearin is most easily obtained by mixing pure mutton-fat, melted in a glass flask, with several times its weight of ether, and suffering the whole to cool. Stearin crystallizes out, while margarin and olein remain in solution. The soft pasty mass may then be transferred to a cloth, strongly pressed, and the solid portion still farther purified by re-crystallization from ether. It is a white friable substance, insoluble in water, and nearly so in cold alcohol; boiling spirit takes up a small quantity. Boiling ether dissolves it with great ease, but when cold retains only $\frac{1}{223}$ of its weight. The melting-point of pure stearin, which is one of its most important physical characters, may be placed at about 130° ($54^{\circ}\cdot5\text{C}$).

When stearin is saponified, it yields, as already stated, glycerin and stearic acid. The latter crystallizes from hot alcohol in milk-white needles, which are inodorous, tasteless, and quite insoluble in water. It dissolves in its own weight of cold alcohol, and in all proportions at a boiling heat; it is likewise soluble in ether. Alkaline carbonates are decomposed by stearic acid. Exposed to heat, it fuses, and at a higher temperature, if air be excluded, volatilizes unchanged. The melting-point of stearic acid is about 158° (70°C).

MARGARIN AND MARGARIC ACID.—The ethereal mother-liquor from which stearin has separated in the process just described yields on evaporation a soft-solid mixture of margarin and olein with a little stearin. By compression between folds of blotting-paper, and re-solution in ether, it is rendered tolerably pure. In this state margarin very much resembles stearin; it is, however, more fusible, melting at 116° ($46^{\circ}\cdot6\text{C}$), and very much more soluble in cold ether. By saponification it yields glycerin and margaric acid. The properties of this last-named substance resemble in the closest manner those of stearic acid; it is different in composition, however, more soluble in cold spirit, and has a lower melting-point, viz., 140° (60°C) or thereabouts. Its salts also resemble those of stearic acid.

A more or less impure mixture of stearic and margaric acids is now very extensively used as a substitute for wax and spermaceti in the manufacture of candles. It is prepared by saponifying tallow by lime, decomposing the insoluble soap so formed by boiling with dilute sulphuric acid, and then pressing out the fluid or oily portion from the acidified fat.

The solid part of olive-oil is said to be a definite compound of true margarin and olein, inasmuch as its melting-point, 68° (20°C), is constant; it gives by saponification a mixture of margaric and oleic acids.


OLEIN AND OLEIC ACID.—It is doubtful whether a perfectly pure olein has yet been obtained: the separation of the last portions of

margarin, with which it is always naturally associated, is a task of extreme difficulty. Any fluid oil, animal or vegetable, which has been carefully decolorized, and filtered at a temperature approaching the freezing-point of water, may be taken as a representative of the substance. Oleic acid much resembles olein in physical characters, being colourless and lighter than water, but it has usually a distinctly acid reaction, a sharp taste, and is miscible with alcohol in all proportions. When submitted to the action of nitric acid, it yields almost the whole series of acids, of which formic, acetic, propionic, butyric, &c., are members, and which has been mentioned in a previous section of this work (see page 480).

When stearic or margaric acid, or ordinary animal fats, are exposed to destructive distillation, they yield margaric acid, a fatty body, incapable of saponification, termed *margarone*, a liquid carbide of hydrogen, and various permanent gases. The neutral fats furnish besides an extremely pungent and even poisonous volatile principle, called *acrolein*, described farther on.

In the manufacture of ordinary soaps both potassa and soda are used; the former yielding *soft*, and the latter *hard* soaps. Animal and vegetable fats are employed indifferently, and sometimes resin is added.

Composition of the preceding Substances.—The following are the formulæ at present assigned to the fatty acids in question: they are chiefly founded on investigations made at Giessen:—



Margaric is thus seen to differ from stearic acid in containing 1 eq. of oxygen more, and stearic acid can actually be converted into margaric by the action of oxidizing agents. Stearic acid is bibasic, and in its crystallized state contains 2 eq. of water. Margaric acid, as represented by the above formula, is likewise, bibasic, but many chemists consider it as a monobasic acid, $C_{34}H_{33}O_3, HO$; its bibasic nature being, in fact, by no means so well established as that of stearic acid. The subject requires farther examination, especially since an opinion has lately been expressed, that stearic and margaric acids are isomeric modifications of the same acid.

Oleic acid, from almond-oil, butter, and beef-suet, gave results agreeing pretty well, and leading to the formula $C_{36}H_{33}O_3, HO$, the oleic acid of goose-fat and olive-oil having the same composition. Former researches had led to different results, which are explained by the extreme proneness to oxidation of the substance itself. The oleic acid obtained from linseed-oil appears to differ from the preceding substance; its analysis having led to the formula $C_{46}H_{48}O_5, HO$.

Margarone probably contains $C_{33}H_{33}O$, or margaric acid minus 1 eq. of carbonic acid.

The composition of stearin, margarin, and olein is most safely

deduced from a comparison of that of the acids to which they give rise, and of glycerin.

Margaric, stearic, and oleic acids have many properties in common; their salts much resemble each other, those of the alkalis being soluble in pure water when warm, but not in saline solutions. A large quantity of cold water added to an alkaline margarate or stearate occasions the separation of a crystalline, insoluble acid salt. The margarates, stearates, and olcates of *lime*, *baryta*, and the oxides of the metals proper are insoluble in water. They are easily obtained by double decomposition, and in some few cases by direct action on the neutral fat. A solution of soap in alcohol is sometimes used as a test for the presence and quantity of lime, &c., in waters under examination (see page 282).

GLYCERIN.—This substance is very readily obtained by heating together olive or other suitable oil, protoxide of lead, and water, as in the manufacture of common *lead-plaster*; an insoluble soap of lead is formed, while the glycerin remains in the aqueous liquid. The latter is treated with sulphuretted hydrogen, digested with animal charcoal, filtered, and evaporated *in vacuo* at the temperature of the air. In a pure state glycerin forms a nearly colourless and very viscid liquid, of sp. gr. 1.27, which cannot be made to crystallize. It has an intensely-sweet taste, and mixes with water in all proportions; its solution does not undergo the alcoholic fermentation, but when mixed with yeast and kept in a warm place, it is gradually converted into propionic acid (see page 457). Glycerin has no action on vegetable colours. Exposed to heat, it volatilizes in part, darkens, and becomes destroyed, one of its products of destruction being a substance possessing a most powerfully penetrating odour, which is called acrolein (see page 604). Nitric acid converts it into oxalic acid.

Glycerin is composed of $C_6H_8O_6$.

Glycerin combines with the elements of sulphuric acid, forming a compound acid, the *sulphoglyceric*, $C_6H_7O_5, 2SO_3, HO$, which gives soluble salts with lime, baryta, and protoxide of lead.

Quite recently M. Berthelot has succeeded in combining glycerin with a great number of acids, and producing in this manner artificially a series of compounds, which are partly identical with the fats occurring in nature, and partly analogous to these substances. They are generally obtained by the direct action, during several hours, of the acids upon glycerin in closed vessels at temperatures varying, according to circumstances, from 212° to 536° (100° to $280^\circ C$). Three compounds of stearic acid with glycerin have been thus produced, which M. Berthelot distinguishes as monostearin, bistearin, and tetrastearin. There are likewise several artificial margarins, palmitins, and oleins. The deportment of these bodies is perfectly analogous to that of neutral fats. Compounds with acetic, butyric, and valeric, benzoic, camphoric, and even with hydrochloric acid have likewise been obtained.

PALM AND COCOA-OILS.—These substances, which at the common temperature of the air have a soft-solid or buttery consistence, are now largely consumed in this country. *Palm-oil* is the produce of the *Elais guineensis*, and comes chiefly from the coast of Africa. It has, when fresh, a deep orange-red tint, and a very agreeable odour; the colouring matter, the nature of which is unknown, is easily destroyed by exposure to light, especially at a high temperature, and also by oxidizing agents. The oil melts at 80° (26°C). By cautious pressure it may be separated into a fluid olein and a solid substance, *palmitin*, which, when purified by crystallization from hot ether, is perfectly white, fusible at 118° (47°C), soluble to a small extent only in boiling alcohol, and convertible by saponification into *palmitic acid*. The latter resembles in the closest manner margaric acid, and has the same melting-point; it differs in composition, however, containing $\text{C}_{32}\text{H}_{51}\text{O}_3, \text{HO}$. By keeping, palm-oil seems to suffer a change similar to that produced by saponification: in this state it is found to contain traces of glycerin, and a considerable quantity of oleic acid, together with a solid fatty acid, first supposed to be margaric, but which is probably palmitic acid. The oil becomes harder and rancid, and its melting-point is raised at the same time. *Cocoa-oil*, extracted from the kernel of the common cocoa-nut, is white, and has a far less agreeable smell than the preceding. It contains olein and a solid fat, often used as a substitute for tallow in making candles, which by saponification gives a crystallizable fatty acid, *cocinic acid*, having the usual properties of these bodies, and melting at 95° (35°C). It is composed of $\text{C}_{26}\text{H}_{51}\text{O}_3, \text{HO}$. Both this and palmitic acid are monobasic.

The solid vegetable fat from the *Myristica moschata* contains a volatile oil, a fluid olein, and a solid, crystallizable, fatty principle; this, when saponified, which occurs with difficulty, yields *myristic acid*. This substance has been examined by Dr. Playfair: it melts at 120° (48°C), and contains $\text{C}_{28}\text{H}_{57}\text{O}_3, \text{HO}$. It is monobasic.

Cacao-butter, extracted from the crushed beans by boiling with water, yields by saponification a fatty acid, identical, according to Dr. Stenhouse, with the stearic acid from animal fat.

ELAIDIN AND ELAIDIC ACID.—When olive-oil is mixed with a small quantity of nitrous acid, nitric acid containing that substance, or solution of nitrate of mercury made in the cold, it becomes after a few hours a yellowish, soft-solid mass, which, pressed and treated with alcohol, furnishes a peculiar white, crystalline, fatty substance, termed *elaidin*. It resembles a neutral fat in properties, melts at 90° (32°C), dissolves with difficulty in boiling alcohol, easily in ether, and is resolved by saponification into glycerin and *elaidic acid*, which much resembles margaric acid. Oleic acid is directly convertible by nitrous acid into elaidic acid. It is not every kind of oil which furnishes elaidin; the drying oils, as those of linseed, poppy-seed, walnuts, &c., refuse to solidify; almond-, olive-, and castor-oils, possess the property in a high degree.

Elaidic acid appears to have the same composition as oleic acid, or $C_{36}H_{33}O_3,HO$.

SUBERIC, SUCCINIC, AND SEBACIC ACIDS.—*Suberic acid* has long been known as a product of the oxidation of *cork* by nitric acid; *succinic acid* is obtained by the distillation of *amber*, a fossil resin. Recently both have been produced by the long-continued action of nitric acid upon stearic and margaric acids. Suberic acid is a white crystalline powder, sparingly soluble in cold water, fusible and volatile by heat; it contains $C_{16}H_{12}O_6,2HO$. Succinic acid forms regular colourless crystals, soluble in 5 parts of cold, and in half that quantity of boiling water; it is also fusible and volatile without decomposition, and contains $C_8H_4O_6,2HO$. The remarkable production of this substance from malic acid by a process of fermentation has been already mentioned (see page 509). *Sebacic acid* is a constant product of the destructive distillation of oleic acid, olein, and all fatty substances containing those bodies; it is extracted by boiling the distilled matter with water; it has also been lately formed by the action of potassa on castor-oil (see page 606). It forms small pearly crystals resembling those of benzoic acid. It has a faintly-acid taste, is but little soluble in cold water, melts when heated, and sublimes unchanged. Sebacic acid is composed of $C_{10}H_8O_3,HO$, or $C_{20}H_{16}O_6,2HO$.

BUTTER; VOLATILE ACIDS OF BUTTER.—Common butter chiefly consists of a solid crystallizable, and easily fusible fat, a fluid oily substance, and a yellow colouring matter, besides mechanical impurities, as casein. The oily part appears to be a mixture of olein and a peculiar odoriferous fatty principle, *butyrin*, not yet isolated, which by saponification yields four distinct volatile acids, the *butyric*, the *caproic*, the *caprylic*, and the *capric*: these are most easily obtained by saponifying butter with potassa or soda, adding an excess of sulphuric acid, and distilling. The acid watery liquid obtained may then be saturated with an alkali, evaporated to a small bulk, and then distilled with excess of sulphuric or phosphoric acid in a retort. The mixed acids are separated by taking advantage of the unequal solubility of their baryta-salts: the less soluble salts of the mixture amounting to about $\frac{1}{20}$ of the whole mass, contain capric and caprylic acids; the larger and more soluble portion, the caproic and butyric acids.

BUTYRIC ACID, when pure, is a thin colourless liquid, of pungent rancid odour and sour taste. It is miscible in all proportions with water and alcohol. Its density is 0.963, and it boils and distils unchanged at 327° ($164^\circ C$). It is attacked by chlorine, with production of oxalic acid and of a chlorinatted compound. Butyric acid contains $C_3H_7O_3,HO$.

CAPROIC ACID forms a colourless liquid, of sp. gr. 0.922 boiling at 388.4 ($198^\circ C$); it has a feeble odour, somewhat resembling that of acetic acid, and is much less soluble in water than butyric acid. It contains $C_{12}H_{11}O_3,HO$. The artificial formation of this acid from cyanide of amyl has been already noticed (see page 474). Caproic

acid has been lately submitted to the action of the galvanic current. Messrs. Brazier and Gossleth have proved that its effect upon this acid is analogous to that upon valeric acid, and that the principal product is the hydrocarbon amyl $C_{10}H_{11}$, previously obtained by Dr. Frankland by the action of zinc upon iodide of amyl (see page 474).

CAPRYLIC ACID is chiefly remarkable for exhaling a powerful and disgusting odour of perspiration. It contains $C_{16}H_{15}O_3, HO$. This acid has been lately obtained by a very interesting reaction, namely, by the oxidation of the new caprylic alcohol discovered by M. Bouis among the products of decomposition of castor-oil (see page 606).


CAPRIC ACID much resembles caproic; it has a mixed odour of acetic acid and the smell of the goat, and is very sparingly soluble in water. Its formula is $C_{20}H_{19}O_3, HO$.

The simple relation existing between the formulæ of the volatile acids of butter, which are all members of the series of fatty acids, has been already pointed out (see page 481).

These acids exist ready formed in rancid butter and in cheese, associated with valeric acid. They are produced in small quantity by the saponification of most animal and some vegetable fats, and are generated, as has been mentioned already (see page 598), together with other products, by the action of nitric acid upon oleic acid. Butyric acid has been observed also as a product of the spontaneous decomposition of fibrin, and pre-exists in the leguminous fruit known as St. John's bread.

Whale- and seal-oil yield by saponification a volatile acid greatly resembling the preceding, called *phocenic* or *delphinic acid*; it was formerly believed to be a peculiar acid, but it is, according to recent experiments, nothing but valeric acid.

Butyric acid has acquired a certain degree of importance from the curious discovery of MM. Pelouze and Gelis, that sugar, under particular circumstances, is susceptible of becoming converted into that substance. A tolerably strong solution of common sugar mixed with a small quantity of casein and some chalk, and exposed for some time to a temperature of 95° ($35^{\circ}C$), yields, by a species of fermentation, in which the casein is the active *ferment*, a large amount of butyrate of lime; carbonic acid and hydrogen gases are evolved during the whole period. This change may be thus expressed—



The mixture directed for lactic acid answers well (see page 421): lactate of lime is first formed in large quantity, and afterwards gradually dissolved and converted into butyrate, which may be decomposed by sulphuric acid and distilled. This is an exceedingly interesting case of the half-artificial formation of an animal product.

WAX.—*Common bees'-wax*, freed from its yellow colouring matter

by bleaching, may be separated by boiling alcohol into two different proximate principles, *cerin* and *myricin*. The first is a white crystalline substance, soluble in about 16 parts of boiling spirit, and melting at 144° ($62^{\circ}\cdot 2\text{C}$); it is the more abundant of the two. It is easily saponified by a solution of caustic potassa. According to Brodie's valuable experiments it consists chiefly of cerotic acid $\text{C}_{54}\text{H}_{51}\text{O}_3\cdot\text{HO}$, which belongs to the series of fatty acids (see page 481). The same body in a very interesting form of combination exists in *Chinese wax*, which, according to Brodie, is a compound ether containing cerotic acid combined with the ether of cerotyl alcohol, $\text{C}_{54}\text{H}_{55}\text{O}\cdot\text{HO}$. It may be viewed as cerotate of oxide of cerotyl, $\text{C}_{54}\text{H}_{55}\text{O}\cdot\text{C}_{54}\text{H}_{53}\text{O}_3$, corresponding to the acetic ether of the wine-alcohol series. When heated with potassa it undergoes the changes peculiar to compound ethers, yielding on the one hand cerotate of potassa, and on the other hand cerotyl alcohol. Myricin is very much less soluble in alcohol, and rather more fusible. It is saponified with difficulty by a dilute solution of caustic potassa, palmitic acid, $\text{C}_{32}\text{H}_{31}\text{O}_3\cdot\text{HO}$ (see page 600), combines with the potassa, and a substance, $\text{C}_{60}\text{H}_{61}\text{O}\cdot\text{HO}$, belonging to the series of alcohols is set free, which has been termed melissic alcohol. Hence myricin is likewise a compound ether, namely, palmitate of oxide of melissyl, $\text{C}_{92}\text{H}_{92}\text{O}_4 = \text{C}_{60}\text{H}_{66}\text{O}\cdot\text{C}_{32}\text{H}_{33}\text{O}_3$.

SPERMACETI.—The soft-solid matter found in very large quantity in a remarkable cavity in the head of the spermaceti whale, when submitted to pressure, yields, as is well known, a most valuable fluid oil, and a crystalline, brownish substance, which, when purified, becomes the beautiful snow-white article of commerce, spermaceti. This substance appears, by the most recent experiments, to be a neutral fatty body of the constitution of compound ethers, and not, as formerly supposed, a mixture of several proximate principles. It melts at 120° ($48^{\circ}\cdot 8\text{C}$), and when cooled under favourable circumstances, forms distinct crystals. Boiling alcohol dissolves it in small quantity, and ether in much larger proportion. Spermaceti is saponified with great difficulty: two products are obtained, a substance, $\text{C}_{32}\text{H}_{34}\text{O}_2$, belonging to the series of alcohols (see page 481), to which the name *cetylic (ethalic) alcohol* has been given, and *cetylic (ethalic) acid*, $\text{C}_{32}\text{H}_{32}\text{O}_4$; the first is a crystallizable fat, whose melting-point is nearly the same as that of spermaceti itself, but its solubility in alcohol is much greater; it is also readily sublimed without decomposition. Cetylic acid stands to cetylic alcohol in the same relation as acetic acid to ordinary alcohol, and may be actually procured from the latter by oxidation; it resembles in many respects margaric acid. By oxidation by nitric acid spermaceti yields a large quantity of succinic acid.

Spermaceti is composed of $\text{C}_{64}\text{H}_{66}\text{O}_4 = \text{C}_{32}\text{H}_{33}\text{O}\cdot\text{C}_{32}\text{H}_{31}\text{O}_3$; it is cetylate of oxide of cetyl, and represents in the cetyl-series the acetic ether of the common alcohol-series.

CHOLESTERIN.—This substance is found in small quantity in various parts of the animal system, as in the bile, in the brain and nerves, and in the blood; it forms the chief ingredient of *biliary calculi*, from which it is easily extracted by boiling the powdered gall-stones in strong alcohol, and filtering the solution while hot; on cooling, the cholesterin crystallizes in brilliant colourless plates. It has the characters of a fat, is insoluble in water, tasteless and inodorous; it is freely soluble in boiling spirit, and also in ether. It altogether resists saponification. Cholesterin melts at 278° (136°C), and contains probably $\text{C}_{26}\text{H}_{52}\text{O}$.

CANTHARIDIN, the active principle of the Spanish fly, may be here mentioned. It is a colourless, crystallizable, fatty body, extracted by ether or alcohol from the insect; it is insoluble in water and dilute acids, and volatile when strongly heated. The vapour attacks the eyes in a very painful manner. Cantharidin contains $\text{C}_{10}\text{H}_6\text{O}_4$.

ACROLEIN.—When a neutral fat is subjected to destructive distillation, it furnishes, as already mentioned, among other products, an excessively volatile acrid substance, which attacks the eyes and the mucous membrane of the nose most distressingly. As the neutral fats alone yield this body, and the fatty acids never, it is known to arise from the elements of the glycerin; and glycerin itself under certain circumstances may be made to produce acrolein abundantly. It is best prepared by distilling glycerin with bisulphate of potassa; both the preparation and purification are attended with great difficulties.

Pure acrolein is a thin, colourless, highly-volatile liquid, lighter than water, and boiling at 126° ($52^{\circ}\cdot9\text{C}$). Its vapour is irritating beyond description. It is sparingly soluble in water, freely in alcohol and ether. According to M. Redtenbacher it contains $\text{C}_6\text{H}_4\text{O}_2$.

When exposed for some time to the air, or when mixed with oxide of silver, acrolein oxidizes with avidity, and passes into *acrylic acid*, which resembles in very many particulars acetic and propionic acids; it contains $\text{C}_6\text{H}_3\text{O}_3\cdot\text{HO}$. Acrolein, by keeping, undergoes partial decomposition, yielding a white, flocculent, indifferent body, *disacryle*; the same substance is sometimes produced together with acrylic acid by exposure to the air. In contact with alkalis, acrolein suffers violent decomposition, producing, like aldehyde, a resinous body.


The action of sulphuric acid upon olive-oil has been studied by M. Frémy. When the oil is slowly and cautiously mixed with half its volume of concentrated sulphuric acid, all rise of temperature being avoided, a homogeneous liquid is obtained, which, when mixed with a little water, separates into two layers, the lower consisting of sulpho-glyceric and free sulphuric acid, and the upper and syrupy

portion of two compound acids, the *sulphomargaric* and *sulpholeic*. These latter dissolve in a large quantity of water, but after some time undergo decomposition into sulphuric acid and several new fatty acids, to which the names *metamargaric*, *hydromargaric*, *hydromargaritic*, *metoleic*, and *hydroleic* were given. The first three are derived from the elements of the sulphomargaric acid; they are solid and crystallizable, and much resemble ordinary margaric acid, differing slightly from that substance and from each other in their melting-points, degree of solubility in alcohol, &c. The metoleic and hydroleic acids are fluid, and are derived from the sulpholeic acid of the mixture. They yield carbonic acid and liquid hydrocarbons by destructive distillation. The composition of these fatty acids is yet uncertain, but in all probability they only differ from margaric and oleic acids by the elements of water. The action of sulphuric acid upon the oil is thus somewhat similar to the effect of saponification, the neutral fat being resolved into margaric and oleic acids and glycerin, the whole of which then combine with the elements of sulphuric acid to form compounds belonging to the large group of substances, of which sulphovinic acid is the typical member.

The sulphuric saponification of fatty bodies is now carried out on a very large scale for producing cheaper varieties of "*stearin candles*." For this purpose, inferior fatty bodies, such as palm-oil, are mixed with 5 or 6 per cent. of concentrated sulphuric acid, and exposed to a temperature of 350° (177°C) produced by overheated steam. After cooling, the black mass thus obtained crystallizes to a tolerably solid fat, which is washed once or twice with water, and then submitted to distillation by the aid of steam, heated to about 560° ($293^{\circ}\cdot 5\text{C}$). The product of the distillation, which is beautifully white, may be at once used for making candles; frequently, however, it undergoes the processes of *cold* and *hot* pressing, whereby a much more solid fat is obtained.

CASTOR-OIL, which differs in some respects from the ordinary vegetable oils, yields, by oxidation with nitric acid, a peculiar product, namely, a volatile fatty acid, to which the term *acanthylic* has been applied. It forms a colourless, oily liquid of aromatic odour and burning taste, and slightly soluble in water. It refuses to solidify at a very low temperature, and cannot be distilled alone without some decomposition, although its vapour passes over readily with that of water. This body has distinct acid properties, forms a series of salts and an ether, and contains $\text{C}_{14}\text{H}_{13}\text{O}_3\cdot\text{HO}$. Under the influence of the galvanic current it undergoes a decomposition similar to that of valeric acid, according to Messrs. Brazier and Gossleth, the principal product being, together with a hydrocarbon containing equal equivalents of carbon and hydrogen, an oily substance $\text{C}_{12}\text{H}_{13}$, boiling at $395^{\circ}\cdot 6$ (202°C), to which the name *cuproyl* has been given, and which may be viewed as the radical of the alcohol of caproic acid, $\text{C}_{12}\text{H}_{13}\text{O}$, HO , still to be discovered.

Castor-oil has lately become the source of a new alcohol in the hands of M. Bouis. According to his researches, there is present in castor-oil a peculiar oleic acid, *ricinoleic acid*, which contains $C_{36}H_{33}O_5$, HO, i. e., 2 eq. of oxygen more than common oleic acid. If this acid, or more conveniently castor-oil itself, be heated with solid hydrate of potassa, an oily liquid distils over, boiling at 356° ($180^\circ C$), which is the alcohol of caprylic acid. It contains $C_{16}H_{17}O$, HO, and is readily converted into caprylic acid (see page 602), by treatment with oxidizing agents. The residue in the retort contains sebocate of potassa. This transformation is represented by the following equation:—



Some doubts are still hanging upon the composition of the substance obtained from castor-oil. Some analyses of M. Bouis himself, and an analysis of Mr. Wills, have led to the formula $C_{14}H_{16}O_2$, according to which this component would represent the alcohol of cenanthylic acid. The later researches, however, of M. Bouis on the one hand, and of Mr. Moschnin on the other, appear to be in favour of the formula adopted in the Manual.

The ether corresponding to caprylic alcohol is not yet known. Compounds, however, of the ether with methylic, ethylic, and amyllic ethers has been lately described by Mr. Wills.

The base corresponding to this alcohol, *caprylamine*, has been obtained by Mr. Squire, but not yet described. His analytical results are likewise in favour of the formula $C_{16}H_{18}O_2$.

VOLATILE OILS.

The volatile oils of the vegetable kingdom are exceedingly numerous; they are secreted by plants, and confer upon their flowers, fruits, leaves, and wood their peculiar odours. These substances are mostly procured by distilling the plant, or part of the plant, with water: their points of ebullition always lie above that of water; nevertheless, at 212° ($100^\circ C$) the oils emit vapour of very considerable tension, which is carried over mechanically, and condensed with the steam. The milky or turbid liquid obtained, when left at rest, separates into oil and water. Sometimes the oil is heavier than the water, and sinks to the bottom; sometimes the reverse happens.

The volatile oils, when pure, are colourless; they very frequently, however, have a yellow, and, in rarer cases, a green colour, from the presence of impurity. The odour of these substances is usually powerful, and their taste pungent and burning. They resist saponification completely, but when exposed to the air frequently become altered by slow absorption of oxygen, and assume the character of

resins. They mix in all proportions with fat oils, and dissolve freely both in ether and alcohol; from the latter solvent they are precipitated by the addition of water. As already mentioned, the volatile oils communicate a greasy stain to paper, which disappears by warming; by this character any adulteration with fixed oils can be at once detected. A solid crystalline matter, corresponding to the margarine of the common oils, frequently separates from these bodies; it bears the general name of *stearoptene*, and differs probably in almost every case.

The essential oils may be conveniently divided into three classes: viz., those consisting of carbon and hydrogen only; those consisting of carbon, hydrogen, and oxygen; and those containing in addition sulphur and nitrogen.

Oils composed of Carbon and Hydrogen.

OIL, OR ESSENCE OF TURPENTIN.—This substance may be taken as the type or representative of the class; it is obtained by distilling with water the soft or semi-fluid balsam called in commerce *crude turpentine*, which exudes from various pines and firs, or flows from wounds made for the purpose in the wood. The solid product left after distillation is common rosin. Oil of turpentin, when farther purified by rectification, is a thin, colourless liquid, of powerful and well-known odour: its density in the liquid state is 0.865, and that of its vapour 4.764; it boils at 312° ($155^{\circ}\cdot 5\text{C}$). In water it dissolves to a small extent, and in strong alcohol and ether much more freely; with fixed oils it mixes in all proportions. Strong sulphuric acid chars and blackens this substance; concentrated nitric acid and chlorine attack it with such violence that inflammation sometimes ensues.

Oil of turpentin is composed of C_5H_4 or $\text{C}_{20}\text{H}_{16}$.

With hydrochloric acid the oil forms a curious compound, which has been called *artificial camphor*, from its resemblance in odour and appearance to that substance. It is prepared by passing dry hydrochloric acid gas into the pure oil, cooled by a freezing mixture. After some time, a white crystalline substance separates, which may be strained from the supernatant brown and highly acid liquid, and purified by alcohol, in which it dissolves very freely. This substance is neutral to test-paper, does not affect nitrate of silver, and sublimes without much decomposition; it contains $\text{C}_{20}\text{H}_{17}\cdot\text{Cl}$, or perhaps $\text{C}_{20}\text{H}_{16}\cdot\text{HCl}$. The dark mother-liquor contains a somewhat similar, but fluid compound. Different specimens of oil of turpentin yield very variable quantities of these substances, which may, perhaps, arise from the coexistence of *two* very similar and isomeric oils in the ordinary article. When these hydrochlorates are decomposed by distillation with lime, they yield liquid oily products differing in some

particulars from the original oil of turpentin, but having the same composition as that substance. That from the solid has received the name of *camphylene*, and that from the liquid compound *terebylene*. The hypothetical and non-isolable modifications of the oil supposed to exist in the solid and liquid camphor are termed respectively *camphene* and *terebene*.

Another isomeric compound, *colophene*, is produced by distilling oil of turpentin with concentrated sulphuric acid. It is a viscid, oily, colourless liquid, of high boiling-point, and exhibiting by reflected light a deep-bluish tint,—a phenomenon often remarked in bodies of this class.

Bromine and iodine also form compounds with oil of turpentin.

Oil of turpentin is very largely used in the arts, in painting, and as a solvent for resins in making varnishes.

Bottles in which rectified oil of turpentin, not purposely rendered anhydrous, has been preserved, are often studded in the interior with groups of beautiful, colourless, prismatic crystals, which form spontaneously. These have the composition of a hydrate of oil of turpentin. These crystals contain $C_{20}H_{16}H_6O_6$.

OIL OF LEMONS is expressed from the rind of the fruit, or obtained by distillation with water. This oil differs very much from the last in odour, but closely resembles it in other respects. It has the same composition as oil of turpentin, and forms with hydrochloric acid two compounds, one solid and crystalline, the other fluid. The solid contains $C_{10}H_8, HCl$.

The oils of *orange-peel*, *bergamot*, *pepper*, *cubeb*, *juniper*, *capivi*, *elemi*, the *laurel-oil* of Guiana, the *East Indian grass-oil*, and the principal part of *hop-oil*, are hydrocarbons, isomeric with the oils of turpentin and lemons.

Essential Oils containing Oxygen.

The essential oils containing oxygen are very numerous, and in fact make up the great bulk of the bodies of this class employed in medicine and perfumery. They are seldom homogeneous, and in consequence do not often exhibit fixed boiling-points. Some of these oils have been made the subjects of much chemical research, but the majority yet require examination. Three of the most interesting, viz., those of bitter almonds, cinnamon, and the *Spiræa ulmaria*, have been already described.


OIL OF ANISEED.—The oil distilled from the fruit of the *Pimpinella anisum* consists of two substances, one of which is a fluid oil, and the other a solid crystalline substance, so abundant as to cause the whole to solidify at the temperature of 50° ($10^{\circ}C$). By pressure between folds of bibulous paper, and crystallization from alcohol, the solid essence may be obtained pure. It forms colourless pearly plates,

more fragrant than the crude oil, which melts when gently heated, and distils at a high temperature. It contains $C_{20}H_{12}O_2$. This substance is attacked energetically by chlorine, bromine, and nitric acid; it combines with hydrochloric acid, but is unaffected by solution of caustic potassa. With bromine the solid essence yields a white inodorous crystallizable compound, *bromanisal*, containing $C_{20}(H_9Br_3)O_2$. The action of chlorine is more complex, several successive compounds being produced. With sulphuric acid two products are obtained, a compound acid analogous to sulphovinic acid, and a white, solid neutral substance, *anisoin*, isomeric with the essence.

The products of the action of nitric acid vary with the strength of the acid employed; the most important are *hydride of anisyl*; *anisic acid*, a substance very much resembling salicylic acid in properties, sparingly soluble in cold water, freely in alcohol and ether; *nitranisic acid*, a yellowish-white, crystalline, sparingly-soluble powder; and *nitraniside*, a resinous body produced by fuming nitric acid.

The hydride of anisyl in a pure state is a yellowish oily liquid, having an aromatic odour of hay; it is heavier than water, and boils at 400° ($254^\circ\cdot5C$). Caustic potassa, concentrated and boiling, slowly decomposes it: with fused hydrate of potassa, it is instantly converted into anisic acid with disengagement of hydrogen; air and oxidizing bodies in general produce the same effect. Ammonia forms with it a crystalline compound analogous to hydrobenzamide. Hydride of anisyl contains $C_{16}H_8O_4$.

Anisic acid contains $C_{16}H_7O_5, HO$, i. e., hydride of anisyl and 2 eq. oxygen. When treated with an excess of lime or baryta, it suffers a decomposition, analogous to that of benzoic and salicylic acid, losing 2 eq. of carbonic acid, and being converted into an oxygenated oil, boiling at 302° ($150^\circ C$), to which the name *anisol* has been given.



The action of nitric acid upon anisol gives rise to the formation of three substitution-products, nitro-, binitro-, and trinitro-anisol, the former of which is a liquid, while the two latter are crystalline solids. They contain respectively $C_{14}(H_7NO_4)O_2$; $C_{14}(H_6[NO_4]_2)O_2$, and $C_{14}(H_5[NO_4]_3)O_2$. Treated with sulphuretted hydrogen these substances are converted into three organic bases, anisidine $C_{14}H_9NO_2$, nitranisidine $C_{14}(H_8NO_4)NO_2$, and binitranisidine $C_{14}(H_7[NO_4]_2)NO_2$.

Nitranisic acid is the nitro-substitute of anisic acid; it contains $C_{16}(H_6NO_4)O_5, HO$.

The solid portion of the oils of bitter fennel and badian is identical with that of oil of aniseed. The fluid component of the fennel-oil is isomeric with oil of turpentin.

Draconic acid, obtained by the action of nitric acid upon the oil of *Artemisia dracunculus*, is identical with anisic acid.

The various substances belonging to this group are homologons to the members of the salicyl-series, described in a former part of the Manual (see page 495), as may be seen from the following comparison :—

Hydride of salicyl	$C_{14} H_6$	O_4 ;	$C_{16} H_8$	O_4 { Hydride of anisyl
Salicylic acid . .	$C_{14} H_6$	O_6 ;	$C_{16} H_8$	O_6 Anisic acid
Nitrosalicylic (anilic) acid . .	$C_{14} \left\{ \begin{smallmatrix} H_5 \\ NO_4 \end{smallmatrix} \right\}$	O_6 ;	$C_{16} \left\{ \begin{smallmatrix} H_7 \\ NO_4 \end{smallmatrix} \right\}$	O_6 Nitranisic acid
Phenol (hydrate of phenyl). . .	$C_{12} H_6$	O_2 ;	$C_{14} H_8$	O_2 Anisol
Nitrophenol (Nitrophenasic) acid	$C_{12} \left\{ \begin{smallmatrix} H_5 \\ NO_4 \end{smallmatrix} \right\}$	O_2 ;	$C_{14} \left\{ \begin{smallmatrix} H_7 \\ NO_4 \end{smallmatrix} \right\}$	O_2 Nitranisol
Binitrophenol (Binitrophenesic) acid	$C_{12} \left\{ \begin{smallmatrix} H_4 \\ (NO_4)_2 \end{smallmatrix} \right\}$	O_2 ;	$C_{14} \left\{ \begin{smallmatrix} H_6 \\ (NO_4)_2 \end{smallmatrix} \right\}$	O_2 Binitranisol
Trinitrophenol (Trinitrophenesic) acid	$C_{12} \left\{ \begin{smallmatrix} H_3 \\ (NO_4)_3 \end{smallmatrix} \right\}$	O_2 ;	$C_{14} \left\{ \begin{smallmatrix} H_5 \\ (NO_4)_3 \end{smallmatrix} \right\}$	O_2 Trinitranisol
Carbazotic acid			$C_{14} H_9$	NO_2 Anisidine
			$C_{14} \left\{ \begin{smallmatrix} H_8 \\ NO_4 \end{smallmatrix} \right\}$	NO_2 Nitranisidine
			$C_{14} \left\{ \begin{smallmatrix} H_7 \\ (NO_4)_2 \end{smallmatrix} \right\}$	NO_2 Binitranisidine

OIL OF CUMIN is a mixture of two bodies, separable in great measure by distillation, *cymol*, a liquid hydrocarbon, containing $C_{20}H_{14}$, the most volatile portion of the oil, and *cuminol*, a colourless transparent oil, of powerful odour, easily changed in the air, and only to be distilled in a current of carbonic acid gas. Cuminol contains $C_{20}H_{12}O_2$, and is consequently isomeric with the solid essence of aniseed. By oxidation, this substance, which is homologous to oil of bitter almonds, yields *cumic acid*, a white, fatty, volatile substance, insoluble in water, having but little odour, and crystallizing in prismatic tables. It contains $C_{20}H_{11}O_3.HO$ (see homologues of benzoic acid, page 494).

OIL OF CEDAR-WOOD, in like manner, contains two substances, a solid crystalline compound, having the formula $C_{32}H_{26}O_2$, and a volatile liquid hydrocarbon, *cedrene*, $C_{32}H_{24}$, which can also be obtained by distilling the solid with anhydrous phosphoric acid.

OIL OF GAULTHERIA PROCUMBENS.—This very remarkable substance is now known in commerce under the name of *winter-green-oil*; it consists almost wholly of a definite principle which distils unchanged at 435° ($223^\circ 8C$), and contains, according to the analysis of M. Cahours, $C_{16}H_6O_6$. When mixed with dilute caustic potassa, it solidifies to a crystalline mass, which is a potassa-salt, *gaultherate* of potassa, and from which the oil may be separated again unchanged on addition of an acid. When distilled, however, with a concentrated

solution of caustic potassa, the oil of gaultheria is resolved into salicylic acid and wood spirit, thus exactly resembling in its behaviour the compound ethers which have been described in a previous section of the Manual (see page 424). This oil is, in fact, a veritable compound ether, *salicylate of oxide of methyl*, $C_2N_3O, C_{14}H_5O_5 = C_{16}H_8O_6$, furnished by nature herself. With ammonia the oil yields salicylamide, $C_{14}H_7NO_4 = C_{14}H_5O_4, NH_2$, isomeric with anthranilic acid (see page 567), which is converted by fuming nitric acid into the nitro-substitute, nitro-salicylamide (anilamide) $C_{14}(H_4NO_4)O_4, NH_2$, crystallizing in yellowish-white needles. Gaultheria oil is isomeric with anisic acid (see page 609), and yields by distillation at a high temperature with anhydrous lime and baryta, *anisol*, $C_{14}H_2O_2$, the same volatile oily liquid which is obtained from anisic acid by a similar process.

OIL OF VALERIAN.—The oil obtained by distilling valerian-root with water has usually a viscid consistence, a yellowish colour, and a powerful and disagreeable odour. It consists of at least three principles, namely, *valerianic acid*, *borneene* (see camphor), a light volatile liquid hydrocarbon, much resembling and isomeric with oil of turpentin, and *valerol*, a neutral oily body, much less volatile than the preceding, of feeble odour, and convertible by oxidizing agents into valeric acid. It contains $C_{12}H_{10}O_2$. Borneene, under certain circumstances not well understood, assimilates the elements of water and yields the solid camphor of Borneo, or *borneol*.

CAMPHOR.—Common camphor yields a good example of a concrete essential oil; it is obtained by distilling with water the wood of the *Laurus camphora*. When pure, it forms a solid, white, crystalline, and translucent mass, tough, and difficult to powder, and having a powerful and very familiar odour. It melts when gently heated, and boils, distilling unchanged at a high temperature. It slowly sublimes at the temperature of the air, and often forms beautiful crystals on the sides of bottles or jars containing it exposed to the light. Camphor is very sparingly soluble in water, but readily soluble in alcohol, ether, and strong acetic acid. It contains $C_{10}H_8O$, or $C_{20}H_{16}O_2$.

By the action of nitric acid aided by heat, camphor is gradually oxidized and dissolved with production of *camphoric acid*: this substance forms small colourless needles or plates, of acid and bitter taste, sparingly soluble in cold water, and containing $C_{10}H_7O_3, HO$. It melts when heated, and yields by distillation a colourless, crystalline, neutral, substance, containing $C_{10}H_7O_3$, generally termed anhydrous camphoric acid.

When camphorate of lime is submitted to distillation, it yields a volatile oil containing oxygen, in its formation and constitution similar to acetone (page 456) or benzophenone (page 486). This substance, *phorone*, contains C_9H_7O , or $C_{18}H_{14}O_2$. By the action of anhydrous phosphoric acid it loses water and furnishes the hydrocarbon *cumol*, $C_{18}H_{12}$ (see page 494).

When camphor in vapour is passed over a mixture of hydrate of potassa and quicklime strongly heated in a tube, it is resolved without disengagement of gas into an acid body termed *campholic acid*, white, crystalline, and sparingly soluble in water, containing $C_{20}H_{17}O_3.HO$. By distillation with anhydrous phosphoric acid, this acid gives a volatile hydrocarbon, *campholene*. Camphor itself, by a similar mode of treatment, yields a colourless volatile liquid, $C_{20}H_{14}$, formerly called *camphogen*, but since found to be identical with the hydrocarbon cymol, occurring in the oil of cumin.

The camphor of Borneo, procured from the *Dryobalanops camphora*, contains $C_{20}H_{18}O_2$; it is accompanied by borneene, identical with that of the oil of valerian, and yields the same substance when distilled with anhydrous phosphoric acid. Nitric acid converts it into common camphor.

The oils of *peppermint*, *lavender*, *rosemary*, *orange-flowers*, *rose-petals*, and many others, belong to the class of oxygenated essential oils.

Essential Oils containing Sulphur.

In the preparation of the sulphuretted volatile oils, distillatory vessels of copper, tin, or lead, must be avoided, as those metals are attacked by the sulphur. In other respects their manufacture offers no peculiarities.

OIL OF MUSTARD.—The most remarkable member of the class is the oil obtained by distillation from black mustard-seed. White mustard yields none. Both varieties give, by expression, a bland fat oil. The volatile oil does not pre-exist in the seed, but is formed in the same manner as bitter-almond oil, by the joint action of water and a peculiar coagulable albuminous matter upon a substance yet imperfectly known, present in the grain, and termed *myronic acid*.

The distilled oil, when pure, is colourless; it has a most powerful, pungent, and suffocating smell, and a density of 1.015. Applied to the skin, it produces almost instant vesication. It boils at 289° ($145^{\circ}8C$). Water dissolves it in small quantity, and alcohol and ether very freely. The oil itself, at a high temperature, dissolves both sulphur and phosphorus, and deposits them in a crystalline form on cooling. It is oxidized with violence by nitric acid, and by *aqua regia*. Alkalies decompose it by the aid of heat, with production of ammonia, an alkaline sulphide, and a sulphocyanide. The remarkable compound with ammonia, thiosinamine, has been already described (see page 577).

Mustard-oil gives by analysis $C_8H_5NS_2$.

The oil of horse-radish, and that obtained from the roots of the *Alliaria officinalis* by distillation with water, are identical with the oil of black mustard-seed.

OIL OF GARLIC.—The crude oil procured by distilling the sliced

bulbs with water is not a homogeneous product; by the action of metallic potassium, however, renewed until it is no longer tarnished, a small portion of oxygenetted oil which it contains may be decomposed and withdrawn, after which the sulphuretted compound may be obtained pure by re-distillation. In this state it forms a colourless liquid, lighter than water, of high refractive power, possessing in a high degree the peculiar odour of the plant, and capable of being distilled without decomposition. It contains C_6H_5S . Garlic-oil dissolved in alcohol, and mixed with solutions of platinum, silver, and mercury, gives rise to crystalline compounds having the characters of double salts, containing the elements of the oil with the sulphur replaced by oxygen or chlorine.

A curious and interesting relation exists between the oils of mustard and garlic: in both these substances, we may assume the existence of a radical C_6H_5 , to which the name *allyl* has been given, when mustard-oil becomes the sulphocyanide, and garlic-oil the sulphide of allyl.

Mustard-oil $C_6H_5NS = C_6H_5C_2NS_2$. Sulphocyanide of allyl.

Garlic-oil $C_6H_5S = C_6H_5S$ Sulphide of allyl.

This relation has been experimentally established. By mixing the oil with hydrate of soda and quicklime, and exposing the whole in a hermetically-sealed tube to a temperature superior to that of boiling water, sulphocyanide of sodium is produced, together with an oily substance which is *oxide of allyl*, a substance chiefly known in combination, and which is the oxygenetted constituent of crude garlic-oil. Again, if mustard-oil be treated in a similar manner with sulphide of potassium, sulphocyanide of potassium and garlic-oil are formed. On the other hand, when the compound of garlic-oil and chloride of mercury is gently heated with sulphocyanide of potassium, mustard-oil, with all its characteristic properties, is called into existence.

The oils of *assafetida*, and *onions*, contain sulphur, and consequently belong to the same series; they have not yet been thoroughly examined.

RESINS AND BALSAMS.

Common resin, or *colophony*, furnishes perhaps the best example of the class. The origin of this substance has been already described. It is a mixture of two distinct bodies, having acid properties, called *pinic* and *sylvic acids*, separable from each other by their difference of solubility in cold and somewhat dilute alcohol, the former being by far the more soluble of the two. Pure sylvic acid crystallizes in small, colourless, rhombic prisms, insoluble in water, soluble in hot, strong alcohol, in volatile oils, and in ether. It melts when heated, but can-

not be distilled without decomposition. The properties of pinic acid are very similar. Both have the same composition, viz., $C_{20}H_{15}O_2$. A third resin-acid, also isomeric with the preceding, the *pinaric*, has been found in the turpentin of the *Pinus maritima* of Bordeaux.

Lac is a very valuable resin, much harder than colophony, and easily soluble in alcohol; three varieties are known in commerce, viz., *stick-lac*, *seed-lac*, and *shellac*. It is used in varnishes, and in the manufacture of hats, and very largely in the preparation of sealing-wax, of which it forms the chief ingredient. Crude lac contains a red dye which is partly soluble in water. Lac dissolves in considerable quantity in a hot solution of borax; Indian ink, rubbed up with this liquid, forms a most excellent *label-ink* for the laboratory, as it is unaffected by acid vapours, and, when once dry, becomes nearly insoluble in water.

Mastic, *Dammar-resin*, and *sandarac* are resins largely used by the varnish-maker. *Dragon's-blood* is a resin of a deep-red colour. *Copal* is also a very valuable substance; it differs from the other resins, in being with difficulty dissolved by alcohol and essential oils. It is miscible, however, in the melted state with oils, and is thus made into varnish. *Amber* appears to be a fossil resin; it is found accompanying brown-coal or lignite.

CAOUTCHOUC.—This curious, and now most useful substance, is the produce of several trees of tropical countries, which yield a milky juice, hardening by exposure to the air. In a pure state it is nearly white, the dark colour of commercial caoutchouc being due to the effects of smoke and other impurities. Its physical characters are well known. It is softened, but not dissolved by boiling water; it is also insoluble in alcohol. In pure ether, rectified native naphtha, and coal-oil, it dissolves, and is left unchanged on the evaporation of the solvent. Oil of turpentin also dissolves it, forming a viscid, adhesive mass, which dries very imperfectly. At a temperature a little above the boiling-point of water caoutchouc melts, but never afterwards returns to its former elastic state. Few chemical agents affect this substance; hence its great practical use, in chemical investigations, for connecting apparatus, &c. Analysis shows it to contain nothing but carbon and hydrogen.

By destructive distillation caoutchouc yields a large quantity of thin volatile oily liquid, of naphtha-like odour, to which the name *caoutchoucine* has been applied. This is probably a mixture of several hydrocarbons, scarcely to be separated from each other by distillation or otherwise. It dissolves caoutchouc with facility.

A substance much resembling caoutchouc in certain respects, and of similar origin, has lately been introduced under the name of *gutta percha*. It promises to afford many useful applications.

Most of the resins, when exposed to destructive distillation, yield liquid, oily pyro-products, usually carbides of hydrogen, which have been studied with partial success. Great difficulties occur in these

investigations; the task of separating from each other, and isolating bodies which scarcely differ but in their boiling-points, is exceedingly troublesome.

Balsams are also, as before hinted, natural mixtures of resins with volatile oils. These differ very greatly in consistence, some being quite fluid, others solid and brittle. By keeping, the softer kinds often become hard. Balsams may be conveniently divided into two classes, viz., those which, like *common* and *Venice turpentin*, *Canada balsam*, *copaiba balsam*, &c., are merely natural varnishes, or solutions of resins in volatile oils, and those which contain benzoic or cinnamic acid in addition, as *Peru* and *Tolu balsams*, and the solid resinous *benzoin*, commonly called *gum-benzoin*.

Tolu-balsam, by distillation with water, yields three products; namely, benzoic-acid, the cinnamein of M. Frémy, (p. 501,) and *tolene*, a volatile colourless hydrocarbon, boiling at 338° (170°C), and containing $\text{C}_{24}\text{H}_{18}$. The balsam freed in this manner from essential oils, exposed to destructive distillation, yields in succession a viscous liquid which crystallizes in the receiver, and a thin liquid heavier than water; carbonic acid and carbonic oxide are largely evolved, and the retort is afterwards found to contain a residue of charcoal. The solid product is chiefly a mixture of benzoic and cinnamic acids; the volatile oil contains at least two substances differing in their boiling-points, and easily separated, namely, *toluol* (benzoene, see page 494), and an oily liquid heavier than water, of high boiling-point, and having the composition and characters of benzoic ether.

Toluol is a thin, colourless liquid, insoluble in water, sparingly soluble in alcohol, more freely in ether: it has the odour of benzol; its sp. gr. is $\cdot 870$, and it boils at 226° (108°C). The density of its vapour is $3\cdot 26$, and its formula C_{14}H_8 . It combines with fuming sulphuric acid to the compound *sulphotoluolic acid*, and with nitric acid yields two products, *nitrotoluol*, $\text{C}_{14}\text{H}_7\text{NO}_4$, and *binitrotoluol*, $\text{C}_{14}\text{H}_6\text{N}_2\text{O}_8$. The former is fluid, heavier than water, and bears a great resemblance in odour and other properties to nitrobenzol; the latter is a solid, fusible, crystallizable substance. The conversion of nitrotoluol into the organic base toluidine, has been already described (see page 571).

Liquid storax distilled with water, holding in solution a little carbonate of soda, yields a small and variable quantity of volatile oil, not homogeneous, but from which, by careful distillation, a liquid volatile hydrocarbon, termed *styrol*, can be extracted in a state of purity. It is thin and colourless, of powerful aromatic odour, refuses to solidify when cooled to 0° ($-17^{\circ}\cdot 7\text{C}$), and boils at 293° (145°C). Its sp. gr. is $\cdot 924$; it is nearly insoluble in water, but mixes freely with alcohol and ether. Styrole contains C_{16}H_8 , and is consequently isomeric with benzol.

When a portion of styrol is hermetically sealed in a glass tube, and then exposed for half an hour to a temperature approaching 400°

(200°C) by means of an oil-bath, it undergoes a most remarkable change, becoming converted into a solid, transparent, glassy, fusible substance, called *metastyrol*, isomeric, as might be expected, with styrol itself. The same change is slowly produced by the influence of sunshine. A portion of metastyrol is always formed when styrol is distilled in a retort without water. Metastyrol is again convertible by distillation at a high temperature into liquid styrol.*

Certain of the products of the distillation of dragon's-blood appear to be identical with these bodies.

* Mem. Chem. Soc., ii. 334.

SECTION VIII.

COMPONENTS OF THE ANIMAL BODY.

ALBUMINOUS PRINCIPLES. ALBUMIN.—The fluid portion of blood which has been some time drawn from the living body, and the white of eggs, contain this substance as their chief and characteristic ingredient. In the purest form in which albumin has yet been obtained it is insoluble, or nearly so, in water. If clear serum of blood, or white of egg mixed with a little water and filtered, be exactly neutralized by acetic acid, and then largely diluted with pure cold water, a copious flocculent precipitate falls, which may be collected on a filter, and washed. In this state it is nearly colourless, inodorous, and tasteless; it dissolves with facility in water containing an exceedingly small quantity of caustic alkali, and gives a solution which has all the characters of the original liquid. When dried by gentle heat, it shrinks to a very small bulk, and becomes a translucent, horny mass, which softens in water, and exhales when exposed to heat the usual ammoniacal products of animal matter, leaving a bulky coal, very difficult of combustion. When white of egg is thinly spread upon a plate, and exposed to evaporation in a warm place, it dries up to a pale-yellow, brilliant, gum-like substance, destitute of all traces of crystalline structure. In this state it may be preserved unchanged for any length of time, the presence of water being in all cases necessary to putrefactive decomposition. The dried white of egg may also be exposed to a heat of 212° (100°C) without alteration of properties. When put into slightly-warm water, it softens, and at length in great measure dissolves. When reduced to fine powder and washed upon a filter with cold water, common salt, sulphate, phosphate, and carbonate of soda are dissolved out, together with mere traces of organic matter, while a soft swollen mass remains upon the filter, which has all the characters of pure albumin obtained by precipitation. When dried and incinerated, this leaves nothing but a little phosphate of lime.

It thus appears likely that albumin is really an insoluble substance, and that its soluble state in the animal system is due to the presence of a little alkali.

When natural albumin is exposed to heat it solidifies, or *coagulates*. The temperature required for this purpose varies with the state of dilution. If the quantity of albumin be so great that the liquid has a slimy aspect, a heat of 145° or 150° ($62^{\circ}\cdot5$ or $69^{\circ}\cdot5\text{C}$) suffices, and the whole becomes solid, white, and opaque; in a very dilute condition, boiling is required, and the albumin then separates in

light, finely-divided flocks. Thus changed by heat, albumin becomes quite insoluble in water; it dries up to a yellow, transparent, horny substance, which when macerated in water resumes its former whiteness and opacity. In dilute caustic alkali it dissolves with facility, and in this respect resembles the *insoluble* albumin just described; it differs, however, from the latter in not being soluble in a strong solution of nitrate of potassa, which dissolves with great ease that substance. The only chemical change that can be traced in the act of coagulation is the loss of alkali and soluble salts, which are removed by the hot water.

A solution of ordinary albumin gives precipitates with excess of sulphuric, hydrochloric, nitric, and *meta*-phosphoric acids; but neither with acetic nor with common or tribasic phosphoric acid. These precipitates, which, though soluble in water, are insoluble in an excess of dilute acid, are looked upon as direct compounds of albumin with the acids in question. Most of the metallic salts, as those of copper, lead, mercury, &c., form insoluble compounds with albumin, and give precipitates with its solution; hence the value of white of egg as an antidote in cases of poisoning with corrosive sublimate. Alcohol, added in large quantity, precipitates albumin. Tannic acid, or infusion of galls, gives with it a copious precipitate. By these characters the presence of albumin may be readily discovered, and its identification effected; a *very* feebly alkaline liquid, if containing albumin, coagulates by heat, becomes turbid on the addition of nitric acid, and previously acidulated by acetic acid, gives a precipitate with solution of corrosive sublimate. It must be remembered, that a considerable quantity of alkali, and very minute quantities of the mineral acids, prevent coagulation by heat, and the addition of acetic acid, indispensable to the mercury-test, produces the same effect.

The chemical composition of albumin has been carefully studied; it contains in 100 parts—

Carbon	53.5
Hydrogen	7.0
Nitrogen	15.5
Oxygen	22.0
Phosphorus	0.4
Sulphur	1.6
						<hr/>
						100.0

The existence of unoxidized sulphur in albumin is easily shown; a boiled egg blackens a silver spoon from a trace of alkaline sulphide formed or separated during the coagulation; and a solution of albumin in excess of caustic potassa, mixed with a little acetate of lead, gives on boiling a black precipitate containing sulphide of lead.

FIBRIN.—This substance is found in solution in the blood. It is procured by washing the coagulum of blood in a cloth until all the

soluble portions are removed, or by agitating fresh blood with a bundle of twigs, when the fibrin attaches itself to the latter, and is easily removed and cleansed by repeated washing with cold water. The only impurity then remaining is a small quantity of fat, which can be extracted by ether. In the fresh state fibrin forms long, white, elastic filaments; it is quite tasteless, and insoluble in both hot and cold water. By long-continued boiling it is partly dissolved. When dried *in vacuo*, or at a gentle heat, it loses about 80 per cent. of water, and becomes translucent and horny; in this state it closely resembles coagulated albumin. Fresh fibrin wetted with concentrated acetic acid, forms, after some hours, a transparent jelly, which slowly dissolves in pure water; put into a very dilute caustic alkali, fibrin dissolves completely, and the solution exhibits many of the characters of albumin. Phosphoric acid produces a similar effect. Boiled with strong hydrochloric acid for several hours, fibrin yields among other products *leucine* (see page 622) and *tyrosine* (see page 591).

The fibrin of arterial and venous blood is not absolutely the same: when the venous fibrin of human blood is triturated in a mortar with $1\frac{1}{2}$ times its weight of water and $\frac{1}{3}$ of its weight of nitrate of potassa, and the mixture is left 24 hours or more at a temperature of 100° — 120° ($37^{\circ}\cdot7$ — $48^{\circ}\cdot8$), it becomes gelatinous, slimy, and eventually entirely liquid; in this condition it exhibits all the properties of a solution of albumin which has been neutralized by acetic acid. It coagulates by heat, it is precipitated by alcohol, corrosive sublimate, &c., and when largely diluted it deposits a flocculent substance, not to be distinguished from insoluble albumin.* With arterial fibrin, on the contrary, no such liquefaction happens, and even the fibrin of venous blood, when long exposed to the air, or to oxygen gas, loses the property in question.

In the soluble state, fibrin is in great measure unknown; when withdrawn from the influence of life, it coagulates spontaneously after a certain interval, giving rise to the production of the clot which appears in blood left to itself, and which consists of a kind of fine network of fibres, swollen with liquid serum, and enclosing the little red colouring particles of the blood, hereafter to be described.

M. Mulder found dried fibrin, carefully freed from fat, to be composed as follows:—

Carbon	52·7
Hydrogen	6·9
Nitrogen	15·4
Oxygen	23·5
Phosphorus	0·3
Sulphur	1·2
							<hr/>
							100·0

* Liebig, Handwörterbuch der Chemie, i. 881.

The ash, or incombustible portion of fibrin, varying from 0·7 to 2·5 per cent., consists chiefly of the phosphate of lime.

FIBRIN OF FLESH.—This was formerly considered to be identical with the fibrin of the blood. Liebig's late researches have proved the contrary. Whether it exists in the body in the coagulated or uncoagulated state is doubtful. The rigor mortis shows that it probably is in the latter state. Fresh-cut meat is treated with cold water, and the residue is mixed with water containing $\frac{1}{10}$ hydrochloric acid; a thickish solution is thus obtained which can be filtered. The acid solution is neutralized by ammonia, which causes a precipitate; this is washed with water, alcohol, and ether. It is then dried. The fibrin thus prepared is soluble in lime water, and the solution coagulates when boiled like albumin. Strecker found the following numbers, which correspond to albumin more than to fibrin of the blood:—

Carbon	55·23
Hydrogen	7·39
Nitrogen	15·84
Oxygen	20·33
Sulphur	1·21

Lehmann has given this substance the name of Syntonin (from *συντείνω*).

CASEIN.—This is the characteristic azotized component of milk, and the basis of the various preparations termed cheese. It probably exists in small quantities in healthy blood. Casein very closely resembles albumin in many particulars, and may even be occasionally confounded with it. Like that substance, it is insoluble in water when in a state of purity, and only assumes the soluble condition in the presence of free alkali, of which, however, a very small quantity suffices for the purpose. To prepare casein, fresh milk is gently warmed with dilute sulphuric acid, the coagulum produced well washed with water, dissolved in a dilute solution of carbonate of soda, and placed in a warm situation to allow the fat or butter to separate from the watery liquid. The latter is then removed by a siphon, and reprecipitated by sulphuric acid. These precipitations and re-solutions in dilute alkali are several times repeated. Lastly, the insoluble casein is well washed with boiling water, and treated with ether to remove the last traces of fat. In this state it is a white curdy substance, not sensibly soluble in pure water or in alcohol, but dissolved with great ease by water containing a little caustic or carbonated alkali. It is also soluble to a certain extent in dilute acids, from which it may be precipitated by cautious neutralization. The precipitate formed by an acid in a strong solution of casein contains acid in combination, which, however, may be entirely removed by washing. In the moist state casein reddens litmus-paper, and masks the reaction of an alkaline carbonate. When incinerated, it leaves about 0·3 per cent. of incombustible matter.

A solution of casein in very dilute alkali, as in milk, does not coagulate on boiling. On evaporation the surface becomes covered by a skin, in consequence of the action of the oxygen of the air on the casein, and the whole eventually dries up to a translucent mass. Acetic acid precipitates casein, which is a distinctive character between that substance and albumin.

By fusion with hydrate of potassa casein yields valeric and butyric acids, besides other products.

The most striking property of casein is its coagulability by certain animal membranes. This is well seen in the process of cheese-making, in the preparation of the *curd*. A piece of the stomach of the calf, with its mucous membrane, is slightly washed, put into a large quantity of milk, and the whole slowly heated to about 122° (50°C). In a short time after this temperature has been attained, the milk is observed to separate into a solid, white coagulum, or mass of curd, and into a yellowish, translucent liquid called *whey*. The curd contains all the casein of the milk, much of the fat, and much of the inorganic matter: the whey retains the milk-sugar and the soluble salts. It is just possible that this mysterious change may be really due to the formation of a little lactic acid from the milk-sugar, under the joint influence of a slowly decomposing membrane and the elevated temperature, and that this acid may be sufficient in quantity to withdraw the alkali which holds the casein in solution, and thus occasion its precipitation in the insoluble state. The loss of weight the membrane itself suffers in this operation is very small; it has been found not to exceed $\frac{1}{1800}$ part.

Casein has been carefully analyzed by Mulder; it contains in 100 parts—

Carbon	53.83
Hydrogen	7.15
Nitrogen	15.65
Oxygen	}	23.37
Sulphur		

100.00

When precipitated by acetic acid and washed with alcohol and ether it contains about 1 per cent. of sulphur. When not treated with acid it contains about 6 per cent. of phosphate of lime.

A comparison of the composition of these three bodies described is very remarkable, as it shows that they are very closely related in composition. The fibrin contains rather a larger quantity of oxygen than the albumin, and the casein contains no phosphorus. As, however, it is very doubtful whether these substances have been obtained in an unmixed and pure state no formulæ can be given.

PROTEIN.—Mulder observed that when albumin, fibrin, or casein was dissolved in a moderately strong solution of caustic alkali, and digested at 140° (60°C), or thereabouts, in an open vessel until the

liquid ceased to blacken with a salt of lead, and then filtered, and mixed with a slight excess of acetic acid, a copious, snow-white flocculent precipitate fell, and a faint odour of sulphuretted hydrogen was evolved. The new substance he called protein.* He stated that it was free from sulphur and phosphorus, and that it was by the combination of different quantities of these elements with protein, that albumin, fibrin, and casein, were produced, the protein pre-existing in each of these substances. It is, however, now admitted, that neither by the above-mentioned treatment, nor in any way, can a substance free from sulphur be obtained, and the protein must therefore be considered as one of the first products of the decomposition of albumin, fibrin, and casein, by moderately-strong caustic alkali.

When albumin, fibrin, or casein, are boiled in strong solution of potassa, as long as ammoniacal vapours are given off, the liquid then neutralized with sulphuric acid, evaporated to dryness, and the product exhausted by boiling alcohol, three compounds are dissolved out, viz., a soluble, brown extract-like substance, *erythroprotide*; a soluble straw-yellow substance, *protide*, and a curious crystallizable principle, *leucine*, which forms small colourless scales, destitute of taste and odour, soluble in water and alcohol, and in concentrated sulphuric acid without decomposition. When heated, it sublimes unchanged. Leucine contains $C_{12}H_{13}NO_4$ (see page 624).

Binoxide and Teroxide of Protein.—These names were given by Mulder to products of the long-continued action of boiling water upon fibrin in contact with air: they are said to be the chief ingredients also of the *buffy coat* of blood in a state of inflammation, being produced at the expense of the fibrin.† They cannot be obtained free from sulphur. *Binoxide of protein* is quite insoluble in water, but dissolves in dilute acids; when dry, it is dark coloured. The soluble part of the fibrin-decoction contains *teroxide of protein*, which somewhat resembles, and has been confounded with, gelatin. It is freely soluble in boiling water, and in dilute alkalis. Coagulated albumin is slowly dissolved by boiling water, and said to be converted into this substance. The solution in cold water gives a precipitate with nitric acid which is re-dissolved on the application of heat, and re-precipitated when cooled. A substance closely resembling this in its reactions and composition has been found in the urine of a patient suffering from *mollities ossium*.‡

When chlorine gas is passed to saturation into a solution of ordinary albumin, or either fibrin or casein dissolved in ammonia, a white, flocculent, insoluble substance falls, which, when washed and dried, becomes a soft yellowish powder. This is supposed to be a compound of chlorous acid and protein; when digested with ammonia, it yields sal-ammoniac and teroxide of protein.

* So called from *πρωτεύω*, *I take the first place*; in allusion to its alleged important relations to the albuminous principles.

† Mulder, *Annalen der Chemie und Pharmacie*, xlvii. 323.

‡ See *Philosophical Trans.* 1848.

GLOBULIN exists in concentrated solution in the crystalline lens, and in the blood-globules. The crystalline lens is triturated with water, and the clear fluid obtained by filtration, is evaporated to dryness at 122° (50°C). The dry residue is then powdered and treated with ether and alcohol, to separate fatty matter and salts. When dissolved in water it is precipitated by strong alcohol, like albumin; it is then no longer soluble in water, but it is partly soluble in dilute boiling alcohol. This reaction distinguishes it from albumin. Like albumin, it is coagulated by heat, and has the same reaction with mineral acids and salts.

Mulder has analyzed the coagulated globulin from the crystalline lens. He gives

Carbon	54.60
Hydrogen	6.94
Nitrogen	16.22
Oxygen }	22.24
Sulphur }	
<hr/>	
	100.00


He found only 0.3 per cent. sulphur and no phosphorus. Others have found 1.134 per cent. sulphur.

GELATIN AND CHONDRIN.—Animal membranes, skin, tendons, and even bones, dissolve in water at a high temperature more or less completely, but with very different degrees of facility, giving solutions which on cooling acquire a soft-solid, tremulous consistence. The substance so produced is called *gelatin*; it does not pre-exist in the animal system, but is generated from the membranous tissue by the action of hot water. The jelly of calves' feet, and common size and glue, are familiar examples of gelatin in different conditions of purity. Isinglass, the dried swimming-bladder of the sturgeon, dissolves in water merely warm, and yields a beautifully pure gelatin. In this state it is white and opalescent, or translucent, quite insipid and inodorous, insoluble in cold water, but readily dissolving by a slight elevation of temperature. Cut into slices and exposed to a current of dry air, it shrinks prodigiously in volume, and becomes a transparent, glassy, brittle mass, which is soluble in warm water, but insoluble in alcohol and ether. By dry distillation a watery fluid is produced, containing much carbonate of ammonia, and a thick brown oil, in which, besides carbonate of ammonia, sulphide of ammonium, cyanide of ammonium, and neutral oily bodies, various basic substances exist, as aniline, picoline, methylamine, trimethylamine, butylamine, and probably many others. In a dry state, gelatin may be kept indefinitely; in contact with water, it putrefies. Long-continued boiling gradually alters it, and the solution loses the power of forming a jelly on cooling. 1 part of dry gelatin or isinglass dissolved in 100 parts of water solidifies on cooling.

An aqueous solution of gelatin is precipitated by alcohol, which withdraws the water; corrosive sublimate in excess gives a white flocculent precipitate, and the same happens with solution of nitrate of the sub- and protoxide of mercury; neither alum, acetate, nor basic acetate of lead affect a solution of gelatin. With tannic acid or infusion of galls gelatin gives a copious, whitish curdy precipitate, which coheres on stirring to an elastic mass, quite insoluble in water, and incapable of putrefaction.

Tannic acid is the only acid that gives a precipitate with a solution of gelatin. It does so even when the solution is exceedingly dilute.

Chlorine passed into a solution of gelatin occasions a dense white precipitate of *chlorite of gelatin*, which envelopes each gas-bubble, and ultimately forms a tough, elastic, pearly mass, somewhat resembling fibrin. Boiling with strong alkalis converts gelatin, with evolution of ammonia, into leucine, and a sweet crystallizable principle, *gelatin-sugar* or *glycecoll*, or better, *glycocine* containing $C_4H_5NO_4$. This remarkable substance was first formed by the action of cold concentrated sulphuric acid upon gelatin, and has lately been obtained by the action of acids upon hippuric acid, which is thereby resolved into benzoic acid and glycocine (see page 493). It forms colourless crystals, freely soluble in water, and unites to crystallizable compounds with a great number of bodies, acids, bases, and salts. Glycocine, when treated with nitrous acid yields an acid homologous to lactic acid (see page 420), to which the name of glycolic acid has been given.



This substance, which is but imperfectly studied, appears to be present likewise in the mother-liquor from which the fulminate of silver has been deposited. There exists a remarkable relation between glycocine, alanine, and leucine, two substances which have been previously described (pages 578 and 622). These three bodies are homologous, as will be seen from the following formulæ:—

Glycocine	$C_4H_5NO_4$
Alanine	$C_6H_7NO_4$
Leucine	$C_{12}H_{13}NO_4$

The deportment of these three substances with nitrous acid is perfectly alike. Leucine, according to M. Strecker, yields a new acid $C_{12}H_{12}O_6$ homologous to glycolic and lactic acids, which has not yet been perfectly examined.

When a dilute solution of gelatin is distilled with a mixture of bichromate of potassa and sulphuric acid, it yields a number of extraordinary products, as acetic, valeric, benzoic, and hydrocyanic acids, and two volatile oily principles termed *valeronitrile* and *valera-*

acetonitrile. The former is a thin colourless liquid, of aromatic odour, like that of hydride of salicyl; it is lighter than water, boils at 257° (125°C), and contains $\text{C}_{10}\text{H}_9\text{N}$. The latter much resembles the first, but boils at 158° (70°C), and contains $\text{C}_{26}\text{H}_{24}\text{N}_2\text{O}_6$. Alkalis convert valerouitrile into valeric acid and ammonia, and valeracetonitrile into valeric and acetic acids and ammonia. It is very probable that the latter compound is a mixture of acetonitrile and valerouitrile.

Dry gelatin, subjected to analysis, has been found to contain in 100 parts:—

Carbon	50.05
Hydrogen	6.47
Nitrogen	18.35
Oxygen	25.13
						<hr/>
						100.00

From these numbers the formulæ $\text{C}_{13}\text{H}_{10}\text{N}_2\text{O}_5$, and $\text{C}_{52}\text{H}_{40}\text{N}_8\text{O}_{20}$, have been deduced. From 0.12 to 0.14 per cent. of sulphur has been found to be present.

The cartilage of the ribs and joints yields a gelatin differing in some respects from the preceding; it is called, by way of distinction, *chondrin*. It is less soluble in boiling water than gelatin. It is precipitated from its solution by acetic acid, and is not soluble in an excess of acid. Other acids in very small quantities precipitate chondrin, but the slightest excess re-dissolves the precipitate. Acetate of lead and solution of alum also precipitate this substance. These reactions distinguish chondrin from gelatin. Scherer gives

Carbon	50.75
Hydrogen	6.90
Nitrogen	14.70
Oxygen	27.65

To chondrin the formulæ $\text{C}_{32}\text{H}_{26}\text{N}_4\text{O}_{14}$ and $\text{C}_{48}\text{H}_{40}\text{N}_6\text{O}_{20}$ have been given.

If a solution of gelatin, albumin, fibrin, casein, or probably any one of the more complex azotized animal principles, be mixed with solution of sulphate of copper, and then a large excess of caustic potassa added, the greenish precipitate first formed is re-dissolved, and the liquid acquires a purple tint of indescribable magnificence and great intensity.

Gelatin is largely employed as an article of food, as in soups, &c.; but its value in this respect has been much overrated. In the useful arts size and glue are consumed in great quantities. These are prepared from the clippings of hides, and other similar matters, enclosed in a net, and boiled with water in a large cauldron. The strained solution gelatinizes on cooling, and constitutes *size*. Gluc is the same substance in a state of desiccation, the size being cut

into slices and placed upon nettings freely exposed to a current of air. Gelatin is extracted from bones with much greater difficulty; the best method of proceeding is said to be to enclose the bones, previously crushed in strong metallie cylinders, and admit high-pressure steam, which attacks and dissolves the animal matter much more easily than boiling water; or, to steep the bones in dilute hydrochloric acid, thereby removing the earthy phosphate, and then dissolve the soft and flexible residue by boiling.

There is an important economical application of gelatin, or rather of the material which produces it, which deserves notice, viz., to the clarifying of wines and beer from the finely-divided and suspended matter which often renders these liquors muddy and unsightly. When isinglass is digested in very dilute cold acetic acid, as sour wine or beer, it softens, swells, and assumes the aspect of a very light transparent jelly, which, although quite insoluble in the cold, may be readily mixed with a large quantity of watery liquid. Such a preparation, technically called *finings*, is sometimes used by brewers and wine-merchants for the purpose before mentioned: its action on the liquor with which it is mixed seems to be purely mechanical, the gelatinous matter slowly subsiding to the bottom of the cask, and carrying with it the insoluble substance to which the turbidity was due.

KREATIN and KREATININE.—Kreatin was first observed by Chevreul, and has been lately studied very carefully by Professor Liebig, who obtained it from the soup of boiled meat. It is best prepared from the juice of raw flesh by the following process:—A large quantity of lean flesh is cut up into shreds, exhausted by successive portions of cold water, strained and pressed. The liquid, which has an acid reaction, is heated to coagulate albumin and colouring matter of blood, and passed through a cloth. It is then mixed with pure baryta-water as long as a precipitate appears, filtered from the deposit of phosphates, and evaporated in a water-bath to a syrupy state. After standing some days in a warm situation, the kreatin is gradually deposited in crystals, which are easily purified by re-solution in water and digestion with a little animal charcoal.

When pure, kreatin forms colourless, brilliant, prismatic crystals, which become dull by loss of water at 212° (100°C). They dissolve readily in boiling water, sparingly in cold, and are but little soluble in alcohol. The aqueous solution has a weak bitter taste, followed by a somewhat acid sensation. In an impure state the solution readily putrefies. Kreatin is a neutral body, not combining either with acids or alkalis. In the crystallized state it contains $\text{C}_8\text{H}_9\text{N}_3\text{O}_4, 2\text{HO}$.

By the action of strong acids, kreatin is converted into *kreatinine*, a powerful organic base, with separation of the elements of water. The new substance forms colourless prismatic crystals, and is much more soluble in water than kreatin; it has a strong alkaline reaction, forms with acids crystallizable salts, and contains $\text{C}_8\text{H}_7\text{N}_3\text{O}_2$.

Kreatinine pre-exists to a small extent in the juice of flesh, together with lactic acid and other bodies yet imperfectly examined. It is also found in conjunction with kreatin in urine.

When kreatin is long boiled with solution of caustic baryta, it is gradually resolved into urea, subsequently decomposed into carbonic acid and ammonia, and a new organic body of basic properties, *sarcosine*. The latter, when pure, forms colourless transparent plates, extremely soluble in water, sparingly soluble in alcohol, and insoluble in ether. When gently heated they melt and sublime without residue. Sarcosine forms with sulphuric acid a crystallizable salt, and contains $C_6H_7NO_4$, being isomeric with lactamide, alanine, and urethane.

The mother-liquid from flesh from which the kreatin has been deposited contains, among other things, a new acid, the *inosinic*, the aqueous solution of which refuses to crystallize. It has a strong acid reaction, and is precipitated in a white amorphous condition by alcohol. It probably contains $C_{10}H_6N_2O_{10},HO$.* Recently, moreover, a kind of sugar, which, however, does not ferment, has been found in the juice from the muscular structure of the heart. It was discovered by Scherer, who calls it *inosite*, and gives the composition $C_{12}H_{12}O_{12}+4HO$. This substance crystallizes in rectangular prismatic crystals.

COMPOSITION OF THE BLOOD; RESPIRATION.—The blood is the general circulating fluid of the animal body, the source of all nutriment and growth, and the general material from which all the secretions, however much they may differ in properties and composition, are derived. Food or nourishment from without can only be made available by being first converted into blood. It serves also the scarcely less important office of removing and carrying off principles from the body which are hurtful, or no longer required.

In all vertebrated animals the blood has a red colour, and probably in all cases a temperature above that of the medium in which the creature lives. In the mammalia this is very apparent, and in the birds still more so. The heat of the blood is directly connected with the degree of activity of the respiratory process. In man the temperature of the blood seldom varies much from 98° ($36^{\circ}6C$), when in a state of health, even under great vicissitudes of climate: in birds it is sometimes as high as 109° ($42^{\circ}8C$). To these two highest classes of the animal kingdom, the mammifers and the birds, the observations about to be made are intended especially to apply.

In every creature of this description two kinds of blood are met with, which differ very considerably in their appearance, viz., that contained in the *left* side of the heart and in the arteries generally, and that contained in the *right* side of the heart and in the veins; the former, or *arterial* blood, has a bright-red colour, the latter, the *venous* blood, is blackish-purple. Further, the conversion of the dark into the florid blood may be traced to what takes place during its ex-

* Liebig, Chemistry of Food.

posure to the air in the lungs, and the opposite change, to what takes place in the capillaries of the general vascular system, or the minute tubes or passages, distributed in countless numbers throughout the whole body which connect the extremities of the arteries and veins. When compared together, little difference of properties or composition can be found in the two kinds of blood; the fibrin varies a little, that from venous blood being, as already mentioned, soluble in a solution of nitrate of potassa, which is not the case with arterial fibrin. It is very prone, besides, to absorb oxygen, and to become in all probability partly changed to the substance called binoxide of protein, which no doubt exists in the fibrin of arterial blood. The only other notable point of difference is in the gaseous matter the blood holds in solution, carbonic acid predominating in the venous, and free oxygen in the arterial variety.

In its ordinary state the blood has a slimy feel, a density varying from 1·053 to 1·057, and a decidedly alkaline reaction, partly from soda combined with albumin, and partly from carbonate and phosphate of soda; it has a saline and disagreeable taste, and, when quite recent, a peculiar odour or *halitus*, which almost immediately disappears. An odour may, however, afterwards be developed by an addition of sulphuric acid, which is by some considered characteristic of the animal from which the blood was obtained.

The coagulation of blood in repose has been already noticed, and its cause traced to the spontaneous solidification of the fibrin: the effect is best seen when the blood is received into a shallow vessel, and left to itself some time. No evolution of gas or absorption of oxygen takes place in this process. By strong agitation coagulation may be prevented; the fibrin in this case separates in cohering filaments.

Fig. 168.



To the naked eye the blood appears a homogeneous fluid, but it is not so in reality. When examined by a good microscope, it is seen to consist of a transparent and nearly colourless liquid, in which float about a countless multitude of little round red bodies, to which the colour is due; these are the *blood-discs* or *blood-corpuscles* of microscopic observers. They are accompanied by colourless globules, fewer and larger, the *white corpuscles of the blood*.

The *blood-discs* are found to present different appearances in the blood of different animals: in the mammals they look like little round red or yellowish discs, thin

when compared with their diameter, being flattened or depressed on opposite sides. In birds, lizards, frogs, and fish, the corpuscles are elliptical. In magnitude, they seem to be pretty constant in all the members of a species, but differ with the genus and order. In man they are very small, varying from $\frac{1}{6000}$ to $\frac{1}{3000}$ of an inch in breadth, while in the frog the long diameter of the ellipse measures at least four times as much. The corpuscles consist of an envelope containing a fluid in which the red colouring-matter of the blood is dissolved.

The coagulation of blood effects a kind of natural proximate analysis; the clear, pale serum, or fluid part, is an alkaline solution of albumin, containing various soluble salts; the clot is a mechanical mixture of fibrin and blood globules, swollen and distended with serum, of which it absorbs a large but variable quantity.

When the coagulum of blood is placed upon bibulous paper, and drained as much as possible from the fluid portion, and then put into water, the envelope, which consists of globulin, dissolves and sets free the colouring matter, forming a magnificent crimson solution, which has many of the characters of a dye-stuff. It contains albumin and globulin, and coagulates by heat and by the addition of alcohol; this albumin and globulin cannot be separated, and attempts to isolate the *hematosin* or red pigment have consequently failed. From its extreme susceptibility of change, it is not known in a state of purity. The above watery solution, exposed with extensive surface in a warm place, dries up to a dark-red, brittle mass, which is again soluble in water. After coagulation it becomes quite insoluble, but dissolves like albumin in caustic alkalis. Carbonic and sulphurous acids blacken the red solution: oxygen, or atmospheric air, heightens its colour; protoxide of nitrogen renders it purple; while sulphuretted hydrogen, or an alkaline sulphide, changes it to a dirty greenish-black.

Hematosin differs from the other animal principles in containing as an essential ingredient a remarkable quantity of the oxide of the metal iron. If a little of the dried clot of blood be calcined in a crucible, and digested with dilute hydrochloric acid, a solution will be obtained rich in oxide of iron; or if the solution of colouring matter just referred to be treated with excess of chlorine gas, the yellow liquid separated from the greyish coagulum formed will be found to give in a striking manner the well-known reactions of the sesquioxide of iron. There is little doubt either about the condition of the metal: sesquioxide of iron is withdrawn from the dry clot by the cautious addition of sulphuric acid, and without much alteration of the colour of the mass.* It is well known that certain organic matters, as sugar and tartaric acid, prevent the precipitation of sesquioxide of iron by alkalis, and its recognition by ferrocyanide of potassium, and

* Liebig, Handwörterbuch, i. 885.

it is very likely that the blood may contain a substance or substances capable of doing the same.

Hematosin, necessarily in a modified state, contains, according to Mulder, in 100 parts :—

Carbon	65.3
Hydrogen	5.4
Nitrogen	10.4
Oxygen	11.9
Iron	7.0

100.0

The following table represents the composition of healthy human blood as a whole; it is on the authority of M. Lecann :—*

	(1.)	(2.)
Water	780.15	785.58
Fibrin	2.10	3.57
Albumin	65.09	69.41
Colouring matter	133.00	119.63
Crystallizable fat	2.43	4.30
Fluid fat	1.31	2.27
Extractive matter of uncertain nature, soluble in both water and alcohol } .	1.79	1.92
Albumin in combination with soda .	1.26	2.01
Chlorides of sodium and potassium; carbonates, phosphates, and sul- phates of potassa and soda } .	8.37	7.30
Carbonates of lime and magnesia; phosphates of lime, magnesia, and iron; sesquioxide of iron } .	2.10	1.42
Loss	2.40	2.59
	<hr/> 1000.00	<hr/> 1000.00

In healthy individuals of different sexes these proportions are found to vary slightly, the fibrin and colouring matter being usually more abundant in the male than in the female; in disease, variations of a far wider extent are often apparent.

It appears singular that the red corpuscles, which are so easily dissolved by water, should remain uninjured in the fluid portion of the blood. This seems partly due to the presence of saline matter, and partly to that of albumin, the corpuscles being alike insoluble in a strong solution of salt and in a highly-albuminous liquid. In the blood the limit of dilution within which the corpuscles retain their integrity appears to be nearly reached, for when water is added they immediately become attacked.

* Ann. Chim. et de Phys. xlviii. 320.

Closely connected with the subject of the composition of the blood are those of respiration, and of the production of animal heat.

The simplest view that can be taken of a respiratory organ in an air-breathing animal, is that of a little membranous bag, saturated with moisture, and containing air, over the surface of which meanders a minute blood-vessel, whose contents, during their passage, are thus subjected to the chemical action of the air, through the substance of the membranes, and in virtue of the solubility of the gaseous matter itself in the water with which the membranes are imbued. In some of the lower classes of animals, where respiration is sluggish and inactive, these air-cells are few and large; but in the higher kinds they are minute, and greatly multiplied in number, in order to gain extent of surface, each communicating with the external air by the windpipe and its ramifications.

Respiration is performed by the agency of the muscles which lie between and about the ribs, and by the diaphragm. The lungs are not nearly emptied of air at each expiration. Under ordinary circumstances about 15 cubic inches only are thrown out, while by a forced effort as much as 50 or 60 cubic inches may be expelled. This is repeated about 18 times per minute when the individual is tranquil and undisturbed.

The expired air is found to have undergone a remarkable change; it is loaded with aqueous vapour, while a very large proportion of oxygen has disappeared, and its place been supplied by carbonic acid; air *once* breathed containing enough of that gas to extinguish a taper. The total volume of air seems to undergo but little change in this process, the carbonic acid being about equal to the oxygen lost. This, however, is found to depend very much upon the nature of the food: it is likely that when fatty substances, containing much hydrogen, are used in large quantities, a disappearance of oxygen will be observed. Nitrogen is in small quantity exhaled from the blood. In health no nitrogen is absorbed; the food invariably containing more of that element than the excretions.

Whatever may be the difficulties attending the investigation of these subjects,—and difficulties there are, as the discrepant results of the experiments prove,—one thing is clear: namely, that quantities of hydrogen and carbon are daily oxidized in the body by the free oxygen of the atmosphere, and their products expelled from the system in the shape of water and carbonic acid. Now, if it be true that the heat developed in the act of combination is a constant quantity, and no proposition appears more reasonable, the high temperature of the body may be the simple result of this exertion of chemical force.

The oxidation of combustible matter in the blood is effected in the capillaries of the whole body, not in the lungs, the temperature of which does not exceed that of the other parts. The oxygen of the air is taken up in the lungs, and carried by the blood to the distant

capillary vessels; by the aid of which, secretion, and all the mysterious functions of animal life, are undoubtedly performed: here the *combustion* takes place, although how this happens, and what the exact nature of the combustible may be, beyond the simple fact of its containing carbon and hydrogen, yet remains a matter of conjecture. The carbonic acid produced is held in solution by the now venous blood, and probably confers, in great measure, upon the latter its dark colour and deleterious action upon the nervous system. Once more poured into the heart, and by that organ driven into the second set of capillaries bathed with atmospheric air, this carbonic acid is conveyed outwards, through the wet membrane, by a kind of *false diffusion*, constantly observed under such circumstances: while at the same time oxygen is, by similar means, carried inwards, and the blood resumes its bright-red colour, and its capability of supporting life. Much of this oxygen is, no doubt, simply dissolved in the serum: the corpuscles, according to Professor Liebig, act as carriers of another portion, in virtue of the iron they contain, that metal being alternately in the state of sesquioxide and of carbonate of the protoxide,—of sesquioxide in the arteries, and of carbonate of protoxide in the veins, by loss of oxygen, and acquisition of carbonic acid. M. Mulder considers the fibrin to act in the same manner; being true fibrin in the veins, and, in part at least, an oxide of protein in the arteries.

It would be very desirable to show, if possible, that the quantity of combustible matter daily burned in the body is adequate to the production of the heating effects observed. Something has been done with respect to the carbon. Comparison of the quantities and composition of the food consumed by an individual in a given time, and of the excretions, shows an excess of carbon in the former over the latter, amounting, in some cases, according to Liebig's high estimate,* to 14 ounces; the whole of which is thrown off in the state of carbonic acid, from the lungs and skin, in the space of twenty-four hours. This statement applies to the case of healthy, vigorous men, much employed in the open air, and supplied with abundance of nutritious food. Females, and persons of weaker habit, who follow in-door pursuits in warm rooms, consume a much smaller quantity; their respiration is less energetic, and the heat generated less in amount. Those who inhabit very cold countries are well known to consume enormous quantities of food of a fatty nature, the carbon and hydrogen of which are, without doubt, chiefly employed in the production of animal heat. These people live by hunting: the muscular exertion required quickens and deepens the breathing; while, from the increased density of the air, a greater weight of oxygen is taken into the lungs, and absorbed into the blood at each inspiration. In this manner the temperature of the body is kept up, notwithstanding the piercing external cold; a most marvellous adjustment of the nature of

* Animal Chemistry, p. 14.

the food, and even of the inclinations and appetite of the man, to the circumstances of his existence, enable him to bear with impunity an atmospheric temperature which would otherwise injure him.

The carbon consumed in respiration in one day by a horse moderately fed, amounted, in a valuable experiment of M. Boussingault, to 77 ounces; that consumed by a cow to 70 ounces. The determination was made in the manner just mentioned, viz., by comparing the quantity and composition of the food.

CHYLE.—The fluid of the lacteal vessels. This is a very variable fluid, milky and feebly alkaline. It begins to coagulate when taken from the vessels, in 9 to 12 minutes, and is perfectly so in 2 to 4 hours. The coagulum is much smaller and weaker than that of the blood. That of the horse, from a yellowish colour changes in the air to light red.

The albuminous, saline serum contains very finely-divided molecules, which consist of the minutest particles of fatty matter, larger chyle globules, and colourless blood globules. Thus the chyle approximates in composition and properties to the blood.

In the chyle of the horse there was found :—

Water	91.00	to	96.00	per cent.
Fixed constituents	9.00		4.00	„
Nuclei and cells	Variable.			
Fibrin	0.19		0.7	„
Albumin	1.93		4.34	„
Fat	1.89		0.53	„
Extraneous matter free from salts	7.27		8.34	„
Soluble salts	7.49		6.78	„
Insoluble	about 2.00			

LYMPH is the name given to the fluid in the lymphatic vessels. It is colourless, has an alkaline reaction, and coagulates in from 4 to 20 minutes. It closely resembles the blood without the blood globules. It contains colourless globules, resembling the white globules of the blood. It contains much less albumin and fat than the serum of the blood. It contains more water, and proportionately more extractive matter.

Closely resembling this fluid is that poured out by serous membranes and the cellular tissue. It has been called exudation fluid, and may be divided into fibrinous and non-fibrinous. It may be considered as the serum of the blood with or without fibrin, which is far more commonly present than has been supposed.

MUCUS AND PUS.—The slimy matter effused upon the surface of various mucous membranes, as the lining of the alimentary canal, that of the bladder, of the nose, lungs, &c., to which the general name *mucus* is given, is so small in quantity, and so variable in consequence of any irritation of the membranes, that it is difficult to characterise. It always contains more or less epithelium and mucous cells. It pro-

bably contains a peculiar nitrogenous principle to which the name *mucin* has been given. It is insoluble in water. Very soluble in dilute alkalies, and precipitable from such solutions by acetic acid. Scherer gives carbon 52·41, hydrogen 6·97, nitrogen 12·82, oxygen 27·80. It contains no sulphur. Mucus often contains more or less albumin, and always extractive matters and salts; among these the chlorides are in excess.

Pus, the natural secretion of a wounded or otherwise injured surface, is commonly a creamy, white, or yellowish liquid, which, under the microscope, appears to consist of multitudes of minute globules floating in a serum. It is neither acid nor alkaline.

The pus globules are distended by very dilute mineral and organic acids. Imperfectly dissolved by alkalis, leaving the membrane of the cells adhering in a gelatinous mass. This cell membrane is an albuminous substance, soluble in very dilute acid. The pus serum contains more or less albumin, in all respects identical with that of the blood. Güterbock, by coagulating pus by alcohol, and extracting the residue, obtained a substance which is characterized by its precipitation, by acetic acid, and a solution of alum. He called it *pyin*. It is an albuminous substance, and has not been found to be always present.

The quantity of fatty substance is remarkable in pus, varying from 2 to 6 per cent. As much as 1 per cent. of cholesterin has been found to be present; but neither by this nor by any other character can the passage of mucus into pus be determined.

HORNY SUBSTANCE, KERATIN.—This is chiefly found in hair, nails, feathers, and epithelium. It is obtained by finely dividing their substances, treating them with warm water, and afterwards with boiling alcohol and ether: the horn substance is then very soluble in caustic potash, and precipitable by acids. By long-continued boiling with water it is decomposed. It putrefies with difficulty.

Scherer found—

	Skin of the sole of the foot.	Hair.	Ox-horn.	Nails.	Feathers.	Quill.
Carbon	50·20	50·37	51·13	50·15	52·10	52·00
Hydrogen	6·78	6·66	6·71	6·82	7·11	7·21
Nitrogen	17·22	17·94	17·28	16·90	17·68	17·89
Oxygen	25·80	25·03	24·88	26·13	23·11	22·90
Sulphur						

MILK, BILE, URINE, AND URINARY CALCULI.

MILK.—The peculiar special secretion destined for the nourishment of the young is, so far as is known, very much the same in flesh-eating animals and in those which live exclusively on vegetable food. The proportions of the constituents may, however, sometimes differ to a considerable extent. The specific gravity varies from 1·018 to 1·045. It will be seen hereafter that the substances

present in milk are wonderfully adapted to its office of providing materials for the rapid growth and development of the animal frame. It contains an azotized matter, casein, nearly identical in composition with muscular flesh, fatty principles, and a peculiar sugar, and lastly, various salts, among which may be mentioned phosphate of lime, held in complete solution in a slightly-alkaline liquid. This last is especially important to a process then in activity, the formation of bone.

The white, and almost opaque, appearance of milk is an optical illusion: examined by a microscope of even moderate power, it is seen to consist of a perfectly-transparent fluid, in which float about numbers of transparent globules: these consist of fat, surrounded by an albuminous envelope, which can be broken mechanically as in the churning, or dissolved by the chemical action of caustic potassa, after which, on agitating the milk with ether the fat can be dissolved.

When milk is suffered to remain at rest some hours at the ordinary temperature of the air, a large proportion of the fat-globules collect at the surface into a layer of *cream*; if this be now removed and exposed for some time to strong agitation, the fat-globules coalesce into a mass, and the remaining watery liquid is expelled from between them and separated. The *butter* so produced must be thoroughly washed with cold water, to remove as far as possible the last traces of casein, which readily putrefies, and would in that case spoil the whole. A little salt is usually added.

Ordinary butter still, however, contains some butter-milk, and when intended for keeping should be *clarified*, as it is termed, by fusion. The watery part then subsides, and carries with it the residue of the azotized matter. The flavour is unfortunately somewhat impaired by this process. The consistence of butter, in other words, the proportions of margarin and olein, is dependent upon the season, or more probably upon the kind of food: in summer the oily portion is always more considerable than in winter. The volatile odoriferous principle of butter, *butyrin*, has been already referred to.

The casein of milk, in the state of cheese, is in many countries an important article of food. The milk is usually heated to about 120° (49°C), and coagulated by *rennet*, or an infusion of the stomach of the calf in water; the curd is carefully separated by a sieve from the whey, mixed with a due proportion of salt, and sometimes some colouring-matter, and then subjected to strong and increasing pressure. The fresh cheese so prepared, being constantly kept cool and dry, undergoes a particular kind of putrefactive fermentation, very little understood, by which principles are generated which communicate a particular taste and odour. The goodness of cheese, as well as much of the difference of flavour perceptible in different samples, depends in great measure upon the manipulation; the best kinds contain a considerable quantity of fat, and are made with new milk; the inferior descriptions are made with skimmed milk.

Some of the Tartar tribes prepare a kind of spirit from milk by suffering it to ferment, with frequent agitation. The casein converts a part of the milk-sugar into lactic acid, and another part into grape-sugar, which in turn becomes converted into alcohol. Mare's milk is said to answer better for this purpose than that of the cow.

In a fresh state, and taken from a healthy animal, milk is always feebly alkaline. When left to itself, it very soon becomes acid, and is then found to contain lactic acid, which cannot be discovered in the fresh condition. The alkalinity is due to the soda which holds the casein in solution. In this soluble form casein possesses the power of taking up and retaining a very considerable quantity of phosphate of lime. The density of milk varies exceedingly; its quality usually bears an inverse ratio to its quantity. From an analysis of cow-milk in the fresh state by M. Haidlen,* the following statement of its composition in 1000 parts has been deduced:—

Water	873·00
Butter	30·00
Casein	48·20
Milk-sugar	43·90
Phosphate of lime	2·31
„ magnesia	0·42
„ iron	0·07
Chloride of potassium	1·44
„ sodium	0·24
Soda in combination with casein	0·42
	<hr/>
	1000·00

Human milk is remarkable for the difficulty with which it coagulates; it generally contains a larger proportion of sugar than cow-milk, but scarcely differs in other respects.

BILE.—This is a secretion of a very different character from the preceding: the largest internal organ of the body, the liver, is devoted to its preparation, which takes place from venous, instead of arterial blood. The composition of the bile has been made the subject of much investigation; the following is a summary of the most important facts which have been brought to light.

In its ordinary state bile is a very deep-yellow, or greenish, viscid, transparent liquid, which darkens by exposure to the air, and undergoes changes which have been yet imperfectly studied. It has a disagreeable odour, a most nauseous, bitter taste, a distinctly alkaline reaction, and is miscible with water in all proportions. When evaporated to dryness at 212° (100°C), and treated with alcohol, the greater part dissolves, leaving behind an insoluble jelly of mucus of the gall-bladder. This alcoholic solution contains colouring-matter and cholesterolin; from the former it may be freed by digestion with animal


* *Annalen der Chemie und Pharmacie*, xlv. 263.

charcoal, and from the latter by a large admixture of ether, in which the bile is insoluble, and separates as a thick, syrupy, and nearly colourless liquid. The colouring-matter may also be precipitated by baryta-water.

Pure bile thus obtained, when evaporated to dryness by a gentle heat, forms a slightly-yellowish brittle mass, resembling gum-arabic. It is completely soluble in water and absolute alcohol. The solution is not affected by the vegetable acids; hydrochloric and sulphuric acids, on the contrary, give rise to turbidity, either immediately or after a short interval. Acetate of lead partially precipitates it; the tribasic acetate precipitates it completely; the precipitate is readily soluble in acetic acid, in alcohol, and to a certain extent in excess of acetate of lead. When carbonized by heat, and incinerated, bile leaves between 11 and 12 per cent. of ash, consisting chiefly of carbonate of soda, with a little common salt and alkaline phosphate. The recent beautiful researches of Strecker, show that bile is essentially a mixture of the soda-salts of two peculiar conjugate acids, very distinctly resembling the resinous and fatty acids. One of these contains nitrogen, but no sulphur, and is termed *cholic acid*, or better, *glyco-cholalic*, being a conjugated compound of a *non-nitrogenous acid*, *cholalic acid*,* with the nitrogenated substance *glycocine* (see page 624); the other, containing nitrogen and sulphur, has received the name *choleic acid*, or better, *tauro-cholalic acid*, being a conjugated compound of the same *cholalic acid* with a body to be presently described under the name of *taurin*, containing both nitrogen and sulphur. The relative proportion in which these acids occur in bile, remains pretty constant with the same animal, but varies considerably with different classes of animals.

GLYCO-CHOLALIC ACID may be thus obtained:—When ox bile is perfectly dried and extracted with cold absolute alcohol, and after filtration is mixed with ether, it first deposits a brownish tough resinous mass, and after some time, stellated crystals which consist of glyco-cholalate of soda and potassa. These mixed crystals were first obtained by Platner, and they compose his so-called crystallized bile.


Glyco-cholalic acid may be obtained by decomposing the glyco-cholalate of soda by sulphuric acid; it crystallizes in fine white needles of a bitterish-sweet taste, is soluble in water and alcohol, but only slightly in ether, and has a strong acid reaction. It is represented by the formula $C_{52}H_{42}NO_{11},HO$. When boiled with a solution of potassa, the acid divides into cholalic acid $C_{48}H_{39}O_9,HO$, and glycocine or gelatin-sugar:—



* Also called *cholic acid* by some authors.

Boiled with concentrated sulphuric or hydrochloric acids, it yields likewise glycocine, but instead of cholalic acid, another white amorphous acid, *choloidinic acid* ($C_{48}H_{39}O_9$ = cholalic acid—1 eq. of water), or, if the ebullition has continued for some time, a resinous substance, from its insolubility in water called *dyslysin*, ($C_{48}H_{36}O_6$ = cholalic acid—4 eq. of water).

TAURO-CHOLALIC ACID is thus procured. Ox bile is freed as far as possible from glyco-cholalic acid by means of neutral acetate of lead, and it is then precipitated by basic acetate of lead, to which a little ammonia is added. The precipitate is decomposed by carbonate of soda, when tolerably pure tauro-cholalate of soda is obtained. By decomposing the tauro-cholalate of lead by sulphuretted hydrogen, tauro-cholalic acid is liberated. This substance, however, which was previously called choleic acid and bilin, has never been obtained in the pure state. Its formula, as inferred from the study of its products of decomposition, would be $C_{52}H_{44}NS_2O_{13},HO$. When boiled with alkalis it divides into cholalic acid and taurin:—



With boiling acids it gives likewise taurin, but instead of cholalic acid, either choloidinic acid or dyslysin, according to the duration of the ebullition.

TAURIN, $C_4H_7NS_2O_6$, crystallizes in colourless regular hexagonal prisms, which have no odour and very little taste. It is neutral to test-paper, and permanent in the air. When burnt, it gives rise to much sulphurous acid. It contains upwards of 25 per cent. of sulphur. It is easily prepared by boiling purified bile for some hours with hydrochloric acid. After filtration and evaporation, the acid residue is treated with five or six times its bulk of boiling alcohol, from which the taurin separates on cooling.

CHOLALIC or CHOLIC ACID, $C_{48}H_{39}O_9,HO$, crystallizes in a tetrahedra. It is soluble in sulphuric acid, and on the addition of a drop of this acid and a solution of sugar (1 part of sugar to 4 parts of water), a purple-violet colour is produced, which constitutes Pettenkofer's test for bile. At 383° ($195^\circ C$) it loses an atom of water, and is converted into choloidinic acid; which change, as has been pointed out, is also produced by ebullition with acids.

Cholalic acid is best obtained by boiling the resinous mass precipitated by ether from the alcoholic solution of the bile with a dilute solution of potassa for 24 or 36 hours, till the amorphous potassa-salt that has separated begins to crystallize. When the dark-coloured soft mass is removed from the alkaline liquid, dissolved in water, and hydrochloric acid added, a little ether causes the deposition of the cholalic acid in crystals.


The principal colouring-matter of the bile has been called *chole-*

pyrrhin. When dry it is reddish-brown and uncrystallizable, insoluble in water, more soluble in alcohol which becomes yellow, and most soluble in caustic alkali. On the addition of nitric acid to the yellow alkaline solution a change ensues. It passes through green, blue, violet, and red; after some time it again turns yellow, probably, in consequence of a gradual process of oxidation.

Another colouring matter has been called *biliverdin*. It is dark green, amorphous without taste or smell, insoluble in water, slightly soluble in alcohol, but soluble in ether. Berzelius considers it to be identical with the chlorophyll, or green colouring-matter of leaves.

According to the researches of Strecker and Gundelach, pigs' bile differs from the bile of other animals. This bile contains an acid, to which the name *hyocholic acid* has been given, which may be prepared in the following manner:—fresh pigs' bile is mixed with a solution of sulphate of soda, the precipitate obtained is dissolved in absolute alcohol, and decolorized by animal charcoal. From this solution ether throws down a soda-salt, yielding on addition of sulphuric acid, hyocholic acid as a resinous mass, which is dissolved in alcohol and re-precipitated by water.

Hyocholic acid contains $C_{54}H_{43}NO_{10}$. When heated with solutions of the alkalis, the acid undergoes a decomposition perfectly analogous to that of glyco-cholalic acid, hyocholic acid, splitting into glyecine and a crystalline acid, very soluble in alcohol, less so in ether, which has been termed *hyocholalic acid*. This substance contains $C_{50}H_{39}O_7, HO$; and the change is represented by the following equation:—



Hence hyocholic acid might be called *glyco-hyocholalic acid*. When boiled with acids, glyco-hyocholalic acid yields likewise glyecine, but instead of hyocholalic acid, a substance representing the dyslysin of the ordinary bile, which might be termed *hyodyslysin*. The composition of hyodyslysin is $C_{50}H_{38}O_6 = \text{hyocholalic acid} - 2 \text{ eq. } HO$.

Pigs' bile contains a very trifling quantity of sulphur, probably in the form of a sulphuretted acid corresponding to the tauro-cholalic acid of ox-bile. Strecker believes this acid to contain $C_{54}H_{45}NS_2O_{12}$, it might be called *tauro-hyocholalic acid*, which, when boiled with an alkali, would yield taurin and hyocholalic acid. The sulphuretted acid must be present in pigs' bile in very minute quantity; it is even less known than tauro-cholalic acid.

The once celebrated *oriental bezoar-stones* are biliary calculi, said to be procured from a species of antelope; they have a brown tint, a concentric structure, and a waxy appearance, and consist essentially of a peculiar and definite crystallizable principle called *lithofellinic acid*. To procure this substance, the calculi are reduced

to powder and exhausted with boiling alcohol; the dark solution is decolorized by animal charcoal, and left to evaporate by gentle heat, whereupon the lithofellinic acid is deposited in small, colourless, transparent six-sided prisms. It is insoluble in water, and with difficulty soluble in ether, but dissolves with ease in alcohol; it melts at 202° ($95^{\circ}5C$), and at a higher temperature burns with a smoky flame, leaving but little charcoal. Lithofellinic acid dissolves without decomposition in concentrated acetic acid, and in oil of vitriol; it forms a soluble salt with potassa, and dissolves also in ammonia, but crystallizes out unchanged on evaporation. By analysis, lithofellinic acid is found to consist of $C_{40}H_{35}O_7, HO$.

URINE.—The urine is the great channel by which the azotized matter of those portions of the body which have been taken up by the absorbents is conveyed away and rejected from the system in the form of urea. It serves also to remove superfluous water, and foreign soluble matters which get introduced into the blood.

The two most remarkable and characteristic constituents of urine, urea and uric acid, have already been fully described; in addition to these, it contains sulphates, chlorides, phosphates of lime, and magnesia, alkaline salts, and certain yet imperfectly known principles, including an odoriferous and a colouring substance (see foot note to page 641).

Healthy human urine is a transparent, light amber-coloured liquid, which, while warm, emits a peculiar, aromatic, and not disagreeable odour. This is lost on cooling, while the urine at the same time occasionally becomes turbid from a deposition of urates, which redissolve with slight elevation of temperature. It is very decidedly acid to test-paper: * this acidity has been ascribed to acid phosphate of soda, to free uric acid, and to free lactic acid; lactic acid can, however, hardly coexist with urate of ammonia, and the amorphous buff-coloured deposit obtained from fresh urine by spontaneous evaporation *in vacuo* is not uric acid, but the ammonia-salt of that substance, modified as to crystalline form by the presence of minute quantities of chloride of sodium. That a free acid is sometimes present in the urine is certain; in this case, the reaction to test-paper is far stronger, and the liquid deposits on standing little, red, hard crystals of uric acid; but this is no longer a normal secretion.

An alkaline condition of the urine from fixed alkali is sometimes met with. Such alkalinity can always be induced by the administration of neutral potassa- or soda-salts of a vegetable acid, as tartaric or acetic acid; the acid of the salt is burned in the blood in the process of respiration, and a portion of the base appears in the urine in the state of carbonate. The urine is often alkaline in cases of retention, from carbonate of ammonia produced by putrefaction in the bladder itself; but this is easily distinguished from alkalinity from fixed alkali, in which it is *secreted* in that condition.

* The degree of acidity appears to vary in the same person at different times. See Philosophical Trans. 1849.

The density of the urine varies from 1·005 to 1·030 ; about 1·020 to 1·023 may be taken as the average specific gravity. A high degree of density in urine may arise from an unusually large proportion of urea ; in such a case, the addition of nitric acid will occasion an almost immediate production of crystals of nitrate of urea, whereas with urine of the usual degree of concentration at least very many hours will elapse before the nitrate begins to separate. The quantity passed depends much upon circumstances, as upon the activity of the skin. It is usually more deficient in quantity and of higher density in summer than in winter. Perhaps about 32 ounces in the 24 hours may be assumed as a mean.

When kept at a moderate temperature, urine after some days, begins to decompose ; it exhales an offensive odour, becomes alkaline from the production of carbonate of ammonia, and turbid from the deposition of earthy phosphates. The carbonate of ammonia is due to the putrefactive decomposition of the urea, which gradually disappears, the *ferment*, or active agent of the change, being apparently the mucus of the bladder, a portion of which is always voided with the urine. It has been found also that the yellow adhesive deposit from stale urine is a most powerful ferment to the fresh secretion. In this putrefied state urine is used in several of the arts, as in dyeing ; and forms, perhaps, the most valuable manure for land known to exist.

Putrid urine always contains a considerable quantity of sulphide of ammonium ; this is formed by the deoxidation of sulphates by the organic matter. The highly-offensive odour and extreme pungency of the decomposing liquid may be prevented by previously mixing the urine, as Liebig suggests, with sulphuric or hydrochloric acid, in sufficient quantity to saturate all the ammonia that can be formed.

The following is an analysis of human urine by Berzelius. 1000 parts contained

Water	933·00
Urea.	30·10
Lactates and extractive matter*	17·14
Uric acid	1·00
Sulphates of potassa and soda . .	6·87
Phosphate of soda	2·92
„ ammonia	1·65
„ lime and magnesia	1·00
Chloride of sodium	4·45
Sal-ammoniac	1·50
Silica	0·03
Mucus of bladder	0·32
	<hr/>
	1000·00

* All dark-coloured, uncrystallizable substances, soluble both in water and alcohol, were confounded by the old chemists under the general name of *ex-*

In certain states of disorder and disease substances appear in the urine which are never present in the normal secretion: of these the most common is albumin. This is easily detected by the addition of nitric acid in excess, which then causes a white cloud or turbidity, which is permanent when boiled, or by corrosive sublimate, the urine being previously acidified by a little acetic acid; boiling causes usually a precipitate which is not dissolved by a drop or two of acid. Mere turbidity by boiling is no proof of albumin, the earthy phosphates being often thrown down from nearly neutral urine under such circumstances; the phosphatic precipitate is, however, instantly dissolved by a drop of nitric acid.

In *diabetes* the urine contains grape-sugar, the quantity of which commonly increases with the progress of the disease, until it becomes enormous, the urine acquiring a density of 1.040 and beyond. It does not appear that the urea is deficient *absolutely*, although more difficult to discover from being mixed with such a mass of syrup. The smallest trace of sugar may be discovered in urine by Trommer's test, formerly mentioned: a few drops of solution of sulphate of copper, are added to the urine, and afterwards an excess of caustic potassa; if sugar be present, a deep-blue liquid results, which, on boiling, deposits red suboxide of copper. With proper management, this test is very valuable; it will even detect sugar in the blood of diabetic patients.* Urine containing sugar, when mixed with a little yeast, and put in a warm place, readily undergoes vinous fermentation, and afterwards yields, on distillation, weak alcohol, contaminated with ammonia.

The urine of children is said sometimes to contain benzoic acid: it is possible that this may be produced by the decomposition of hippuric acid, which frequently occurs in the urine of healthy persons. When benzoic acid is taken, the urine after a few hours yields on concentra-

trative matter. The progress of modern science constantly tends to extricate from this confused mass one by one the many definite organic principles therein contained in a more or less modified form, and to restrict within narrower limits the application of the term. In the above instance, the colouring matter of the urine, and it may be several other substances, are involved.

Professor Liebig states that all his endeavours to obtain direct evidence of the existence of lactic acid in the urine, either in a fresh or putrid state, completely failed. Putrid urine yielded a volatile acid in a notable quantity, which turned out to be acetic acid: a little benzoic acid was also noticed, and traced to a small amount of hippuric acid in the recent urine. The acid reaction of urine is ascribed to an acid phosphate of soda, produced by the partial decomposition of some of the common phosphate, the reaction of which is alkaline, by the organic acids (uric and hippuric) generated in the system, aided by the sulphuric acid constantly produced by the oxidation of the protein-compounds of the food, or rather of the body.—*Lancet*, June, 1844.

Still more recently Liebig has announced the discovery in the urine of kreatin and kreatinine, already described. Putrid urine contains kreatinine only.

* Dr. Bence Jones, Med. Chirur. Trans. vol. xxvi. Great care must be taken in using this test, which depends on the instantaneous reduction of the oxide of copper. By long boiling very many organic substances produce this reaction.

tion, and the addition of hydrochloric acid, needles of hippuric acid, soiled by adhering uric acid.

The deposit of buff-coloured or pinkish amorphous sediment, which so frequently occurs in urine upon cooling, after unusual exercise or slight derangements of health, consists chiefly of urate of soda with urate of ammonia: it may be at once distinguished from a deposit of ammonio-magnesian phosphate by its instant disappearance on the application of heat. The earthy phosphates, besides, are hardly ever deposited from urine which has an acid reaction. The colouring matter of the urine is constantly undergoing change: by means of neutral and basic acetate of lead it may be separated into two substances which contain different amounts of carbon. The substance which contains most carbon may be obtained as a dark-blue powder: when dry it has a copper colour like indigo, and dissolves in alcohol, giving a purple-blue solution. It is said to occur most evidently in Bright's disease. Virehow states that he met with this blue pigment in crystals in unhealthy urine. Heller distinguishes three colouring matters in the urine to which he has given the names uroxanthin, uroglauin, and uorhodin; they have not been chemically examined on account of the difficulty of preparing them.

The yellow principle of bile may be observed in urine in cases of jaundice.

The urine of the carnivorous mammifera is small in quantity, and highly acid; it has a very offensive odour, and quickly putrefies. In composition it resembles that of man, and is rich in urea. In birds and serpents the urine is a white pasty substance, consisting almost entirely of urate of ammonia. In herbivorous animals it is alkaline and often turbid from earthy carbonates and phosphates: urea is still the characteristic ingredient, while of uric acid there is scarcely a trace; hippuric acid is usually, if not always, present, sometimes to a very large extent. When the urine putrefies, this hippuric acid, as already noticed, becomes changed to benzoic acid.

URINARY CALCULI.—Stony concretions, differing much in physical characters and in chemical composition, are unhappily but too frequently formed in the bladder itself, and give rise to one of the most distressing complaints to which humanity is subject. Although many endeavours have been made to find some solvent or solvents for these calculi, and thus supersede the necessity of a formidable surgical operation for their removal, success has been but very partial and limited.

Urinary calculi are generally composed of concentric layers of crystalline or amorphous matter, of various degrees of hardness. Very frequently the central point or nucleus is a small foreign body: curious illustrations of this will be seen in any large collection. Calculi are not confined to man; the lower animals are subject to the same affliction; they have been found in horses, oxen, sheep, pigs, and almost constantly in rats.

The following is a sketch of the principal characters of the different varieties of calculi:—

1. *Uric Acid*.—These are among the most common; externally they are smooth or warty, of yellowish or brownish tint; they have an imperfectly crystalline, distinctly concentric structure, and are tolerably hard. Before the blowpipe the uric acid calculus burns away, leaving no ash. It is insoluble in water, but dissolves with facility in caustic potassa, with but little ammoniacal odour; the solution mixed with acid gives a copious white curdy precipitate of uric acid, which speedily becomes dense and crystalline. Cautiously heated with nitric acid, and then mixed with a little ammonia, it gives the characteristic reaction of uric acid, viz., deep purple-red murexide.

2. *Urate of Ammonia*.—Calculi of urate of ammonia much resemble the preceding; they are easily distinguished, however. The powder boiled in water dissolves, and the solution gives a precipitate of uric acid when mixed with hydrochloric acid. It dissolves also in hot carbonate of potassa with copious evolution of ammonia.

3. *Fusible Calculus; Phosphate of Lime with Phosphate of Magnesia and Ammonia*.—This is one of the most common kinds. The stones are usually white or pale-coloured, smooth, earthy, and soft; they often attain a large size. Before the blowpipe this substance blackens from animal matter which earthy calculi always contain; then becomes white, and melts to a bead with comparative facility. It is insoluble in caustic alkali, but readily soluble in dilute acids, and the solution is precipitated by ammonia. Calculi of unmixed phosphate of lime are rare, as also those of phosphate of magnesia and ammonia; the latter salt is sometimes seen forming small brilliant crystals in cavities in the fusible calculus.

4. *Oxalate of Lime Calculus; Mulberry Calculus*.—The latter name is derived from the rough, warty character, and dark blood-stained aspect of this variety; it is perhaps the worst form of calculus. It is exceedingly hard; the layers are thick and imperfectly crystalline. Before the blowpipe the oxalate of lime burns to a carbonate by a moderate red-heat, and, when the flame is strongly urged, to quicklime. It is soluble in moderately-strong hydrochloric acid by heat, and very easily in nitric acid. When finely powdered and long boiled in a solution of carbonate of potassa, oxalate of potassa may be discovered in the filtered liquid, when carefully neutralized by nitric acid, by white precipitates with solutions of lime, lead, and silver. A sediment of oxalate of lime in very minute, transparent, octahedral crystals, only to be seen by the microscope, is of common occurrence in urine, in which a tendency to deposits of urates exists.

5. *Cystic and Xanthic Oxides* have already been described; they are very rare, especially the latter. Calculi of cystic oxide are very crystalline, and often present a waxy appearance externally; sediments of cystic oxide are sometimes met with. As before mentioned, this substance is a definite crystallizable organic principle, containing sul-

phur to a large amount ; it is soluble both in acids and alkalis. When the solution in nitric acid is evaporated to dryness, it blackens ; when dissolved in a large quantity of caustic potassa, a drop of solution of acetate of lead added, and the whole boiled, a black precipitate containing sulphide of lead makes its appearance. By these characters cystic oxide is easily recognized.

Xanthic oxide, also a definite organic principle, is distinguished by the peculiar deep-yellow colour produced when its solution in nitric acid is evaporated to dryness ; it is soluble in alkalis, but not in hydrochloric acid.

Very many calculi are of a composite nature, the composition of the different layers being occasionally changed, or alternating : thus, urate of ammonia and oxalate of lime are not unfrequently associated in the same stone.

NERVOUS SUBSTANCE ; ELASTIC TISSUE ; BONES.

NERVOUS SUBSTANCE.—The brain and nerves contain from 7 to 9 per cent. of an albuminous substance, also several remarkable fatty principles, constituting from 5 to 14 per cent., capable of being extracted by alcohol and ether, some of which are yet very imperfectly known, and from 75 to 80 per cent. of water. According to Frémy, if the nervous substance be boiled with alcohol, elain, cholesterin, oleic and margaric acids are extracted, partly combined with soda, potassa, or lime ; if then the residuc be treated with boiling ether, cholesterin, cerebrie acid, and oleo-phosphoric acid are dissolved. These acids are also in combination with soda and lime. The first is solid, white, and crystalline, soluble without difficulty in boiling alcohol and ether, and forming with hot water a soft gelatinous mass. It melts when heated, and decomposes almost immediately afterwards, exhaling a peculiar odour, and leaving a quantity of charcoal which contains free phosphoric acid, and is in consequence very difficult to burn. It combines with the alkalis, but forms insoluble compounds. Cerebrie acid contains in 100 parts :—

Carbon	66·7
Hydrogen	10·6
Nitrogen	2·3
Oxygen	19·5
Phosphorus	0·9

100·0

The oleo-phosphoric acid has been even less perfectly studied than the preceding substance. It is of soft oily consistence, soluble in hot alcohol and ether, and saponifiable. When boiled with water, it is resolved into a fluid neutral oil, called *cerebrolein*, and phosphoric acid, which dissolves. Frémy gives about 2 per cent. of phosphoric acid.

The oily matter of the brain is sufficient in quantity to form with the albuminous portion a kind of emulsion, which, when beaten up, remains long suspended in water.

ELASTIC TISSUE; SKIN.—The skin and tendons contain a substance which resists the action of boiling water even for 60 hours. It is insoluble in cold concentrated acetic acid, and in tolerably concentrated caustic potassa. By long-continued boiling in acetic acid it is gradually dissolved; it is more easily so in hydrochloric acid. Tilanus found in the ligamentum nuchæ, carbon 55·75, hydrogen 7·41, nitrogen 17·74.

The principle of tanning, of such great practical value, is easily explained. When the skin of an animal, carefully deprived of hair, fat, and other impurities, is immersed in a dilute solution of tannic acid, the cellular and elastic tissues gradually combine with that substance as it penetrates inwards, forming a perfectly insoluble compound, which resists putrefaction completely: this is leather. In practice, lime-water is used for cleansing and preparing the skin, and an infusion of oak-bark or sometimes catechu, or other astringent matter, for the source of tannic acid. The process itself is necessarily a slow one, as dilute solutions only can be safely used. Of late years, however, various contrivances, some of which show great ingenuity, have been adopted, with more or less success, for quickening the operation. All leather is not tanned: glove leather is dressed with alum and common salt, and afterwards treated with a preparation of the yolks of eggs, which contain an albuminous matter and a yellow oil. Leather of this kind still yields a size by the action of boiling water.

BONES.—Bones are constructed of a dense cellular tissue of membranous matter, made stiff and rigid by insoluble earthy salts, of which phosphate of lime ($3\text{CaO}, \text{PO}_5$) is the most abundant. The proportions of earthy and animal matter vary very much with the kind of bone and with the age of the individual, as will be seen in the following table, in which the corresponding bones of an adult and of a still-born child are compared:—

	ADULT.		CHILD.	
	Inorganic matter.	Organic matter.	Inorganic matter.	Organic matter.
Femur . .	62·49	37·51	57·51	42·49
Humerus . .	63·02	36·98	58·08	41·92
Radius . .	60·51	39·49	56·50	43·50
Os temporum .	63·50	36·50	55·90	44·10
Costa . .	57·49	42·51	53·75	46·25

The bones of the adult being constantly richer in earthy salts than those of the infant.

The following complete comparative analysis of human and ox bones is due to Berzelius:—

	Human bones.	Ox bones.
Animal matter soluble by boiling	32·17 }	33·30
Vascular substance . . .	1·13 }	
Phosphate of lime, with a little } fluoride of calcium . . . }	53·04	57·35
Carbonate of lime . . .	11·30	3·85
Phosphate of magnesia . . .	1·16	2·05
Soda, and a little common salt	1·20	3·45
	<hr/> 100·00	<hr/> 100·00

The teeth have a very similar composition, but contain less animal matter; their texture is much more solid and compact. The enamel does not contain more than 2 or 3 per cent. of animal matter.

ON THE FUNCTION OF NUTRITION IN THE ANIMAL AND VEGETABLE KINGDOMS.

The constant and unceasing waste of the animal body in the process of respiration, and in the various secondary changes therewith connected, necessitates an equally constant repair and renewal of the whole frame by the deposition or organization of matter from the blood, which is thus gradually impoverished. To supply this deficiency of solid material in the circulating fluid is the office of the food. The striking contrast which at first appears in the nature of the food of the two great classes of animals, the vegetable feeders and the carnivorous races, diminishes greatly on close examination: it will be seen that, so far as the materials of blood, or, in other words, those devoted to the repair and sustenance of the body itself, are concerned, the process is the same. In a flesh-eating animal great simplicity is observed in the construction of the digestive organs; the stomach is a mere enlargement of the short and simple alimentary canal; and the reason is plain: the food of the creature, flesh, is absolutely identical in composition with its own blood, and with the body that blood is destined to nourish. In the stomach it undergoes mere solution, being brought into a state fitted for absorption by the lacteal vessels, by which it is nearly all taken up, and at once conveyed into the blood; the excrements of such animals are little more than the comminuted bones, feathers, hair, and other matters which refuse to dissolve in the stomach. The same condition, that the food employed for the nourishment of the body must have the same or nearly the same chemical composition as the body itself, is really fulfilled in the case of animals that live exclusively on vegetable substances. It has been shown* that certain of the azotized principles of plants, which often abound, and are never altogether absent, have a chemical composition and assemblage of properties which assimilate them in the closest manner, and it is believed even identify them, with the azo-

* Liebig, *Ann. der Chem. und Pharm.* xxxix. 129.

tized principles of the animal body: vegetable albumin, fibrin, and casein are scarcely to be distinguished from the bodies of the same name extracted from blood and milk.

If a portion of wheaten flour be made into a paste with water, and cautiously washed on a fine metallic sieve, or in a cloth, a greyish, adhesive, elastic, insoluble substance will be left, called *gluten* or *glutin*, and a milky liquid will pass through, which by a few hours' rest becomes clear by depositing a quantity of starch. If now this liquid be boiled, it becomes again turbid from the production of a flocculent precipitate, which, when collected, washed, dried, and purified from fat by boiling with ether, is found to have the same composition as animal albumin. The gluten itself is a mixture of true vegetable fibrin and a small quantity of a peculiar azotized matter called *gliadin*, to which its adhesive properties are due. The gliadin may be extracted by boiling alcohol, together with a thick, fluid oil, which is separable by ether; it is gluey and adhesive, quite insoluble in water, and, when dry, hard and translucent like horn; it dissolves readily in dilute caustic alkali, and also in acetic acid. The fibrin of other grain is unaccompanied by gliadin; barley and oatmeal yield no gluten, but incoherent filaments of nearly pure fibrin.

Vegetable albumin in a soluble state abounds in the juice of many soft succulent plants used for food; it may be extracted from potatoes by macerating the sliced tubers in cold water containing a little sulphuric acid. It coagulates when heated to a temperature dependent upon the degree of concentration, and cannot be distinguished when in this state from boiled white of egg in a divided condition.

Almonds, peas, beans, and many of the oily seeds, contain a principle which bears the most striking resemblance to the casein of milk. When a solution of this substance is heated, no coagulation occurs, but a skin forms on the surface, just as with boiled milk. It is coagulable by alcohol, and by acetic acid; the last being a character of importance. Such a solution, mixed with a little sugar—an emulsion of sweet almonds, for instance—left to itself, soon becomes sour and curdy, and exhales an offensive smell; it is then found to contain lactic acid.

All these substances dissolve in caustic potassa, with production of a small quantity of alkaline sulphide; the filtered solutions mixed with excess of acid give precipitates of protein.

The following is the composition in 100 parts of vegetable albumin and fibrin: it will be seen that they agree very closely with the results before given:—

	Albumin.	Fibrin.
Carbon	55.01	54.60
Hydrogen	7.23	7.30
Nitrogen	15.92	15.81
Oxygen, sulphur, and phosphorus	21.84	22.29
	<hr/> 100.00	<hr/> 100.00

The composition of vegetable casein, or *legumin*, has not been so well made out: so much discrepancy appears in the analyses as to lead to the supposition that different substances have been operated upon.

The great bulk, however, of the solid portion of the food of the herbivora consists of bodies which do not contain nitrogen, and therefore cannot yield sustenance in the manner described: some of these, as vegetable fibre or lignin, and waxy matter, pass unaltered through the alimentary canal; others, as starch, sugar, gum, and perhaps vegetable fat, are absorbed into the system, and afterwards disappear entirely: they are supposed to contribute very largely to the production of animal heat.

On these principles, Professor Liebig* has very ingeniously made the distinction between what he terms *plastic elements of nutrition* and *elements of respiration*; to the former class belong

Vegetable fibrin,
Vegetable albumin,
Vegetable casein,
Animal flesh,
Blood.

To the latter,

Fat,		Grape-sugar,
Starch,		Milk sugar,
Gum,		Pectin,
Cane-sugar,		Alcohol?

In a flesh-eating animal, the waste of the tissues is very rapid, the temperature being, as it were, kept up in great measure by the burning of azotized matter; in a vegetable feeder it is probably not so great, the non-azotized substances being consumed in the blood in place of the organic fabric.

When the muscular movements of a healthy animal are restrained, a genial temperature kept up, and an ample supply of food containing much amylaceous or oily matter given, an accumulation of fat in the system rapidly takes place: this is well seen in the case of stall-fed cattle. On the other hand, when food is deficient, and much exercise is taken, emaciation results. These effects are ascribed to differences in the activity of the respiratory function: in the first instance, the heat-food is supplied faster than it is consumed, and hence accumulates in the form of fat; in the second, the conditions are reversed, and the creature is kept in a state of leanness by its rapid consumption. The fat of an animal appears to be a provision of nature for the maintenance of life during a certain period under circumstances of privation.

The origin of fat in the animal body has at one time been made

* Animal Chemistry, p. 96.

the subject of much animated discussion. On the one hand it was contended that satisfactory evidence exists of the conversion of starch and saccharine substances into fat, by separation of carbon and oxygen, the change somewhat resembling that of vinous fermentation: it was argued on the other side, that oily or fatty matter is invariably present in the food supplied to the domestic animals, and that this fat is merely absorbed and deposited in the body in a slightly-modified state. The question has now been decided in favour of the first of these views, which was enunciated by Professor Liebig, by the very chemist who formerly advocated the second opinion. By a series of very beautiful experiments, MM. Dumas and Milne Edwards proved that bees exclusively feeding upon sugar were still capable of producing wax, which was pointed out as a veritable fact.

It is not known in what manner *digestion*, the reduction in the stomach of the food to a nearly fluid condition, is performed. The natural secretion of that organ, the *gastric juice*, is said to contain a very notable quantity of free hydrochloric acid. Dilute hydrochloric acid, aided by a temperature of 98° ($36^{\circ}\cdot6\text{C}$) or 100° ($37^{\circ}\cdot7\text{C}$), dissolves coagulated albumin, fibrin, &c.; but many hours are required for that purpose. The gastric secretion has been supposed to contain a peculiar organic principle called *pepsin*, said to have been isolated, to which this power of dissolving albuminous substances in conjunction with the hydrochloric acid is attributed. In the saliva a peculiar organic principle exists, which causes the conversion of starch into sugar. If starch is held in the mouth even for two minutes, this change is found to occur. The active cause of this change has been looked on as a kind of animal diastase. The fluid which is obtained from the pancreas has also the same action, but to a greater degree. Neither the bile, the gastric juice, nor free acid, prevent the transformation of the starch into sugar.

The food of animals, or rather that portion of the food which is destined to the repair and renewal of the frame itself, is thus seen to consist of substances identical in composition with the body it is to nourish, or requiring but little chemical change to become so.

The chemical phenomena observed in the animal system resemble so far those produced out of the body by artificial means, that they are all, or nearly all, so far as is known, changes in a descending series. Albumin and fibrin are probably more complex compounds than gelatin or the membrane which furnishes it: this, in turn, has a far greater complexity of constitution than urea, the regular form in which rejected azotized matter is conveyed out of the body. The animal lives by the assimilation into its own substance of the most complex and elaborate products of the organic kingdom;—products which are, and, apparently, can only be, formed under the influence of vegetable life.

The existence of the plant is maintained in a manner strikingly dissimilar:—the food supplied to vegetables is *wholly inorganic*; the

carbonic acid and nitrogen of the atmosphere, the water which falls as rain, or is deposited as dew; the minute trace of ammoniacal vapour present in the air; the alkali and saline matter extracted from the soil;—such are the substances which yield to plants the elements of their growth. That green healthy vegetables do possess, under circumstances to be mentioned immediately, the property of decomposing carbonic acid absorbed by their leaves from the air, or conveyed thither in solution through the medium of their roots, is a fact positively proved by direct experiment, and rendered certain by considerations of a very stringent kind. To effect this very remarkable decomposition, the influence of light is indispensable; the diffuse light of day suffices in some degree, but the direct rays of the sun greatly exalt the activity of the process. The carbon separated in this manner is retained in the plant in union with the elements of water, with which nitrogen is also sometimes associated, while the oxygen is thrown off into the air from the leaves in a pure and gaseous condition.

The effect of ammoniacal salts upon the growth of plants is so remarkable, as to leave little room for doubt concerning the peculiar function of the ammonia recently discovered in the air. Plants which in their cultivated state contain, and consequently require, a large supply of nitrogen, as wheat, and the cereals in general, are found to be greatly benefited by the application to the land of such substances as putrefied urine, which may be looked upon as a solution of carbonate of ammonia, the *guano** of the South Seas, which usually contains a large proportion of ammoniacal salt, and even of a pure sulphate of ammonia. Some of these manures doubtless owe a part of their value to the phosphates and alkaline salts they contain; still, the chief effect is certainly due to the ammonia.

Upon the members of the vegetable kingdom thus devolves the duty of building up, as it were, out of the inorganic constituents of the atmosphere,—the carbonic acid, the water, and the ammonia,—the numerous complicated organic principles of the perfect plant, many of which are afterwards destined to become the food of animals, and of man. The chemistry of vegetable life is of a very high and mysterious order, and the glimpses occasionally obtained of its general nature are few and rare. One thing, however, is manifest, namely, the wonder-

* Guano is the partially decomposed dung of birds, found in immense quantities on some of the barren islets of the western coast of South America, as that of Peru. More recently, similar deposits have been found on the coast of Southern Africa. The guano now imported into England from these localities is usually a soft, brown powder, of various shades of colour. White specks of bone-earth, and sometimes masses of saline matter, may be found in it. That which is most recent, and probably most valuable as manure, often contains undecomposed uric acid, besides much oxalate or hydrochlorate of ammonia, and alkaline phosphates, and other salts: it has a most offensive odour. The specimens taken from older deposits have but little smell, are darker in colour, contain no uric acid, and much less ammoniacal salt; the chief components are bone-earth, a peculiar dark-coloured organic matter, and soluble inorganic salts. See also p. 546.

ful relations between the two orders of organized beings, in virtue of which the rejected and refuse matter of the one is made to constitute the essential and indispensable food of the other. While the animal lives, it exhales incessantly from its lungs, and often from its skin, carbonic acid ; when it dies, the soft parts of its body undergo a series of chemical changes of *degradation*, which terminate in the production of carbonic acid, water, carbonate of ammonia, and, perhaps, other products in small quantity. These are taken up by a fresh generation of plants, which may in their turn serve for food to another race of animals.

SECTION IX.

ON CERTAIN PRODUCTS OF THE DESTRUCTIVE DISTILLATION
AND SLOW PUTREFACTIVE CHANGE OF ORGANIC MATTER.

SUBSTANCES OBTAINED FROM TAR.

THERE are three principal varieties of tar:—(1.) *Tar of the wood-vinegar maker*, procured by the destructive distillation of dry hard wood; (2.) *Stockholm tar*, so largely consumed in the arts, as in ship-building, &c., which is obtained by exposing to a kind of rude *distillatio per descensum* the roots and useless parts of resinous pine and fir-timber; and, lastly, (3.) *Coal or mineral tar*, a by-product in the manufacture of coal-gas. This is viscid, black, and ammoniacal.

All these tars yield by distillation, alone or with water, oily liquids of extremely complicated nature, from which a number of curious products, to be presently described, have been procured; the solid brown or black residue constitutes pitch. Hard-wood tar furnishes the following:—

PARAFFIN; TAR-OIL STEARIN.—This remarkable substance is found in that part of the wood-oil which is heavier than water; it is extracted by re-distilling the oil in a retort, collecting apart the last portions, gradually adding a quantity of alcohol, and exposing the whole to a low temperature. Thus obtained, paraffin appears in the shape of small, colourless needles, fusible at 110° ($43^{\circ}\cdot3\text{C}$) to a clear liquid, which on solidifying becomes glassy and transparent. It is tasteless and inodorous; volatile without decomposition; and burns, when strongly heated, with a luminous yet smoky flame. It is quite insoluble in water, slightly soluble in alcohol, freely in ether, and miscible in all proportions, when melted, with both fixed and volatile oils. The most energetic chemical reagents, as strong acids, alkalis, chlorine, &c., fail to exert any action on this substance; it is not known to combine in a definite manner with any other body, whence its extraordinary name, from *parum affinis*.

Paraffin contains carbon and hydrogen only, and in the same proportions as in olefant gas, or CH . M. Lewy, of Copenhagen, makes it $\text{C}_{20}\text{H}_{21}$. The rational formula is unknown.

EUPIONE.*—This is the chief component of the light oil of wood-tar; it occurs also in the tar of animal matters, and in the fluid product

* From εὔ, good, beautiful, and πῖον, fat.

of the distillation of rape-seed oil. Its separation is effected by the agency of concentrated sulphuric acid, or of a mixture of sulphuric acid and nitre, which oxidizes and destroys most of the accompanying substances. In a pure state, it is an exceedingly thin, colourless liquid, of agreeable aromatic odour, but destitute of taste: it is the lightest known liquid, having a density of 0.655. At 116° ($46^{\circ}.6\text{C}$) it boils and distils unchanged. Dropped upon paper, it makes a greasy stain, which after a time disappears. Eupione is very inflammable, and burns with a bright luminous flame. In water it is quite insoluble, in rectified spirit nearly so, but with ether and oils freely miscible.

Eupione is a hydrocarbon; according to M. Hess it consists of C_5H_6 . It is very probable that eupione frequently contains and sometimes entirely consists of hydride of amyl (see page 474).

Other volatile oils, having a similar origin, and perhaps a similar composition, but differing from the above in specific gravity and boiling-point, are sometimes confounded with eupione. The study of these substances presents many serious difficulties. It is even doubtful whether the eupione be not *formed* by the energetic chemical agents employed in its supposed purification; and this remark applies with even greater force to the next three or four tar-products to be noticed.

PICAMAR.*—A component of the heavy oil of wood; it is a viscid, colourless, oily liquid, of feeble odour, but intensely-bitter taste. Its density is 1.095, and it boils at 518° (270°C). It is insoluble in water, but dissolves in all proportions in alcohol, ether, and the oils. The most characteristic property of picamar is that of forming with the alkalis and ammonia crystalline compounds, which, although decomposed by water, are soluble without change in spirit. The composition of this substance is unknown.

KAPNOMOR.†—Such is the name given by Dr. Reichenbach to another oily liquid obtained from the same source as the last, by a long and complex process, in which strong solutions of caustic potassa are freely used. It is described as a colourless volatile oil, of high boiling-point, and rather lighter than water; it has an odour of ginger, and a taste feeble at first, but afterwards becoming connected with an insupportable sense of suffocation. Water refuses to dissolve it; alcohol and ether take it up easily; and oil of vitriol combines with it, giving rise to a complex acid, the potassa-salt of which is crystallizable. Its composition is unknown.

CEDRIRET.‡—The lighter oil of hard-wood tar contains a substance, separable from the eupione, &c., by caustic alkalis, which in contact with oxidizing agents, as sulphate of sesquioxide of iron, chromic acid, or even atmospheric air, yields a mass of small, red,

* From *pix*, and *amarus*, in allusion to its bitter taste.

† From *καπνός*, smoke, *μοίρα*, part.

‡ From *cedrium*, the old name for acid tar-water, and *rete*, a net.

reticulated crystals, infusible by heat, and soluble in concentrated sulphuric acid with deep indigo-blue colour. This substance is insoluble in water, alcohol, and ether; nothing is known respecting its composition.

KREOSOTE.*—This is by far the most important and interesting body of the group. Its discovery is due to Dr. Reichenbach: it is the principle to which wood-smoke owes its power of curing and preserving salted meat and other provisions. Kreosote is most abundantly contained in the heavy oil of beech-tar, as procured from the wood-vinegar maker, and is thence extracted by a most tedious and complicated series of operations; it certainly pre-exists, however, in the original material. The tar is distilled in a metallic vessel, and the different products are collected apart; the most volatile portion, which is lighter than water, and consists chiefly of eupione, is rejected; the second portion is denser, and contains the kreosote, and is set aside; the distillation is stopped when paraffin begins to pass over in quantity. The impure kreosote is first agitated with carbonate of potassa to remove adhering acid, separated and re-distilled, the first part being again rejected; it is next strongly shaken with a solution of phosphoric acid, and again distilled: a quantity of ammonia is thus separated. Afterwards, it is dissolved in a solution of caustic potassa of specific gravity 1.12, and decanted from the insoluble oil which floats on the surface: this alkaline liquid is boiled, and left some time in contact with air, by which it acquires a brown colour, from the oxidation of some yet unknown substance present in the crude product. The compound of kreosote and alkali is next decomposed by sulphuric acid; the separated kreosote is again dissolved in caustic potassa, boiled in the air, and the solution decomposed by acid; and this treatment repeated until the product ceases to become coloured by the joint influence of oxygen and the alkaline base. When so far purified, it is well washed with water, and distilled. The first portion contains water; that which succeeds is pure kreosote.

In this condition kreosote is a colourless, somewhat viscid oily liquid, of great refractive and dispersive power. It is quite neutral to test-paper; it has a penetrating and most peculiar odour, that, namely, of smoked meat, and a pungent and almost insupportable taste when placed in a very small quantity upon the tongue. The density of this substance is 1.037, and its boiling-point 397° (202° ·8C). It inflames with difficulty, and then burns with a smoky light. When quite pure, it is unalterable by exposure to the air: much of the kreosote of commerce becomes, however, under these circumstances, gradually brown. 100 parts of cold water take up about $1\frac{1}{4}$ parts of kreosote; at a high temperature rather more is dissolved, and the hot solution abandons a portion on cooling. The kreosote itself absorbs water also to a considerable extent. In acetic acid it dissolves in much larger quantity.

* Derived from κρέας, flesh, and σώζω, I preserve.

Alcohol and ether mix with kreosote in all proportions. Concentrated sulphuric acid, by the aid of heat, blackens and destroys it. Caustic potassa dissolves kreosote with great facility, and forms with it a definite compound, which crystallizes in brilliant pearly scales.

Kreosote consists of carbon, hydrogen, and oxygen, but its exact composition is yet uncertain. The formula $C_{14}H_8O_2$ has been given.

The most remarkable and characteristic feature of the compound in question is its extraordinary antiseptic power. A piece of animal flesh steeped in a very dilute solution of kreosote dries up to a mummy-like substance, but absolutely refuses to putrefy. The well-known efficacy of impure wood vinegar in preserving provisions is with justice attributed to the kreosote it contains; and the effect of mere wood-smoke is also thus explained. In a pure state, kreosote is sometimes employed by the dentist for relieving toothache, arising from putrefactive decay in the substance of the tooth.

CHRYSEN AND PYREN.—M. Laurent extracted from pitch, by distillation at a high temperature, two new solid bodies to which he gave the preceding names; they condense together, with a quantity of oily matter, partly in the neck of the retort, and partly in the receiver, and are separated by the aid of ether. *Chrysen*, so called from its golden colour, is a pure yellow crystalline powder, which fuses by heat, and sublimes without much decomposition. It is insoluble in water and alcohol, and nearly insoluble in ether: warm oil of vitriol dissolves it, with the development of a beautiful deep-green colour. Boiling nitric acid converts it into an insoluble red substance, which has not been studied. *Chrysen* is composed of C_3H .

Pyren differs from the preceding substance in being colourless, crystallizing in small, soft, micaceous scales, soluble in boiling alcohol and ether. It is fusible and volatile. *Pyren* contains C_5H_2 .

Oil of ordinary tar, obtained by distillation alone, or with water, consists in great measure of unaltered oil of turpentin, mixed, however, with empyreumatic oily products, which give it a powerful odour and a dark colour. The residual pitch contains much pine-resin, and thus differs from the solid portion of the hard wood-tar so frequently mentioned.

Volatile Principles of Coal-Tar.

Coal-tar yields on distillation a large quantity of thin, dark-coloured, volatile oil, which, when agitated with dilute sulphuric acid to remove ammonia, and twice rectified with water, becomes nearly colourless: it is very volatile, lighter than water, very inflammable, and possesses in a high degree the property of dissolving caoutchouc, on which account it is very extensively used in the manufacture of water-proof fabrics containing that material.

This coal-oil is a mixture of a great variety of liquids and solids dis-

solved in the oil. By the action of acids and alkalis, this mixture may be conveniently divided into three separate groups. (1) A group of basic compounds soluble in acids; (2) an acid portion soluble in alkalis; and (3) a group of neutral constituents.

The basic constituents form but a small part of coal-tar oil. They are extracted by agitating successively large quantities of the oil with hydrochloric acid, and afterwards distilling the acid watery liquid obtained with excess of hydrate of lime. The bases thus obtained consist chiefly of picoline (see page 574), aniline (see page 566), and leucoline (see page 574), and are separated by distillation; these three compounds boiling at very different temperatures.

The acid portion of coal-tar oil consists essentially of carbolic acid or phenol.

CARBOLIC ACID; PHENOL.—Common coal-tar oil is agitated with a mixture of hydrate of lime and water, the whole being left for a considerable time; the aqueous liquid is then separated from the undissolved oil, decomposed by hydrochloric acid, and the oily product obtained purified by cautious distillation, the first third only being collected. Or crude coal-oil is subjected to distillation in a retort furnished with a thermometer, and the portion which passes over between the temperatures of 300° — 400° (194° — 204°C) collected apart. This product is then mixed with a hot strong solution of caustic potassa, and left to stand; a whitish, somewhat crystalline, pasty mass is obtained, which by the action of water is resolved into a light oily liquid and a dense alkaline solution. The latter is withdrawn by a siphon, decomposed by hydrochloric acid, and the separated oil purified by contact with chloride of calcium and re-distillation. Lastly, it is exposed to a low temperature, and the crystals formed drained from the mother-liquor and carefully preserved from the air.


Pure carbolic acid forms long colourless prismatic needles, which melt at 95° (35°C) to an oily liquid, boiling at 370° (180°C), and greatly resembling kreosote* in many particulars, having a very penetrating odour and burning taste, and attacking the skin of the lips. Its sp. gr. is 1.065. It is slightly soluble in water, freely in alcohol and ether, and has no acid reaction to test-paper. The crystals absorb moisture with avidity, and liquefy. It coagulates albumin. Sulphur and iodine dissolve in it; nitric acid, chlorine, and bromine attack it with energy. Carbolic acid contains $\text{C}_{12}\text{H}_5\text{O}, \text{HO}$.

In its chemical deportment carbolic acid stands very near the alcohols; a fact to which allusion has been made already in former sections (see pages 492 and 498): we may assume in it a compound radical, *phenyl*, $\text{C}_{12}\text{H}_5 = \text{Pyl}$, analogous to ethyl, when carbolic acid becomes PylO, HO , or hydrated oxide of phenyl.

* A great deal of the kreosote which occurs in commerce is, in fact, nothing but more or less pure carbolic acid.

With sulphuric acid hydrate of oxide of phenyl forms the compound acid, *sulphophenic acid*, $C_{12}H_5O, 2SO_3, HO = PylO, 2SO_3, HO$, which assumes a syrupy state in the dry vacuum. This acid closely corresponds to sulphovinic acid (see page 432). The baryta-salt crystallizes from alcohol in minute needles.

Phenyl-alcohol dissolves potassium with evolution of hydrogen, a compound $C_{12}H_5O, KO$ being produced, which is analogous to the substance formed in a similar manner from common alcohol (see page 417). On heating this potassa-compound with iodide of methyl, ethyl, or amyl, a series of double ethers are produced represented by the following formulæ:—



These substances, also described by the names *anisol* (because it is likewise produced by the distillation of anisic acid) (see page 609), *phenetol* and *phenamylol*, are evidently analogous to the compounds of oxide of methyl with those of ethyl and amyl, which have been mentioned in pages 464 and 473.

A *chloride of phenyl*, $C_{12}H_5Cl = PylCl$, has been produced by the action of pentachloride of phosphorus upon hydrated oxide of phenyl. This compound, however, which is a heavy oil, is but very imperfectly known.

Cyanide of phenyl, $C_{14}H_5N = C_{12}H_5C_2N = PylCy$, has not yet been produced from phenyl-alcohol directly. The substance, however, which has been described under the name of benzonitrile (page 491), is both by composition and deportment *cyanide of phenyl*, perfectly analogous to cyanide of ethyl (see page 426). Boiled with potassa it is converted into ammouia and benzoic acid, cyanide of ethyl furnishing ammonia and propionic acid. Starting from this decomposition, benzoic acid may be viewed as *phenyl-oxalic acid*, $C_{14}H_5O_3, HO = C_{12}H_5, C_2O_3, HO$, just as propionic acid may be regarded as ethyl-oxalic acid (see page 477).

Hydrated oxide of phenyl when treated with chloride of benzoyl (see page 488) yields hydrochloric acid and a white fusible crystalline compound which is *benzoate of phenyl*, $C_{12}H_5O, C_{14}H_5O_3 = PylO, BzO$, analogous to benzoate of ethyl. When heated with ammonia, phenyl-alcohol yields *aniline*, $C_{12}H_7N = C_{12}H_5H_2N = PylH_2N$ (*phenylamine*), the ethylamine of the phenyl-series (see page 566).

The following table gives a synopsis of the phenyl-compounds, which have been placed in juxtaposition with the corresponding terms of the ethyl-series:—

Phenyl-alcohol	PyIO,HO	AeO,HO	Ethyl-alcohol
Oxide of phenyl-potassa	PyIO,KO	AeO,KO	Oxide of ethyl-potassa
Sulphophenic acid . . .	PyIO,2SO ₃ ,HO	AeO,2SO ₃ ,HO	Sulphovinic acid
		AeO	Oxide of ethyl
Chloride of phenyl . . .	PyICl(?)	AeCl	Chloride of ethyl
Cyanide of phenyl (benzonitrile)	PyICy	AeCy	{ Cyanide of ethyl (propio-nitrile)
Benzoate of phenyl . . .	PyIO,PyIC ₂ O ₃	AeO,Ae,C ₂ O ₃	Propionate of ethyl
Phenyl-amine (aniline) . . .	NH ₂ PyI	NH ₂ Ae	Ethylamine
Phenyl-urea	C ₂ (H ₃ PyI)NO ₂	C ₂ (H ₃ Ae)NO ₂	Ethyl-urea.

Chlorophenismic acid.—This is the characteristic and principal product of the action of chlorine on hydrate of oxide of phenyl. The pure substance is not necessary for the preparation of this body, those portions of crude coal-oil which boil between 360°—400° (182°·2—204°·5C) answering very well. The oil is saturated with chlorine, and distilled in the open air, the first and last portions being rejected; the product is again treated with chlorine until the whole solidifies. The crystals are drained and dissolved in hot dilute solution of ammonia; on cooling, the sparingly soluble chloropheniscate of ammonia crystallizes out. This is dissolved in pure water, decomposed by hydrochloric acid, washed, and, lastly, distilled.

Chlorophenismic acid forms exceedingly fine, colourless, silky needles, which melt when gently heated; it has a very penetrating, persistent, and characteristic odour, is very sparingly soluble in water, but dissolves freely in alcohol, ether, and hot concentrated sulphuric acid. It slowly sublimates at common temperatures, and distils with ebullition when strongly heated. Chlorophenismic acid forms well-defined salts, and contains C₁₂(H₂Cl₃)O,HO. By the action of a great excess of chlorine an analogous acid richer in chlorine is formed. It is called *chlorophenismic acid*, and contains C₁₂Cl₅O,HO. *Bromophenismic acid* is prepared by analogous means, and possesses a constitution and character greatly resembling those of the chlorine-compound.

Nitrophenismic acid.—On distilling phenyl-alcohol with very dilute nitric acid, beautiful yellow needles are obtained, soluble in ammonia and potassa, and yielding a beautiful red silver-salt. This substance is *nitrophenismic acid*, C₁₂H₄NO₅,HO=C₁₂(H₄NO₄)O,HO. *Nitrophenismic and nitrophenismic acids* may be prepared directly from the oil which is employed in the preparation of chlorophenismic acid. The oil is carefully mixed in a large open vessel with rather

more than its own weight of ordinary nitric acid. The action is very violent. The brownish-red substance produced is slightly washed with water, then boiled with dilute ammonia, and filtered hot. A brown mass remains on the filter, which is preserved to prepare nitrophenisic acid, and the solution deposits on cooling a very impure ammoniacal salt of nitrophenisic acid, which requires several successive crystallizations, after which it is decomposed by nitric acid and the product crystallized from alcohol.

Nitrophenisic acid forms blonde-coloured prismatic crystals, very sparingly soluble even in boiling water, but freely soluble in alcohol. It has no odour. Its taste, at first feeble, becomes after a short time very bitter. At 219° (104°C) it melts, and on cooling crystallizes. In very small quantity it may be distilled without decomposition, but when briskly heated it often detonates, but not violently. The salts of this acid are yellow or orange and very beautiful; they are mostly soluble in water, and detonate feebly when heated. The acid contains $\text{C}_{12}\text{H}_3\text{N}_2\text{O}_9$, $\text{HO}=\text{C}_{12}\text{H}_3(\text{NO}_4)_2\text{O}, \text{HO}$. Nitrophenisic acid is identical with picric or carbazotic acid (see page 585). It may be prepared with great economy from impure nitrophenisic acid, or from the brown mass insoluble in dilute ammonia already referred to. It is purified by a process similar to that employed in the case of the preceding substances. Nitrophenisic acid contains $\text{C}_{12}\text{H}_2\text{N}_3\text{O}_{13}$, $\text{HO}=\text{C}_{12}\text{H}_2(\text{NO}_4)_3\text{O}, \text{HO}$.*

The following table exhibits the relation of these substitution-products:—

Phenyl-alcohol	C_{12}H_5	$\text{O}, \text{HO} = \text{Phenol}$.
Chlorophenisic acid	$\text{C}_{12}(\text{H}_2\text{Cl}_2)$	$\text{O}, \text{HO} = \text{Trichlorophenol}$
Nitrophenasic acid	$\text{C}_{12}(\text{H}_4\text{NO}_4)$	$\text{O}, \text{HO} = \text{Nitrophenol}$
Nitrophenisic acid	$\text{C}_{13}(\text{H}_3[\text{NO}_4]_2)$	$\text{O}, \text{HO} = \text{Binitrophenol}$
Nitrophenisic acid	$\text{C}_{12}(\text{H}_2[\text{NO}_4]_3)$	$\text{O}, \text{HO} = \text{Trinitrophenol}$.

The neutral portion of coal-tar naphtha, consists of a great variety of hydrocarbons, partly liquid, partly solid. The liquid hydrocarbons have been already described (see pages 486 and 494). They are chiefly *benzol*, *toluol*, *xylol*, *cumol*, and *cymol*.† The solid hydrocarbons are *naphthalin* and *paranaphthalin*, together with several similar substances less perfectly known.

NAPHTHALIN.—When, in the distillation of coal-tar, the last portion of the volatile oily product is collected apart and left to stand, a quantity of solid, crystalline matter separates, which is principally composed of the substance in question. An additional quantity may be obtained by pushing the distillation until the contents of the vessel

* Ann. Chim. et Phys. 3rd series, iii. 195.

† The same hydrocarbons have been lately found by M. Cahours in the oily liquid precipitated by water from commercial wood-spirit (see page 472).

begin to char; the naphthalin then condenses in the solid state, but dark-coloured and very impure. By simple sublimation, once or twice repeated, it is obtained perfectly white. In this state naphthalin forms large, colourless, transparent, brilliant, crystalline plates, exhaling a faint and peculiar odour, which has been compared to that of the narcissus. Naphthalin melts at 176° (80°C) to a clear, colourless liquid, which crystallizes on cooling; it boils at 413° ($211^{\circ}\cdot6\text{C}$), and evolves a vapour whose density is $4\cdot528$. When strongly heated in the air, it inflames and burns with a red and very smoky light. It is insoluble in cold water, but soluble to a slight degree at the boiling temperature; alcohol and ether dissolve it easily; a hot saturated alcoholic solution deposits fine iridescent crystals on cooling.

Naphthalin is found by analysis to contain C_{10}H_8 or $\text{C}_{20}\text{H}_{16}$.

Naphthalin dissolves in warm concentrated sulphuric acid, forming a red liquid, which, when diluted with water, and saturated with carbonate of baryta, yields salts of at least two distinct acids, analogous to sulphovinic acid. One of these, the *sulphonaphthalic acid* of Mr. Faraday, crystallizes from a hot aqueous solution in small white scales, which are but sparingly soluble in the cold. The free acid is obtained in the usual manner by decomposing the baryta-salt with sulphuric acid; it forms a colourless, crystalline, brittle mass, of acid, metallic taste, very deliquescent, and very soluble in water. The second baryta-salt is still less soluble than the preceding. The composition of sulphonaphthalic acid is $\text{C}_{20}\text{H}_7\text{S}_2\text{O}_5\cdot\text{HO}$.

Fuming nitric acid at a high temperature attacks naphthalin; the products are numerous, and have been attentively studied by M. Laurent. The same chemist has described a long series of curious products of the action of chlorine on naphthalin. Nitric acid gives rise to a great number of nitro-substitutes, the most interesting of which is the compound known by the name *nitronaphthalase*, which, when submitted to Zinin's process, is converted into *naphthalidine* (see page 571). Among the derivatives of naphthalin, a compound deserves to be mentioned, which has been described under the name of *phthalic acid*. This acid has not yet been produced directly from naphthalin, but may be obtained by boiling one of the products of the action of chlorine upon naphthalin, namely, the tetrachloride of naphthalin ($\text{C}_{20}\text{H}_8\text{Cl}_4$) with nitric acid. The same substance is formed by submitting alizarin to the action of nitric acid.

Phthalic acid crystallizes in yellow plates, it is but slightly soluble in cold water, but dissolves freely in alcohol and ether. Phthalic acid is bibasic, and contains $\text{C}_{16}\text{H}_4\text{O}_6\cdot 2\text{HO}$: when heated it loses 2 eq. of water, and becomes $\text{C}_{16}\text{H}_4\text{O}_6$. Treated with fuming nitric acid it yields a nitro-acid, nitro-phthalic acid, $\text{C}_{16}(\text{H}_3\text{NO}_4)\text{O}_6\cdot 2\text{HO}$. When distilled with baryta it is converted into benzol:—



accumulations of clay and sand, hereafter destined to become shale and gritstone, the organic tissue undergoes a kind of fermentation by which the bodies in question, or certain of them, are slowly produced. Carbonic acid and light carbonetted hydrogen are by-products of the reaction; hence their frequent disengagement, the first from beds of lignite, and the second from the farther advanced and more perfect coal.

The vegetable origin of coal has been placed beyond doubt by microscopic research; vegetable structure can be thus detected even in the most massive and perfect varieties of coal when cut into thin slices. In coal of inferior quality, much mixed with earthy matter, it is evident to the eye. The leaves of ferns, reeds, and other succulent plants, more or less resembling those of the tropics, are found in a compressed state between the layers of shale or slaty clay, preserved in the most beautiful manner, but entirely converted into bituminous coal. The coal-mines of Europe, and particularly those of our own country, furnish an almost complete fossil flora; a history of many of the now lost species which once decorated the surface of the earth.

In the lignites the woody structure is much more obvious. Beds of this material are found in very many of the newer strata, above the true coal, to which they are consequently posterior. As an article of fuel, brown-coal is of comparatively small value; it resembles peat, giving but little flame and emitting a disagreeable, pungent smell.

Jet, used for making black ornaments, is a variety of lignite.

The true bitumens are destitute of all organic structure: they appear to have arisen from coal or lignite by the action of subterranean heat; and very closely resemble some of the products yielded by the destructive distillation of those bodies. They are very numerous, and have yet been but imperfectly studied.

1. *Mineral pitch*, or *compact bitumen*, the *asphaltum* or *Jew's pitch* of some authors.—This substance occurs abundantly in many parts of the world; as, in the neighbourhood of the Dead Sea in Judea; in Trinidad, in the famous *pitch lake*, and elsewhere. It generally resembles in aspect common pitch, being a little heavier than water, easily melted, very inflammable, and burning with a red, smoky flame. It consists principally of a substance called by M. Boussingault *asphaltene*, composed of $C_{20}H_{16}O_3$. It is worthy of remark, that M. Laurent found paranaphthalin in a native mineral pitch.

2. *Mineral tar* seems to be essentially a solution of asphaltene in an oily fluid called *petrolene*. This has a pale yellow colour and peculiar odour; it is lighter than water, very combustible, and has a high boiling-point. It has the same composition as the oils of turpentin and lemon-peel, namely $C_{10}H_8$. Asphaltene contains, consequently, the elements of petrolene, together with a quantity of oxygen, and probably arises from the oxidation of that substance.

3. *Elastic bitumen*; *mineral caoutchouc*.—This curious substance

has only been found in three places: in a lead-mine at Castleton, in Derbyshire; at Montrelais, in France; and in the state of Massachusetts. In the two latter localities it occurs in the coal-series. It is fusible, and resembles in many respects the other bitumens.

Under the names *petroleum* and *naphtha* are arranged various mineral oils which are observed in many places to issue from the earth, often in considerable abundance. There is every reason to suppose that these owe their origin to the action of internal heat upon beds of coal, as they are usually found in connection with such. The term *naphtha* is given to the thinner and purer varieties of rock-oil, which are sometimes nearly colourless; the darker and more viscid liquids bear the name of *petroleum*.

Some of the most noted localities of these substances are the following:—The north-west side of the Caspian Sea, near Baku, where beds of marl are found saturated with naphtha. Wells are sunk to the depth of about 30 feet, in which naphtha and water collect, and are easily separated. In some parts of this district so much combustible gas or vapour rises from the ground, that when set on fire, it continues burning, and even affords heat for economical purposes. A large quantity of an impure variety of petroleum comes from the Birman territory in the East Indies: the country consists of sandy clay, resting on a series of alternate strata of sandstone and shale. Beneath these occurs a bed of pale-blue shale loaded with petroleum, which lies immediately on coal. A petroleum-spring exists at Colebrook Dale, in Shropshire. The sea near the Cape de Verd Islands has been seen covered with a film of rock-oil. The finest specimens of naphtha are furnished by Italy, where it occurs in several places.

In proof of the origin attributed to these substances, an experiment of Dr. Reichenbach may be cited, who, by distilling with water about 100 lbs. of pit-coal, obtained nearly 2 ounces of an oily liquid exactly resembling the natural naphtha of Amiano, in the Duchy of Parma.

The variations of colour and consistence in different specimens of these bodies certainly depends in great measure upon the presence of pitchy and fatty substances dissolved in the more fluid oil. Dr. Gregory found paraffin in petroleum from Rangoon.

The boiling-point of rock-oil varies from about 180° to near 600° ($82^{\circ}\cdot 2$ to $315^{\circ}\cdot 5\text{C}$). A thermometer inserted into a retort in which the oil is undergoing distillation, never shows for any length of time a constant temperature: hence it is inferred to be a mixture of several different substances. Neither do the different varieties of naphtha give similar results on analysis: they are all, however, carbides of hydrogen. The use of these substances in the places where they abound is tolerably extensive; they often serve the inhabitants for fuel, light, &c. To the chemist pure naphtha is valuable, as offering facilities for the preservation of the more oxidable metals, as potassium and sodium.

The following are of rarer occurrence :—

Retinite, or *Retinasphalt*, is a kind of fossil resin met with in brown coal; it has a yellow or reddish colour, is fusible and inflammable, and readily dissolved in great part by alcohol. The soluble portion has been called *retinic acid* by Prof. Johnston. *Hatchetin* is a somewhat similar substance met with in mineral coal at Merthyr-Tydvil, and also near Loch Fyne, in Scotland. *Idrialin* is found associated with native cinnabar, and is extracted from the ore by oil of turpentin, in which it dissolves. It is a white, crystalline substance, scarcely volatile without decomposition, but slightly soluble in alcohol and ether, and composed of $C_{42}H_{14}O$; it is generally associated with a hydrocarbon *idryl*, which contains $C_{42}H_{14}$.

Ozokerite, or *fossil wax*, is found in Moldavia, in a layer of bituminous shale; it is brownish, and has a somewhat pearly appearance; it is fusible below 212° ($100^{\circ}C$), and soluble with difficulty in alcohol and ether, but easily in oil of turpentin. It appears to contain more than one definite principle.

POSTSCRIPT.

ACETATE OF ALUMINA AND ALUMINA.

WHILE the preceding pages were passing through the press, some very interesting researches on acetate of alumina, have been published by Mr. W. Crum.*

Acetate of alumina (see page 453) is generally prepared by decomposing sulphate of alumina $\text{Al}_2\text{O}_3, 3\text{SO}_3$, a salt now manufactured on a large scale under the name of concentrated alum, by means of acetate of lead. The solution may be supposed to contain the neutral acetate of alumina $\text{Al}_2\text{O}_3, 3\text{C}_4\text{H}_3\text{O}_3$. This salt cannot, however, be obtained in the dry state. If the solution be rapidly evaporated at low temperatures, by being spread in thin layers on glass or porcelain, a basic *soluble* acetate is obtained, having the composition $\text{Al}_2\text{O}_3, 2\text{C}_4\text{H}_3\text{O}_3 + 4\text{HO}$, but if the solution be left to stand, or submitted to the action of heat, *insoluble* basic salts are precipitated, differing in composition from the former only by containing instead of 4 eq. of water either 2 or 5 eq.

The soluble acetate of alumina, when exposed in a dilute solution to the temperature of boiling water for several days, undergoes a very remarkable change. The whole, or nearly the whole, of the acetic acid is expelled by the action of heat, and a peculiar allotropic modification of alumina remains in solution. At the temperature of boiling water this alumina retains 2 eq. of water; *it entirely re-dissolves in water*. The soluble modification of alumina is instantaneously coagulated by mineral and vegetable acids, by the alkalies, and by a great number of salts.

* Chem. Soc. Quar. Jour. vi. 216.

APPENDIX.

HYDROMETER TABLES.

COMPARISON OF THE DEGREES OF BAUME'S HYDROMETER WITH
THE REAL SPECIFIC GRAVITIES.

1. *For Liquids heavier than Water.*

Degrees.	Specific Gravity.	Degrees.	Specific Gravity.	Degrees.	Specific Gravity.
0	1.000	26	1.206	52	1.520
1	1.007	27	1.216	53	1.535
2	1.013	28	1.225	54	1.551
3	1.020	29	1.235	55	1.567
4	1.027	30	1.245	56	1.583
5	1.034	31	1.256	57	1.600
6	1.041	32	1.267	58	1.617
7	1.048	33	1.277	59	1.634
8	1.056	34	1.288	60	1.652
9	1.063	35	1.299	61	1.670
10	1.070	36	1.310	62	1.689
11	1.078	37	1.321	63	1.708
12	1.085	38	1.333	64	1.727
13	1.094	39	1.345	65	1.747
14	1.101	40	1.357	66	1.767
15	1.109	41	1.369	67	1.788
16	1.118	42	1.381	68	1.809
17	1.126	43	1.395	69	1.831
18	1.134	44	1.407	70	1.854
19	1.143	45	1.420	71	1.877
20	1.152	46	1.434	72	1.900
21	1.160	47	1.448	73	1.924
22	1.169	48	1.462	74	1.949
23	1.178	49	1.476	75	1.974
24	1.188	50	1.490	76	2.000
25	1.197	51	1.495		

2. *Baumé's Hydrometer for Liquids lighter than Water.*

Degrees.	Specific Gravity.	Degrees.	Specific Gravity.	Degrees.	Specific Gravity.
10	1.000	27	0.896	44	0.811
11	0.993	28	0.890	45	0.807
12	0.986	29	0.885	46	0.802
13	0.980	30	0.880	47	0.798
14	0.973	31	0.874	48	0.794
15	0.967	32	0.869	49	0.789
16	0.960	33	0.864	50	0.785
17	0.954	34	0.859	51	0.781
18	0.948	35	0.854	52	0.777
19	0.942	36	0.849	53	0.773
20	0.936	37	0.844	54	0.768
21	0.930	38	0.839	55	0.764
22	0.924	39	0.834	56	0.760
23	0.918	40	0.830	57	0.757
24	0.913	41	0.825	58	0.753
25	0.907	42	0.820	59	0.749
26	0.901	43	0.816	60	0.745

These two tables are on the authority of M. Francœur ; they are taken from the *Handwörterbuch der Chemie* of Liebig and Poggendorff. Baumé's hydrometer is very commonly used on the Continent, especially for liquids heavier than water. For lighter liquids the hydrometer of Cartier is often employed in France. Cartier's degrees differ but little from those of Baumé.

In the United Kingdom Twaddell's hydrometer is a good deal used for dense liquids. This instrument is so graduated that the real sp. gr. can be deduced by an extremely simple method from the degree of the hydrometer, namely, by multiplying the latter by 5, and adding 1000 ; the sum is the sp. gr., water being 1000. Thus 10° Twaddell indicates a sp. gr. of 1050, or 1.05 ; 90° Twaddell, 1450, or 1.45.

In the Customs and Excise Sikes' hydrometer is used.

ABSTRACT

OF DR. DALTON'S TABLE OF THE ELASTIC FORCE OF VAPOUR OF
WATER AT DIFFERENT TEMPERATURES, EXPRESSED
IN INCHES OF MERCURY.

Temperature.		Force.	Temperature.		Force.	Temperature.		Force.
Fah.	Cent.		Fah.	Cent.		Fah.	Cent.	
32°	0°·0	0·200	57°	13°·88	0·474	90°	32°·2	1·36
33	0°·55	0·207	58	14°·4	0·490	95	35°	1·58
34	1°·1	0·214	59	15°	0·507	100	37°·77	1·86
35	1°·66	0·221	60	15°·5	0·524	105	40°·5	2·18
36	2°·2	0·229	61	16°·1	0·542	110	43°·3	2·53
37	2°·77	0·237	62	16°·66	0·560	115	46°·1	2·92
38	3°·3	0·245	63	17°·2	0·578	120	48°·88	3·33
39	3°·88	0·254	64	17°·77	0·597	125	51°·66	3·75
40	4°·4	0·263	65	18°·3	0·616	130	54°·4	4·34
41	5°	0·273	66	18°·88	0·635	135	57°·2	5·00
42	5°·55	0·283	67	19°·4	0·665	140	60°	5·74
43	6°·1	0·294	68	20°	0·676	145	62°·77	6·53
44	6°·66	0·305	69	20°·55	0·698	150	65°·5	7·42
45	7°·2	0·316	70	21°·1	0·721	160	71°·1	9·46
46	7°·77	0·328	71	21°·66	0·745	170	76°·66	12·13
47	8°·3	0·339	72	22°·2	0·770	180	82°·2	15·15
48	8°·88	0·351	73	22°·77	0·796	190	87°·77	19·00
49	9°·4	0·363	74	23°·3	0·823	200	93°·3	23·64
50	10°	0·375	75	23°·88	0·851	210	98°·88	28·84
51	10°·55	0·388	76	24°·4	0·880	212	100°	30·00
52	11°·1	0·401	77	25°	0·910	220	104°·4	34·99
53	11°·66	0·415	78	25°·5	0·940	230	110°	41·75
54	12°·2	0·429	79	26°·1	0·971	240	115°·5	49·67
55	12°·77	0·443	80	26°·66	1·000	250	121°·1	58·21
56	13°·3	0·458	85	29°·44	1·170	300	148°·88	111·81

TABLE

OF THE PROPORTION BY WEIGHT OF ABSOLUTE OR REAL ALCOHOL
IN 100 PARTS OF SPIRITS OF DIFFERENT SPECIFIC GRAVITIES.
(FOWNES.)

Sp. Gr. at 60° (15°·5C).	Percentage of real Alcohol.	Sp. Gr. at 60° (15°·5C).	Percentage of real Alcohol.	Sp. Gr. at 60° (15°·5C).	Percentage of real Alcohol.
0·9991	0·5	0·9511	34	0·8769	68
0·9981	1	0·9490	35	0·8745	69
0·9965	2	0·9470	36	0·8721	70
0·9947	3	0·9452	37	0·8696	71
0·9930	4	0·9434	38	0·8672	72
0·9914	5	0·9416	39	0·8649	73
0·9898	6	0·9396	40	0·8625	74
0·9884	7	0·9376	41	0·8603	75
0·9869	8	0·9356	42	0·8581	76
0·9855	9	0·9335	43	0·8557	77
0·9841	10	0·9314	44	0·8533	78
0·9828	11	0·9292	45	0·8508	79
0·9815	12	0·9270	46	0·8483	80
0·9802	13	0·9249	47	0·8459	81
0·9789	14	0·9228	48	0·8434	82
0·9778	15	0·9206	49	0·8408	83
0·9766	16	0·9184	50	0·8382	84
0·9753	17	0·9160	51	0·8357	85
0·9741	18	0·9135	52	0·8331	86
0·9728	19	0·9113	53	0·8305	87
0·9716	20	0·9090	54	0·8279	88
0·9704	21	0·9069	55	0·8254	89
0·9691	22	0·9047	56	0·8228	90
0·9678	23	0·9025	57	0·8199	91
0·9665	24	0·9001	58	0·8172	92
0·9652	25	0·8979	59	0·8145	93
0·9638	26	0·8956	60	0·8118	94
0·9623	27	0·8932	61	0·8089	95
0·9609	28	0·8908	62	0·8061	96
0·9593	29	0·8886	63	0·8031	97
0·9578	30	0·8863	64	0·8001	98
0·9560	31	0·8840	65	0·7969	99
0·9544	32	0·8816	66	0·7938	100
0·9528	33	0·8793	67		

OF THE PRINCIPAL MINERAL WATERS OF GERMANY

Grains of Anhydrous Ingredients in One Pound Troy.	Carlsbad.	Ems.	Schlesischer. Obersalz- Brunnen.
Carbonate of Soda . .	7·2712	8·0625	7·6211
Ditto of Lithia . .	0·0150	0·0405	..
Ditto of Baryta	0·0022	..
Ditto of Strontia . .	0·0055	0·0080	0·0170
Ditto of Lime . .	1·7775	0·8555	1·5464
Ditto of Magnesia . .	1·0275	0·5915	1·5496
Ditto (Proto) of Manganese	0·0048	0·0028	0·0026
Ditto (Proto) of Iron .	0·0208	0·0120	0·0356
Sub-Phos. of Lime . .	0·0012
Ditto of Alumina . .	0·0019	0·0014	..
Sulphate of Potassa	0·4050	0·3160
Ditto of Soda . .	14·9019	..	2·5106
Ditto of Lithia
Ditto of Lime
Ditto of Strontia
Ditto of Magnesia
Nitr. of Magnesia
Chlor. of Ammonium	0·0164
Ditto of Potassium	0·0338	..
Ditto of Sodium . .	5·9820	5·7255	0·8682
Ditto of Lithium
Ditto of Calcium
Ditto of Magnesium
Ditto of Barium
Ditto of Strontium
Bromide of Sodium	0·0051
Iodide of Sodium
Fluoride of Calcium . .	0·0184	0·0014	..
Alumina
Silica . .	0·4329	0·3104	0·2423
Total . .	31·4606	16·0525	14·7309
Carbonic Acid Gas in 100 cubic inches . .	58	51	98
Temperature . .	Sprud. 165° (73°·8C) Neub. 138° (58°·8C) Mühl. 128° (53°·3C) Ther. 122° (50°·C)	Kess. 117° (47°·2C) Krän. 84° (28°·8C)	58°(14°·5C)
Analyzed by . .	Berzelius.	Struve.	Struve.

TABLE OF ANALYSES

673

AND OF THE SARATOGA CONGRESS SPRING OF AMERICA.

Saratoga Congress Spring.	Kissingen. Ragozi.	Marienbad. Kreutbr.	Auschwitz. Ferdinands- Brunnen.	Eger. Franzens- Brunnen.
0·8261	..	5·3499	4·5976	3·8914
..	..	0·0858	0·0507	0·0282
..
0·0672	0·0592	0·0028	0·0040	0·0023
5·8531	4·8180	2·9509	3·0085	1·3501
4·1155	1·3185	2·0390	2·2867	0·5040
0·0202	0·0121	2·0288	0·0692	0·0322
0·0173	0·1397	0·1319	0·2995	0·1762
..	0·0172
0·1379	1·2540	..	0·0040	0·0092
..	..	28·5868	16·9022	18·3785
..
..	5·5485
..
..
0·1004
0·0326	0·0364
1·6256
19·6653	39·3733	10·1727	6·7472	6·9229
..
..
..	3·6599
..
0·1613	0·3331
0·0046
..
0·0069	..	0·0023
0·1112	0·1609	0·2908	0·5023	0·3548
32·7452	56·7136	51·6417	34·4719	31·6670
114	96	105	146	154
50° (10°C)	53° (11°·6C)	53° (11°·6C)	49° (9°·5C)	54° (12°·2C)
Schweitzer	Struve.	Berzelius.	Steinmann.	Berzelius.

OF THE PRINCIPAL MINERAL WATERS OF GERMANY AND

Grains of Anhydrous Ingredients in One Pound Troy.	Pyrmont.	Spa Pouhon.	Fachingen.
Carbonate of Soda	0·5531	12·3328
Ditto of Lithia
Ditto of Baryta
Ditto of Strontia
Ditto of Lime . .	4·7781	0·7387	1·8667
Ditto of Magnesia	0·8421	1·2983
Ditto (Proto) of Manganese	0·0364	0·0389	..
Ditto (Proto) of Iron .	0·3213	0·2813	..
Sub-Phos. of Lime	0·0102	0·0061
Ditto of Alumina . .	0·0110	0·0064	..
Sulphate of Potassa . .	0·0314	0·0593	..
Ditto of Soda . .	1·6092	0·0281	0·1267
Ditto of Lithia . .	0·0067
Ditto of Lime . .	5·0265
Ditto of Strontia . .	0·0154
Ditto of Magnesia . .	2·3684
Nitr. of Magnesia
Chlor. of Ammonium
Ditto of Potassium
Ditto of Sodium	0·3371	3·2337
Ditto of Lithium
Ditto of Calcium
Ditto of Magnesium . .	0·8450
Ditto of Barium
Ditto of Strontium
Bromide of Sodium
Iodide of Sodium
Fluoride of Calcium
Alumina
Silica . .	0·3727	0·3739	0·0657
Total . .	15·4221	3·2691	18·9300
Carbonic Acid Gas in 100 } cubic inches . .	160	136	135
Temperature (F.) . .	56°(13°·3C)	50°(10°C)	50°(10°C)
Analyzed by . .	Struve.	Struve.	Bischoff.

TABLE OF ANALYSES

675

OF THE SARATOGA CONGRESS SPRING OF AMERICA—*continued.*

Selters.	Seidschütz.	Püllna.	Kreuznach. Elisen- Brunnen.	Adelheids- Quelle.
4·6162	5·2443
..	0·0902
0·0014	0·0024
0·0144	0·0387
1·4004	5·1045	0·5775	0·2058	0·4703
1·5000	0·8235	4·8045	1·1812	0·2980
..	0·0032	..	0·0072	0·0012
..	0·0095	..	0·1495	0·0121
0·0007	0·0117	0·0026
0·0020	0·0088
0·2978	3·6705	3·6000	..	0·0066
..	17·6220	92·8500
..
..	1·1287	1·9500
..	0·0347
..	62·3535	69·8145
..	5·9302
..
0·2685	0·7287	0·1845
12·9690	54·6917	28·4608
..	0·0562	..
..	9·7358	..
..	1·2225	14·7495
..	0·2366	..
..	0·5494	..
..	0·2304	0·3060
..	0·0024	0·1500
0·0013
..	0·0086	0·0166
0·2265	0·0900	0·1320	0·2355	0·1922
21·2982	98·0133	188·4806	68·0190	35·4739
126	20	7	12	10
58°(14°·5C)	58°(14°·5C)	58°(14°·5C)	47°(8°·3C)	58°(14°·5C)
Struve.	Struve.	Struve.	Struve.	Struve.

WEIGHTS AND MEASURES.

480·0 grains Troy	=	1 oz. Troy.
437·5 ,,	=	1 oz. Avoirdupois.
7000·0 ,,	=	1 lb. Avoirdupois.
5760·0 ,,	=	1 lb. Troy.

The imperial gallon contains of water at 60°(15°·5C)	70,000· grains.
The pint ($\frac{1}{8}$ of gallon)	8,750· ,,
The fluid-ounce ($\frac{1}{20}$ of pint)	437·5 ,,
The pint equals	34·66 cubic inches.

The French *kilogramme* = 15,433·6 grains, or 2·679 lbs. Troy, or
2·205 lbs. avoirdupois.

The <i>gramme</i>	=	15·4336 grains.
„ <i>decigramme</i>	=	1·5434 ,,
„ <i>centigramme</i>	=	0·1543 ,,
„ <i>milligramme</i>	=	0·0154 ,,

The <i>mètre</i> of France	=	39·37 inches.
„ <i>decimètre</i>	=	3·937 ,,
„ <i>centimètre</i>	=	0·394 ,,
„ <i>millimètre</i>	=	0·0394 ,,

INDEX.

	PAGE	ACIDS— <i>continued</i>	PAGE	ACIDS— <i>cont.</i>	PAGE
ABSORPTION of heat	74	bromo-hydrosalicy-		chromic . . .	316
Acer saccharinum	400	lic . . .	496	cinnamic . . .	499
Acetal . . .	449	bromo-phenisic .	659	citraconic . .	508
Acetamide . .	430	butyric . . .	480, 601	citric . . .	507
Acetate of oxide of		campholic . . .	612	cocinic . . .	600
amyl . . .	474	camphoric . . .	611	comenic . . .	551
Acetates . . .	453	capric . . .	481, 602	croconic . . .	415
Acetic acid . .	450, 481	caproic . . .	481, 601	cumaric . . .	498
anhydrous . .	452	caprylic . . .	481, 602	cunic . . .	494, 610
ether . . .	429	carbazotic . . .	585	cyanic . . .	523
Acetone . . .	456	carbolic . . .	657	cyanuric . . .	523, 525
Acetonitrile . .	453	carbonic . . .	135	delphinic . . .	602
Acetyl . . .	447	liquefaction of	48	dextro-racemic .	506
Acid, acetic . .	450, 480	carminic . . .	590	dialuric . . .	543
anhydrous . .	452	cerebric . . .	645	dithionic . . .	144
aconitic . . .	508	cerotic . . .	603	draconic . . .	669
acrylic . . .	604	cerotyllo . . .	481	elaidic . . .	600
aldehydic . . .	449	cetyllic . . .	481, 603	ellagic . . .	513
alloxanic . . .	540	chelidonic . . .	551	equisetic . . .	508
alphaorsellic . .	588	chloracetic . . .	381, 455	erythric . . .	587
althionic . . .	442	chlorhydric . . .	152	ethalic . . .	603
amalic . . .	556	chloric . . .	157	ethionic . . .	442
amygdalic . . .	520	chlorocarbonic .	138	euchronic . . .	415
anilic . . .	497, 585	chlorochromic .	317	euxanthic . . .	593
anilotic . . .	497	chlorohydrosalicy-		evernic . . .	588
anisic . . .	609	lic . . .	496	everninic . . .	589
anthranilic . .	567	chlorohyponitric	155	ferric . . .	307
antimonie . . .	342	chloronaphthalic	662	formic . . .	468, 480
arsenic . . .	347	chloroniceic . .	572	formobenzoic .	490
arsenious . . .	346	chloronitrous . .	155	fulminic . . .	526
aspartic . . .	509, 558	chlorophenisic .	659	fumaric . . .	510
auric . . .	357	chlorosulphuric	142, 439	gallic . . .	510, 512
azotic . . .	128	chlorous . . .	156	glyco-benzoic .	493
balenic . . .	482	cholalic . . .	638	glyco-cholalic .	637
benzoic . . .	484	choleic . . .	637	glyco-hyo-cholalic	639
anhydrous . .	488	choloidinic . . .	638	glycolic . . .	493
betaorsellic . .	588	chrysammic . . .	593	glucic . . .	403
bismuthic . . .	324	chrysanilic . . .	567, 586	hemipinic . . .	549
boracic . . .	166	chrysolopic . . .	593	hippuric . . .	492
bromic . . .	162	chrysophanic . .	590	regeneration of	493

ACIDS—cont.	PAGE	ACIDS—cont.	PAGE	ACIDS—cont.	PAGE
humic	403	methionic	442	purreic	593
hydriodic	160	metoleic	605	pyrogallie	514
hydrobromic	162	mucic	414	pyromeconic	551
hydrochloric	152	muratic	152	pyromucic	414
hydrocyanic	516	mykomelinic	541	pyrophosphoric	246
hydroferricyanic	532	myristic	600	pyrotartaric	505
hydroferrocyanic	529	myronic	612	quadrichlorovaleric	478
hydrofluoric	163	nitric	128	racemic	505
hydrofluosilicic	165	nitranisic	609	artificial produc-	
hydroleic	605	nitrobenzoic	485	tion of	506
hydromargaric	605	nitrococcusic	591	retinic	665
hydromargaritic	605	nitrocunnic	494	rhodizonic	415
hydrosalicyllic	495	nitrophenasic	659	ricinoleic	606
hydrosulphocyanic	535	nitrophenesic	659	rubiacic	592
hydrosulphuric	181	nitrophenisic	585, 659	rubic	512
hyocholalic	639	nitrosalicyllic	497, 585	saccharic	413
hyocholic	639	nitrotoluylic	494	sacchulmic	403
hypochloric	156	nitrous	132	salicylic	497
hypochlorous	155	œnanthic	431	salicylous	495
hyponitric	132	œnanthylic	481, 605	sebacic	601
hypophosphorous	148	oleic	597	selenic	146
hyposulphobenzic	486	oleophosphoric	645	selenions	146
hyposulphuric, sul-		opianic	549	silicic	164
phuretted	144	orsellinic	587, 588	stearic	597
hyposulphurous	144	oxalic	410	stypbnic	593
igasuric	544	oxalovinic	433	suheric	414, 601
indinic	584	oxaluric	542	succinic	601
inosinic	627	oxamic	412	sulphamylic	474
itaconic	508	oxanilic	570	sulphindigotic	582
iodic	161	palmitic	600	sulphindylic	582
iodo-sulphuric	145	parabanic	541	sulphobenzoic	485
isatinic	584	paratartaric	505	sulphoglyceric	599
isethionic	442	parellic	589	sulpholeic	605
japonic	512	pectic	409	sulphomargaric	605
kakodylic	461	pelargonic	431, 482	sulphomethylic 466, 468	
kalisaccharic	403	pentathionic	145	sulphonaphthalic	661
kinic	553, 554	perchloric	158	sulphophenic	658
lactic	420	perchromic	317	sulphosaccharic	402
lecanoric	587, 588	periodic	161	sulphotoluolic	603
levo-racemic	506	permanganic	303	sulphovinic	432
lithic	538	phocenic	602	sulphuric	141
lithofellinic	639	phosphethylic	433	sulphuric, anhy-	
malamic	509	phosphobiethylic	433	drous	143
maleic	510	phosphoric	149	sulphurous	140
malic	508	anhydrous	247	sylvic	613
manganic	303	bibasic	246	tannic	510
margaric	597	glacial	247	tartaric	503
meconic	550	monobasic	246	tartaric, anhydrous	505
melanic	496	tribasic	245	inactive	506
melasinic	403	phosphorous	148	tartrafic	505
melissic	482	phosphovinic	432	tartrelic	505
mellitic	414	phthalic	661	tartrovinic	433
mesoxalic	541	picric	585	tauro-cholalic	637
metacetonic	457	pimanic	614	tauro-hyo-cholalic	639
metagallic	514	pinic	618	telluric	345
metamargaric	605	propionic	457, 480	tellurous	345
metapectic	409	prussic	516	terchlorovaleric	478
metaphosphoric	246	purpuric	545	thionuric	542

Acids—cont.	PAGE		PAGE		PAGE
trithionic . . .	144	Algaroth, powder of	343	Ammonium.	231, 271
ulmic . . .	403	Alizarin . . .	591	cyanide of . . .	522
uramic . . .	543	Alkalimeter . . .	263	ferrocyanide of . . .	532
uric . . .	538, 545	Alkalimetry . . .	262	salicylide of . . .	496
usnic . . .	590	Alkaloids . . .	547	Amorphous quinine	553
valerianic . . .	475	artificial . . .	559	Amygdalic acid . . .	520
valeric . . .	480, 475	Alkargen . . .	461	Amygdalin 483, 518,	519
anhydrous . . .	489	Alkarsin . . .	459	Amylaceous group	399
valero-benzoic . . .	488	Allantoin . . .	539	Amyl and its com-	
xanthic . . .	445	Alliaria officinalis, oil		pouuds . . .	472
salts . . .	232	of . . .	612	series, bases of the	566
anhydrous 452, 488,	489	Alloxan . . .	540	Amylamine . . .	566
bibasic . . .	245	Alloxanic acid . . .	541	-urea . . .	566
fatty . . .	482	Alloxantin . . .	543	Amyl-ammonia . . .	566
hydrogen-theory of	247	Alloys . . .	229	Amylene . . .	475
monobasic . . .	245	of copper . . .	330	Amylic ether . . .	473
notation of . . .	247	Allyl . . .	613	mercaptan . . .	474
oxygen-theory of	247	oxide of . . .	613	Amylotriethyl-ammo-	
polybasic . . .	245	sulphide of . . .	613	nium, oxide of . . .	573
terminology of . . .	140	sulphocyanide of	613	Analcime . . .	293
tribasic . . .	245	Almonds, oil of bitter	483	Analysis, ultimate, of	
vegetable . . .	502	Aloes . . .	593	organic bodies	384
Aconitates . . .	508	Alphaorsellic acid	588	Analysis of carbonates	266
Aconitic acid . . .	508	Althionic acid . . .	442	Analytical method of	
Aconitine . . .	557	Aluns . . .	291	chemical research	118
Aconitum, acid of	508	Alum, common . . .	291	Anhydrous acids 452, 488	
Aconitum napellus	557	Roman . . .	291		489
Acrolein . . .	598, 604	Alumina . . .	290	Anilic acid . . .	497, 585
Acrylic acid . . .	604	acetate of . . .	453	Aniline 487, 566, 570, 586	
Adcheidsquelle, water		analytical remarks	293	homologues of . . .	571
of . . .	677	silicates of . . .	293	-urea . . .	570
Affinity, chemical	208	sulphate of . . .	291	Anilotic acid . . .	497
After-damp of coal-		Aluminium . . .	290	Animal heat . . .	632
mines . . .	137	chloride of . . .	290	body, components of	
Air-pump . . .	11, 13	Alum stone . . .	291		617
Air, atmospheric . . .	125	Amalgam, ammoniacal		Aniseed, oil of . . .	608
Alanine 421, 448, 578			271	Anisic acid . . .	609
Albite . . .	293	Amalgam . . .	229, 366	Anisoin . . .	609
Alhumim . . .	617	Amalic acid . . .	556	Aisol . . .	609
Aluminous principles	617	Amariue . . .	491, 576	Anisyl, hydride of	609
Alcohol . . .	416	Amber . . .	601, 614	Anthranilic acid 567, 586	
absolute . . .	416	Amidin . . .	406	Antiarin . . .	558
benzoic . . .	489	Amidogen . . .	274	Antimonic acid . . .	342
butylic . . .	479	Amidogen-bases . . .	561	Antimony . . .	341
caprylic . . .	480, 602	Ammelide . . .	536	bases . . .	579
ccrotylic . . .	480, 603	Ammcline . . .	536	crude . . .	343
cctylic . . .	480, 603	Ammonia . . .	179	potassa, tartrate of	504
ethalic . . .	603	acctate of . . .	453	Aqua regia . . .	155
propylic . . .	479	alum . . .	292	Arabin . . .	408
Alcohols, generally	480	analytical remarks		Archil . . .	587
Alcohol, melissic 480, 603		on . . .	274	Argand lamp . . .	176
table of, in aqueous		benzoate of . . .	485	Argol . . .	418, 502
mixtures . . .	673	cyanate of . . .	524	Ariciue . . .	553
Aldchde 423, 448, 450		malate ofl. . . .	509	Arragonite . . .	283
bases from . . .	577	oxalate of . . .	412	Arrow poison of ceu-	
resin . . .	448	purpurate of . . .	544	tral America . . .	557
Aldehydic acid . . .	449	tartrate of . . .	504	Arrowroot . . .	407
Alcmbroth, sal . . .	363	urate of . . .	644, 539	Arsenio acid . . .	347

	PAGE		PAGE		PAGE
Arsenic and its com- pounds	346	Baryta and its hy- drate	276	BENZOYL— <i>cont.</i>	
analytical details	348	acetate of	453	benzoate of	488
detection in organic mixtures	349	analytical remarks on	278	Berberine	557
Arsenious acid	346	aconitate of	508	Berberis vulgaris	556
Artemisia	558	fulminate of	527	Bergamot, oil of	608
Arterial blood	627	tartrate of	503	Berthollet's fulminat- ing silver	356
Assafoetida	593	Bases	110	Beryl	293
oil of	613	from aldehyde	577	Beryllia	293
Asparagin	509, 558	amidogen-	561	Beryllium	293
Asparagus	558	from animal-oil	575	Betaorcin	590
Aspartic acid	509, 558	antimony-	579	Betaorsellic acid	588
Aspen	557	organic, containiug chlorine	568	Bezoar stones	639
Asphaltene	663	from coal-tar-oil	574	Biamylamine	566
Asphaltum	663	of the ethyl-series	561	Bibasic acids	246
Astatic needle	99	imidogen	561	Biborate of soda	269
Atmosphere, chemical relations of	125	artificial, containing mercury	365	Bicarbonate of po- tassa	253
composition and analysis	126	mixed artificial	572	Bicarbonate of soda	262
physical constitu- tion of	11	nitrile-	561	Bichloraniline	568
purifying	285	from volatile oils by ammonia	575	Bichlorethylamine	563
vapour of water in	46	organic	547	Bichloride of tin	335
Atmospheric electricity	94	organic, artificial	559	Bichlorisatin	585
Atomic theory	206	phosphorous-	579	Bichlorokinone	554
Atomic weight	208	containing plati- num	369	Bichlorosaligenen	497
Atoms	206	Bassorin	408	Bichromate of po- tassa	316
Atropa belladonna	557	Battery, constant	221	Biethylamine	563
Atropine	557	Baume's hydrometer	671	-urea	563
Attenuation of wort	419	Bay salt	270	Biethyl-ammonia	563
Attraction	208	Beberine	557	Biethyl-amylaniline	573
Augite	289	Beer	418	Biethylaniline	572
Auric acid	357	Beetroot, sugar from	400	Biethyl-phenylamine	572
Auschwitz, water of	675	Bell metal	330	Biethyl phenyl-ammo- nium, oxide of	572
Axes of crystals	237	Bengal light	345	Biethylo-toluidine	572
Axinite	293	Benzamide	489	Biliary calculi	604
Azobenzol	487	Benzile	491	Bile	636
Azotic acid	128	Benzilic acid	491	test of Pettenkofer	638
		Benzimide	491	Bilin	638
		Benzine	486	Bimethylamine	565
		Benzoates	485	Binary theory of salts	247
		Benzoate of benzoyl	488	Binitranisidine	609
		of phenyl	658	Binitranisol	609
		Benzoic acid	484, 557	Binitrobenzol	487, 568
		anhydrous	488	Binitrotoluol	603
		alcohol	489	Binoxide of barium	276
		Benzoin	491	of protein	622
		Benzol	486, 571	of tin	335
		Benzol, homologues of	571	Biscuit	298
		Benzoline	576	Bism-ethyl	447
		Benzone	486	Bismuth	324
		Benzonitrile	491, 658	analytical remarks	325
		Benzophenone	486	Bismuthic acid	324
		Benzoyl	492	Bisulphate of potassa	255
		and its compounds	483	of soda	267
				Bisulphide of carbon	189
				Bitter almonds, oil of	483

B

Badian-oil	609
Balenic acid	482
Balsams	613
Balsam, Canada	615
copaiba	615
Peru	501
Tolu	501
Barilla	260
Barium	276
ferrocyanide of	532
salicylide of	496
Barley sugar	401
Barometer	16

	PAGE		PAGE		PAGE
Bitumen . . .	662	Butter . . .	601, 621	Carbolic acid . . .	657
compact . . .	663	of antimony . . .	343	Carbon . . .	133
elastic . . .	663	Butyl . . .	477	chloride of . . .	444
Black flux . . .	350	Butylamine . . .	575	bisulphide of . . .	189
Bleaching . . .	284	Butylene . . .	477, 486	compounds with oxy-	
Bleaching powder	284	Butyric acid . . .	480, 601	geu . . .	135
testing its value	285	ether . . .	430	estimation in organic	
salts . . .	155	Butyrin . . .	601	bodies . . .	384
Blende . . .	322			Carbonate of baryta	278
Blood . . .	627			of copper . . .	322
arterial . . .	627			of lead . . .	331
circulation of the	627	C.		of lime . . .	282
corpuscles . . .	628	Cacao butter . . .	600	of magnesia . . .	288
discs . . .	628	Cadet's fuming liquid	459	of oxide of amyl	474
globules . . .	628	Cadmium . . .	323	of potassa . . .	252
serum of . . .	629	analytical remarks	324	of silver . . .	355
venous . . .	627	Caffeine . . .	555	of soda . . .	260
Blowpipe . . .	175	-muroxide . . .	556	of zinc . . .	322
Blue ink . . .	531	Calamine . . .	321	Carbonates . . .	137
light . . .	345	Calcium and its com-		analysis of . . .	262
Prussian . . .	530, 531	pounds . . .	279	of ammonia . . .	272
Turnbull's . . .	533	fluoride of . . .	283	Carbonetted hydrogen,	
Boilers, deposits in	283	analytical remarks	286	light . . .	168
Boiling point . . .	37	Calc sinter . . .	283	Carbonic acid . . .	135
Bones . . .	646	Calculi, biliary . . .	604	ether . . .	428
Boric acid . . .	166	urinary . . .	534, 643	oxide . . .	137
ether . . .	428	fusible . . .	644	Carbyl, sulphate of	441
Borax . . .	269	mulberry . . .	644	Carlsbad, water of	674
Borneene . . .	611	Calomel . . .	362	Carmine . . .	590
Borncol . . .	611	Camphene . . .	608	Carmine acid . . .	590
Boron . . .	166	Camphogeu . . .	612	Cartier's hydrometer	671
chloride of . . .	189	Campholene . . .	612	Carthamin . . .	592
fluoride of . . .	166	Campholic acid . . .	612	Carragheeu moss . . .	408
Brass . . .	330	Camphor . . .	611	Casein . . .	620
Brazil wood . . .	592	artificial . . .	607	Cassava . . .	408
Bread . . .	420	Camphoric acid . . .	611	Cassius, purple . . .	336
Brewing . . .	418	Camphylene . . .	608	Castor-oil . . .	605
British gum . . .	407	Canada balsam . . .	615	Catechu . . .	511, 512
Bromal . . .	443	Cane-sugar . . .	399	Cedar wood, oil of	610
Bromaniline . . .	568	Candle, flame of . . .	175	Cedrene . . .	610
Bromanisal . . .	609	Candles, stearin . . .	605	Cedriret . . .	654
Bromic acid . . .	162	Cantharidin . . .	604	Cellulose . . .	409
Bromide of amyl . . .	473	Caoutchouc . . .	614	Cement . . .	280
of arsenic . . .	348	mineral . . .	663	Cements, lime . . .	280
of benzoyl . . .	489	tubes (note) . . .	136	Cement, Parker's, or	
of cyanogen . . .	528	Caoutchoucine . . .	614	Roman . . .	280
of ethyl . . .	426	Capric acid . . .	480, 601	Cerasin . . .	408
of potassium . . .	259	Capivi, oil of . . .	608	Cerebric acid . . .	645
Bromine . . .	161	Caproic acid . . .	482, 601	Cerebrolein . . .	645
Bromisatin . . .	584	Caproyl . . .	605	Cerin . . .	603
Bromoform . . .	443, 470	Caprylamine . . .	606	Cerite . . .	294
Bromo-hydrosaliclic		Caprylic acid . . .	480, 601	Cerium . . .	294
acid . . .	496	alcohol . . .	480, 602	Cerotate of oxide of	
Bromophenisis acid	659	Caramel . . .	401	cerotyl . . .	603
Bromosamide . . .	497	Carbamide . . .	538	Cerotic acid . . .	603
Brown coal . . .	662	Carbazotic acid . . .	585	Cerotyl . . .	603
Brucine . . .	554	Carbides of hydrogen	163	Cerolytic acid . . .	480
Bunsen's battery . . .	223			alcohol . . .	480, 603

	PAGE		PAGE		PAGE
Cetyl-series . . .	603	Chlorides of carbon . . .	440	Cinnamol . . .	500, 615
Cetylic acid . . .	480	Chlorine . . .	150	Cinnamon, oil of . . .	499
alcohol . . .	481, 603	compounds with		Cinnamyl and its	
Chalk . . .	282	oxygen . . .	155	compounds . . .	499
stones . . .	539	estimation in or-		Circular polarization	
Chameleon, mineral	304	ganic bodies . . .	394	of light . . .	65
Charcoal, animal and		peroxide of . . .	156	Circulation of the	
vegetable . . .	135	Chlorisatin . . .	584	blood . . .	627
Cheildonic acid . . .	551	Chlorobenzol . . .	488	Citraconic acid . . .	508
Chelidonium majus	551	Chlorobenzide . . .	488	Citrates . . .	507
Chemical philosophy	191	Chloro-carbonic acid	138	Citric acid . . .	507
Chimneys, action of	33	ether . . .	431	Clarifying wines and	
Chinese wax . . .	603	Chlorochromic acid	317	beer . . .	626
Chinoline . . .	574	Chlorochinose . . .	500	Clay ironstone . . .	310
Chinoidine . . .	553	Chloroform . . .	443, 470	origin of . . .	292
Chloracetates . . .	455	Chloro-hydro-salicylic		Cleavage . . .	234
Chloracetic acid . . .	373, 455	acid . . .	496	Coal, brown . . .	662
Chloral . . .	442, 450	Chloro-hyponitric acid	155	gas . . .	169
insoluble . . .	443	Chlorokinone . . .	554	Cobalt . . .	319
Chloranile . . .	554	Chlorometry . . .	285	analytical remarks	
Chloraniline . . .	568	Chloroniccic acid . . .	572	on . . .	321
Chlorate of potassa	256	Chloronicene . . .	572	cyanide of . . .	523
Chlorethral . . .	443	Chloronicine . . .	572	acetate of . . .	454
Chlorhydric acid . . .	152	Chloro-nitrous acid	155	Cobalto-cyanogen	533
Chloric acid . . .	157	Chloro-phenisic acid	659	Cobalt-ultramarine	321
Chloride of aluminium	290	Chloro-phenussic acid	659	Cocculus indicus . . .	558
of ammonium . . .	272	Chloro-naphthalic acid	662	Coccus cacti . . .	590
of amyl . . .	473	Chloropicrin . . .	586, 593	Cochineal . . .	590
of antimony . . .	343	Chloro-saligenin . . .	497	Cocinic acid . . .	600
of arsenic . . .	348	Chlorosamide . . .	497	Cocoa oil . . .	600
of barium . . .	277	Chloro-sulphuric acid		Cocodeine . . .	549
of benzoyl . . .	488	142, 439		Cohesion . . .	13, 208
of boron . . .	189	Chlorous acid . . .	156	Coke . . .	135
of calcium . . .	280	Cholesterin . . .	604	Colchicine . . .	555
of chromium . . .	315	Cholestrophane . . .	556	Collodion . . .	414
of cinnamyl . . .	500	Cholic acid . . .	637	Colophene . . .	608
of copper . . .	329	Choloidinic acid . . .	638	Colophony . . .	613
of cyanogen . . .	528	Chondrin . . .	623	Colouring principles,	
of ethyl . . .	425	Chromate of lead . . .	316	organic . . .	581
of gold . . .	357	of potassa . . .	316	Columbium . . .	339
of hydrocarbon . . .	170	Chrome-yellow . . .	316	Combination by	
of iodine . . .	189	Chromic acid . . .	316	volume . . .	200
of kakodyl . . .	469	Chromium . . .	314	by weight . . .	194
of lime . . .	284	analytical remarks	316	Combining quanti-	
of magnesium . . .	287	Chrysammic acid . . .	593	ties . . .	197, 199
of methyl . . .	465	Chrysanic acid . . .	567, 586	Combustion . . .	172
of mercury . . .	362	Chrysen . . .	656	Comenic acid . . .	551
of nitrogen . . .	186	Chrysoplepic acid . . .	593	Common salt . . .	270
of olefant gas . . .	439	Chrysolite . . .	289	Compass, mariner's	85
of phenyl . . .	658	Chrysophanic acid	590	Composition, laws of	194
of phosphorus . . .	188	Chyle . . .	633	Concretions, gouty	539
of platinum . . .	368	Cinchonine . . .	551	Condensation of gases	
of potassium . . .	258	Cinchonicine . . .	552	and vapours . . .	45, 47
of silicium . . .	189	Cinchonidine . . .	552	Conduction of heat	34
of silver . . .	355	Cinchovatine . . .	553	Concine . . .	555
of sodium . . .	270	Cinnabar . . .	359, 365	Conine . . .	555
of sulphur . . .	188	Cinnamein . . .	501	Constant battery . . .	221
of zinc . . .	322	Cinnamic acid . . .	499	Cotarnine . . .	549

	PAGE
Copaiba balsam . . .	615
Copal . . .	614
Copper . . .	327
acetates of . . .	455
alloys of . . .	330
analytical rem. on . . .	329
ferrocyanide of . . .	532
salicylide of . . .	496
Cork . . .	601
Corn-oil . . .	479
Corundum . . .	290
Corrosive sublimate . . .	363
Cream of tartar . . .	503
Croconic acid . . .	415
Crown-glass . . .	295
Crucibles . . .	299
Cryophorus . . .	50
Crystals . . .	233
Crystallization . . .	233
Crystalline forms . . .	233
Crystallization, water of . . .	233
phenomena of . . .	233
Cube . . .	237
Cubebs, oil of . . .	608
Cudbear . . .	587
Cumaric acid . . .	498
Cumarin . . .	498
Cumic acid . . .	610, 494
Cumidine . . .	571
Cumin oil . . .	610
Cuminol . . .	494, 610
Cumol . . .	494, 611
Curarine . . .	557
Curd . . .	620
Cyanates . . .	524
Cyanethine . . .	427
Cyameline . . .	523
Cyanic acid . . .	523
Cyanide of amyl . . .	474
of benzoyl . . .	489
of ethyl . . .	426
of hydrogen . . .	516
of kakodyl . . .	461
of methyl . . .	465
of phenyl . . .	658
Cyanides . . .	520
Cyaniline . . .	568
Cyanite . . .	293
Cyanogen . . .	515
bromide of . . .	528
chloride of . . .	528
compounds and de- rivatives . . .	515
iodide of . . .	528
Cyanuric acid . . .	525, 527
Cymol . . .	494, 610
Cystic oxide . . .	545

D.	PAGE	E.	PAGE
Dammar resin . . .	614	Earthenware . . .	297, 299
Daniell's battery . . .	221	Eblanin . . .	472
Dutch liquid 170, 380, 439		Ebullition . . .	37
Datura stramonium . . .	557	Effervescing draughts . . .	503
Daturine . . .	557	Efflorescence . . .	233
Daphne mezereum . . .	558	Eger, water of . . .	675
Daphnin . . .	558	Egg, white of . . .	617
Decay . . .	383	Elaidic acid . . .	600
Declination mag- netic . . .	84	Elaidin . . .	600
Decolorization by charcoal . . .	135	Elain . . .	596
Deliquescence . . .	233	Elais guianensis . . .	600
Delphinic acid . . .	602	Elaldehyde . . .	449
Delphinine . . .	557	Elaterin . . .	558
Delphinium staphis- agria . . .	557	Electric eel . . .	97
Dew, origin and cause . . .	74	Electric machine . . .	91
Density . . .	3	Electrical current . . .	95
Density of vapours determination of . . .	396	Electricity . . .	88
Dextrin . . .	406	Electro-chemical de- composition . . .	213
Dextro-racemic acid . . .	506	Electrodes . . .	213
Diabetes . . .	401, 642	Electrolysis . . .	213
insipidus, sugar from . . .	403	Electro-magnetism . . .	98
Dialuric acid . . .	543	Electrophorus . . .	94
Diamagnetic bodies . . .	85	Electro-plating . . .	224
Diamond . . .	133	Electrolytes . . .	213
Diastase . . .	407	Electrotype . . .	223
Diathermancy . . .	76	Elementary bodies . . .	103
Didymium . . .	294	substances, table of . . .	198
Diffusion . . .	113	symbols of . . .	204
false . . .	632	Elements . . .	163
Digestion . . .	650	Eleni, oil of . . .	597
Dimorphism . . .	234	Ellagic acid . . .	513
Dippel's oil . . .	575	Emerald . . .	293
Disacryle . . .	604	Emery . . .	290
Disinfection . . .	152, 286	Emetive . . .	557
Disinfecting solu- tion of Labarraque . . .	284	Ems, water of . . .	674
Disposing influence . . .	211	Emulsin . . .	518
Distillation . . .	41	Epsom salt . . .	287
dry or destructive . . .	382	Equator, magnetic . . .	84
Distilling . . .	416	Equisetic acid . . .	508
Dithionic acid . . .	144	Equisetum, acid of . . .	508
Dodecahedron . . .	237	Equivalents, table of . . .	198
Double salts . . .	232	volume . . .	201
Draconic acid . . .	609	law of . . .	196
Dragon's blood . . .	614	Erbium . . .	293
Dropsy, fluid of . . .	620	Eremacausis . . .	383
Dulcose . . .	404	Erythrasin . . .	461
Dyes, red or yellow . . .	593	Erythric acid . . .	587
Dyeing, action of . . .	581	Erythroprotide . . .	622
Dyslysin . . .	638	Essence of turpentin . . .	607
		Essential oils . . .	607
		Ethalic acid . . .	603
		alcohol . . .	603

	PAGE		PAGE
Gilding	358	Hahnemann's soluble	
Glass, coloured . . .	297	mercury	361
manufacture of . . .	295	Halitus	628
Glauber's salt . . .	267	Haloid salts	231
Glass, variety of . .	295	Hardness of water .	282
soluble	297	permanent	282
Gliadin	648	temporary	282
Globulin	623	Harmaline	555
Glucic acid	403	Harmine	555
Glucinum	293	Hatchetin	665
Glucose	401	Heat, absorption . .	74
Glue	625	animal	632
Gluten	405	capacity for . . .	52
Glutin	405	conduction of . .	34
Glycerin	596, 599	latent	35
Glyco-beuzoic acid .	493	phenomena of . .	20
Glycocne	493, 624	radiation	72
Glycocoll	624	reflection	72
Glyco-cholic acid . .	637	specific	52
Glyco-hydrocholic acid	639	transmission . . .	76
Glycolamide	493	Heavy spar	277
Glycolic acid	493	Helicin	497
Glycyrrhizin	403	Helicoidin	497
Goniometry	235	Hemihedral crystals	242
Gold, analytical re-		Hemipinic acid . . .	549
marks	358	Hematite	306
and its compounds .	356	Hematosin	629
cyanide of	523	Hematoxylin	593
-dust	358	Hepar sulphuris . .	257
-leaf	358	Herrings, liquor of	
standard of England	358	salt	565
Goulard water . . .	454	Hesperidin	558
Gouty concretions .	539	Heculaudite	293
Gramme	678	Hippuric acid	492
Grape sugar	401	Homologues, term . .	481
Graphite	134	Homologues of aniline	569
Grass oil	608	of benzol	571
Gravitation	13	of the glycocine-se-	
Gravity, specific . .	3	ries	624
Greenheart timber .	557	of the salicyl-series	610
Green fire	279	Houestone	414
Green salt of Magnus	369	Hop	418
Groups, isomorphous	242	oil of	608
Grove's battery . . .	222	Hornblende	289
Guanine	546	Horn silver	355
Guano	546	Horny substance . .	634
Gum	408	Horse-radish, oil of	612
arabic	408	Huano	546
benzoin	615	Humic acid	403
British	407	Humus	403
of cherry tree . . .	408	Hydrarg-ethyl . . .	447
tragacanth	408	nitrate of	447
Gun cotton	414	chloride of	447
Gun metal	330		
Gunpowder	254		
Gutta percha	614		
Gypsum	281		
		Hydrate of oil of tur-	
		pentin	608
		Hydrates, term . . .	122
		Hydride of anisyl . .	609
		Hydride of benzoyl .	483
		Hydride of cinnamyl	499
		Hydriodic acid . . .	160
		ether	426
		Hydrobenzamide . .	490
		Hydrobromic acid . .	161
		ether	426
		Hydrocarbon, chlo-	
		ride of	170
		Hydrochloric acid . .	152
		ether, heavy	443
		Hydrocyanic acid . .	516
		Hydroferricyanic acid	532
		Hydroferrocyanic acid	529
		Hydrofluoric acid . .	163
		Hydrofluosillic acid .	165
		Hydrogen	111
		antimonetted . . .	344
		arsnetted	348
		binoxide of	118, 123
		carbides of	168
		carbonetted	168
		estimation in orga-	
		nic bodies	384
		persulphide	183
		phosphorette . . .	184
		selenietted	184
		sulphuretted . . .	181
		Hydrokiuonc, colour-	
		less	554
		green	554
		Hydroleic acid	605
		Hydromargaric acid .	605
		Hydromargaritic acid	605
		Hydrometer tables .	670
		Hydrosalicylic acid .	495
		Hydrosulphocyanic	
		acid	535
		Hydsulphuric acid .	181
		Hygrometer, dew-	
		point	51
		wet bulb-	47
		Hyocholic acid	639
		Hyocholic acid	639
		Hyoscyamine	557
		Hyoscyamus niger . .	557
		Hyodlysin	639
		Hypochloric acid . .	156
		Hypochlorous acid . .	155
		Hypnitric acid	132
		Hypophosphorous	
		acid	148
		Hyposulphate of silver	355
		Hyposulphite of soda	267

	PAGE	IRON—cont.	PAGE		PAGE
Hyposulphite of silver	355	sesquioxide, benzo-		Lactic acid . . .	420
Hyposulphites . . .	144	ate of . . .	485	Lactide . . .	422
Hyposulphobenzic		Isatin . . .	583	Lactin . . .	404
acid . . .	486	Isathic acid . . .	584	Lactone . . .	422
Hyposulphuric acid	144	Isatyde . . .	584	Lake . . .	581
bisulphuretted . . .	145	Isethionic acid . . .	442	Lamp, argand . . .	176
Hyposulphuric acid,		Isinglass . . .	623	Lampblack . . .	134
sulphuretted . . .	144	Isomeric-bodics . . .	381	Lamp, flame of . . .	175
trisulphuretted . . .	145	Isomorphism . . .	242	safety . . .	178
Hyposulphurous acid	144	Isomorphous . . .	242	spirit . . .	176
		Itaconic acid . . .	508	without flame . . .	450
I.				Land and sea breezes,	
Iceland moss . . .	408	J.		causc . . .	75
Idrialin . . .	665	Jade . . .	289	Lanthanium . . .	294
Imidogen-bases . . .	561	Japonic acid . . .	512	Laughing-gas . . .	130
Inclination, magnetic	84	Jet . . .	664	Laumonite . . .	293
Incrustations in boil-		Jews' pitch . . .	663	Laurel oil . . .	608
ing . . .	283	Juice, gastric . . .	650	Lavender, oil of . . .	612
Indiau yellow . . .	593	Juniper, oil of, . . .	608	Lead . . .	330
Indigo . . .	581			acetates of . . .	454
red . . .	582	K.		alloys of . . .	333
vat . . .	582			analytical remarks	
white or deoxidized	582	Kakodyl . . .	458	on . . .	333
Indin . . .	584	-compounds . . .	459	benzoate of . . .	485
Indinic acid . . .	584	Kakodylic acid . . .	461	binoxide of . . .	331
Inosmic acid . . .	627	Kalisaccharic acid	403	malate of . . .	509
Inosite . . .	627	Kaolin . . .	299	-plaster . . .	599
Ink, label . . .	614	Kapnomor . . .	654	protoxide of . . .	330
blue sympathetic	320	Katalysis . . .	211, 415	red . . .	331
Inulin . . .	408	Kelp . . .	158	sugar of . . .	454
Iodic acid . . .	161	Keratin . . .	634	-tree . . .	224
Iodide of amyl . . .	473	Kermes mineral . . .	344	white . . .	332
of arsenic . . .	348	Kinic acid . . .	551, 553	Leaven . . .	420
of benzoyl . . .	489	Kino . . .	511	Lecanora parella . . .	589
of cyanogen . . .	528	Kinone . . .	553	tartarea . . .	587
of ethyl . . .	426	Kish . . .	134	Lecanoric acid . . .	587, 588
of kakodyl . . .	461	Kissengen, Ragozi		Legumin . . .	649
of mercury . . .	364	water . . .	675	Lemous . . .	558
of methyl . . .	465	Kreatin . . .	626	oil of . . .	608
of nitrogen . . .	187	Kreatinine . . .	555, 626	Leucine . . .	622
of potassium . . .	271	Kreosote . . .	655	Leucoline . . .	574
of silver . . .	355	Kreuznach . . .	677	Lcukol . . .	574
Iodine . . .	158	Kyanol . . .	574	Levo-racemic acid	506
chloride of . . .	189	Kyan's method of pre-		Leyden jar . . .	93
Iodoform . . .	470	serving timber . . .	364	Lichens . . .	586
Iodo-sulphuric acid	145			Light . . .	58
Ipecacuanha . . .	557	L.		blue or Bengal . . .	337
Iridium . . .	374			chemical rays of . . .	68
Iron, acetate of . . .	454	Labarraque's disin-		Lightning rods . . .	95
analytical remarks		fecting fluid . . .	284	Light, polarized . . .	63
on . . .	309	Label ink . . .	614	Lignin . . .	409
and its compounds	305	Lac . . .	614	Lignite . . .	662
cyanide of . . .	523	Lactamide . . .	422	Lignone . . .	472
manufacture of . . .	310	Lactates . . .	422	Lime . . .	279
protoxide, lactate of	422			acetate of . . .	454

	PAGE		PAGE		PAGE
LIME— <i>cont.</i>		Marble	282	Methionie acid	442
carbonate of	282	artificial coloured	281	Methyl	463
chloride of	284	Marc-brandv, fusel-		Methylamine	564
lactate of	422	oil of	479	-urea	565
malate of	509	Margaric acid	597	Methyl-ammonia	564
oxalate of	413	ether	430	Methyl-compounds	463
phosphates of	283	Margarin	596, 597		467
Lime, tartrate of	504	Margarone	598	Methyl-ether	464
Limestone	282	Marienburg, water of	675	Methyl-ethyl-amyl-	
Liquefaction of gases	47	Mariotte's law	17	amine	573
Liquor ammonia	180	Marsh-gas	168	-urea	565
Liquorice sugar	403	Marsh-mallow	558	Methyl-ethyl-amyl-	
Litharge	330	Marls	292	phenylammon-	
Lithia	275	Massicot	330	ium, oxide of	573
Lithic acid	545	Mastic	614	Methyl-mercaptan	470
Lithium	275	Meadow sweet, oil of	495	Methyl- biethyl-	
Lithofellinic acid	639	Mcasures	678	amyl - ammo-	
Litmus	586	Meat	647	num, oxide of	573
Loadstone	81, 307	Meconic acid	550	Methyl, saticylate	
Loaf-sugar	400	Meconine	550	of oxide of	611
Logwood	592	Meerschaaum	289	Methyl-series, ba-	
Lupulin	418	Melam	536	ses of the	565
Lungs	628	Melamine	536	Metoleic acid	605
Lymph	633	Melaniline	569	Metre	678
		Melanic acid	496	Mica	293
M.		Melasinic acid	403	Microcosmic salt	268
Madder	591	Melissic acid	482	Milk	634
Magnesia	287	alcohol	480, 603	spirit from	636
acetate of	454	Mellite	414	Milk sugar	404
aconitate of	508	Mellitic acid	414	Mindererus, spirit of	453
alba	288	Mellon	535	Mineral chameleon	304
analytical remarks		Membraneous tissue	646	waters, tables of	674
on	289	Membranes, mucous	633	Molasses	400
carbonate of	288	Meraptan	444	Molecular actions	208
phosphate of	288	methyl-	471	Molybdenum	337
silicates of	289	Mercury, acetates of	455	Momordica elaterium	558
sulphate of	287	analytical remarks		Monobasic acids	245
tartrate of	504	on	365	Mordant	335
Magnesium	286	cyanide of	522	Mordants	581
chloride of	287	fulminate of	527	Morphia	574
Magnetism	81	its compounds	359	Morphine	574
Magnus, green salt of	369	Meridian, magnetic	84	Mortar	280
Malachite	329	Mesitilol	457	Mosaic gold	336
Malamic acid	509	Mesityl	457	Mucic acid	414
Malamide	509	Mesotype	293	Mucilage	408
Malates	509	Mesoxalic acid	541	Mucous membranes	633
Maleic acid	510	Metacetone	457	Mucus	633
Malic acid	509	Metacetic acid	457	Mulberry calculus	644
Malleability of metals	227	Metaldchide	449	Multiple proportions	194
Malting	418	Metagallie acid	514	Multiplier	77
Manganese, acetate of	454	Metals	226	Murexan	545
and its compounds	300	classification	248	Murexide	544
assay of	302	Metamargaric acid	605	caffein	556
Manna sugar	404	Metapectin	409	Muriatic acid	152
Mannite	404	Metapectic acid	409	ether, heavy	443
Manures	651	Metaphosphoric acid	246	Muscovado sugar	400
Maple, sugar from	400	Metastyrol	616	Mushroom sugar	404
		Meteorites	305	Must	418

	PAGE		PAGE		PAGE
Mustard, oil of . . .	612	Nitrogen . . .	124	Oil —cont.	
bases from the oil		binoxide of . . .	131	of lemon . . .	608
of . . .	577	chloride of . . .	186	of meadow-sweet . . .	495
Mykomelinic acid . . .	541	compounds with		of mustard . . .	612
Myricin . . .	603	oxygen . . .	127	of onions . . .	613
Myristic acid . . .	600	estimation in organic		of orange flowers . . .	612
Myristica moschata . . .	600	hodies . . .	389	of orange peel . . .	608
Myronic acid . . .	612	iodide of . . .	187	of pepper . . .	608
		Nitro-naphthalasc . . .	661	of peppermint . . .	612
N.		Nitro-phenasic acid . . .	659	of rosemary . . .	612
Naphtha . . .	664	Nitro-phenesic acid . . .	659	of rose petals . . .	612
Naphthalidine . . .	571	Nitro-phenisic acid . . .	585, 659	of spiraea ulmaria . . .	495
Naphthalin . . .	660	Nitro-prussides . . .	533	of turpentin . . .	607
Narceine . . .	550	Nitro-salicylamide . . .	611	of valerian . . .	611
Narcogenine . . .	549	Nitro-salicylic acid . . .	497	of vitriol . . .	143
Narcotine . . .	549		585	of wine, heavy and	
Nepheline . . .	293	Nitro-toluol . . .	571, 615	light . . .	437
Nervous substance . . .	645	Nitro-tolylic acid . . .	494	of wuitergreen . . .	610
Neutrality of salts . . .	230	Nitrous acid . . .	132	Oils . . .	595
Neutralization . . .	199	ether . . .	427	drying or non-drying . . .	595
Nickel . . .	317	oxide . . .	130	volatile . . .	606
acetate of . . .	454	Nitro-xytol . . .	571	Olefiant gas . . .	169
analytical remarks . . .	319	Nomenclature . . .	191	and its compounds . . .	437
Nicotine . . .	555, 572	Norium . . .	295	Oleic acid . . .	598
Niobium . . .	340	Notation, chemical . . .	203	Olein . . .	597, 598
Nitraniline . . .	568	Nutgalls . . .	511	Olive oil . . .	596
Nitranisic acid . . .	609	Nutrition . . .		Onions, oil of . . .	613
Nitraniside . . .	609	plastic elements of . . .	649	Opianmon . . .	549
Nitranisidine . . .	609			Opianic acid . . .	549
Nitranisol . . .	609	O.		Opianine . . .	550
Nitrate of ammonia . . .	273	Octahedron . . .	237	Opium . . .	547
of haryta . . .	277	Cenanthic acid . . .	431	Orange flowers, oil of . . .	612
of bisnuth . . .	325	ether . . .	431	oil of -peel . . .	608
of lead . . .	331	Cenanthylic acid . . .	481	Oranges . . .	558
of oxide of methyl . . .	466	Oil gas . . .	169	Orcein . . .	589
of potassa . . .	254	of alharia officinalis . . .	612	Orcin . . .	587, 589
of soda . . .	267	of aniseed . . .	608	Organic bases . . .	547
of silver . . .	354	of assafetida . . .	613	bases, artificial . . .	559
Nitrates . . .	129	of badian . . .	609	substances, action	
of mercury . . .	360	of bergamot . . .	608	of heat on . . .	382
Nitre . . .	254	of bitter almonds . . .	483	substances, classifi-	
cubic . . .	267	of bitter fennel . . .	609	cation . . .	382
sweet spirits of . . .	428	of capivi . . .	608	substances, compo-	
Nitric acid . . .	128	of cedar wood . . .	610	sition elementary . . .	378
acid, fuming . . .	133	of cinnamon . . .	499	substances, decom-	
ether . . .	427	of elemi . . .	608	position of . . .	383
oxide . . .	131	of cubebs . . .	608	substances, ultimate	
Nitrile-bases . . .	561	of cumin . . .	610	analysis of . . .	384
Nitro-benzamide . . .	570	of garlic . . .	612	Orpiment . . .	347
Nitro-benzoic acid . . .	485	of gaultheria pro-		Orsellinic acid . . .	587, 588
Nitro-benzol . . .	487, 571	cumbens . . .	498, 610	Osmium . . .	376
Nitro-chloronitene . . .	572	of Guiana-laurel . . .	608	Othyl . . .	452
Nitro-coccusic acid . . .	591	of hops . . .	608	Oxalate of oxide of	
Nitro-cumic acid . . .	494	of horseradish . . .	612	methyl . . .	467
Nitro-cumol . . .	571	of juniper . . .	608	Oxalates . . .	411
		of lavender . . .	612	Oxalic acid . . .	410
				ether . . .	429
				Oxalo-nitrile . . .	570
				Oxalo-vinic acid . . .	433

	PAGE		PAGE	PHOSPHORIC—cont.	PAGE
Oxaluria acid . . .	542	Parapectin . . .	409	acid, glacial . . .	247
Oxamethane . . .	429	Parafatartarie acid . . .	505	acid, monobasic . . .	246
Oxamethylane . . .	467	Parellie acid . . .	589	acid, tribasic . . .	245
Oxamic acid . . .	412	Parmelia parietina . . .	590	ether . . .	427
ether . . .	429	Pear, flavour of . . .	474	Phosphorous acid . . .	148
Oxamide . . .	412	Pearlash . . .	253	Phosphorus . . .	147
Oxanilic acid . . .	570	Pectic acid . . .	409	-bases . . .	579
Oxanilide . . .	570	Pectin . . .	409	chloride of . . .	188
Oxide, cystic . . .	545	Pelargonic acid . . .	431, 481	compounds of . . .	148
of allyl . . .	613	Pelopium . . .	340	Phosphovinic acid . . .	432
of amyl, hydrated . . .	472	Pentathionic acid . . .	145	Photography . . .	68
of benzoyl . . .	484	Pepper, oil of . . .	608	Phthalic acid . . .	661
of bismuth . . .	324	Peppermint, oil of . . .	612	Picamar . . .	654
of copper . . .	328	Pepsin . . .	650	Picoline . . .	574
of kakodyl . . .	459	Perchlorate of potassa . . .	256	Picric acid . . .	585, 659
of methyl . . .	464	Perchloric acid . . .	158	Piero-erythrin . . .	587
of methyl, hydrated . . .	463	Percussion-caps . . .	527	Picrotoxin . . .	558
xanthic . . .	545	Periodic acid . . .	161	Pimaric acid . . .	614
Oxides . . .	110	Peroxide of chlorine . . .	156	Pinic acid . . .	613
of antimony . . .	342	Persulphide of hydro- gen . . .	183	Piperine . . .	557
of chromium . . .	314	Peru balsam . . .	501	Pitch . . .	653
of gold . . .	357	Peruvian . . .	501	Pit coal . . .	662
of hydrogen . . .	117	Petallite . . .	293	Pitch, mineral . . .	663
of manganese . . .	301	Petinine . . .	575	Plants, supply of car- bon to . . .	137
of mercury . . .	360	Pettenkofer's bile-test . . .	638	Plaster of Paris . . .	281
of platinum . . .	367	Petroleum . . .	664	Plate glass . . .	295
of potassium . . .	251	Petrolene . . .	663	Platinum and its com- pounds . . .	366
of silver . . .	354	Petuntze . . .	299	analytical remarks . . .	371
of sodium . . .	260	Phenetol . . .	658	bases . . .	369
of zinc . . .	322	Phenol . . .	657	black . . .	367
Oxygen . . .	104	Phenyl . . .	657	surface-action of 116, 117	
acids . . .	231	Phenylalcohol . . .	566	Plumbago . . .	134
Oxy-hydrogen, flame and blowpipe . . .	114	benzoate of . . .	658	Polarity, magnetic . . .	81
safety jet . . .	179	chloride of . . .	658	Polybasic acids . . .	245
Oxy-salts . . .	231	cyanide of . . .	658	Pontil or puntil . . .	296
Ozone . . .	110	hydrated oxide . . .	657	Populin . . .	557
		series, bases of . . .	566	Porcelain . . .	297
P.		Phenyl-amine . . .	566	clay . . .	292
Palladium, cyanide of . . .	372, 523	Philosophy, chemical . . .	191	Porphyroxine . . .	550
Palmitate of oxide of melissyl . . .	603	Phloretin . . .	498	Potash . . .	251
Palmitin . . .	600	Phloridzin . . .	498	crude . . .	253
Palmitic acid . . .	600	Phocenic acid . . .	602	Potassa . . .	251
Palm-oil . . .	600	Phorone . . .	611	acetate of . . .	453
Papaverine . . .	550	Phosgene gas . . .	138	alum . . .	292
Parahanic acid . . .	541	Phosphate of lime . . .	283	analytical remarks . . .	
Paracyanogen . . .	515	Phosphate of magnesia . . .	288	on . . .	259
Paraffin . . .	653	of magnesia and am- monia . . .	288	benzoate of . . .	485
Parakakodylic oxide . . .	462	Phosphate of soda . . .	268	bicarbonate of . . .	253
Paramagnetic bodies . . .	85	Phosphethylic acid . . .	433	hisulphate of . . .	255
Paramide . . .	415	Phosphide of calcium . . .	281	carbonate of . . .	252
Paramorphine . . .	550	Phosphobiethylic acid . . .	423	chlorate of . . .	256
Paramylene . . .	475	Phosphoretted hydro- gen . . .	184	cyanate of . . .	524
Paranaphthalin . . .	662	Phosphoric acid . . .	149	nitrate of . . .	253
		acid, anhydrous . . .	247	oxalate of . . .	411
		acid, bihasic . . .	246	perchlorate of . . .	256
				sulphate of . . .	255

POTASSA— <i>cont.</i>	PAGE		PAGE		PAGE
tartrates of . . .	503	Pyrophosphoric acid . . .	246	Rubic acid . . .	512
urate of . . .	539	Pyrotartaric acid . . .	505	Rust . . .	306
Potassium and its		Pyroxylic spirit . . .	463	Ruthenium . . .	375
compounds . . .	250	Pyroxylin . . .	413		
bromide of . . .	259			S.	
chloride of . . .	258			Saccharic acid . . .	413
cyanide of . . .	520			Saccharic group . . .	399
ferricyanide of . . .	532	Q.		Saccharometer . . .	65
ferrocyanide of . . .	529	Quadrichlorovaleric		Sacchulmic acid . . .	403
salicylide of . . .	496	acid . . .	478	Sacchulmin . . .	403
sulphides of . . .	256	Quercitron bark . . .	593	Safety lamp . . .	177
sulphocyanide of . . .	534	Quicksilver . . .	359	Safflower . . .	592
Potato-oil . . .	472	Quina . . .	552	Saffron . . .	593
Precipitate, white . . .	363	Quinicine . . .	552	Sage . . .	408
Prehnite . . .	293	Quinidine . . .	552	Sal-a-lenbroth . . .	363
Proof spirit . . .	417	Quinine . . .	551	Sal-a-umoniac . . .	272
Propione . . .	457, 480	Quinine, amorphous . . .	553	Salicin . . .	494, 557
Propionic acid . . .	457, 480	Quinoline . . .	574	Salicyl and its com-	
Proportionals . . .	197	Quinoidine . . .	553	pounds . . .	494
Proportions, multiple . . .	194			hydride of . . .	558
Propyleue . . .	473	R.		Salicylate of oxide of	
Protein . . .	621	Radiation of heat . . .	72	methyl . . .	611
binoxide of . . .	622	Racemic acid . . .	505	Salicylic acid . . .	497
teroxide of . . .	622	artificial production		Salicylides . . .	496
Protide . . .	622	of . . .	506	Salicylous acid . . .	495
Protochloride of tin . . .	335	Realgar . . .	347	Saligenin . . .	497
Protoxide of tin . . .	334	Red dyes . . .	590	Saliretin . . .	497
Prussian blue . . .	530, 531	Red fire . . .	279	Saliva . . .	650
Prussiate of potash,		Red lead . . .	331	Salsola soda . . .	260
red . . .	532	Reflection of heat . . .	72	Salt, definition . . .	110
yellow . . .	529	of light . . .	59	of sorrel . . .	411
Prussic acid . . .	516	of light . . .	59	-radical . . .	231
Pseudo-erythrin . . .	588	Refraction, double . . .	63	Salts, super or acid . . .	232
Pseudo-morphine . . .	550	of light . . .	59	binary theory of . . .	249
Pudding . . .	311	Rennet . . .	635	constitution of . . .	229
Pöllna, water of . . .	677	Resins . . .	613	double . . .	232
Purple of Cassius . . .	336	Respiration . . .	627	neutral . . .	230
Purpurate of ammonia . . .	544	Respiration, elements		Saltpetre . . .	129, 254
Purpuric acid . . .	545	of . . .	649	Sandarac . . .	614
Purpurin . . .	592	Retinic acid . . .	665	Santonin . . .	558
Purree . . .	593	Retinite . . .	665	Saponification . . .	596
Purreic acid . . .	593	Reverberatory furnace . . .	174	Saratoga Congress	
Purrenone . . .	593	Rhodium . . .	372	spring . . .	675
Pus . . .	633	Rhodizonic acid . . .	415	Sarcosine . . .	627
Putrefaction . . .	383	Ricinoleic acid . . .	606	Saturation . . .	199
Putty powder . . .	334	Rocella tiuctoria . . .	587, 588	Scagliola . . .	281
Pyren . . .	656	Rocellin . . .	588	Schlesischer Obersalz	
Pyrites . . .	308	Rochelle salt . . .	503	brunnen . . .	674
Pyrmont, water of . . .	676	Rock oil . . .	664	Scheele's green . . .	329
Pyroacetic spirit . . .	456	Rock salt . . .	270	Sea water . . .	121
Pyro-acids . . .	383	Roman alum . . .	291	Sebacic acid . . .	601
Pyrobenzolin . . .	576	Rosemary, oil of . . .	612	Seed lac . . .	614
Pyrogallie acid . . .	514	Rubia tiuctorum . . .	591	Seggars . . .	298
Pyrogen acids . . .	514	Rubiacin . . .	592	Seidschutz, water of . . .	677
Pyromeconic acid . . .	551	Rubiatic acid . . .	592	Seignette salt . . .	503
Pyromucic acid . . .	414	Rubian . . .	592	Selenic acid . . .	146
Pyrophorus of Hom-					
berg . . .	292				

	PAGE		PAGE	SUGAR— <i>cont.</i>	PAGE
Selenietted hydrogen	184	Sparteine	555	copper, test for the	
Selenious acid	146	Specific gravities of		varieties of	402
Selenite	272	metals	227	from diabetes	401
Selenium	145	gravity of solids and		from diabetes insi-	
Seleno-cyanogen	535	liquids	3	pidus	403
Selters, water of	677	heat	52	from starch or dex-	
Serpentine	289	Speculum metal	330	trin	406
Serum of blood	629	Spectrum	61	gelatin-	624
Silica	164	Speiss	321	of lead	454
Silicates of alumina	293	Spermaceti	603	of milk	404
of magnesia	289	Spirit from milk	636	Sulphamylic acid	474
Silicic ether	423	of Mindererus	453	Sulphasatyde	584
Silicium	164	pyroxylic	463	Sulpbate of alumina	291
chloride of	189	Spirits, table of spec.		of ammonia	272
fluoride of	165	gr. of	673	of baryta	277
Silver, acetate of	455	Spodumene	293	of carbyl	441
analytical remarks	356	Springs	122	of copper	328
benzoate of	485	Stannethyl	446	of lime	281
cyanide of	522	oxide of	446	of magnesia	287
fulminate of	527	chloride of	446	of oxide of methyl	466
its compounds	352	bromide of	446	of potassa	255
standard of England	356	iodide of	446	of silver	355
Sykes' hydrometer	671	nitrate of	446	of soda	267
Sinapoline	577	Starch	404	of zinc	322
Sinnameine	577	State, change of—by		Sulphates of mercury	361
Size	625	beat	35	Sulphesatyde	584
Shellac	614	Steambath	40	Sulphide of allyl	613
Skin	646	Steam engine	40	of amyl	474
Smalt	321	specific gravity of	122	of arsenic	347
Smee's battery	223	latent beat of	36	of barium	277
Soap	596	Stearic acid	597	of benzoyl	489
Soap stone	289	Stearin	596, 597	of calcium	281
Soap-test of Dr. Clark	282	candles	605	of ethyl	426
Soda, acetate of	453	Stearoptene	607	of kakodyl	461
alum	292	Steatite	289	of silver	355
analytical remarks		Steel	312	of sodium	270
on	271	Stibethyl	447, 579	Sulpbides	139
ash	261	Sticklac	614	of ammonium	273
ash, testing its value		Stilbite	293	of antimony	343
	264	Stoneware	299	of mercury	365
bicarbonate of	262	Strontia	278	of potassium	256
carbonate of	260	acetate of	453	of tin	336
hydrate of	260	tartrate of	504	test for	533
oxalate of	412	Strontium and its com-		Sulpbindigotic acid	582
tartrates of	503	pounds	278	Sulpbindylic acid	582
urate of	539	Strychnine	554	Sulphite of oxide of	
Sodium	259	Styphnic acid	593	ethyl	427
cyanide of	522	Styracin	501	Sulpbites	141
ferrocyanide of	532	Styrol	500, 615	Sulphobenzide	486
oxides of	260	Styrone	501	Sulphobenzoic acid	481
Solanine	557	Suberic acid	414, 601	Sulphocyanide of allyl	613
Solder	333	Sublimatc, corrosive	363	Sulphocyanides	534
Soleil's saccharometer	66	Sublimation	41	Sulphocyanogen and	
Solids, expansion of	23	Substitution, law of	380	its compounds	534, 535
Sorbin	404	products, organic	380	Sulphoglyceric acid	599
Sorrel, salt of	411	Succinic acid	601	Sulpholeic acid	605
Spa Pouhon, water of	676	Sugar	399	Sulphomethylic acid	466,
Spar, calcareous	283	candy	400		468

	PAGE		PAGE		PAGE
Sulphomargaric acid	605	Tauro-hyo-cholalic acid	639	Trimethyl-ammonia	565
Sulphonaphthalic acid	661	Teeth	647	Trinitranisol	609
Sulphophenic acid	658	Telluric acid	345	Trithionic acid	144
Sulphosaccharic acid	402	Tellurium	345	Trona	262
Sulphotoluic acid	603	Tellurous acid	345	Tungsten	337
Sulphovinic acid	432	Tension	11	Turkey red	592
decomposed by heat	434	Tension of vapours	43	Turneric	593
Sulphur	138	Terbium	293	Turnhull's blue	533
acids	232	Terchlorovaleric acid	478	Turpentin	607
auratum	344	Terebene	608	common	607
bases	232	Terehylene	608	hydrated oil of	608
chloride of	188	Terioxide of protein	622	oil of	607
compounds with ox-		Tetra-chloro-kinone	554	venetian	615
ygen	140	Tetra-methyl-ammo-		Type metal	345
estimation in orga-		niun, hydrated		Tyrosine	591
nic bodies	394	oxide of	565	Twaddell's hydrometer	671
salts	232	Tetramyl-ammonium,		U.	
Sulphuretted hydrogen	181	hydrated oxide of	566	Ulmic acid	403
Sulphuric acid	141	Tetrathionic acid	145	Ulmia	403
ether	423, 427	Tetrethyl-ammonium,		Ultramarine	270
Sulphurous acid	140	hydrated oxide of	563	Upas antiar	558
ether	427	Thebaine	550	Uramile	542
Super salts	232	Theine	555	Uramilic acid	543
Surface-action of pla-		Theobromine	556	Uranium	326
tinum, charcoal,		Thermo-electrical phe-		Urates	539
gold, &c. 116, 117,	135	uomena	77	Urea	524, 536
Sylvic acid	613	Thermometer	21	Urethane	431
Symbols	203	Thialdine	448, 577	Urethylanc.	468
Synthetical method of		Thionuric acid	542	Uric acid	538, 545, 640
chemical research	118	Thiosinamine	577	products from	539
Systems of crystals	237	Thoria	295	Urinary calculi	534, 643
Synaptase	518	Thorite	295	Urine	640
		Thorium	295	Usnea barbata	590
T.		Tin	334	Usnic acid	590
		analytical remarks		V.	
Tannates	512	on	336	Valeracetonitrile	624
Tannic acid	510	Tinned plate	336	Valeramide	476
Tannin	511	Tissue, membranous	646	Valerianic acid	475, 611
Tanning	646	Titanium	340	ether	430
Tantalum	339	Tolene	615	Valcrian, oil of	611
Tapioca	407	Tolu balsam	501, 615	Valeric acid	475, 481
Tar	653	Toluidine	571, 572	anhydrous	489
mineral	663	Toluol	494, 571, 615	Valero-benzoic acid	488
oil	653	Toluylic acid	493	Valerol	611
Tartar	502	Tonka bean	498	Valeronitrile	476, 624
cream of	503	Trade winds	31	Valyl	477
emetic	342, 504	Transmission of heat	76	Vanadium	338
soluble	503	Travertin	283	Vapour of water, ten-	
Tartaric acid	503	Triamylamine	566	sion	672
acid, anhydrous	505	Triamyl-ammonia	566	Vapours, determina-	
inactive	506	Trihasic acids	245	tion of the den-	
Tartaric acid	505	Trichlor-aniline	568	sity of	396
Tartrates	503	Trichloro-kinone	554	maximum density of	44
Tartrelic acid	505	Triethylamine	563		
Tartrovinic acid	433	Triethyl-ammonia	563		
Taurin	637	Triethyl-stibin	579		
Tauro-cholalic acid	638	Trimethylamine	565		

	PAGE		PAGE		PAGE
Varec	260	Water	117	Xanthiu	592
Vapours, tension of	43	analysis of	118	Xanthorrhoea hastilis	585
Variolaria	587	distilled	121	Xylidine	571
Varvicite	302	expansion by heat	28	Xylite	472
Vegetable acids	502	hardness of	282	Xyloldin	413
nutrition	647	of crystallization	233	Xyloe	494, 571
Vegeto-alkalis	547	oxygenated	123		
Venous blood	627	tension of its vapour	43		
Ventilation	34	Wax	602		
Veratria	555	fossil	665	Y.	
Veratrine	555	Weights	678	Yeast	416, 419
Verdigris	455	specific	3	Yellow dyes	590
Verditer	329	Welding	305	Yttria	293
Vermilion	365	Whey	621	Yttrium	293
Vinous fermentation	416	White lead	332		
Viscous fermentation	422	precipitate	363		
Vitriol, blue	328	vitriol	322	Z.	
Vitriol, green	308	Winds	31	Zaffer	321
oil of	141	Wine	417	Zeise's combustible	
oil of, fuming	141	clarifying of	626	platinum salts	441
Volatile oils	606	Wintergreen oil	610	Zeolites	293
Volume, combination		Witherite	278	Zinc	321
by	200	Wolframium	337	analytical remarks	323
equivalent	201	Wood ether	464	cyanide of	523
Voltaic battery	96	spirit	463	-ethyl	445
pile, chemistry of		Woody tissue	409	fulminate of	527
the	213	Wootz	313	lactate of	422
Voltameter	217	Wort	418	Zinin's process	567
Volta's pile	95			Zircon	295
		X.		Zirconia	295
W.		Xanthic acid	445	Zirconium	295
Wash, distiller's	419	oxide	545		



LONDON PRINTED BY WILLIAM CLOWES AND SONS, STAMFORD STREET.

ERRATA.

Page 144, line 7 from below, *read* " $\text{KO}, \text{S}_2\text{O}_2$," *instead of*
" $\text{KO}, \text{S}_2\text{O}$."

Page 160, last line, *read* "hydrated phosphorous acid,"
instead of "hydrated."





✓

BOUND BY
EDMONDS & REMNANTS
LONDON

